

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220744

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220744

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER


Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before 10.04.2026 up to 11:30 AM and the same shall be opened on the same day at 12:00 A.N. in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on 09.04.2026 up to 4:30 PM and the application for issue of tender form shall be received on 09.04.2026 up to 5:00 PM.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/o Ambulance road from Duddla Chanda Saryali road Km. 0/00 to 3/00 (SH:- C/o Hume Pipe Culvert 900mm dia at RDs 1/045 with wing wall.) DMFT Deposit	3,99,333/-	8,000/-	1 Month	350/-
2.	C/o link road Delag to Shivghatti Gram Panchyat Sanan Km. 0/210 to 0/600.) DMFT Deposit	4,36,813/-	9,000/-	1 Month	350/-
3	C/o Ambulance link road from Rudal to Harijan Basti Kathalu Km. 0/00 to 0/250 (SH:- Formation Cutting in Km. 0/00 to 0/250) DMFT Deposit	90,786/-	2,000/-	1 Month	350/-
4	C/o Ambulance link road from Rudal to Harijan Basti Kathalu Km. 0/00 to 0/250 (SH:- C/o R/wall at RDs 0/00 to 0/015, 0/045 to 0/060) DMFT	4,95,534/-	10,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.



Executive Engineer
Arki Division
H.P.P.W.D. Arki

Dated:-

No: PW-AD-EA-I-Tender-2025-26-

Copy forwarded for the following for information and necessary action to:-


- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

Certificate

Certified that the tenders called vide this notice inviting tender for

4(Four) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

SCHEDULE OF QUANTITY				Estimated Cost: -Rs3,99,333/- only		
Name of Work:-C/o Ambulance Road from Duddla Chanda Saryali Road Km 0/00 to 3/00. (SH:- C/o Hume Pipe Culvert 900mm dia at Rd 1/045 with wing wall.) DMFT Deposit				Earnest Money :-Rs8,000/-Only		
				Time :-One Month		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	55.25	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	9470
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 40mm (fourty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts . The rate including octroi, royalty, malkhana, toll tax sale tax or other taxes imposed by the Government.	48.72	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	241417
3	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	16.88	5291.95	Rupees five thousand two hundred ninety one and paise ninety five only	P.Cum.	89328
4	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	18.48	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	22237
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe.including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	7.50	3882.55	Rupees three thousand eight hundred eighty two and paise fifty five only	P.Rmt	29119
6	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	28.30	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	7761
					Total	399333

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-C/o Link Road Delag to Shivghati Gram Panchyat Sanan Km 0/00 to 1/500. (SH:- Formation Cutting in Km 0/210 to 0/600.)DMFT Deposit

Estimated Cost: -Rs 4,36,813/- only


Earnest Money :-Rs9,000/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 177.20 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2126.44	Per. Cum.	205.42	Rupees two hundred five and paise fourty two only .	436813
					Total	436813

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-C/o Ambulance Link Road from Rudal to Harijan Basti Kathalu Km 0/00 to 0/250. (SH:- Formation Cutting in Km 0/00 to 0/250.)DMFT Deposit

Estimated Cost: -Rs 90,786/- only


Earnest Money :-Rs2,000/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner, tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 46.12 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	501.80	Per. Cum.	180.92	Rupees one hundred eighty and paise ninety two only .	90786
					Total	90786

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
B&R Division HPPWD
Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs4,95,534/- only

Name of Work:-C/o Ambulance Link Road from Rudal to Harijan Basti Kathalu Km 0/00 to 0/250. (SH:- C/o R/wall at RD 0/00 to 0/015,0/045 to 0/060) DMFT


Earnest Money :-Rs10,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	51.45	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	8819
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	100.20	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	439938
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	28.80	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	34655
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	44.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	12122
					Total	495534

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki