

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2026-27

743-51

Dated:- 16/04/2026


To

The Executive Engineer (IT Cell)  
H.P.P.W.D. Nigam Vihar Shimla-2.

**Subject:- Notice Inviting Tender for uploading the same on departmental website.**


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

**Encl:-Copy of NIT**

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

**NOTICE INVITING TENDER**

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **25.04.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **24.04.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **24.04.2026 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/o Sinthighat to Nanihas road km. 0/00 to 2/300 (SH:- C/o Wire crate at RDs 0/930 to 0/940 and 2/075 to 2/090.) DMFT	4,97,138/-	10,000/-	1 Month	350/-
2.	C/o road from Banali Ghati to Bairghat Pajeena road km. 0/00 to 4/500 (SH:- C/o R/wall at RD's 2/845 to 2/853.50, 2/853.50 to 2/862.80 and 2/862.80 to 2/868.80) DMFT	4,97,054/-	10,000/-	1 Month	350/-
3.	C/o link road from Samana Paza Kaldwar road km. 0/00 to 2/500 (SH:- F/C in km. 0/900 to 1/405) DMFT	4,66,483/-	10,000/-	1 Month	350/-
4.	C/o link road from Samana Paza Kaldwar road km. 0/00 to 2/500 (SH:- F/C in km. 1/405 to 1/900) DMFT	4,76,314/-	10,000/-	1 Month	350/-
5.	C/o Arki Chamyawal road km. 0/00 to 5/00 (SH:- Formation cutting in km. 0/085 to 0/250 and C/o R/wall between RD 0/00 to 0/350) Under DMFT	4,75,157/-	9,600/-	1 Month	350/-
6.	C/o Arki Chamyawal road km. 0/00 to 5/00 (SH:- C/o PCC R/wall between km. 0/800 to 1/500) Under DMFT	4,82,868/-	9,700/-	1 Month	350/-
7.	C/o Sinthighat to Nanihas road km. 0/00 to 2/300 (SH:- ROFD in km. 1/750 to 1/765, 1/870 to 1/885 and 1/915 to 2/285) DMFT	4,74,882/-	10,000/-	1 Month	350/-

	C/o Soria to Bahra road km. 0/00 to 2/00 (SH:- Formation deficiency in km. 0/495 to 0/930) DMFT	4,80,906/-	9700/-	1 Month	350/-
9	C/o Soria to Bahra road km. 0/00 to 2/00 (SH:- C/o R/wall at RD 0/570 to 0/585 and 0/710 to 0/725) DMFT	4,85,119/-	9800/-	1 Month	350/-
10.	Construction of playground for Govt. Senior Secondary School Bawasi Tehsil Arki, Distt. Solan HP. (SH:- Providing and Laying stone soling and cement concrete 1:4:8 in ground etc.) Under DMFT 2025-26	1,04,533/-	2,500/-	1 Month	350/-
11.	C/o link road Badehan to Ghat km. 0/00 to 1/500 (SH:- Construction of Retaining wall at RD end portion of road) Under DMFT for 2025-2026	4,99,730/-	10,000/-	1 Month	350/-
12	Restoration of rain damages on Talab (Rao Khad) Behli road km. 0/00 to 2/170. (SH:- Construction of PCC Retaining wall at RD 1/425 to 1/460) Under PDNA 2023 Balance work thereof.	4,89,026/-	10,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2026-27- 743-51

Dated:- 16/04/2026


Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3<sup>rd</sup> Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.

  
Executive Engineer  
Arki Division  
H.P.P.W.D. Arki.

**Certificate**

Certified that the tenders called vide this notice inviting tender for 12 (Twelve) jobs are due to exigencies/emergency of works in the larger public interest.

  
Executive Engineer  
Arki Division  
H.P.P.W.D. Arki.

## SCHEDULE OF QUANTITY

Name of Work:-C/o Sinthighat to Nanihas Road Km 0/00 to 2/300.(SH:- C/o Wire Crate at Rd,s 0/930 to 0/940 and 2/075 to 2/090.) DMFT

Estimated Cost: -Rs4,97,138/- only

Earnest Money :-Rs10,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	57.75	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	9898
2	P/L of boulder apron laid in wire crates with 4mm dia GI wire confirming to IS:280 and IS:4826 in 100mmx100mm mesh(woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and clause 1301. technical specifications. Directed by Engineer-In- Charge	145.25	3149.45	Rupees three thousand one hundred forty nine and paise fourty five only	P.Cum.	457458
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	24.75	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	29782
					Total	497138

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

## SCHEDULE OF QUANTITY

Name of Work:-C/o Road from Banali Ghati to Bairghat Pajeena Road Km 0/00 to 4/500.( SH:- C/o R/wall at Rd,s 2/845 to 2/853.50, 2/853.50 to 2/862.80 and 2/862.80 to 2/868.80) DMFT		Estimated Cost: -Rs4,97,054/- only				
		Earnest Money :-Rs10,000/-Only				
		Time :-One Month				
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	39.79	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	6820
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	101.47	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	445514
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	27.46	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	33043
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	42.58	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	11678
					Total	497054

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

### SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road from Samana to Paza Kaldwar Road Km 0/00 to 2/500.  
(SH:-F/C in Km 0/900 to 1/405)DMFT

Estimated Cost: -Rs 4,66,483/- only


Earnest Money :-Rs10,000/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner, tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrcted by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is <b>143.45</b> cubic meter in all cases falling which recovery @ Rupees <b>300/-</b> only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2941.81	Per. Cum.	158.57	Rupees one hundred fifty eight and paise fifty seven only .	466483
					Total	466483

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 B&R Division HPPWD  
 Arki

### SCHEDULE OF QUANTITY


Name of Work:- C/o Link Road from Samana to Paza Kaldwar Road Km 0/00 to 2/500.  
(SH:-F/C in Km 1/405 to 1/900)DMFT

Estimated Cost: -Rs 4,76,314/- only  
Earnest Money :-Rs10,000/-Only  
Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is <b>118.67</b> cubic meter in all cases falling which recovery @ Rupees <b>300/-</b> only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2945.85	Per. Cum.	161.69	Rupees one hundred sixty one and paise sixty nine only .	476314
					<b>Total</b>	<b>476314</b>

Quoted Rate Percentage in Figure


Quoted Rate Percentage in Words

  
Executive Engineer  
B&R Division HPPWD  
Arki

## SCHEDULE OF QUANTITY

Name of Work:-C/o Arki Chamyawal Road Km 0/00 to 5/00.( SH:- Formation Cutting in Km 0/085 to 0/250 and C/o R/wall between Rd 0/00 to 0/350) Under DMFT				Estimated Cost: -Rs4,75,157/- only		
				Earnest Money :-Rs9,600/-Only		
				Time :-One Month		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Excavation in earthwork in hilly area by mechanical means all heights and depth, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation, including rock excavation shall be carried out true to lines grades, side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. The recovery of useful stone that is 150.57 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	709.91	283.87	Rupees two hundred eighty three and paise eighty seven only	P.Cum.	201522
2	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	26.88	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	4607
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In-Charge	58.80	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	258167
4	Providing and laying 100mm dia metre PVC pipe for wheel holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	39.60	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	10860
					Total	475157

Quoted Rate Percentage in Figure  
Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs482868/- only	
Name of Work:- C/O Arki Chamyawal road km 0/00 to 5/00 {SH:- C/O PCC R/Wall between Km 0/800 to 1/500} Under DMFT					Earnest Money :-Rs9700/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	19.98	171.40	Rupees one hundred seventy one and paise forty only	P.Cum.	3425
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	105.45	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	462989
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	60.00	274.25	Rupees two hundred seventy four and paise twenty five only	Rmt	16455
					Total	482868

Quoted Rate Percentage in Figure  
Quoted Rate Percentage in Words

  
Executive Engineer  
Arki Division HPPWD  
Arki

### SCHEDULE OF QUANTITY


Name of Work:- C/o Sinthighat to Nanihas Road Km 0/00 to 2/300.(SH:- ROFD in Km 1/750 to 1/765, 1/870 to 1/885 and 1/915 to 2/285.)DMFT

Estimated Cost: -Rs 4,74,882/- only  
Earnest Money :-Rs10,000/-Only  
Time :- One Month

S.No.	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner, tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is <b>256.34</b> cubic meter in all cases falling which recovery @ Rupees <b>300/-</b> only (Rupees three hundered only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2630.05	Per. Cum.	180.56	Rupees one hundred eighty and paise fifty six only .	474882
					Total	474882

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 B&R Division HPPWD  
 Arki


**DRAFT SCHEDULE OF QUANTITY**

**NAME OF WORK:- C/O Soria to Bahra Raod km 0/0 to 2/00 (SH :- Formation deficiency in km0/495 to 0/930 under DMFT)**

Estimated Cost :- Rs 4,80,906.00  
 Earnest money :- Rs 10,000.00  
 Time: One months


Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1.00	Excavation in earth work in hilly area all height and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specification for rural Road, August, 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions or as directed by the Engineer-IN-Charge for smooth riding. The recovery of useful stone that is 103.29 cum. In all cases, @ Rupees 300/- cum. shall be effected on pro rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2700.96	cum	178.05	Rupees One Hundred seventy eight and Five paise only	Per cubic metre	480906.00
						<b>Total</b>	<b>480906.00</b>

Draft Schedule of Quantity dully Approved for Rs 4,80,906/- only (Rupies four lakhs eighty thousand nine hundred six and zero paise) for the year 2025-2026 and entered at DNIT register Sr No.

  
**Executive Engineer**  
 Arki Division (B&R)  
 HP. PWD. Arki.

SCHEDULE OF QUANTITY						Estimated Cost: -Rs485119/- only
Name of Work: C/O Soria Bahra road km 0/00 to 2/00 {SH:- C/O R/Wall at Rds 0/570 to 0/585 and 0/710 to 0/725 } DMFT						Earnest Money :-Rs9800/-Only
						Time :-One Month
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	61.80	171.40	Rupees one hundred seventy one and paise forty only	P.Cum.	10593
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	98.85	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	434011
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	22.50	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	27074
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	49.01	274.25	Rupees two hundred seventy four and paise twenty five only	Rmt	13441
					Total	485119

Quoted Rate Percentage in Figure  
Quoted Rate Percentage in Words

  
Executive Engineer  
Arki Division HPPWD  
Arki


**SCHEDULE OF QUANTITY**

Name of work: -Construction of playground for Govt Senior secondary School Bawasi Tehsil Arki Distt Solan Himachal Pradesh.(Sh:- Providing and Laying stone Soling and cement concrete 1:4:8 in grond etc.) under DMFT for 2025-2026

Estimated Cost:  
1,04,533.00  
Earnest money: 2,500.00  
Time: One month

Sr.N	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	21.75	cum	171.40	Rupees One hundred seventy one and paise forty only	Per cubic metre	3728.00
2	Providing, laying, stone soling properly hand packed filling interstics with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials mooram or earth etc. complete as per HP,PWD specification 150mm spread thickness.(finished work including materials and Labour)including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge.	10.88	Cum	1300.10	Rupies One thousand three hundred and Paise ten only	Per cubic metre	14145.00
3	Providing and laying Plain cement concrete 1:4:8(one cement isto Four sand isto Eight graded crushed stone aggregate 25 milimetre( Twenty five milimetre) nominal size for plain /reinforced concrete in open foundation and plinths or similar works complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer In Charge	7.25	Cum	4955.20	Rupies Four thousand Nine hundred fifty five and Paise twenty only	Per cubic metre	35925.00
4	Providing and laying in position specified grade of cement concrete excluding the cost of centering and shuttering :- all work upto plinth level 1:2:4 (one cement : two sand : four graded stone aggregate 20mm twenty milimetre nominal size) and curing complete including the cost of form work with steel plates and fixed by bitumen drums in dressiest as per drawing and HP.PWD specifications as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts	7.25	Cum	6376.30	Rupees Six thousand three hundred seventy six and paise thirty only	Per cubic metre	46228.00
5	Providing and fixing glass strips in joints of terrazo/cement concrete floorings etc.complete and HP.PWD specifications as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts	79.00	Rmt	57.05	Rupees Fifty seven and paise five only	Per running metre	4507.00
						<b>Total</b>	<b>104533.00</b>
<p>Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted. (ii) Cement will be taken from the nearest civil supply Depot if available.</p>							

Quated rate Percentage in figures  
Quated rates Percentage in words

  
 Executive Engineer  
 Arki Division (B&R)  
 HP, PWD. Arki.

**Name of work: -Construction of Link Road Badehan to Ghat km 0/00 to 1/500.(Sh:- Construction of Retaining wall at Rd end portion of road) Under DMFT for 2025-2026**

**SCHEDULE OF QUANTITY**

Estimated Cost:  
4,99,730.00  
Earnest money: 10,000.00  
Time: One month

Sr.N	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	54.38	cum	171.40	Rupees One hundred seventy one and paise forty only	Per cubic metre	9321.00
2	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre( forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	102.00	Cum	4390.60	Rupies Four thousand three hundred ninety four and Paise sixty only	Per cubic metre	447841.00
3	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred )milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	64.70	Rmt	274.25	Rupees Two hundred seventy four and paise twenty five only	Per running metre	17744.00
4	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	20.63	Cum	1203.30	Rupees One thousand two hundred three and paise thirty only	Per cubic metre	24824.00
Total						Total	499730.00
Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted. (ii) Cement will be taken from the nearest civil supply Depot if available.							

Quated rate Percentage in figures  
Quated rates Percentage in words

Executive Engineer  
Arki Division (B&R)  
HR. PWD. Arki.

**SCHEDULE OF QUANTITY**

Name of Work:-Restoration of rain Damages on Talab (Rao Khad) Behli road road km 0/00 to 2/170.					Estimated Cost :- Rs 4.89,026.00		
.(Sh :Construction-of Pcc Retaining wall at Rd 1/425 to 1/460)Under PDNA 2023. Balance work there of					Earnest money :- Rs 10,000.00		
					Time: one months		
Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	2	3			6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	69.83	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	11969.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre( forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	105.00	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	461013.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred )milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	58.50	cum	274.25	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	16044.00
Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.						<b>Total</b>	<b>489026.00</b>

Quoted Rate Percentage in Figures  
Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division (B&R)  
 HP. PWD. Arki.