



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **10-04-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 09-04-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 09-04-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Darang Ghanetta Jhareth road (SH:- C/O U-shape drain with Edge Wall at RD. 2/950 to 2/978)	97,868/-	2000/-	Three Month	350/-
2	Restoration of rain damages on Various roads under HPPWD., Sub Division Dheera (SH:- C/O Unlined drain and maintenance of earthen shoulder on various roads)	99,120/-	2000/-	Three month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna


On behalf of Governor of Himachal Pradesh
Dated:- 2-4-2026

No. PWD/BWD/TA/NIT/2025-26/

23-32

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5thCircle, HPPWD.,Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26- 23-32 dated 2-4 -2026.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Name of Work :- Restoration of rain damages on Darang Ghanetta Jhareth road. (SH:- C/o U-shape drain with Edge wall at RD 2/950 to 2/978).

Estimated Cost :-Rs. 97,868/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	6300.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.64	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	87318.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17	250.00	Rupees Two Hundred Fifty Only	Each	4250.00
Total :-						97868.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity


Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Dheera. (SH:- C/o Un-lined drain and Maintenance of earthen shoulder on various roads)

Estimated Cost :-Rs. 99,120/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre) in soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 2 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 1902. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1190.00	40.00	Rupees Forty Only	Per Running metre	47600.00
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GDT and any other taxes imposed by the government	1472.00	35.00	Rupees Thirty Five Only	Per Square metre	51520.00
Total :-						99120.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna