

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2026-27- 25838-872 Dated:- 31-03-2026

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025-300858 dated 09-10-2025 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhama
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhama
Ph. 0177-2790534



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhama on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **10.04.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **09.04.2026 up to 5.00 PM** and the application for issue of tender form shall be received on **09.04.2026 up to 3:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhama must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	A/R & M/O rest house building at Sunni Distt. Shimla H.P.(SH: C/O Porch at Rest house Sunni). (Steel work thereof).	98626 /-	2000/-	One Month	Rs.350/-
2	A/R & M/O rest house building at Sunni Distt. Shimla H.P.(SH: C/O Porch at Rest house Sunni). (Roofing work thereof).	99840 /-	2000/-	One Month	Rs.350/-
3	R/R damages on Balag Ghatti to Bawin road Km. 0/00 to 1/200 (SH: C/O R/Wall at Rd. 1/184 to 1/187.80).	99232/-	2000/-	One Month	Rs.350/-
4	C/O proposed link road from Shalaghat to Jamlog Km. 0/00 to 1/300 (SH: Preparation of FRA case in all respect).	70000 /-	1500/-	One Month	Rs.350/-
5	R/R damages on Khel Ka Chaura Gainchari road Km. 0/00 to 0/550 (SH: C/O B-Wall at Rd. 0/490 to 0/500).	99927 /-	2000/-	One Month	Rs.350/-
6	R/R damages on Pakki Bouri Shakrah Sedan road Km. 0/00 to 5/700 (SH: C/O R-Wall at Rd. 3/360 to 3/370).	99717 /-	2000/-	One Month	Rs.350/-
7	R/R damages on Pakki Bouri Shakrah Sedan road Km. 0/00 to 5/700 (SH: C/O R-Wall at Rd. 3/670 to 3/680).	99632 /-	2000/-	One Month	Rs.350/-
8	R/R damages on Bhajyar Devidhar road Km. 0/00 to 2/165 (SH: C/O B-Wall at Rd. 1/260 to 1/268).	99647 /-	2000/-	One Month	Rs.350/-

9	R/R damages on Bhajyar Devidhar road Km. 0/00 to 2/165 (SH: C/O B-Wall at Rd. 1/270 to 1/278).	99664 /-	2000/-	One Month	Rs.350/-
10	A/R & M/O on Shoghi Mehli road Km. 0/00 to 12/375 (SH: P/F of high intensity retro reflective all weather multi colour taps/sheet of approved shade in black spots in various Rds.) Job No.1.	99450 /-	2000/-	One Month	Rs.350/-
11	Special repair to Transgender & Disabled Toilet at District Court Complex Chakkar Shimla, Distt. Shimla H.P.	56333 /-	1200/-	One Month	Rs.350/-
12	R/R damages on various roads under Totu sub division (SH: Hiring of JCB machine for clearance of land slide & dressing of berms etc.).	98550 /-	2000/-	One Month	Rs.350/-
13	R/R damages on (i) Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (ii) Shyalmu Badog road Km. 0/00 to 1/500 (SH: Removal of slips and C/O unlined drain at various Rds.).	99904 /-	2000/-	One Month	Rs.350/-
14	R/R damages on Shimloh Mandhorghat road Km. 0/00 to 6/00 (SH: C/O B/Wall at Rd. 5/600 to 5/605.70).	99594 /-	2000/-	One Month	Rs.350/-
15	R/R damages on Hiranagar Dhamoon road Km. 0/00 to 8/00 (SH: C/O R/Wall at Rd. 6/429 to 6/433).	99603 /-	2000/-	One Month	Rs.350/-
16	R/R damages on Devnagar Moolbari road Km. 0/00 to 1/200 (SH: C/O edge Wall at Rd. 0/120 to 0/136).	86590 /-	2000/-	One Month	Rs.350/-
17	R/R damages on Ghanahatti Bhajol road Km. 0/00 to 14/00 (SH: C/O R/Wall at Rd. 1/797 to 1/803.60).	86085/-	2000/-	One Month	Rs.350/-
18	R/R damages on Reodhar Piplidhar road Km. 0/00 to 2/600 (SH: C/O R/Wall at Rd. 2/270 to 2/278).	99845/-	2000/-	One Month	Rs.350/-
19	R/R damages on Reodhar Piplidhar road Km. 0/00 to 2/600 (SH: C/O R/Wall at Rd. 2/282 to 2/290).	99809/-	2000/-	One Month	Rs.350/-
20	A/R & M/O Phayal Dawanti via Shamleeg road Km. 0/00 to 4/135 (SH: C/O R/Wall at Rd. 4/004.50 to 4/010).	97702/-	2000/-	One Month	Rs.350/-
21	R/R damages on Banuti Pahal road Km. 0/00 to 17/105 (SH: C/O B/Wall at Rd. 14/090 to 14/097.70).	99307/-	2000/-	One Month	Rs.350/-
22	A/R & M/O Shimla Mandi road Km. 22/000 to 33/200 (SH: Trimming of grass, Maintenance of earthen shoulders, Maintenance of drain, Maintenance of culverts & White washing in Km. 26/500 to 28/000).	99576/-	2000/-	One Month	Rs.350/-
23	A/R & M/O Shimla Manoi road Km. 22/000 to 33/200 (SH: Trimming of grass, Maintenance of earthen shoulders, Maintenance of drain, Maintenance of culverts & White washing in Km. 25/000 to 26/500).	99979/-	2000/-	One Month	Rs.350/-
24	R/R damages on Balag Ghatti to Bawin road Km. 0/00 to 1/200 (SH: C/O R/Wall at Rd. 1/180 to 1/183.50).	91949/-	2000/-	One Month	Rs.350/-
25	R/R damages on Shimloh Mandhorghat Nagar via Dargi road Km. 0/00 to 2/825 (SH: C/O R/Wall at Rd. 2/375 to 2/380).	98618/-	2000/-	One Month	Rs.350/-
26	R/R damages on link road Dishu Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 2/740 to 2/744).	99199/-	2000/-	One Month	Rs.350/-
27	R/R damages on Shimloh Mandhorghat Nagar via Dargi road Km. 0/00 to 2/825 (SH: C/O R/Wall at Rd. 1/770 to 1/775.50).	99454/-	2000/-	One Month	Rs.350/-
28	C/O School play Ground in Govt. Sr. Sec. School Bychari Distt. Shimla (SH: P/L Duty interlock paver-balance work) Deposit work.	99392 /-	2000/-	One Month	Rs.350/-
29	P/R damages on Dargi Macharyana Judloo Km. 0/00 to 11/900 (SH: C/O B/Wall at Rd. 11/725 to 11/733).	99787/-	2000/-	One Month	Rs.350/-
30	R/R damages on Balag Ghatti to Bawin road Km. 0/00 to 1/200 (SH: C/O R/Wall at Rd. 1/188 to 1/190.50).	64917/-	1000/-	One Month	Rs.350/-

31	R/R damages on link road Dishti Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 2/735 to 2/739).	99199/-	2000/-	One Month	Rs.350/-
32	R/R damages on Dargi Macharyana Judloo Km. 0/00 to 11/900 (SH: C/O B/Wall at Rd. 11/735 to 11/743).	99787/-	2000/-	One Month	Rs.350/-
33	R/R damages on Shimloh Mandhorghat road Km. 0/00 to 6/00 (SH: C/O B/Wall at Rd. 5/606 to 5/611.70).	99594 /-	2000/-	One Month	Rs.350/-
34	R/R damages on Shimloh Mandhorghat Nagar via Dargi road Km. 0/00 to 2/825 (SH: C/O R/Wall at Rd. 1/750 to 1/754.20).	99449/-	2000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhani

Certificate

Certified that the tenders called vide this notice inviting tender for 34 (Thirty four) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhani.

Schedule Of Quantity

Name Of Work :- A/R & M/O Rest House building at Sunni Distt. Shimla (HP) (SH:- Construction of Porch at Rest House Sunni) *(steel work thereof)*

Estimated Cost:- 98,626.00

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
				In figures	In words		
1	2						
1	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carnage of material in all leads and lifts as per direction of the Engineer in charge.	798.72	Kg	123.48	Rupees One Hundred Twenty Three and Paise Forty Eight Only	Per Kilogram	98626
Total Rs.							98626
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi. *[Signature]*



Name Of Work :- A/R & M/O Rest House building at Sunni Distt. Shimla (HP) (SH:- Construction)		Estimated Cost:- 99,840.00		Earnest Money:- 2000.00		Time:- One Months.	
S.No	Description of Work	No. of Qty.	Rate	In figures	In words	Unit	Amount
1	Providing and fixing polycarbonatd tranparent sheet 5mm thick in roofing with galvanised J or L hooks bolts and nuts with G.I Limpe and bitumen rubber washer complete with all accesories as required as per direction of Engineer in Charge.	41.60	Sqm	2400.00	Rupees Two Thousand Four Hundred Only	Per Square metre	99840
1	2	3	4	5	6	7	8
Total Rs.						99840	
Amount Quoted by the Contractor in Percentage						99840	
Note :- All the material will pro cured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami. *HPD*

Schedule Of Quantity
Name Of Work :- A/R & M/O Rest House building at Sunni Distt. Shimla (HP) (SH:- Construction)
Job No. (Roofing work sheet)

Name of Work - Restoration of rain damages on Balag Chatti to Bawin Road Km. 0/00 to 1/200 (Site Construction of R-wall at Rd. 1/154 to 1/157.80)		Estimated Cost - Rs 99232 (-) only Earnest Money - Rs. 2000 (-) only		Time - One Month	
S. No.	Sub head and items of work	Qty.	Rate		Amount
			Figures	Unit	
1	Excavation in soil in hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other detritious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	4.56	Cum	Rupees Two Hundred Thirty Three and Paise Forty Only	1254.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads and lifts, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	6.54	Cum	Rupees Three Hundred Fifty Six and Paise Fifty Only	2438.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal max). Including cartage of material upto all leads and lifts as per the directions of Engineer-in-Charge	20.10	Cum	Rupees Four Thousand Six Hundred Only	52450.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material. Including cartage of material within all leads upto leads as per the direction of Engineer-in-Charge	2.43	Cum	Rupees Eight Hundred Forty One and Paise	2046.00
5	Providing weapholes in brick masonry / stone masonry plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(h) towards drawing face complete as per drawing and technical specification. Including cartage of material upto all leads and lifts as per the direction of Engineer -in-Charge	7.20	Runl.	Rupees One Hundred Seventy Only	1224.00
0				Total:	58222.00

Rs.

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
H.P.W.D., Dharam

SCHEDULE OF QUANTITY

Name of Work: - Construction of Proposed link road from Shalaghat to Jamlog Km. 0/00 to 1/300 under Dhami Sub Division HPPWD (SH: -Preperation of FRA case in all respect)

Estimated Cost: - Rs 70000/- only

Earnest Money : - Rs. 1500/-only

Time: - One Month

Rate in Unit Amount

figures In words 6 7

4 5 Rupees Seventy Thousand Only Each 70000.00

1 No. 70000.00

1 Preparation of Geo refrence digital map and Collecting the data from proposed site including field visits Preparation of Kml file. Geo coordinates along with making of Habitations to be benefited by construction of project and dumping area of proposed site. Making The alignment in soft copy and submission in hard copy.Preperation of Forest case(FRA) proposed road in Dhami Sub Division.Preperation of Folders complete in all respect and submit to the department as per the direction of Engineer- in- charge.

Total: 70000.00

Rs.

Amount Quoted by the Contractor in precentage

EXECUTIVE ENGINEER
SHIMLA RURAL DIVISION
HPPWD, DHAMI

SCHEDULE OF QUANTITY				Estimated Cost: - Rs 99927 /- only		
Name of Work:- Restoration of rain damages on Khel Ka Chaura Gainchari Road Km. 0/00 to 0/550 (Sh: C/o Breast wall at Rd. 0/490 to 0/500)				Earnest Money : - Rs. 2000 /-only		
				Time: - One Month		
S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	5.96 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1391.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.57 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1986.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.59 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94714.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	10.80 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1836.00
0					Total:	99927.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama



SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Pakki Bawari Shakrah Sedan Road Km. 0/00 to 5/100 (Sh: C/o Retaining wall at Rd. 3/360 to 3/370)

Estimated Cost: - Rs 99717 /- only
Earnest Money : - Rs. 2000 /- only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	5.89	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1375.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.50	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1961.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.33	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93518.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.18	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	993.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.00	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1870.00
0					Total:	99717.00

Amount Quoted by the Contractor in Percentage Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWB, Dhamsi

Name of Work:- Restoration of rain damages on Pakki Bawari Shakrah Sedan Road Km. 0/00 to 5/740 (Sh: C/o Retaining wall at Rd. 3/670 to 3/680)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 99632 /- only
 Earnest Money - Rs 2000 /-only
 Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Unit	Amount	
		3	4	figures	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	5.89	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1375.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	5.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1961.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.33	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93518.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.18	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	993.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	10.50	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1785.00
0						Total:	99632.00

Amount Quoted by the Contractor in Percentage Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhami

Name of Work:- Restoration of rain damages on Bhajyar Devidhar Road Km. 0/00 to 2/165 (Sh: Construction of B-wall at Rd. 1/260 to 1/268)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 99647 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
		3	4	5	6		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	5.93	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1384.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.53	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1971.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.46	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94116.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	12.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2176.00
0						Total:	99647.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain damages on Bhajiyar Devidhar Road Km. 0/00 to 2/165 (Sh: Construction of B-wall at Estimated Cost - Rs 99664 /- only Earnest Money - Rs 2000 /-only Rd. 1/270 to 1/278)

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	figures		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	5.93	4	5	Per cubic metre	1384.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	5.53	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1571.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.46	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	94116.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	12.90	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2193.00
0					Total:	99664.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.


Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi


Name of Work: - Annual Repair & Maintenance on Shoghi Mehli Road Km. 0/000 to 12/375 (SH:- Providing and fixing of high intensity retro reflective all weather multi colour taps / sheet of approved shade in black spots in various RDe.) Job No. 1

SCHEDULE OF QUANTITY

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Providing and fixing of high intensity reflective all weather proof multi colour taps/ sheet size 300 mm x 450 mm of approved shade and quality, fixed over on front face of longitudinal channel rail of W-Metal beam crash barrier with mechanical means with high visibility from long distance in fog prone area, black spot point and narrow curve etc. including rubbing and fixing the sheet etc. as per HPPWD specification including carriage of materials by all modes of transportation in all leads and lifts, complete in all respect and as per direction of the Engineer-in-charge.	117.00	850.00	Rupees Eight Hundred Fifty Only	Per Running Meter	99450.00
0						
Total:						99450.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.


 Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi

Schedule Of Quantity
Name of Work: Special Repair to Transgender & Disabled Toilet at District court Complex
Chakker Shimla, Distt -Shimla H.P

Estimated Cost:- 56,333.00
 Earnest Money:- 1200.00
 Time:- One Month

Sr. No.	Description of work	No. of Qty.		Rate		Unit
				In figures	In words	
1	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	86.94	Sqm	₹ 79.00	Rupees Seventy Nine Only	₹ 6,868.00
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.90.1 Old work (one or more coats)	86.94	Sqm	₹ 73.00	Rupees Seventy Three Only	₹ 6,347.00
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : 13.99.1 One or more coats on old work	22.18	Sqm	₹ 76.00	Rupees Seventy Six Only	₹ 1,685.00
4	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete : White solid plastic seat with lid	2.00	each	₹ 591.00	Rupees Five Hundred Ninety One Only	₹ 1,182.00
5	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm or 340x410x265 mm sizes respectively.	1.00	each	₹ 1,880.00	Rupees Seventy Six Only	₹ 1,880.00
6	Providing and fixing 8 mm dia C.P. / S.S. Jet 8 with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	2.00	each	₹ 1,000.00	Rupees One Thousand Only	₹ 2,000.00
7	Providing and fixing C.P. Brass Jet with upto 1.2 metre long with S.S.flexible pipe & wall hook to European type W.C. of quality and make as approved by Engineer - in - charge	2.00	each	₹ 1,277.00	Rupees One Thousand Two Hundred Seventy Seven Only	₹ 2,554.00

8	Providing and fixing C.P. brass toilet paper holder including the cost of fittings complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	2.00	each	₹ 1,037.00	Rupees One Thousand Thirty Seven Only	₹ 2,074.00
9	Providing and fixing white vitreous china wash basin size 55x40x83cm No. 10008 VIKING with Pedestal No. 11003 of Hindware including making all connections including the cost of all fittings.	2.00	each	₹ 4,762.00	Rupees Four Thousand Seven Hundred sixty Two Only	₹ 9,524.00
10	Providing and fixing P.V.C. waste pipe for sink or wash basin & urinal basin including P.V.C. waste fittings complete. Semi rigid pipe 32 mm dia	1.00	each	₹ 264.00	Rupees Two Hundred Sixty Four Only	₹ 264.00
11	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.:-15 mm nominal bore with 45cm length.	4.00	each	₹ 259.00	Rupees Two Hundred Fifty Nine Only	₹ 1,036.00
12	Providing & fixing 125mm dia C.P/ S.S grating for floor of approved quality and colour. Square type including carriage of material within all leads and lifts.	3.00	each	₹ 420.00	Rupees Four Hundred Twenty Only	₹ 1,260.00
13	Providing and fixing 15mm dia C.P. brass Angle Stop Cock with flange of JAL Cat. No. 3548 (heavy duty ISI marked IS:8931 & 8934) including carriage of materials within all leads and lifts.	5.00	each	₹ 950.00	Rupees Nine Hundred Fifty Only	₹ 4,750.00
14	Providing and fixing 15mm dia CP brass pillar tap with capstan head (heavy duty ISI marked IS:8931 & 8934) including carriage of materials within all leads and lifts.	2.00	each	₹ 734.00	Rupees Seven Hundred Thirt Four Only	₹ 1,468.00
15	Providing and fixing 15 mm dia nominal bore G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. - Exposed on wall 15 mm dia nominal bore	3.00	Rmt	₹ 355.00	Rupees Three Hundred Fifty Five Only	₹ 1,065.00
16	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with :	1.59	Sqm	₹ 111.00	Rupees One Hundred Eleven Only	₹ 176.00

17	Providing & fixing Sanitary Automatic Sanitary Napkin Vending Machine	2.00	each	₹ 6,100.00	Rupees Six Thousand One Hundred Only	₹	12,200.00
						₹	56,333.00

Executive Engineer
 Shimla Rural Division
 HPPWD Dhami.

Name of Work:- Restoration of Rain damages on various roads under Totu Sub Division (Sh: Hiring of JCB machine for clearance of Land Slide & dressing of berms etc.)

Schedule of Quantity

Estimated Cost - Rs 98550 /- only
 Earnest Money - Rs 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	
1	Hiring of JCB Machine for removal of Malwa/debris and Dressing of Berms along road with Minimum capacity 45 cum per hour minimum six hours per day including pay of operator, P O L charges, maintenance of any minor or major accidents and other damages to private and Govt. property occur during working hour is whole responsibility of contractor disposal of unserviceable materials and stacking of serviceable material along road side in all leads and lift and as per the direction by the Engineer in charge	90.00 Cum	1095.00	Rupees One Thousand Ninety Five Only	Per cubic metre	98550.00
0					Total:	98550.00

Amount Quoted by the Contractor in Percentage Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD,Dhami

Name of Work :- R/R damages on (i) Bangora Kallhatti Bastigunana road km . 0/00 to 11/675 (ii) Shyalmu Badog road km. 0/00 to 1/500 (SH: Removal of slip and construction of unlined drain at Various Rds)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 99904 /- only
 Earnest Money - Rs 2000 /-only
 Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Unit	Amount
		3	4	figures	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all leads and lifts as per technical specification 302 3.5 and 1611 and as per the direction of in charge	256.88	Cum	95.00	Rupees Ninety Five Only	24404.00
2	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	5.00	No	1600.00	Rupees One Thousand Six Hundred Only	8000.00
3	Construction of unlines surface drains of average cross-sectional area 0.40 Sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment with a lift upto 3m and lead Of 50m (average lead 25m) as per technical specification clause 307.	1350.00	Rmt	50.00	Rupees Fifty Only	67500.00
Total:						99904.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Rs.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhama

Schedule Of Quantity						Estimated Cost:- 99,594.00	
Name of Work :- R/R damages on Shimloh Mandhorghat road km. 0/00 to 6/00 (SH:- Construction of B/wall at Rd 5/600 to 5/605.70)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	5.59	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1305
2	Earth work in excavation for structures as per drawing and technical specification clauses 305. 1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	4.90	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1747
3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight crushed stone aggregate 20mm (Twenty millimeter) nominal size) mechanical mixed and vibrated including curing complete excluding cost of form work in foundation and plinth and as per HP. PWD. specifications of 1990 volume-I. including carriage of materials, labour, tool and plants through all modes of transportation with in all leads and lifts, and as per direction of the Engineer-in-charge.	20.35	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93610
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	17.25	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	2933
Total Rs							99594
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi.

Name of Work:- Restoration of rain damages on Hiranagar Dhamoon Road Km. 0/00 to 8/00 (Sh: Construction of Retaining wall at Rd. 6/429 to 6/433)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 99603 /- only
 Earnest Money: - Rs 2000 /-only
 Time - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical MORD specification directed by Engineer-in Charge.	4.75	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	1109.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.54	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	1975.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.05	Cum	4600.00	Rupees Four Thousand Six Hundred Only	92230.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	3.56	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	2997.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.60	Rmt.	170.00	Rupees One Hundred Seventy Only	1292.00
0						
Total:						99603.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhami

Name of Work:- Restoration of Rain damages on Devnagar Moolbari Road In Km. 0/00 to 1/200 (Sh: C/o Edge wall at Rd. 0/120 to 0/136)

Schedule of Quantity

Estimated Cost - Rs 86590/- only
 Earnest Money - Rs 2000/- only
 Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	9.60 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3422.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.08 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	83168.00
0					Total:	86590.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhani



Name of Work:- Restoration of Rain damages on Ghanahatti Bhajol Road in Km. 0/00 to 14/00 (Sh: C/o R-wall at 1/797 to 1/803.60)

Schedule of Quantity

Estimated Cost - Rs 86085 /- only
 Earnest Money - Rs 2000 /- only
 Time - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
		3	4	5	6		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	3.56	Cum	233.40		Per cubic metre	831.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	6.14	Cum	356.50		Per cubic metre	2189.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	17.16	Cum	4600.00		Per cubic metre	78936.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8. (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.37	Cum	841.80		Per cubic metre	2837.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.60	Rmt.	170.00		Per Running Metre	1292.00
0							Total: 86085.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhamsi



Name of Work:- Restoration of rain damages on Reodhar Piplidhar Road Km. 0/00 to 2/600 Sh: Construction of R-wall at Rd. 2/270 to 2/278)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 99845 /- only
Earnest Money :- Rs. 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	5.89	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 1375.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 1961.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.33	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 93518.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.18	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 993.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.10	Rmt.	180.00	Rupees One Hundred Eighty Only	Per Running Metre 1998.00
0						Total: 99845.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Reodhar Pipildhar Road Km. 0/00 to 2/600 Sh: Construction of R-wall at Rd. 2/282 to 2/290)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 99809 /- only
 Earnest Money - Rs 2000 /- only
 Time - One Month

S. No.	Sub head and Items of work	Qty.		Rate figures		Unit	Amount
		3	4	5	6		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	5.89	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1375.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1961.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.33	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93518.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.18	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	993.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	10.90	Rmt.	180.00	Rupees One Hundred Eighty Only	Per Running Metre	1962.00
0						Total:	99809.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhama

Schedule Of Quantity

Estimated Cost:- 97,702.00
Earnest Money:- 2,000.00
Time:- One Months.

Name Of Work :- A/R & M/O Phayal Dawanty via Shamleeg road km 0/00 to 4/135 (C/O R/wall at Rd 4/004.5 to 4/010)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	8.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	1914
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50mm dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	1.21	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	431
3	Providing and Laying concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded crushed stone Aggregate 20 mm nominal mix)	19.47	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	93456
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	10.00	No	190.00	Rupees One Hundred Ninety Only	Each	1900
Total Rs.							97702
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP,PWD, Dhamsi

Name of Work:- Restoration of Rain damages on Banuti Pahal Road via Nehwat in Km. 0/000 to 17/105 (Sh: Construction of Breast wall at Rd. 14/090 to 14/097.70)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 99307 /- only
Earnest Money :- Rs. 2000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	4.16 Cum	233 40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	971 00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	9.55 Cum	356 50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3405 00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.02 Cum	4600 00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92092 00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	16.70 Rmt.	170 00	Rupees One Hundred Seventy Only	Per Running Metre	2839 00
0					Total:	99307.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama



SCHEDULE OF QUANTITY
 NAME OF WORK:- A/R & M/O on Shimla Mandi Road km 22/000 to 33/200 (SH:- Trimming of grass , Maintenance of Eathen Shoulders , Maintenance of drain ,Maintenance of Culverts & white Washing in Km 26/500 to 28/000

Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Amount.	Estimated cost:-
							99,576.00
							Earnest money:-
							2000.00
							Time:-
							One Month
		Qty.	Unit	Rate in figure.	Rate in word.	Amount.	
1	Trimming of grass and weeds from the shoulders/birms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3000	Per Sqm	4.50	Rupees Four and Paise Fifty Only	13500.00	
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3045	Per Sqm	24.95	Rupees Twenty Four and Paise Ninety Five Only	75973.00	
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907, including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	1000	Rmt	4.50	Rupees Four and Paise Fifty Only	4500.00	
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only	5250.00	
5	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	10.08	Sqm	35.00	Rupees Thirty Five Only	353.00	
						Total:-	99576.00


Executive Engineer
 Shimla Rural Division,
 HP,PWD, Dhamsi



SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O on Shimla Mandi Road km 22/000 to 33/200 (SH:- Trimming of grass , Maintenance of Eathen Shoulders , Maintenance of drain ,Maintenance of Culverts & white Washing in Km 25/000 to 26/500

Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Estimated cost:-
						Amount.
						99,979.00
						2000.00
						One Month
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3000	Per Sqm	4.50	Rupees Four and Paise Fifty Only	13500.00
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3150	Per Sqm	24.95	Rupees Twenty Four and Paise Ninety Five Only	78593.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	900	Rmt	4.50	Rupees Four and Paise Fifty Only	4050.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only	3500.00
5	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	9.6	sqm	35.00	Rupees Thirty Five Only	336.00
					Total:-	99979.00


 Executive Engineer,
 Shimla Rural Division,
 HP,PWD, Dhamsi

Name of Work:- Restoration of rain damages on Balag Ghatti to Bawin Road Km. 0/00 to 1/200 (Sh: Construction of R-wall at Rd. 1/180 to 1/183.50)

SCHEDULE OF QUANTITY

Estimated Cost : - Rs 91949 /- only
Earnest Money : - Rs. 2000 /-only
Time : - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	4.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 980.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	6.30	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 2246.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.52	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 85192.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	2.74	Cum	841.80	Rupees Eight Hundred Forty One and Paise	Per cubic metre 2307.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.20	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 1224.00
0						Total: 91949.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami



Name of Work:- Restoration of rain damages on Shimloh Mandhorghat Nagar via Dargi Road Km. 0/000 to 2/825 (Sh: Construction of R- wall at Rd. 2/375 to 2/380)

Schedule of Quantity

Estimated Cost - Rs 98618 /- only
Earnest Money - Rs 2000 /- only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	2.58 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	602.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	9.52 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3394.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.87 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91402.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.21 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1860.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	8.00 Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1360.00
0					Total:	98618.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama

Estimated Cost:- 99,199.00
Earnest Money:- 2,000.00
Time:- One Months.

Schedule Of Quantity

Name Of Work :- R/R damages on link raod Dishiti km. 0/00 to 3/00 (SH:-

Construction of retaining wall at Rd. 2/735 to 2/739)

S.No	Description of Work	No. of Qty.	Rate	In figures		Unit	Amount
				In figures	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	2.68	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	626
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50mm dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORd specification directed by Engineer-in-Charge.	4.16	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	1483
3	Providing and Laying concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded crushed stone Aggregate 20 mm nominal mix)	19.62	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	90252
4	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	5.76	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	4849
5	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	11.70	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	1989
Total Rs.							99199
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhami.

Name of Work:- Restoration of rain damages on Shimloh Mandhorghat Nagar via Dargi Road Km. 0/000 to 2/825 (Sh: Construction of R-
 Schedule of Quantity
 wall at Rd. 1/770 to 1/775.50)
 Estimated Cost - Rs 99454 /- only
 Earnest Money :- Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	figures		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORd specification directed by Engineer-in-Charge.	2.81	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	656.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORd specification directed by Engineer-in-Charge.	5.61	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	2000.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix), including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.69	Cum	4600.00	Rupees Four Thousand Six Hundred Only	90574.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (1) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.05	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	5093.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of (1v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	6.65	Rmt.	170.00	Rupees One Hundred Seventy Running Metre	1131.00
0	Total:					99454.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive-Engineer
 Shmla Rural Division
 HPPWD, Dhami

HIMACHAL PRADESH

SCHEDULE OF QUANTITY					Estimated Cost: - Rs 99392 /- only		
Name of work :- Construction of School Play Ground in Govt Sr. Sec. School <i>Bychan</i> (SH:- Providing & laying Duty interlock paver-balance work) Deposit Work					Earnest Money : - Rs. 2000 /-only		
					Time: - One Month		
S. No.	Sub head and items of work	Qty.		Rate	Unit	Amount	
		3	4	5	6	7	
				figures			
1.00	Providing and laying heavy duty cement concrete inter locking paver blocks vibro compacting upto M-50 grade i/c border or kurb grey or coloured subbase of concrete with 25 mm thick average thickness of cement mortar 1:4 laid over and jointed with cement slurry mixed with pigment to match the shade of blocks i/c curring rubbing and polishing complete subbase concrete floor to be paid for 60 mm thick inter locking blocks. (NTC make or its equivalent) including the carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	62.12	Sqm	1600.00	Rupees One Thousand Six Hundred Only	Per Square Metre	99392.00
0					Total:		99392.00

Amount Quoted by the Contractor in Percentage	Rs.	
---	-----	--

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami



Schedule of Quantity							Estimated Cost: - Rs 99787 /- only	
Name of Work:- Restoration of rain damages on Dargi Macharyana Judloo Road Km. 0/00 to 11/900 (Sh: Construction of Breast wall at Rd. 11/735 to 11/743)							Earnest Money : - Rs. 2000 /-only	
							Time - One Month	
S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount	
				4	5			
1	2	3	4	5	6	7		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	3.08	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	719.00	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	4.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1604.00	
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.70	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	95220.00	
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v).20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	13.20	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2244.00	
0						Total:	99787.00	

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami



Name of Work:- Restoration of rain damages on Balag Ghatti to Bawin Road Km. 0/00 to 1/200 (Sh: Construction of R-wall at Rd. 1/188 to 1/190.50).

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 64917 /- only
Earnest Money : - Rs. 1000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	figures		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	3.00 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	700.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts directed by Engineer-in-Charge.	4.50 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1604.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	13.23 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	60858.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.60 Cum	841.80	Rupees Eight Hundred Forty One and Paise	Per cubic metre	1347.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	2.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	408.00
0					Total:	64917.00

Amount Quoted by the Contractor in Percentage	Rs.	
---	-----	--

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami



Schedule Of Quantity

Estimated Cost:- 99,199.00

**Name Of Work :- R/R damages on link road Dishti km. 0/00 to 3/00 (SH:-
Cosntruction of retaining wall at Rd. 2/740 to 2/744)**

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2			5	6	7	8	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	2.68	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	626	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50mm dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	4.16	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	1483	
3	Providing and Laying concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded crushed stone Aggregate 20 mm nominal mix)	19.62	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	90252	
4	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	5.76	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	4849	
5	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	11.70	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	1989	
Total Rs.								99199
Amount Quoted by the Contractor in Percentage								
Note :- All the material will procured by the contractor him self								

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.



Name of Work:- Restoration of rain damages on Dargi Macharyana Judloo Road Km. 0/00 to 11/900 (Sh: Construction of Breast wall at Rd. 11/725 to 11/733)				Schedule of Quantity		Estimated Cost: - Rs 99787 /- only	
				Earnest Money :- Rs. 2000 /-only		Time :- One Month	
S No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount		
1	2	3	4	5	6	7	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	3.08 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	719.00	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	4.50 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1604.00	
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.70 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	95220.00	
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge	13.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2244.00	
0					Total:	99787.00	

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami



Schedule Of Quantity


**Name of Work :- R/R damages on Shimloh Mandhorghat road km. 0/00 to 6/00
(SH:- Construction of B/wall at Rd 5/606 to 5/611.70)**

Estimated Cost:- 99,594.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	5.59	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1305
2	Earth work in excavation for structures as per drawing and technical specification clauses 305. 1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	4.90	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1747
3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight crushed stone aggregate 20mm (Twenty millimeter) nominal size) mechanical mixed and vibrated including curing complete excluding cost of form work in foundation and plinth and as per HP. PWD. specifications of 1990 volume-I. including carriage of materials, labour, tool and plants through all modes of transportation with in all leads and lifts, and as per direction of the Engineer-in-charge.	20.35	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93610
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	17.25	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	2933
Total Rs							99594
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							


 Executive Engineer,
 Shimla Rural Division,
 HP,PWD, Dhami.



Name of Work:- Restoration of rain damages on Shimloh Mandhorghat Nagar via Dargi Road Km. 0/000 to 2/825 (Sh: Construction of R-wall at Rd. 1/750 to 1/754.20)

Schedule of Quantity

Estimated Cost. - Rs 99449 /- only
Earnest Money :- Rs. 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	2.81 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	656.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	7.01 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2499.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.61 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90206.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.05 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5093.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v)20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	5.85 Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	995.00
0					Total:	99449.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD Dhami

