

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2026-27- 546-75

Dated:- 10-04-2026

To

✓
The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025-300858 dated 09-10-2025 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhama on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **21.04.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **20.04.2026 up to 5.00 PM** and the application for issue of tender form shall be received on **20.04.2026 up to 3:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhama must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on Salapper- Tatapani- Sunni- Luhri road portion Km. 86/00 to 104/00 (SH: C/O R/wall at Rds. 100/825 to 100/835).	264645/-	5300/-	One Month	Rs.350/-
2	R/R damages on Shara Nallah to village Nadoth road Km. 0/00 to 2/700 (SH: Protection works R/Wall at Km. 1/392 to 1/404). (PCC).	462969/-	10000/-	One Month	Rs.350/-
3	R/R damages on Gallu to Palged road Km. 0/00 to 9/600 (SH: C/O B/Wall at Rd. 5/680 to 5/715).	482388/-	10000/-	One Month	Rs.350/-
4	R/R damages on Gallu to Palged road Km. 0/00 to 9/600 (SH: C/O B/Wall at Rd. 3/285 to 3/297, 3/12 to 3/325 & 3/335 to 3/345).	494153/-	10000/-	One Month	Rs.350/-
5	R/R damages on Banuna to Himri road Km. 0/00 to 3/825 (SH: C/O R/Wall at Rd. 0/410 to 0/420, R/Wall at Rd. 1/015 to 1/020 & B/Wall at Rd. 1/750 to 1/762).	498977/-	10000/-	One Month	Rs.350/-
6	A/R & M/O on Salapper- Tatapani- Sunni- Luhri road portion Km. 86/00 to 104/00 (SH: C/O R/wall at Rds. 86/217 to 86/232).	499376/-	10000/-	One Month	Rs.350/-
7	A/R & M/O on Salapper- Tatapani- Sunni- Luhri road portion Km. 86/00 to 104/00 (SH: P/L G-III, prime coat, P/L 50 mm thick Bitumen macadam, C/O V-shape & U-shape drain a/w P/L RCC hume pipe NP2 for culvert at various Rds. in between Km. 93/200 to 94/000).	498845/-	10000/-	One Month	Rs.350/-
8	R/R damages on Karyali to Shara Nallah road Km. 0/00 to 6/00 (SH: Protection works, B/Wall at Km. 0/846 to 0/860). PCC.	192342/-	3800/-	One month	Rs.350/-
9	R/R damages on Chaba Makarcha road Km. 0/00 to 1/500 (SH: C/O R/Wall at Rd. 0/495 to 0/510).	430854/-	10000/-	One month	Rs.350/-
10	R/R damages on Badamin Ghaini road Km. 0/00 to 6/500 (SH: C/O B-Wall at Rds. 1/555 to 1/565).	171151 /-	3500/-	One Month	Rs.350/-
11	R/R damages on Badamin Ghaini road Km. 0/00 to 6/500 (SH: C/O B-Wall at Rds. 1/585 to 1/595 & 1/615 to 1/627).	377785 /-	7600/-	One Month	Rs.350/-

12	R/R damages on Bag to Kangri road Km. 0/00 to 7/250 (SH: C/O R-Wall at Rd. 0/385 to 0/395).	172568/-	3500/-	One Month	Rs.350/-
13	R/R damages on Badamin to Ghaini road Km. 0/00 to 6/500 (SH: C/O B-Wall at Rds. 3/800 to 3/825).	454743/-	9100/-	One Month	Rs.350/-
14	C/O Shimla Mandi road Km. 39/200 to 52/300 (SH: Providing U-shape cross drain & grating over drain at RD. 45/840 & U-shape side drain from Rd. 45/810 to 45/840).	498169/-	10000/-	One Month	Rs.350/-
15	Widening/Improvement of Salapper Tatapani Sunni Luhri road Km. 72/00 to 86/00 (SH: Formation/Cutting from Rd. 81/875 to 81/885).	488101/-	10000/-	One Month	Rs.350/-
16	Widening/Improvement of Salapper Tatapani Sunni Luhri road Km. 72/00 to 86/00 (SH: Formation/Cutting from Rd. 81/895 to 81/902 (Balance Work)).	452842/-	10000/-	One Month	Rs.350/-
17	R/R damages on Shimla Mandi road Km. 22/000 to 33/200 (SH: Hiring of JCB for removal of slips on RD. 28/940 to 28/975).	370881/-	7418/-	One Month	Rs.350/-
18	R/R damages on Chauri Ki ghatti to Yan via Bhad road Km. 0/00 to 9/600 (SH: C/O R/Wall at Rd.9/315 to 9/330).	342191/-	7000/-	One month	Rs.350/-
19	R/R damages on Salana to Sari road portion beyond Sari Km. 0/00 to 1/700 (SH: C/O Edge Wall in between Km. 0/00 to 0/011 and R/Wall between Km. 0/015 to 0/026.10).	351844/-	7100/-	One month	Rs.350/-
20	R/R damages on Tara Devi Gamber road Km. 0/00 to 11/550 (SH: C/O R-Wall between Km. 7/680 to 7/695).	356039/-	7200/-	One month	Rs.350/-
21	A/R & M/O Salana Sari road Km. 0/00 to 4/200 (SH: Providing and laying Bitumen penetration macadam in between Km. 3/000 to 4/200).	499382/-	10000/-	One month	Rs.350/-
22	A/R & M/O Totu Taradevi bypass road Km. 0/00 to 4/105 (SH: Providing and laying Bitumen penetration macadam in between Km. 0/000 to 4/105).	499811/-	10000/-	One month	Rs.350/-
23	A/R & M/O phayal Rampuri via Matholi road Km. 0/00 to 5/200 (SH: Providing and laying Bitumen penetration macadam in between Km. 0/000 to 1/000).	499382/-	10000/-	One month	Rs.350/-
24	R/R damages on Phayal Rampuri via Matholi road Km. 0/00 to 5/200 (SH: C/O R-Wall at Rd. 0/610 to 0/625).	450266/-	9000/-	One month	Rs.350/-
25	C/O link road from Dharthalag to Nalthalag Km. 0/00 to 0/930 (SH: C/O Box culvert (1.5x1.5mtr) at Rd. 0/225 Balance work thereof) Under MMGSY.	493047/-	9900/-	One month	Rs.350/-
26	A/R & M/O on Shoghi Mehli road Km. 0/00 to 12/375 (SH: Cutting at Km. 10/760 to 10/835).	497750/-	10000/-	One month	Rs.350/-
27	A/R & M/O on Shoghi Mehli road Km. 0/00 to 12/375 (SH: Cutting at Km. 7/900 to 7/975).	492350/-	10000/-	One month	Rs.350/-
28	A/R & M/O Sharda Kajail road via Janol in Km. 0/00 to 6/060 (SH: Providing and Laying V-Shape drain in Km. 0/160 to 0/320).	499306/-	10000/-	One month	Rs.350/-
29	Restoration of Rain Damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:-C/O R-Wall at Rd.5/155 to 5/163).	310333/-	6000/-	One month	Rs.350/-
30	C/O link road from link road Hiranagar to upper Fathechi Km. 0/00 to 0/780 (SH: Providing Stone Soling in Km. 0/000 to 0/500).	476625/-	10000/-	One Month	Rs. 350/-
31	A/R & M/O link road to village Fagula Km. 0/00 to 0/600 (SH: C/O V-shape drain in KM. 0/00 to 0/600).	396972/-	8000/-	One Month	Rs. 350/-
32	R/R damages on Kanda Ladvi Kunihar road Km. 0/00 to 9/150 (SH: C/O R-Wall at Rd. 2/180 to 2/191.50).	474360/-	10000/-	One month	Rs.350/-
33	R/R damages on Shimla Nalagarh road Km. 7/00 to 22/00 (SH: C/O B-Wall at Rd.14/135 to 14/147).	292308/-	6000/-	One month	Rs.350/-
34	R/R damages on link road from Banuti to Mansa Mata Mandir Km. 0/00 to 0/660 (SH: C/O R-Wall at Rd.0/470 to 0/490).	447499/-	9000/-	One month	Rs.350/-
35	R/R damages on Hiranagar Dhamoon road Km. 0/00 to 8/00 (SH: C/O R-Wall at Rd.6/690 to 6/700).	389693/-	8000/-	One month	Rs.350/-
36	R/R damages on G/Hatti Kalihatti Arki road Km. 0/00 to 8/060 (SH: C/O R-Wall at Rd.6/205 to 6/227).	492633/-	10000/-	One month	Rs.350/-
37	A/R & M/O Ghanahatti Bhajol road Km. 0/00 to 14/000 (SH: Improvement of Sharp curve in various Rds. 1/700 to 4/000).	475829/-	10000/-	One month	Rs.350/-
38	R/R damages on link road to Pawaboo Km. 0/00 to 1/300 (SH: C/O R-Wall at Rd. 0/810 to 0/823).	426738/-	9000/-	One month	Rs.350/-
39	A/R & M/O on various roads in Badheri section under Jutogh sub division (SH: Trimming of grass and drain clearing).	198127/-	4000/-	One month	Rs.350/-

40	R/R damages on Shimla Nalagarh road Km. 7/00 to 22/00 (SH: C/O R-Wall at Rd. 14/310 to 14/324.50).	475179/-	10000/-	One month	Rs.350/-
41	R/R damages on Ghanahatti Parech road Km. 0/00 to 0/800 (SH: C/O R-Wall at Rd. 0/933 to 0/945).	192325/-	4000/-	One month	Rs.350/-
42	A/R & M/O on Shimla Nalagarh road Km. 6/900 to 22/000 (SH: C/O U-shape drain at Rd. 8/150 to 8/345) Balance Work.	302253/-	6000/-	One month	Rs.350/-
43	A/R & M/O on Shimla Nalagarh road Km. 6/900 to 22/000 (SH: P/F of steel grating on existing drain in Km. 7/625 to 8/00 at various Rds.)	444681/-	9000/-	One month	Rs.350/-
44	R/R damages on Hiranagar Jutogh road Km. 0/00 to 1/200 (SH: C/O R/Wall at Rd. 0/420 to 0/436).	484379/-	10000/-	One month	Rs.350/-
45	R/R damages on Chornti to Pahal road Km. 0/00 to 4/500 (SH: C/O R/Wall at Rd. 3/895 to 3/905) Balance work.	434126/-	9000/-	One month	Rs.350/-
46	R/R damages on Devnagar Moolvari road Km. 0/00 to 1/200 (SH: C/O R/Wall at Rd. 0/195 to 0/200).	141443/-	3000/-	One month	Rs.350/-
47	R/R damages on Ghanahatti Bhajol road Km. 0/00 to 14/000 (SH: C/O R/Wall at Rd. 3/631 to 3/651).Balance work.	197697/-	4000/-	One month	Rs.350/-
48	A/R & M/O Khalag Ka Ghat to Khairi Lohali road Km. 0/000 to 2/000 (SH: C/O V-shape drain in Km. 0/00 to 0/800).	463377/-	9000/-	One month	Rs.350/-
49	R/R damages on Paoghatti to Khari Lohali road Km. 0/000 to 2/200 (SH: P/L 25 mm thick Bituminous concrete along with providing and laying of Hot Applied Thermoplastic compound 2.50 mm thick for edge line in between Km. 1/00 to 1/320).	433546/-	9000/-	One month	Rs.350/-
50	R/R damages on Didoghatti Karechi Road in Km. 0/00 to 12/015 (SH: C/O B/Wall at Rd. 3/970 to 4/000).	385091/-	8000/-	One month	Rs.350/-
51	R/R damages on Khairi Lohali road in Km. 0/00 to 2/220 (SH: C/O B/Wall at Rd. 0/00 to 0/018).	439030/-	9000/-	One month	Rs.350/-
52	Improvement & Widening of Shimla to Mandi road Km. 6/00 to 22/000 (SH: M/T of extended portion at various Rds in Km. 6/00 to 22/000).	495975/-	10000/-	One month	Rs.350/-
53	R/R damages on Neri Sangti road in Km. 0/00 to 6/465 (SH: C/O R/Wall at Rd. 2/030 to 2/045).	455521/-	9000/-	One month	Rs.350/-
54	A/R & M/O link road to village Bashol Km. 0/00 to 1/075 (SH: Cutting at various Rds. for curve improvement and construction of catchpit at Km. 0/450 alongwith construction of U shape drain in Km. 0/430 to 0/448).	422991/-	10000/-	One Month	Rs. 350/-
55	R/R damages on Thachi Seri Shalli road Km. 0/00 to 3/285 (SH: C/O R-Wall in between Km. 0/458.50 to 0/465).	236762/-	4800/-	One month	Rs.350/-
56	R/R damages on link road Bainsh to Bangera Km. 0/00 to 3/00 (SH: C/O PCC R-Wall in between Km. 1/185 to 1/191).	284225/-	6000/-	One month	Rs.350/-
57	C/O Bainsh Bangera Ambulance road Km. 0/00 to 3/00 (SH: C/O RCC 900 mm dia Hume pipe culvert at Rd. 0/800 along with wing wall).	197668/-	4000/-	One month	Rs.350/-
58	R/R damages on Rattanpur Bathmana road Km. 0/00 to 1/600 (SH: C/O R-Wall at Rds. 0/090 to 0/105).	192074/-	4000/-	One month	Rs.350/-
59	R/R damages on Nehra Bhukoo road Km. 0/00 to 8/825 (SH: C/O R-Wall at Rds. 0/026 to 0/038 and P/F W-Metal Beam Crash Barrier at Rd. 7/015 to 7/038).	474286/-	9000/-	One month	Rs.350/-
60	R/R damages on Thachi Seri Shalli road Km. 0/00 to 3/285 (SH: C/O B-Wall at Rds. 0/375 to 0/378.75) from road level to Govt. Primary School Thachi building).	497172/-	10000/-	One month	Rs.350/-
61	R/R damages on Pakki Bawari Shakrah Sedan road Km. 0/00 to 5/700 (SH: C/O R-Wall at Rds. 3/610 to 3/615 to protect the house of Smt. Batti Devi W/O Lt. Sh. Musu Ram, V.P.O, Shakrah Distt. Shimla).	256800/-	5000/-	One month	Rs.350/-
62	C/O link road Palkari Makri Km. 0/00 to 1/600 (SH: C/o V-Shape drain in Km. 0/800 to 1/550).	480356/-	10000/-	One month	Rs.350/-
63	C/O link road Palkari Makri Km. 0/00 to 1/600 (SH: C/o PCC parapets at various Rds. in Km. 0/00 to 1/600).	479166/-	10000/-	One month	Rs.350/-
64	Special repair to Judicial Academy at Ghandal Shimla (SH: Providing and applying waterproofing treatment in water harvesting tanl to avoid sinking/leakage) Job No.1.	464094/-	9000/-	One month	Rs.350/-
65	C/O Ambulance road Bainsh to Bangera road Km. 0/00 to 3/00 (SH: P/L WBM-G-I in Km. 1/900 to 2/800).	492774/-	10000/-	One month	Rs.350/-

66	R/R damages on Reodhar Piplidhar road Km. 0/00 to 2/600 (SH: C/O R/Wall at Rd. 1/585 to 1/600).	354542/-	7000/-	One month	Rs.350/-
67	R/R damages on Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: C/O R-Wall at Rds. 8/684 to 8/691).	360852/-	7000/-	One month	Rs.350/-
68	A/R & M/O on Nehra Bhukoo road Km. 0/00 to 8/00 (SH: C/O PCC R/Wall at Rd. 6/600 to 6/609).	461006/-	10000/-	One month	Rs.350/-
69	A/R & M/O on Nehra Bhukoo road Km. 0/00 to 8/00 (SH: C/O PCC R/Wall at Rd. 6/800 to 6/815).	497848/-	10000/-	One month	Rs.350/-
70	R/R damages on Pakki Bawari Shakrah Sedan road Km. 0/00 to 5/700 (SH: C/O B-Wall at Rds. 3/430 to 3/440).	476124/-	10000/-	One month	Rs.350/-
71	R/R damages on link road Bainsh to Bangera Km. 0/00 to 3/00 (SH: C/O R-Wall in between Km. 0/135 to 0/153).	495848/-	10000/-	One month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni

Certificate

Certified that the tenders called vide this notice inviting tender for 71 (Seventy one) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni.

Schedule Of Quantity

Name of Work :- R/R Damages on Salapper-Tatapani-Sunni-Luhri road Portion km 86/00 to 104/00 (SH-10 R/Wall at between km. 150/825 to 150/835.)							Estimated Cost:- 2,64,645.00
S.No Description of Work							Earnest Money:- 5,300.00
							Time:- One Months.
1	2	No. of Qty.	Rate	In figures	In words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1.1	14.20	Cum	194.00	Rupees One Hundred Ninety Four Only	Per cubic metre	2755
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	13.20	Cum	425.00	Rupees Four Hundred Twenty Five Only	Per cubic metre	5610
3	Providing concrete for plain/ reinforced concrete In open foundation & Plinth complete as per drawing and technical specification clause-802, 803, 1202 & 1203 including carriage of materials as per the direction of engineer-in-charge (i) Cement concrete 1:3:6 nominal mix (1 cement : 3 sand : 6 graded crushed stone aggregate 20mm nominal size)	44.10	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per cubic metre	246960
4	Providing weap holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(h) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7	20.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	3800
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. Granular material	4.80	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per cubic metre	5520
Total Rs.							
Amount Quoted by the Contractor in Percentage							264645
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmu

Schedule of Quantity							
Name of Work :- Restoration of Rain Damages on Shara Nallah to Village nadodh road km 0/00 to 2/700 SH: Protection works, R/walls at km 01/392 to 01/404 (PCC)					Estimated Cost:- 462969.00 Only. Earnest Money: 10000.00 Only. Time: - One month		
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
1	2	3	4	In Figure 5	In word 6	7	8
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with the lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1	22.20	per cum	₹ 199.00	Rupees One Hundred Ninety Nine Only	per cum	4418.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 I/c setting out, construction of shoring and bracing removal of stums and other deleterious materials and disposal upto a lead of 50 metre, dressing of sides and bottom and back filling in tranches with excavated suitable material.	4.80	per cum	₹ 356.50	Rupees Three Hundred Fifty Six and Fifty Paise	per cum	1711.00
3	Providing concrete for plain/reinforced concrete 1:4:8 (in 20 mm aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 & 1203.	87.72	per cum	₹ 5,000.00	Rupees Five Thousand Only	per cum	438600.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.	24.00	Nos.	₹ 190.00	Rupees One Hundred Ninety Only	Nos.	4560.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material.	13.68	per cum	₹ 1,000.00	Rupees One Thousand Only	per cum	13680.00
					Total		462969.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Schedule of Quantity							
Name of Work :- RRD on Gallu to Palged road km 0/00 to 9/600 (SH: C/O B/wall at Rd 5/680 to 5/715)					Estimated Cost:- ₹ 4,82,388.00 Only.		
					Earnest Money: ₹10,000.00 Only.		
					Time: - One month		
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2			5	6	7	8
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with the lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1	23.45	per cum	₹ 199.00	One Hundred Ninety Nine Rupees	per cum	₹ 4,667.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out , construction of shoring the bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtr. dressing of sides and bottom and back filling in trenches with with excavated suitable material carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	5.95	per cum	₹ 356.50	Three Hundred Fifty Six Rupees Fifty Paise	per cum	₹ 2,121.00
3	Providing concrete for plain/reinforced concrete 1:4:8 in (20 mm crushed stone agg)in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 & 1203.	91.70	per cum	₹ 5,000.00	Five Thousand Rupees	per cum	₹ 4,58,500.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	90.00	Nos.	₹ 190.00	One Hundred Ninety Rupees	Nos.	₹ 17,100.00
					Total		₹ 4,82,388.00
Amount procured by the contractor in percentage		Rs.					
Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted							

Executive Engineer
Shimla Rural Division
HPPWD Dham

Schedule of Quantity

Name of Work :- RRD on Gallu to Palged road km 0/00 to 9/600 (SH: C/O B/wall at Rd 3/285 to 3/297, 3/312 to 3/325 & 3/335 to 3/345)

Estimated Cost:- ₹ 4,94,153.00 Only.

Earnest Money: ₹10,000.00 Only.

Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
1	2			5	6	7	8
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with the lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1	23.45	per cum	₹ 199.00	One Hundred Ninety Nine Rupees	per cum	₹ 4,667.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring the bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtr. dressing of sides and bottom and back filling in trenches with with excavated suitable material carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	38.95	per cum	₹ 356.50	Three Hundred Fifty Six Rupees Fifty Paise	per cum	₹ 13,886.00
3	Providing concrete for plain/reinforced concrete 1:4:8 in (20 mm crushed stone agg) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 & 1203.	91.70	per cum	₹ 5,000.00	Five Thousand Rupees	per cum	₹ 4,58,500.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	90.00	Nos.	₹ 190.00	One Hundred Ninety Rupees	Nos.	₹ 17,100.00
					Total		₹ 4,94,153.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dhamu

Schedule of Quantity

Name of Work :- RRD on Banuna to Himri road km 0/00 to 3/825(SH: C/O R/wall at Rd 0/410 to 0/420 , R/Wall at Rd 1/015 to 1/020, & B/Wall at Rd 1/750 to 1/762)

Estimated Cost:- ₹ 4,98,977.00 Only.
Earnest Money: ₹ 10,000.00 Only.
Time: - One month

S. No		Description of Work		Nos of Qty		Rate		Unit	Amount
1	2	3	4	In Figure	In word				
				5	6	7	8		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with the lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1	27.71	per cum	₹ 199.00	One Hundred Ninety Nine Rupees	per cum	₹ 5,514.00		
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out , construction of shoring the bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtr. dressing of sides and bottom and back filling in trenches with with excavated suitable material carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	6.47	per cum	₹ 356.50	Three Hundred Fifty Six Rupees Fifty Paise	per cum	₹ 2,307.00		
3	Providing concrete for plain/reinforced concrete 1:4:8 in (20 mm crushed stone agg)in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 & 1203.	95.65	per cum	₹ 5,000.00	Five Thousand Rupees	per cum	₹ 4,78,250.00		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	57.19	Rmt.	₹ 190.00	One Hundred Ninety Rupees	Rmt.	₹ 10,866.00		
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material.	2.04	per cum	₹ 1,000.00	One Thousand Rupees	per cum	₹ 2,040.00		
Amount procured by the contractor in percentage		Rs.		Total			₹ 4,98,977.00		
Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted									

Executive Engineer
Shimla Rural Division
HPPWD Dharni

Schedule Of Quantity

Name Of Work :- A/R & M/O Slapper -Tattapani-Sunni-Luhri road , Portion km. 86/000 to 104/000 (SH:- C/o R/wall in between km. 86/217 to 86/232)

Estimated Cost:- 4,99,376.00

Earnest Money:- 10,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1.1	18.60	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per Cubic metre	3701
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling of trenches with excavated suitable material	24.74	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	8820
3	Providing and laying concrete for plain reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-charge (i) Cement Concrete 1:3:6 nominal mix (1 Cement 3 sand 6 graded crushed stone aggregate 20mm nominal size)	83.04	Cum	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic metre	456720
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204, 3.7.	35.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running Meter	6300
5	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD. specifications of 1990 volume-I including carriage of material within all leads and lifts.	3.00	Cum	1000.00	Rupees One Thousand Only	Per Cubic metre	3000
6	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106 600mm Dia	7.50	Rmt	2778.00	Rupees Two Thousand Seven Hundred Seventy Eight Only	Per Running Meter	20835
Total Rs.							499376
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HPPWD, Disptg

Schedule Of Quantity						Estimated Cost:- 4,98,845.00	
Name Of Work :- A/R & M/O SlapperT attapani Sunni luhri Road portion km 86/000 to 104/000 (SH:- Providing and laying G-III, prime coat , P/L Bituminous Macadam , C/O V-shpae & U-shape drain a/w P/L RCC hume pipe NP2 for culvert at various Rd in between km 93/200 to 94/000)						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing, laying, spreading and compacting stone aggregates of specific sizes (53mm to 22.40mm) water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3- wheeled steel/vibrator roller 80-100 tonne in stages to proper grade and camber, applying and brooming, requisite type of screening/buiding material to fill up the interstices of course aggregate, watering and compacting to the required density Grading-III.	27.99	Cum	3398.00	Rupees Three Thousand Three Hundred Ninety Eight Only	Per Cubic metre	95110
2	Providing and applying prime coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying prime at the rate of 0.60 kg/Sqm using mechanical means.	373.25	Sqm	76.00	Rupees Seventy Six Only	Per Cubic metre	28367
3	Providing and applying prime tack coat with Bitumen emulsion (RS-1) using distribytor at the rate of 0.25 to 0.30 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification clause 503.	373.25	Sqm	24.00	Rupees Twenty Four Only	Per Cubic metre	8958
4	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equiped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifcatons and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity.	18.66	Sqm	8809.00	Rupees Eight Thousand Eight Hundred Nine Only	Per Square metre	164376
5	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	35.41	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	12624

6	Providing and laying concrete for plain /reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 122 & 1203 for plain . Reinforcement including carriage of materials as per the directions of Engineer-in-Charge. (i) Cement Concrete 1:3:6 nominal mix (1 Cement :3 sand : graded crushed stone aggregate 20 mm nominal size)	30.65	Cum	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic metre	168575
7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.	7.50	Rmt	2778.00	Rupees Two Thousand Seven Hundred Seventy Eight Only	Per running metre	20835
Total Rs.							
Amount Quoted by the Contractor in Percentage							498845
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharti.

Schedule Of Quantity							
Name Of Work :- R/R Damages on Sal to Karyali road km 0/00 to 3/00 (SH:- Protection work, B/wall at km 0/846 to 0/860) PCC						Estimated Cost:- 1,92,342.00	
						Earnest Money:- 3,800.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	10.78	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	2516
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	6.30	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	2246
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203	36.68	Cum	5000.00	Rupees Five Thousand Only	Per Cubic metre	183400
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	22.00	No	190.00	Rupees One Hundred Ninety Only	Each	4180
Total Rs.							
Amount Quoted by the Contractor in Percentage							192342
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.

Schedule Of Quantity							
Name Of Work :- Restoration of Rain Damages on Chaba Makarcha road km. 0/00 to 1/500 (SH:- C/O R/Wall at Rd. 0/495 to 0/510)						Estimated Cost:- 4,30,854.00	
						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	6	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	26.70	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6232
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	9.90	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3529
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.35	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	392610
4	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	24.75	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	20835
5	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	40.25	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	7648
Total Rs.							430854
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Simla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 1,71,151.00	
Name Of Work :- Restoration of Rain Damages on Badmain Ghaini road km 0/000 to 6/500 (SH:- C/O B/wall at Rd 1/555 to 1/565)						Earnest Money:- 3,500.00	
S.No	Description of Work	No.of Qty.		Rate		Time:- One Months.	
				In figures	In words	Unit	Amount
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	22.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	5252
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	10.60	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	3779
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	33.30	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	159840
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	12.00	No	190.00	Rupees One Hundred Ninety Only	Each	2280
Total Rs.							171151
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer.
Shimla Rural Division.
HP.PWD, Dhami.

Schedule Of Quantity						Estimated Cost:- 3,77,785.00	
Name Of Work :- Restoration of Rain Damages on Badmain Ghaini road km 0/000 to 6/500 (SH:- C/O B/wall at Rd 1/585 too 1/595 & 1/615 to 1/627)						Earnest Money:- 7,600.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	49.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	11553
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	23.32	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	8314
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	73.26	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	351648
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	33.00	No	190.00	Rupees One Hundred Ninety Only	Each	6270
Total Rs.							377785
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP.PWD, Dhani

Schedule Of Quantity							
Name of Work :- R/R damages on Bag to Kangri road km. 0/00 to 7/25 (SH:- C/O R/wall at RD 0/385 to 0/395)						Estimated Cost:- 1,72,568.00	
S.No Description of Work						Earnest Money:- 3,500.00	
						Time:- One Months.	
1	2	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	6.40	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1494
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	10.40	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3708
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	32.30	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	155040
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	25.00	NO	190.00	Rupees One Hundred Ninety Only	Each	4750
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material	9.00	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty	Per cubic metre	7576
Total Rs.							172568
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhani.

Schedule of Quantity						Estimated Cost: 4,54,743 /- only	
Name of work: RR Damages on Badmain to Ghaini road km 0/000 to 6/500. (SH : C/O B/Wall at RD 3/825 to 3/850).						Earnest Money: 9100 /-only.	
						Time: - One month	
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
1	2	3	4	In Figure 5	In word 6	7	8
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer –in- Charge .	53.25	Per Cum	233.40	Two hundred thirty three rupee forty Paise only	Per Cum	12429.00
2	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setti:g out construction of shoring and bracing ,removal of stumps and othe: deleterious material and disposal upto all lead and lifts dressiong of side and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer –in- Charge.	10.25	Per Cum	356.50	Three hundred fifty six rupees fifty paise only	Per Cum	3654.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction –in- Charge.	90.00	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	432000.00
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	37.00	Per Rmt	180.00	One hundred eighty rupees only	Per Rmt	6660.00
Amount Quoted by the Contractor in Percentage				Total			454743.00
Note :- All the material will procured by the contractor him self							

Executive Engineer
Shimla Rural Division
HP.PWD, Dharti

Schedule of Quantity							
Name of Work : C/O Shimla Mandi road Km 39/200 to 52/300. (SH : Providing U-Shape Cross Drain & Grating over drain at RD 45/840 & U-Shape side drain from RD 45/810 to 45/840).						Estimated Cost:4,98,169/- only	
						Earnest Money: 10000 /-only.	
						Time: - One month	
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
1	2	3	4	In Figure 5	In word 6	7	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	23.80	Per Cum	364.00	Three Hundred sixty four rupees only	Per Cum	8663.00
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. including cost of centering and shuttering. Nominal Mix 1:2:4 (20 mm aggregate)	11.70	Per Cum	7479.00	Seven Thousand four hundred seventy nine rupees only	Per Cum	87504.00
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3406.80	Per Cum	118.00	One hundred eighteen rupees only	Per Cum	402002.00
Amount Quoted by the Contractor in Percentage					Total		498169.00
Note :- All the material will procured by the contractor him self							

Executive Engineer
Shimla Rural Division
HP.PWD, Dhamsi

Name of work:- Widening/Improvement of Slapper Tatapani Suni Luhri road Km. 72/000 to 86/000.
Sub Head:- Formation/cutting from Rd 81/875 to 81/885

Schedule of Quantity

Estimated Cost:- 488101.00

Earnest Money : 10000.00

Time:- One Month

Sr. No.	Description of Work	Qty	Unit	Rate		Amount
				In figures	In words	
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock .All work of rock cutting by blastingshall be carried out by taking all necessary precautions against soil erosion ,damages to hill side ,water pollution etc. and to protect stability of hill side .Rock shall be excavated with chiseling and wedging out of rock (where blasting is prohibited) .All earth work in cutting /excavation including rock excavation shall be carried out true to lines ,grades ,sides slopes,width,camber,super-elevation and level as shown on the drawing and as directed by the Engineer-in-Charge in conformity with the requirement of technical specification for Rural Road,August 2004 and clause 16.2 of General conditions for contract to achive designed formation width including hauling and stacking of materials useful for constrcution at suitable sites safe manner including arrangement of dumping site trimming ,filling of unevenness blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding .The recovery for stones ,whether usefule or not ,for 138.74 cubic metre at the rate of Rs 300/-only (Rupees three hundred only) per cubic meter shall be effected on prorata basis in all circumstances .Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor ,which shall have to be duly compensated by him in all cases.	816.10	Per Hours	598.09	Rupees Five Hundred Ninety Eight and Paise Nine Only	488101.00
Total						488101.00
Amount Quoted by the Contractor in Percentage						
Note :- All the material will procured by the contractor him self and bills will be submitted						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.

Schedule of Quantity						
Name of work:- Widening/Improvement of Slapper Tatapani Suni Luhri road Km. 72/000 to 86/000.				Estimated Cost:- 452842.00		
Sub Head:- Formation/cutting from Rd 81/895 to 81/902 (Balance Work)				Earnest Money : 10000.00		
				Time:- One Month		
Sr. No.	Description of Work	Qty	Unit	Rate		Amount
				In figures	In words	
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock .All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion ,damages to hill side ,water pollution etc. and to protect stability of hill side .Rock shall be excavated with chiseling and wedging out of rock (where blasting is prohibited) .All earth work in cutting /excavation including rock excavation shall be carried out true to lines ,grades ,sides slopes,width,camber,super-elevation and level as shown on the drawing and as directed by the Engineer-in-Charge in conformity with the requirement of technical specification for Rural Road,August 2004 and clause 16.2 of General conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites safe manner including arrangement of dumping site trimming ,filling of unevenness blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding .The recovery for stones ,whether useful or not ,for 116.73 cubic metre at the rate of Rs 300/-only (Rupees three hundred only) per cubic meter shall be effected on prorata basis in all circumstances .Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor ,which shall have to be duly compensated by him in all cases.	795.87	Per Hours	568.99	Rupees Five Hundred Sixty Eight and Paise Ninety Nine Only	452842.00
Total						452842.00
Amount Quoted by the Contractor in Percentage						
Note :- All the material will procured by the contractor him self and bills will be submitted						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.

Schedule Of Quantity							
NAME OF WORK :- RR Damages on Shimla Mandi road Km 22/000 to 33/200. (SH:--Hiring of JCB for removal of slips on RD 28/940 to 28/975).					Estimated cost: 370881.00 only /-		
					Earnest Money: 7418.00 only-		
					Time : One Month		
S.No	Description of Work	No.of Qty.	Unit	Rate		Unit	Amount
1	2	3	4	In figures	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5	2131.50	Cum	174.00	One Hundred Twenty Two Rupees Only	Per Cubic Meter	370881.00
Amount Quoted by the Contractor in Percentage						Total	370881.00
Note :- All the material will procured by the contractor himself							

Executive Engineer
Shimla Rural Division
HPPWD Dham

Schedule Of Quantity						Estimated Cost:- 3,42,191.00	
Name Of Work :- R/R damages on Chauri Ki Ghatti to Yan Via Bhad km. 0/00 to 9/600 (SH:- C/O R/wall at Rd 9/315 to 9/330)						Earnest Money:- 7000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited), all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts	14.70	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3431
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts	17.70	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	6310
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.20	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	309120
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.3.7	55.00	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	10450
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD specifications of 1990 volume-I Including carriage of material within all leads and lifts	15.30	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	12880
Total Rs.							342191
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity
Item of work:- R/R damages on Salana to Sari road portion beyond sari Km 0/00 to 1/700. (SH: C/O
Edge wall in b/w km 0/00 to 0/011 R/Wall between Km 0/015 to Km 0/026.10)

Estimated Cost:-3,51,844.00

Earnest Money:- 7100.00

Time:- One Month.

S.No		Description of Work				No. of Qty.		Rate		Unit	Amount
						In figures		In words			
1						5		6		7	8
1		Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge				32.27	cum	356.50	Rupees Three hundred fifty six and paise fifty only	Per cubic metre	11505.00
2		Providing and laying Plain cement concrete 1:4:8(one cement isto four sand isto eight graded crushed stone aggregate 20 millimetre(twenty milimetre) nominal size for plain /reinforced concrete in open foundation and plinths or similar works complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.				69.88	Cum	4600.00	Rupees Four thousand six hundred only	Per cubic metre	321430.00
3		Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.				9.99	Cum	1089.60	Rupees One thousand Eighty nine and sixty Paise only	Per cubic metre	10885.00
4		Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.				47.20	Rmt	170.00	Rupees One hundred seventy only	Per running metre	8024.00
										Total:-	351844.00
		Amount Quoted by the Conctrator in percentage				Rs.					
		Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.									

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhani.

Draft Schedule Of Quantity							Estimated Cost:- 3,56,039.00
Name of Work :- R/R damages on Tara Devi Gamber road km 0/00 too 11/550 (SH:- C/O R/wall b/w km 7/680 to 7/695)							Earnest Money:- 7,200.00
							Time:- One Months.
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	5 In figures	6 In words	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	14.70	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3431
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	17.85	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	6364
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	67.65	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	324720
4	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	15.30	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	12880
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	45.50	Rmt	190.00	Rupees One Hundred Ninety Only	Per running Metre	8645
Total Rs.							356039

DNIT Approved for Rs. 3,56,039 /- only (Rupees Three Lacs Fifty Six Thousand & Thirty Nine) only for the year 2025-26 entred for DNIT Reg. Sr.No. 776

Executive Engineer,
Shimla Rural Division,
HP.PWD, Dharmu

Schedule Of Quantity							
of work:- Annual Surfacing on Salana Sari 0/00 to 4/200 (Sh:- Providing and laying Bitumen penetration macadam in between km. 3/000 to 4/200)							
Description of Work				Estimated Cost:-4,99,382.00		Earnest Money:- 10,000.00	
				Time:- One Month.			
1	2	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
		3	4	5	6	7	8
1	Proving and applying tack coat with bitumen emulsion (RS – 1) using emulsion pressure distributor at the rate of 0.25 kg to 0.30 kg per Sqm. On the prepared bituminous surface cleaned with hydraulic broom as per Technical Specification clause 503. including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	873.00	cum	21.55	Rupees twenty one and paise fifty five only	Per cubic metre	18813.00
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate application of bituminous binder & key aggregates & rolling with a 3 wheel 80-100 KN static roller to achieve the desired degree of compaction as per technical specification clause 506. (50 mm thick) including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	873.00	Cum	550.48	Rupees five hundred fifty and paise forty eight only	Per cubic metre	480569.00
Amount Quoted by the Conctrator in percentage						Total:-	499382.00
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.		Rs.					

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhani.

Schedule Of Quantity

Work:- Annual Surfacing on Totu TaraDevi Bypass Road Km. 0/00 to 4/105 (Sh:- Providing and
penetration macadam in between km. 0/00 to 4/105)

Bypass Road Km. 0/00 to 4/105 (Sh:- Providing and						Estimated Cost:-4,99,811.00	
Description of Work						Earnest Money:- 10,000.00	
						Time:- One Month.	
2	No. of Qty.	Rate		Unit	Amount		
		In figures	In words				
1	3	4	5	6	7	8	
Proving and applying tack coat with bitumen emulsion (RS – 1) using emulsion pressure distributor at the rate of 0.25 kg to 0.30 kg per Sqm. On the prepared bituminous surface cleaned with hydraulic broom as per Technical Specification clause 503. including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	873.75	cum	21.55	Rupees twenty one and paise fifty five only	Per cubic metre	18829.00	
2	873.75	Cum	550.48	Rupees five hundred fifty and paise forty eight only	Per cubic metre	480982.00	
Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate application of bituminous binder & key aggregates & rolling with a 3 wheel 80-100 KN static roller to achieve the desired degree of compaction as per technical specification clause 506. (50 mm thick) including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.							
Amount Quoted by the Contractor in percentage							
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							
Rs.						Total:-	499811.00

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi.

A/R 21/11/17

Schedule Of Quantity

Work:- **Annual Surfacing on Phayal Rampuri via Matholi Road Km. 0/00 to 5/200 (Sh:-**
ing and laying Bitumen penetration macadam in between km. 0/000 to 1/000)

Estimated Cost:-4,99,382.00

Earnest Money:- 10,000.00

Time:- One Month.

	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2 Proving and applying tack coat with bitumen emulsion (RS – 1) using emulsion pressure distributor at the rate of 0.25 kg to 0.30 kg per Sqm. On the prepared bituminous surface cleaned with hydraulic broom as per Technical Specification clause 503. including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	873.00	cum	21.55	Rupees twenty one and paise fifty five only	Per cubic metre	18813.00
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate application of bituminous binder & key aggregates & rolling with a 3 wheel 80-100 KN static roller to achieve the desired degree of compaction as per technical specification clause 506. (50 mm thick) including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	873.00	Cum	550.48	Rupees five hundred fifty and paise forty eight only	Per cubic metre	480569.00
Amount Quoted by the Conctrator in percentage						Total:-	499382.00
Conditions:-(i) All the materials will be procured by the contractor himself and bills will be submitted.							

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharni.

Schedule Of Quantity						Estimated Cost:- 4,50,266.00	
Name Of Work :- R/R Damages on Phayal Rampuri via Matholi road km 0/000 to 5/200 (SH:- C/O R/wall at Rd 0/610 to 0/625)						Earnest Money:- 9,000.00	
Time:- One Months.							
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	5	6	7	8
				In figures	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	44.55	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	10398
2	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	86.58	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	415584
3	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8	21.15	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	17804
4	Providing and laying 100mm dia metre pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	36.00	No	180.00	Rupees One Hundred Eighty Only	Each	6480
Total Rs.							
Amount Quoted by the Contractor in Percentage							450266
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharni.

Schedule Of Quantity						Estimated Cost:- 4,93,047.00	
Name Of Work :- C/O link road from Dharthalag to Nalthalag km 0/00 to 0/930 (SH:- C/O Box Culvert (1.5x1.5mtr) at Rd 0/225 Balance work thereof)						Earnest Money:- 9,900.00	
S.No						Time:- One Months.	
Description of Work		No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50mm dressing of sides and bottom and backfilling in trenches with excavated suitable material	48.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	17290
2	Providing concrete for plain/ reinforced concrete in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 P.C.C. M15 grade 91:2:5:5)	49.85	Cum	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	309070
3	Supplying, fitting and placing HYSD bar reinforced (Fe 415) in substructure complete as per drawing and technical specification clause 1002, 1005, 1010, & 1202.	1.52	Tonne	99982.74	Rupees Ninety Nine Thousand Nine Hundred Eighty Two and Paise Seventy Four Only	Per tonne	151974
4	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	13.37	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	11255
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	18.20	No	190.00	Rupees One Hundred Ninety Only	Each	3458
Total Rs.							
Amount Quoted by the Contractor in Percentage							493047
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.

Name of Work:- Annual Repair & Maintenance of Shoghi Mehli Road 00/00 to 12/375 (SH:Cutting at Km. 10/760 to 10/835)

Schedule Of Quantity

Estimated Cost:- Rs. 497750/- only

Earnest Money:- 10,000.00

Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones , shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard roack) 170.88 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundered only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	1070.20	Cum	465.10	Rupees Four Hundred Sixty Five and Paise Ten Only	Per Cubic metre	497750.00
Total Rs.							497750.00
Amount Quoted by the Contractor in Percentage							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dham

Name of Work:- A/R & M/O On Shoghi Mehli Road 00/00 to 12/375 (SH:Cutting in between Km.7/900 to 7/975)					Schedule Of Quantity		Estimated Cost:- Rs. 4,87,633/-	
S.No	Description of Work	No. of Qty.	Rate				Earnest Money:- 10,000.00	
1	2	3	4	5	6	7	8	
				In figures	In words	Unit	Amount	
	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones , shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 169.38 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundered only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	1058.59	Cum	465.10	Rupees Four Hundred Sixty Five and Paise Ten Only	Per Cubic metre	492350.00	
Total Rs.							492350.00	
Amount Quoted by the Contractor in Percentage								

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhadi.

Schedule Of Quantity						Estimated Cost:- 4,99,306.00	
Name Of Work :- A/R & M/O Sharda kajail road via Janol in km . 0/00 to 6/060) (SH:- Providing & Laying V-Shape drain in km . 0/160 to 0/320)						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	5	6	7	8
				In figures	In words		
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	41.25	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	14706
3	Providing and laying cement concrete drain with cement concrete 1:3:6 (one cement : 3 sand : 6 graded stone aggregate 20 mm nominal size) mechanically mixed in open surface drain with plinth protection having internal size 20x15 cm & with side wall of 10 cm thick & inside plastering with CM. 1:3 including earthwork & finished with floating coat of neat cement complete as per standard design as per HPPWD specification 1990 volume - I including carriage of all labour equipments and materials to various location through complete including carriage of material in all leads and lifts as per direction of Engineer in Charge.	96.92	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	484600
Total Rs.							499306
Amount Quoted by the Contractor in Percentage						Rs.	
Note:- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Name of Work:- Restoration of Rain Damages on Hiranagar Sharog Road Km. 0/00 to 5/500 (Sh: Construction R-wall at Rd. 5/155 to 5/163)

SCHEDULE OF QUANTITY

S. No.	Sub head and items of work	Qty.	Estimated Cost - Rs 310333 /- only Earnest Money - Rs 6000 /-only Time - One Month		
			Rate figures	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	11 52 Cum	233 40	Rupees Two Hundred Thirty Three and Paise Forty Only	2689 00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	15 62 Cum	356 50	Rupees Three Hundred Fifty Six and Paise Fifty Only	5569 00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1 4 8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	63 64 Cum	4600 00	Rupees Four Thousand Six Hundred Only	292744 00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	22 80 Rmt.	170 00	Rupees One Hundred Seventy Only	3876 00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8. (I) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6 48 Cum	841 80	Rupees Eight Hundred Forty One and Paise Eighty Only	5455 00
0					
Amount Quoted by the Contractor in Percentage			Total: 310333.00		
			Rs.		

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Sikim Rural Division
HPPWD, Dharwad

Name of Work:- Construction of Link Road from Link Road Hiranagar to Upperli Fatechi Road Km. 0/00 to 0/780 (Sh: Providing Stone Soling in Km. 0/ 00 to 0/500)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 476625 /- only
Earnest Money - Rs. 10000 /- only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate figures	Unit	Amount
1	2	3	4	5	6	7
1	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum materials and labour) including Carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	232.50	Cum	2050.00	Rupees Two Thousand Fifty Only	476625.00
0						
Total:						476625.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama

SCHEDULE OF QUANTITY
Name of Work:- Annual Repair & Maintenance of Link Road to village Fagla Km. 0/00 to 0/600 (Sh: Construction of V-Shape drain in Km. 0/00 to 0/600)

Estimated Cost - Rs 396972 /- only
 Earnest Money - Rs 8000 /- only
 Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	63.99 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	22812.00
2	Providing and laying compacting stone soling of specific size to properly hand packed tightly in under flooring as per drawing complete and technical specification by manual means (i) 100 mm thickness including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	60.00 Cum	1400.00	Rupees One Thousand Four Hundred Only	84000.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	55.80 Cum	5200.00	Rupees Five Thousand Two Hundred Only	290160.00
0					
				Total:	396972.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 4,74,360.00	
Name Of Work :- Restoration of Rain on Kanda Ladvi Kunihar road in km 0/00 to 9/150 (SH:- Construction of R/wall at Rd 2/180 to 2/191.50)						Earnest Money:- 10,000.00	
Description of Work						Time:- One Month.	
S.No	2	No. of Qty.		Rate		Unit	Amount
1		3	4	In figures	In words		
				5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	22.77	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	5315
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	32.32	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	11522
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	91.49	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic metre	439152
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	14.15	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	11911
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	34.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	6460
Total Rs.							
Amount Quoted by the Contractor in Percentage							474360
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharm

Name of Work:- Restoration of Rain damages on Shimla Nalagarh Road Km. 7/00 to 22/00 (Sh: Construction of B-Wall at Rd. 14/135 to 14/147)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 292308 /- only
Earnest Money : - Rs 6000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	21.60 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	5041.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	22.56 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	8043.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	59.40 Cum	4600.00	Rupees Four Thousand Six Hundred Only	273240.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	35.20 Rmt.	170.00	Rupees One Hundred Seventy Only	5984.00
0					
Total:					292308.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of Rain damages on Link Road from Banuti to Mansa Mata Mandir Km. 0/00 to 0/660 (Sh: Construction of R-Wall at Rd. 0/470 to 0/490)

SCHEDULE OF QUANTITY

S. No.	Sub head and items of work	Qty.	Rate figures	Estimated Cost : - Rs 447499 /- only Earnest Money : - Rs. 9000 /-only Time: - One Month		
				Unit	Amount	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	22.40 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5228.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	27.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	9626.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	90.00 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	414000.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	15.00 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	12627.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	35.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	6018.00
0					Total:	447499.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

SCHEDULE OF QUANTITY
of Work: - Restoration of Rain damages on Hiranagar Dhamoon Road Km. 0/00 to 8/00 (Sh: C/o R-wall at R.D. 6/690 to 6/700)

Estimated Cost: - Rs 389693 /- only
 Earnest Money: - Rs. 8000 /-only
 Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	14.40	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	3381.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	19.52	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	6959.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	79.55	Cum	4600.00	Rupees Four Thousand Six Hundred Only	365930.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	25.60	Rmt.	170.00	Rupees One Hundred Seventy Only	4352.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.80	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	9091.00
0						
Total:						389693.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Rs.

Executive Engineer
 Shimla Rural Division
 HPPWD,Dhami

Name of Work:- Restoration of Rain Damages on Ghanahatti Kalihatti Arki Road Km. 0/00 to 8/060 (Sh: Construction of R-wall at Rd. 6/205 to 6/227)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 492633 /- only
Earnest Money - Rs. 10000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	24.64	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	5751.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	29.70	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	10588.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	99.00	Cum	4600.00	Rupees Four Thousand Six Hundred Only	455400.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	16.50	Cum	841.80	Rupees Eight Hundred Forty One and Paise	13890.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v).20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	41.20	Rmt.	170.00	Rupees One Hundred Seventy Only	7004.00
0						
Total:						492633.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Chikla Rural District,
APR 2010, Ghanahatti

SCHEDULE OF QUANTITY

Name of Work: - Annual Repair & Maintenance of Ghanahatti Bhajol Road Km. 0/000 to 14/000 (Sh: Improvement of Sharp Curve in various Rds. 1/700 to 4/000)

Estimated Cost: - Rs 475829 /- only

Earnest Money : - Rs. 10000 /-only

Time- One Month

S.No.		Sub head and items of work			Qty.			Rate		Unit	Amount
1		2			3		In figure	In words	6	7	
1		Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 66.52 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decrease in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be efacted any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.			1448.93	Cum	328.40	Rupees Three Hundred Twenty Eight and Paise Forty Only	Per cubic metre	475829.00	
									Total:	475829.00	
Amount Quoted by the Contractor in Percentage											

Executive Engineer,
Shimla Rural Division,
HPPWD Dhamsi

Name of Work:- Restoration of rain damages of Link road to Pawaboo Km. 0/00 to 1/300 (Sh: Construction of R-wall at Rd. 0/810 to 0/823)

SCHEDULE OF QUANTITY

Estimated Cost - Rs. 426738 /- only
Earnest Money :- Rs. 9000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	26.00 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6068.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	39.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	13904.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	85.02 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	391092.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.40 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	8755.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	40.70 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	6919.00
0						
					Total:	426738.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Annual Repair & Maintenance on various Roads in Badheri Section under Jutogh Sub Division (Sh: Trimming of Grass and Drain clearing)

SCHEDULE OF QUANTITY

Estimated Cost : - Rs 198127 /- only
Earnest Money : - Rs. 4000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	5850.00 Rmt.	4.00	Rupees Four Only	Per Running Meter	23400.00
2	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	43680.00 Sqm	4.00	Rupees Four Only	Per Square Meter	174720.00
0						
Total:						198120.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Name of Work:- Restoration of rain damages on Shimla Nalagarh Km. 7/00 to 22/00 (Sh: Construction of R-wall at Rd. 14/310 to 14/324.50)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 475179 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	2			5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	29.00 Cum		233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	6769.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	43.50 Cum		356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	15508.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	94.83 Cum		4600.00	Rupees Four Thousand Six Hundred Only	436218.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.60 Cum		841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	9765.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	40.70 Rmt.		170.00	Rupees One Hundred Seventy Only	6919.00
0						
					Total:	475179.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Ghanahatti Parech Road Km. 0/00 to 1/800 (Sh: Construction of R-wall at Rd. 0/933 to 0/945)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 192325 /- only
Earnest Money : - Rs. 4000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			3	4		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.10 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1891.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	18.60 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	6631.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	39.00 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	179400.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	25.90 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	4403.00
0					Total:	192325.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Annual Repair & Maintenance of Shimla Nalagarh Road Km. 6/900 to 22/000 (Sh: Construction of U-Shape drain at Rd. 8/150 to 8/345) Balance work

SCHEDULE OF QUANTITY

Estimated Cost : - Rs 302253 /- only
Earnest Money : - Rs. 6000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	132.48 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	47229.00
2	Providing and laying compacting stone soling of specific size to properly hand packed tightly in under flooring as per drawing complete and technical specification by manual means (i) 100 mm thickness including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	33.12 Cum	1200.00	Rupees One Thousand Two Hundred Only	Per cubic metre	39744.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	41.40 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	215280.00
0					Total:	302253.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

SCHEDULE OF QUANTITY						
Name of Work:- Annual Repair & Maintenance of Shimla Nalagarh Road Km. 6/910 to 22/000 (Sh: Providing and Fixing of steel grating on existing drain in km. 7/625 to 8/00 at various Rds.)						
				Estimated Cost : - Rs 444681/- only Earnest Money : - Rs. 9000/-only Time: - One Month		
S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
1	2	3	4	5	6	7
				figures		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	2.00 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	10400.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4216.32 Kg	103.00	Rupees One Hundred Three Only	Per Kilogrammm	434281.00
0					Total:	444681.00

Amount Quoted by the Contractor in Percentage		Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Hiranagar Jutogh Road Km. 0/00 to 1/200 (Sh: Construction of R-wall at Rd. 0/420 to 0/436)

SCHEDULE OF QUANTITY

Estimated Cost : - Rs 484379 /- only
Earnest Money : - Rs. 10000 /-only
Time : - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	23.04 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5378.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	26.88 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	9583.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	97.20 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	447120.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	45.60 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	7752.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	17.28 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	14546.00
0					Total:	484379.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of Rain damages on Chorti to Pahar Road KM. 0/00 to 4/500 (Sh: Construction of Retaining wall at Rd. 3/895 to 3/905) *Balance Work*

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 434126 /- only
Earnest Money : - Rs. 9000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	27.00 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	6302.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	18.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	6417.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	88.05 Cum	4600.00	Rupees Four Thousand Six Hundred Only	405030.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	9.60 Cum	841.80	Rupees Eight Hundred Forty One and Paise	8081.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	48.80 Rmt.	170.00	Rupees One Hundred Seventy Only	8296.00
0					
				Total:	434126.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of Rain damages on Devnagar Moolbari Road Km. 0/00 to 1/200 (Sh: Construction of Retaining wall at Rd. 0/195 to 0/200)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 141443 /- only
Earnest Money : - Rs. 3000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	8.10 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1891.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	9.70 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3458.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	28.40 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	130640.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.45 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2904.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	15.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2550.00
0					Total:	141443.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhamsi

SCHEDULE OF QUANTITY
Name of Work:- Restoration of Rain damages on Ghanahatti Bhajol Road Km. 0/00 to 14/000 (Sh: Construction of Retaining wall at Rd. 3/631 to 3/651) Balance work

Estimated Cost - Rs 197697 /- only
 Earnest Money : - Rs. 4000 /-only
 Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	11.34 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	2647.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	13.58 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	4841.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	39.76 Cum	4600.00	Rupees Four Thousand Six Hundred Only	182896.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.83 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	4066.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	19.10 Rmt.	170.00	Rupees One Hundred Seventy Only	3247.00
0					
				Total:	197697.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhami

Name of Work:- Annual Repair & Maintenance on Khalag Ka Ghat to Khairi Lohali Road Km. 0/000 to 2/00 (Sh: Construction of V-Shaped Drain in Km. 0/00 to 0/800)

SCHEDULE OF QUANTITY

S. No.	Sub head and Items of work	Qty.	Estimated Cost: - Rs 463377 /- only		Earnest Money : - Rs. 9000 /-only	
			Time: -		One Month	
1	2	3	4	5	6	7
			Rate figures		Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	85.32 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	30417.00
2	Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding material moorem earth etc. complete as per HPPWD specification 100 mm spread thickness (Finished work including material and labour) including carriage of material upto all leads and lifts as per the direction of Enigneer in Charge.	38.40 Cum	1200.00	Rupees One Thousand Two Hundred Only	Per cubic metre	46080.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	74.40 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	386880.00
0						
					Total:	463377.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama

Name of work:- Restoration of rain damages on Paoghatti to Khari Lohali Road Km. 0/00 to 2/220 (Sh:- Providing and laying 25 mm thick Bituminous Concrete along with providing & laying of Hot Applied Thermoplastic compound 2.50 mm thick for edge line in between km. 1/00 to 1/320)

Schedule of Quantity

Estimated Cost - Rs 433546 /- only
Earnest Money - Rs 9000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1.00	Providing and applying tack coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per the direction of Engineer in Charge.	1020.50 Sqm	24.79	Rupees Twenty Four and Paise Seventy Nine Only	Per cubic metre	25298.00
2.00	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	153.08 Sqm	514.28	Rupees Five Hundred Fourteen and Paise Twenty Eight Only	Per cubic metre	78726.00
3.00	Providing and laying bituminous concrete 25 mm (twenty five milimetre) thick with 100-120 (one hundred -one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 (five point four to five point six) per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five hundred nine) complete in all respects including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	25.51 Cum	12415.61	Rupees Twelve Thousand Four Hundred Fifteen and Paise Sixty One Only	Per cubic metre	316722.00
4.00	Providing and Laying of Hot applied Thermoplastic compound 2.50 mm thick including rectorising glass beads @ 250 grams per square metre area. Thick ness of 2.50 mm is exclusive of surface applied glass beads as per IRC: 35. The finished surface to be level uniform and free from streaks and holes including entire carriage of materials upto all leads and lifts through all modes of transportation as per the direction of Engineer in Charge.	32.00 Sqm	400.00	Rupees Four Hundred Only	Per Running Metre	12800.00
0					Total:	433546.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD Dharni

Name of Work:- Restoration of rain damages on Didoghatti Karechi Road in Km. 0/00 to 12/015 (Sh: Construction of B-Wall at Rd. 3/970 to 4/000)

Schedule of Quantity

Estimated Cost: - Rs 385091 /- only
Earnest Money : - Rs. 8000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	16.20 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	3781.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	37.20 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	13262.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	78.00 Cum	4600.00	Rupees Four Thousand Six Hundred Only	358800.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	54.40 Rmt.	170.00	Rupees One Hundred Seventy Only	9248.00
0					
				Total:	385091.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Khairi Lohali Road Km 0/00 to 2/220 (Sh: Construction B-Wall at Rd. 0/00 to 0/018)

Schedule of Quantity

Estimated Cost - Rs 439030 /- only
Earnest Money - Rs 9000 /- only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	figures		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	36.00 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	8402.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	33.84 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	12064.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	89.10 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	409860.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	51.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	8704.00
0					Total:	439030.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama

DRAFT SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER Kasumpti DIVISION H.P.P.W.D.						Estimated Cost:- 4,95,975.00	
Name of Work :- Improvement & Widening of Shimla to Mandi road Km 6/00 to 22/000 (SH:- M/T of extended portion at Various Rds In Km 6/00 to 22/000).						Earnest Money :- 10,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer-in-charge at site. according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2917.50	Cum	170.00	Rupees One Hundred Seventy Only	Per Cubic Metre	495975.00
	Quoted rates Percentage in figures					Total	495975.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

DNIT approved for Rs. 4,95,975/- Only vide DNIT Register Sr.No..... the financial year 2025-26. T/S No Amt 510854.00

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

Name of Work:- Restoration of rain damages on Neri Sangti Road Km. 0/00 to 6/465 (Sh: Construction of R-wall at Rd. 2 /030 to 2/045)

Schedule of Quantity

Estimated Cost: - Rs 455521 /- only

Earnest Money : - Rs. 9000 /-only

Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	21.60 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 5041.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	25.20 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 8984.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	91.13 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 419198.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	45.60 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 7752.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	17.28 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 14546.00
0					Total: 455521.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Schedule Of Quantity

Name Of Work :- A/R & M/O Link road to Basol km. 0/00 to 1/075 (SH:- Cutting at various Rds for curve improvement and construction of Catchpit at Km 0/450 along with construction of U shape drain in between km 0/430 to 0/448)

Estimated Cost:- 4,22,991.00

Earnest Money:- 10,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP PWD specifications of 1999 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the useless materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones, shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 89.33 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	898	Cum	368.00	Rupees Three Hundred Sixty Eight Only	Per Cubic metre	330454
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	26.73	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	9529
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P C C grade M 10, (i) C. C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	15.66	Cum	5300.00	Rupees Five Thousand Three Hundred Only	Per Cubic metre	82998
Total Rs.							422991
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP PWD, Dhara

Schedule Of Quantity						Estimated Cost:- 2,36,762.00	
Name Of Work :- Restoration of Rain Damages on Thachi Seri Shalli road km 0/00 to 3/285 (SH:- C/o R/wall in b/w km 0/458.50 to 0/465)						Earnest Money:- 4,800.00	
S.No	Description of Work	No. of Qty.	Rate	In figures	In words	Unit	Amount
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	8.58	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per Cubic metre	1707
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	9.88	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	3522
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	47.52	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	218592
4	Back filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	11.31	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	9521
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	18.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	3420
Total Rs.							236762
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi

SCHEDULE OF QUANTITY
Name of Work:- Restoration of Rain damages on Link Road Bainsh To Bagera Km. 0/00 to 3/000 (Sh: Construction of PCC R/Wall at Rd. 1/185 to 1/191)

Estimated Cost: - Rs 284225 /- only
 Earnest Money : - Rs. 6000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.41 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1729.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	29.76 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	10609.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	57.07 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	262522.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.48 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5455.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	23.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	3910.00
0						
Total:						284225.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD,Dhami

Name of Work:- Construction of Bainsh Bangera Ambulance Road Km. 0/00 to 3/00 (Sh: Construction of RCC 900 mm dia Hume pipe culvert at Rd. 0/800 along with wing wall)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 197668 /- only
Earnest Money : - Rs. 4000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	28.00 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6535.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	34.30 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	157780.00
3	Providing and laying reinforced cement concrete pipe NP2 as per design in single Row. Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. (c) 900 mm dia	7.50 Rmt.	3616.60	Rupees Three Thousand Six Hundred Sixteen and Paise Sixty Only	Per Running Metre	27125.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	3.36 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2828.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	20.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	3400.00
0					Total:	197668.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Rattanpur Bathmana Road Km. 0/000 to 1/600 (Sh: Construction of Retaining Wall at Rd. 0/090 to 0/105)

SCHEDULE OF QUANTITY

S. No.	Sub head and items of work	Qty.		Estimated Cost - Rs 192074 /- only Earnest Money - Rs 4000 /-only Time - One Month		
		3	4	Rate figures	Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603 1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	11.25	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	2626.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	10.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	3744.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	38.85	Cum	4600.00	Rupees Four Thousand Six Hundred Only	178710.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.00	Rmt.	170.00	Rupees One Hundred Seventy Only	5100.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (I) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.25	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	1894.00
0						
					Total:	192074.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

NAME OF WORK:- Restoration of Rain damages on Ghanahatti Nehra Bhukho Road Km. 0/00 to 8/825 (Sh: Construction of R-wall at Rd. 0/026 to 0/038 and Providing & fixing W-Metal Beam Crash Barrier at Rd. 7/015 to 7/038)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 474286 /- only
Earnest Money : - Rs. 9000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	14.22 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3319.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	36.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	12834.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C. grade M 20, Nominal mix (1:2:4) (one Cement isto two sand isto four graded crushed stones aggregate 20 mm (twenty milimetre) nominal size including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	2.77 Cum	5659.10	Rupees Five Thousand Six Hundred Fifty Nine and Paise Ten Only	Per cubic metre	15676.00
4	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix . Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	79.01 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	363446.00
5	Providing and erecting a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal rail 70 cm. above road/ground level fixed on GI Sheet channel vertical post 150x75x5 mm spaced 1.5 m center to center, 1.8 m high, 1.1 m below ground /road level, all steel part and fitments to be galvanised by hot dip process, all fitting to conforms to IS:1367 and Is:1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810 including high intensity grade all weather proof reflective sheeting multi colour tape fixed with mechanical means with high visible(cautionary) from long distance i.e. in fog prone area, black spot point and narrow curve etc.	18.00 Rmt.	3818.00	Rupees Three Thousand Eight Hundred Eighteen Only	Per Running Metre	68724.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.32 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3637.00
7	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	35.00 Rmt.	190.00	Rupees One Hundred Ninety Only	Per Running Metre	6650.00
0						
Total:						474286.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Rs.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

Name of Work:- Restoration of rain damages on Thachi Seri Shalli Road Km. 0/00 to 3/285 (Sh: Construction of Breast Wall at Rd. 0/375 to 0/378.75) from road level to Govt. Primary School Thachi Building)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 497172 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	2					
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	22.09 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5156.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	14.40 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	5134.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	103.50 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	476100.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	6.75 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5682.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	5100.00
0						
					Total:	497172.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

19-10-2025
per

Work: - Restoration of rain damages on Pakki Bawari Sakrah Sedan Road Km. 0/00 to 5/700 (Sh: Construction of Retaining Wall in Km. 3/610 to 3/615 to protect the house of Smt. Batti Devi W/o Lt. Sh. Musu Ram, V.P.O. Shakrah District Shimla)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 256800 /- only
Earnest Money : - Rs. 5000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate figures		Unit	Amount
			3	4		
1	Removal of Inad slides / slips clearance, Removal of land slide in hilly area in ordinary Rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a all leads and lifts as per technical specification 302.3.5 and 1611 and as per the direction of Engineer in Charge.	92.00 Cum	250.00	Rupees Two Hundred Fifty Only	Per cubic metre	23000.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	12.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	4278.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	51.95 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	238970.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.05 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9302.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	25.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	4250.00
0					Total:	256800.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Construction of Link Road Palkari Makri Km. 0/00 to 1/600 (Sh: Construction of V-Shape drain in Km. 0/800 to 1/550)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 480356 /- only
Earnest Money - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	112.50 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 40106.00
2	Providing and laying compacting stone soling of specific size to properly hand packed tightly in under flooring as per drawing complete and technical specification by manual means (i) 100 mm thickness including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	41.25 Cum	1400.00	Rupees One Thousand Four Hundred Only	Per cubic metre 57750.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Millimetre size) concrete mix, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	75.00 Cum	5100.00	Rupees Five Thousand One Hundred Only	Per cubic metre 382500.00
0				Total:	480356.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharni

7820110
2-01-60
2-01-60
2-01-60

Work:- Construction of Link Road Palkari Makri Km. 0/00 to 1/600 (Sh: Construction of PCC Parapets at various RDs. in km. 0/00 to 1/600)

SCHEDULE OF QUANTITY

S. No.	Sub head and items of work	Qty.		Rate figures	Unit	Amount
		3	4			
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	23.09	Cum	356 50	Rupees Three Hundred Fifty Six and Paise Fifty Only	8232 00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	92.34	Cum	5100 00	Rupees Five Thousand One Hundred Only	470934 00
0					Total:	479166.00

Estimated Cost - Rs 479166 /- only
Earnest Money - Rs. 10000 /-only
Time - One Month

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work: Special Repair to Judicial Academy at Ghandal Shimla (Sh: Providing and applying waterproofing treatment in water harvesting tank to avoid sinking / leakage) Job No. 1

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 464094 /- only
Earnest Money : - Rs. 9000 /-only
Time: - One Month

S. No.		Sub head and Items of work		Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6	7	
1	Providing and repairing all cracks wider than 1 mm, construction joints, wall to floor and wall to wall joints need to be opened into a v-groove and filled with a mixture of Polymer Modified Repair Mortar and mixed in a ratio of 1:3, as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by the Engineer In charge allowing drying gap between successive coats. Providing and applying three coats Crystallflex 2K Superstrong over the prepared surface as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by the Engineer In charge allowing drying gap between successive coats. Providing and applying One coat Acryflex 2K Extrastrong over the prepared surface as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by the Engineer In charge allowing drying gap between successive coats. Before applying AcryFlex 2K ExtraStrong, the substrate has to be pre-wetted thoroughly in order to achieve a slightly (not shiny) humid surface. Remove excess water or puddles. Providing and applying One coat of AB-POX 016 Epoxy Primer over the prepared surface and sprinkling of dry quartz sand (approx. 0.5 kg/Sq. m) as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by the Engineer In charge allowing drying gap between successive coats. Providing and applying 2 final coats of AB-POX 466 WI as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by the Engineer In charge allowing drying gap between successive coats.	187.21	Sqm	2479.00	Rupees Two Thousand Four Hundred Seventy Nine Only	Per Square Metre	464094.00
0							
						Total:	464094.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Name of Work:- Construction of Ambulance Road Bainsh to Bangera Road Km. 0/00 to 3/00 (SH:- Providing and laying WBM-G-I in Km. 1/900 to 2/800)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 492774 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	2	3	4	5	6	7
1	Preparation of sub grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil complete as per H.P.PWD. Specifications including carriage of materials in all leads and lift as per direction of Engineer-in-Charge.	2722.50 Sqm	3.00	Rupees Three Only	Per Square Metre	8168.00
2	Consolidation of sub-grade with power road roller including making the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade complete as per H.P.PWD specification including carriage of materials with in all leads and lift and as per the direction by the Engineer-In- charge	2722.50 Sqm	3.00	Rupees Three Only	Per Square Metre	8168.00
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405. By Mechanical Means including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	272.25 Cum	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per cubic metre	476438.00
0					Total:	492774.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Name of Work:- Restoration of rain damages on Reodhar Piplidhar Road Km. 0/00 to 2/600 (Sh: Construction of R-wall at Rd. 1/585 to 1/600)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 354542 /- only
Earnest Money : - Rs. 7000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	10.05 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	2346.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	15.60 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	5561.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	70.05 Cum	4600.00	Rupees Four Thousand Six Hundred Only	322230.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	21.60 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	18183.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	36.60 Rmt.	170.00	Rupees One Hundred Seventy Only	6222.00
0				Total:	354542.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhama

Name of Work:- Restoration of Rain damages on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Construction of Retaining wall at Rd. 8/684 to 8/691)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 350852 /- only
Earnest Money - Rs 7000 /- only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	13.72 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 3202.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	16.80 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 5989.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	72.73 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 334558.00
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	24.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 4080.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	15.47 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 13023.00
0					
				Total:	360852.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Rs.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Schedule Of Quantity						Estimated Cost:- 4,61,006.00	
Name Of Work :- A/R & M/O on Nehra Bhukho road km. 0/00 to 8/00 (SH:- Construction of PCC R/wall at Rd. 6/600 to 6/609)						Earnest Money:- 10,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	17.64	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	4117
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	39.24	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	13989
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	93.51	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	430146
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (1) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	9.90	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	8334
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	26.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	4420
Total Rs.							461006
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama

Schedule Of Quantity						Estimated Cost:- 4,97,848.00	
Name Of Work :- A/R & M/O on Nehra Bhukho road km. 0/00 to 8/00 (SH:- Construction of PCC R/wall at Rd. 6/800 to 6/815)						Earnest Money:- 10,000.00	
Description of Work						Time:- One Months.	
S.No	2	No. of Qty.		Rate		Unit	Amount
1		3	4	5	6		
				In figures	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	18.48	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	4313
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	21.14	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	7536
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	102.34	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	470764
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8. (1) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	12.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	10135
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	30.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	5100
Total Rs.							
Amount Quoted by the Contractor in Percentage							497848
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Name of Work:- Restoration of rain damages on Pakki Bawari Shakrah Sedan Road Km. 0/00 to 5/700 (Sh: C/o ^{Breast} Retaining wall at Rd. 3/430 to 3/440)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 476124 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	12.35 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 2882.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	52.20 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 18609.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	95.12 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 437552.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.80 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 9091.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	47.00 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 7990.00
0					
				Total:	476124.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Bainsh Bangera Road km. 0/000 to 3/000 (Sh: Construction of Retaining wall at Rd. 0/135 to 0/153)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 495848 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	15.84 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 3697.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	22.35 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 7968.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	99.79 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 459034.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	20.06 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 16887.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	48.60 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 8262.00
0					Total: 495848.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami