HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.: PW/ESDD/CONT/2025-26/- 11083-92 **Dated:** 31-03-2026

To

The Executive Engineer (IT Cell),
Nigam Vihar, Shimla-2.

Subject: **Publishing of Tender Notice.**

Jai Hind

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender along with Schedule of Quantities for uploading on departmental website as per Notification Pr. SEC(PW) to the Govt. of HP letter No. PBW(B)A9(3)1/2020 dated Shimla-26th July 2021.

It is certified that the works mentioned in the Notice Inviting Tenders are urgent in nature and in public Interest.

DA/NIT,SQs

Executive Engineer
Electrical Division
HP PWD Palampur

Copy forwarded to the following for information and necessary action please:

1. The Superintending Engineer, 2nd Electrical Circle, HP PWD Dharamshala.
2. All the Assistant Engineers Working under this Division.
3. Drawing Branch of this office.
4. The Notice board in this office.

Executive Engineer
Electrical Division
HP PWD Palampur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"Notice Inviting Tenders"

Sealed percentage rate tenders on form 7&8 are hereby invited by the Executive Engineer, Electrical Division, HP PWD Palampur on behalf of the Governor of H.P. for the following work from the approved and eligible contractors enlisted in HP PWD (Elect.) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act 1968 so as to reach in his office on or before **07-04-2026** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **06-04-2026** up to 4.00 P.M. and the application for issue of tender form shall be received on **06-04-2026** up to 12.00 noon.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time Limit	Form No.	Cost of Form
1	R/M of EI in various Govt. H/R buildings under ESD HPPWD Dharamshala, District Kangra (H.P.) (Providing and fixing Air Conditioning System in the chamber of Chief Engineer (H.P.) HPPWD Dharamshala)	92,095/-	1900/-	Three months	7/8	350/-
2	Replacement of old/damaged heating element 25 kw capacity installed in hot water generator of HVAC plant, Auditorium building Dr. RPGMC Kangra at Tanda	99,250/-	2000/-	One month	7/8	350/
3	Refilling of portable Fire Extinguishers of different capacity and types installed at Autopsy Block, Ozygen Plant Room area, Burn Unit Building and Maharaja sansar Chand Guest House at Dr. RPGMC Kangra at Tanda for the year 2026-27	90,800/-	2000/-	One month	7/8	350/
4	Repair and Maintenance of Portable Fire Extinguishers installed in 500 Bedded Hospital Dr. RPGMC Tanda (SH: Refilling of Portable Fire Extinguishers of different Capacity and type at OPD block, treatment block, maternity block and general male and female wards etc. of 50 bedded hospital Dr. RPGMC Tanda in Distt. Kangra (H.P.) for the year 2025-2026	88,360/-	1800/-	One month	7/8	350/
5	Repair servicing & comprehensive maintenance of different type air conditioning units installed in ozygen plant room, medicine store room in basement floor of 500 bedded hospital Dr. RPGMC Kangra at Tanda for the year 2026-2027	82,780/-	1700/-	One year	7/8	350/
6	Providing and fixing of portable fire extinguishers and Refilling of existing Portable Fire Extinguishers installed in PG Hostel for Boys at Dr. RPGMC Tanda in Distt. Kangra (HP)	99,558/-	2000/-	One month	7/8	350/
7	Repair, Servicing & Comprehensive Maintenance of different types air-conditioning units installed in NICU SICU Wards and Labour room etc. in Ist floor of 500 Bedded Hospital Dr. RPGMC Kangra at Tanda for the year 2026-27	71,697/-	1500/-	One year	7/8	350/
8	Repair, Servicing & Comprehensive Maintenance of cassette type air-conditioning units installed in AICU/Trauma Centre at 1st & 2nd floor casualty block of 500 bedded Hospital Dr. RPGMC Kangra at Tanda for the year 2026-27	76,500/-	1600/-	One year	7/8	350/

HIM SUCHNA AVAM JAN SAMPARK VIBHAG

This is certified that the above works are required to be carried out immediately being emergent nature of work in Public Interest. The Tender documents shall be issued only to those contractor/firm who fulfill the following criteria/documents with the application.

Conditions:

1. The contractor should have the EPF registration certificate should be attached with application.
2. The GST registration certificate
3. The contractor should produce a copy of latest enlistment/renewal.
4. The latest ITR filed should be attached with application.
5. The bidders enlisted in a particular class shall be eligible to tender for his own class or one step below.
6. The bidder should attach authorization and work done certificate with application for Specialized Jobs.
7. In case of Holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
8. Ambiguous/telephonic/conditional tenders or tenders fax/email/whatsapp shall not be considered and will be summarily be rejected.
9. The FDR duly pledged should be attached separately with each tender.
10. Only two number tender forms will be issued to the eligible contractor.
11. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected.
12. The Executive Engineer, Electrical Division, HP PWD Palampur reserves the right to reject any tender without assigning any reasons.

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-R/M of El in various Govt. N/R buildings under ESD HPPWD Dharamshala, District Kangra (H.P.) (Providing and fixing Air Conditioning System in the chamber of Chief Engineer (H.P.)HPPWD Dharamshala).		(1)	**ESTIMATED COST:92,095/-only.** **EARNEST MONEY: Rs.1900-/-only** **TIME ALLOWED:-Three Months**

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1.00	Supplying, installation, testing and commissioning of Following Ton (Hot & Cold) 3 star Inverter Split type Air-Conditioning unit with R32 Refrigerent, Power supply 1 Phase 50 Hz, 230 V of following make confirming to I.S.I.-1391 PART-1992 with ammendment No. 1 (expect power consumption norms) fitted with hermatically shielded air-compressor, making connections , testing etc. as required complete in all respects.					
1.02	**A.C. Unit 1.8/ 2.0 Ton capacity (Split Inverter)**	1	71585	Rs. Seventy one thousand five hundred eighty five only	Each	71585
1.03	**Makes:- Daikin/ O-General /Mitsubishi/ Toshiba**					
2.00	Providing & fixing of **M.S. Outdoor heavy duty stand** powder coated suitable suitable to hang Following type AC with six nos. anchor bolts (The make of outdoor units and compressor shall be same) as required complete in all respects.					
2.01	**MS Outdoor Stand for Split AC 1.8 / 2.0 TR**	1	750	Rs. Seven hundred fifty only	Each	750

3.00	Supplying, Installation, testing & Commissioning of the insulated refrigerant piping Size of (6.4-12.7) mm and (9.5-15.9) mm for all the Outdoor Units as per specifications with insulation of thick 19 mm Nitrile rubber through out the running length of the refrigerant piping. Nitrile Rubber of Density 50+/20% (Class O) kg/m3 to interconnect Indoor & Outdoor Units for each circuit etc. as required complete in all respects.					
3.01	**Ref. Copper Piping for AC 2.0 TR**	5	1056	Rs. One thousand & fifty six only	Per Meter	5280
4.00	Supplying and fixing of PVC hard drain piping with fitting, valves & Insulation with 10mm for indoor Application Closed Cell nitrile rubber 60+/-10kg/m3 with the accessories in surface/recess including cutting the wall and making good the same etc. as required complete in all respect.	8	135	Rs. One hundred thirty five only	Per Meter	1080
5.00	Supplying and fixing of cable tray DLP trunking size 105mmx50mm for covering of copper pipe along with the accessories etc. as required complete in all respects.	8	1480	Rs. One thousand four hundred eighty only	Per Meter	11840
6.00	Providing and laying of Communication Shielded cabling between ODU & IDU and between ODU & central controller in flexible PVC Conduit etc. as required complete in all respects.					
6.01	Control cabling from indoor to outdoor unit Split AC	8	195	Rs. One thousand ninety five only	Per metre	1560
	Total:-					**92095**

Draft Schedule of Quantity Checked & Approved for Rs. 92,095=/only

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Replacement of old/damaged heating element 25 kw capacity installed in hot water generator of HVAC plant, Auditorium building Dr. RPGMC Kangra at Tanda.

(2)

ESTIMATED COST:99,250/-only.
EARNEST MONEY: Rs.2000-/-only
TIME ALLOWED:- One Month

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Supplying and fixing of 25 kw electrical water heater for 125 kw hot water generator complete with all accessories including testing, commissioning etc. as required complete in all respects and to the best satisfaction of Engineer-in-charge.					
1.1	**25 kw electrical water heater for 125 kw hot water**	5	19850.00	Rs. Ninteen thousand eight	Each	99250
	Makes:-Rapid cool					
	Dismantel Credit of Useful Material Rs. (-)2000/-					**99250**
	Total:-					

Draft Schedule of Quantity checked & Approved for Rs. 99250-/Only

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Refilling of portable Fire Extinguishers of different capacity and types installed at Autopsy Block, Oxygen Plant Room area , Burn Unit Building and Maharaja sansar Chand Guest House at Dr, RPGMC Kangra at Tanda for the year 2026-27.

(3)

ESTIMATED COST:90,800/-only.
EARNEST MONEY: Rs.2000-/-only
TIME ALLOWED:- One Month

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Refilling of Portable Fire extinguishers,CO2 type 4.5 kg. Capacity as required complete in all respect.	20	1450.00	Rs. One thousand four hundred fiftty only	Each	29000
2	Refilling of Portable Fire extinguishers Water Co2 Gas Cartridge type capacity 9 litrs. as required complete in all respect.	6	750.00	Rs. Seven hundred fifty only	Each	4500
3	Refilling of Portable Fire extinguishers Water type(S/P) Capacity 9 litrs. as required complete in all respect.	5	800.00	Rs. Eight hundred only	Each	4000
4	Refilling of Portable Fire extinguishers ABC type(filled with 50 Map Powder) 4 kg capacity as required complete in all respect.	4	1260.00	Rs. One thousand sixty only	Each	5040
5	Refilling of Portable Fire extinguishers ABC type (filled with 50 Map Powder) 6 kg.capacity as required complete in all respect.	2	1590.00	Rs. One thousand five hundred ninety only	Each	3180
6	Refilling of Portable Fire extinguishers ABC type (filled with 50 Map Powder) 9 kg.capacity as required complete in all respect.	15	2190.00	Rs. Two thousand one hundred ninety only	Each	32850
7	Replacement of ABC Cylinder Pipe as required complete in all respect.	8	560.00	Rs five hundred sixty only	Each	4480
8	Replacement of Water Type Cylinder Pipe as required complete in all respect.	3	600.00	Rs. Six hundred only	Each	1800

9	Replacement of Co2 Cylinder Pipe 1 mtr. Capacity as required complete in all respect.	7	850.00	Rs. Eight hundred fifty only	Each	5950
	Total:-					**90800**

Draft Schedule of Quantity checked & Approved to be 90980/-

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of Portable Fire Extinguishers installed in 500 Bedded Hospital Dr. RPGMC Tanda.(SH: Refilling of Portable Fire Extinguishers of different Capacity and type at OPD block , treatment block , maternity block and general male and female wards etc. of 50 bedded hospital Dr. RPGMC Tanda in Distt. Kangra (H.P).for the year 2025-2026.

(4)

ESTIMATED COST:86,360-only.
EARNEST MONEY: Rs.1800-/-only
TIME ALLOWED:-One month

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Refilling of Portable Fire extinguishers,CO2 type 4.5 kg. Capacity complete in all respect.	15	1450	Rs. One thousand four hundred fifty only	Each	21750
2	Refilling of Portable Fire extinguishers Water type (S/P) Capacity 9 litrs. complete in all respect.	16	800	Rs. Eight hundred only	Each	12800
3	Refilling of Portable Fire extinguishers ABC type (filled with 50 Map Powder) 6 kg.capacity complete in all respect.	15	1590	Rs. One thousand five hundred ninety only	Each	23850
4	Refilling of Portable Fire extinguishers Mechanical Foam type 9 liters Capacity. Complete in all respect.	15	1100	Rs. One thousand one hundred only	Each	16500
5	Replacement of ABC Cylinder Pipe	6	560	Rs. Five hundred sixty only	Each	3360
6	Replacement of Water Type Cylinder Pipe	5	600	Rs. Six hundred only	Each	3000
7	Replacement of Co2 Cylinder Discharge Pipe with 1 Mtrers	6	850	Rs. Eight hundred fifty only	Each	5100
	Total:-					**86360**

Draft Schedule of Quantity checked & Approved for Rs. 86,360-/-

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair, Servicing & Comprehensive Maintenance of different types air-conditioning units installed in Oxygen plant room, Medicine store room in basement floor of 500 Bedded Hospital Dr. RPGMC Kangra at Tanda for the year 2026-27.		5	***ESTIMATED COST:82,780/-only.*** ***EARNEST MONEY: Rs.1700-/-only*** ***TIME ALLOWED:-one year***

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Repair, servicing & comprehensive Maintenance of Split Air-Conditioning Units having following capacity including maintenance of voltage stabilizer and all other accessories extra copper pipes with sleeves, drain pipe, wire, insulation and battens etc. with servicing, cleaning the filters, charging/topping up of refrigerant/R-22 Gas when required throughout the year excluding replacement of the compressor of A.C. units which are beyond repair. The repair and maintenance has been done as per instructions and directions to the best satisfaction of Engineer-in-charge.					
1.1	**Split type A.C. units 2 T.R capacity**	4	4500.00	Rs. Four thousand five hundred only	Each	18000
2	Replenishment/charging of refrigerant R-22/32 (Gas) in split air-conditioning units as required complete in all respects as per the direction and to the best satisfaction of Engineer-in-charge.	3	2390.00	Rs. Two thousand three hundred ninety only	Per Kg	7170
3	Supplying and fixing of following accessories suitable for 1.5/2 Ton capacity split type air-conditioning units as required complete in all respects and as per directions of Engineer-in-charge.					
3.1	**PCB**	2	14200.00	Rs. Forteen thousand two hundred only	Each	28400

3.2	**Capacitor 40 - 65 MFD**	1	690.00	Rs. Six hundred ninety only	Each	**690**
4	Providing & fixing of extra copper tubes for refrigerant and condensate (1/4" x 1/2") for 1.5 T.R. split type A.C. units and wiring with suitable size of HRFRLS copper conductor single core cables, including the cost of insulation etc. as required complete in all respects.	3	1300.00	Rs. One thousand three hundred only	Per Mtr.	**3900**
5	Supplying, installation, testing and commissioning of compressor of following capacity suitable for required size/ capacity air-conditioning units complete in all respects and to the best satisfaction in Engineer-in-charge.					
5.1	**Compressor for 2 Ton A.C. unit**	1	15800.00	Rs. Fifteen thousand eigh hundred only	Each	**15800**
6	Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	2	621.00	Rs. Six hundred twenty one only	Each	**1242**
7	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required					
7.1	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	10	311.00	Rs. Three hundred elevn only	Per Mtr.	**3110**
8	Supplying and fixing wall mounting voltage stabilizer of following rating with output 240 volts with voltage regulation range from 130 volt to 300 volt and auto cut off beyond this range and time delay operation for the surges and fluctuations suitable for 2 T.R. capacity split type Air-Conditioner including making connections etc. as required complete in all respects.					

8.1	**Automatic Voltage Stabilizer 4 kVA**	1	4468.00	Rs. Four thousand four hundred sixty eight only	Each	4468
	Makes:- Voltas/Microtek/V-Guard					
	Total:					**82780**

Draft Schedule of Quantity Checked & Approved for Rs. 82780-by

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Providing and fixing of portble fire extinguishers and Refilling of existing Portable Fire Extinguishers installed in PG Hostel for Boys at Dr. RPGMC Tanda in Distt. Kangra (HP).			(6)	**ESTIMATED COST:99,558/-only. EARNEST MONEY: Rs.2000-/-only TIME ALLOWED:- One Month**		
SR. NO.	**DESCRIPTION**	**job No**	**RATES**	**WORDS**	**UNIT**	**AMOUNT**
1	Refilling of Portable Fire extinguishers,CO2 type 4.5 kg. Capacity complete in all respect.	6	1450	Rs. One thousand four hundred fifty only	Each	8700
2	Refilling of Portable Fire extinguishers Water type (S/P) Capacity 9 litrs. complete in all respect.	6	800	Rs. Eight hundred only	Each	4800
3	Refilling of Portable Fire extinguishers ABC type (filled with 50 Map Powder) 6 kg.capacity complete in all respect.	6	1590	Rs. One thousand five hundred ninety only	Each	9540
4	Providing and fixing Carbon dixoide CO2 4.5 kg type fire extingushers ISI mark. CE and EN Certfied, consisting of seamless cylindrical body, squeeze lever discharge valve fitted with pressure indicating guage internal discharge tube, 30cms long high pressure discharge hoase, discharge nozzle, suspension bracket, confirming to IS: 15683 finished externally with red enamel paint and M S Wheel type complete with internal charge as required complete in all respects.	3	12476.00	Rs. Twelve thousand four hundred seventy six only	Each	37428
	Make: Minimax//Padmini/Aska/OMEX					

5	Providing and fixing stored pressure vessel ABC 6 Kgs. Powder type fire extingushers ISI mark. CE and EN Certfied,consisting of seamless cylindrical body, squeeze lever discharge valve fitted with pressure indicating guage internal discharge tube, 30cms long high pressure discharge hoase, discharge nozzle, suspension bracket, confirming to IS: 15683 finished externally with red enamel paint and fixed to wall with brackets complete with internal charge.	2	6835	Rs. Six thousand eight hundred thirty five only	Each	13670
	Make: Minimax//Padmini/Aska/OMEX					
6	Providing & fixing of IS marked 15683 Water type 9 Litre (S/P) cylindrical body, squeeze lever discharge valve fitted with pressure discharge hose, discharge nozzle, etc. finished externally with red enamel paint and fixed to wall with brackets complete with internal charges.	4	6355	Rs. Six thousand three hundred fifty five only	Each	25420
	Make: Minimax//Padmini/Aska/OMEX					
	Total:					99558

Draft Schedule of Quantity checked & Approved
for Rs. 99,558 tty

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-Repair, Servicing & Comprehensive Maintenance of different types air-conditioning units installed in NICU-SICU Wards and Labour room etc. in Ist floor of 500 Bedded Hospital Dr. RPGMC Kangra at Tanda for the year 2026-27.			***ESTIMATED COST:71,697/-only. EARNEST MONEY: Rs1500-/-only TIME ALLOWED:-One year***

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Repair, servicing & comprehensive Maintenance of Split Air-Conditioning Units having following capacity including maintenance of voltage stabilizer and all other accessories extra copper pipes with sleeves, drain pipe, wire, insulation and battens etc. with servicing, cleaning the filters, charging/topping up of refrigerant/R-22 Gas when required throughout the year but excluding replacement of the compressor of A.C. units which are beyond repair. The repair and maintenance has been done as per instructions and directions to the best satisfaction of Engineer-in-charge.					
1.1	**Split type A.C. units 2 T.R capacity**	8	4500.00	Rs. Four thousand five hundred only	Each	36000
2	Replenishment/charging of refrigerant R-22/32 (Gas) in split air-conditioning units as required complete in all respects as per the direction and to the best satisfaction of Engineer-in-charge.	6	2390.00	Rs. Two thousand three hundred ninety only	Per Kg	14340
3	Supplying and fixing of following accessories suitable for 1.5/2 Ton capacity split type air-conditioning units as required complete in all respects and as per directions of Engineer-in-charge.					
3.1	PCB	1	14200.00	Rs. Forteen thousand two hundred only	Each	14200

3.2	Capacitor 40 - 65 MFD	3	690.00	Rs. Six hundred ninety only	Each	2070
4	Providing & fixing of extra copper tubes for refrigerant and condensate (1/4" x 1/2") for 1.5 T.R. split type A.C. units and wiring with suitable size of HRFRLS copper conductor single core cables, including the cost of insulation etc. as required complete in all respects.	2	1300.00	Rs. One thousand three hundred only	Per Mtr.	2600
5	Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	1	621.00	Rs. Six hundred twenty one only	Each	621
6	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required					
6.1	**2 X 4 sq. mm + 1 X 4 sq. mm earth wire**	6	311.00	Rs. Three hundred elevn only	Per Mtr.	1866
	Total:					***71697***

Draft Schedule of Quantity Checked & Approved
for Rs 71697/-

Executive Engineer
Electrical Division
HPPWD Palampur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Repair, Servicing & Comprehensive Maintenance of cassette type air-conditioning units installed in AICU/Trauma Centre at 1st & 2nd floor casualty block of 500 bedded Hospital Dr. RPGMC Kangra at Tanda for the year 2026-27.		***ESTIMATED COST:76,500/-only.*** ***EARNEST MONEY: Rs.1600-/-only*** ***TIME ALLOWED:-one year***

SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Repair, Servicing & Comprehensive Maintenance of cassette type A.C. units (Hot & Cold) 'Daikin' make includes following services in case of breakdown during the AMC contract period as required complete in all respects and to the best satisfaction of Engineer-in-charge.	7	9500	Rs. Nine thousand five hundred only	each	66500
i)	Quarterly services i.e. 3 dry and 1 wet or immediate attendance of breakdown if any, Refrigerent Gas charging (if required), Replacement of compressor oil , Spare Parts shall be replaced in case of minor breakdown during AMC. Compressor and PCB parts are excluded in AMC as required compete in all respects.					

ii)	Routine Maintenance and proper Operation of Air-conditioner including regular cleaning of Air-Filter, Checking of communication wire, PCB, Checking of running and starting capacitor, Checking of 3 phase supply at outdoor ,cleaning of condensor coil,cleaning of Evaporator Unit , Cleaning of indoor Panel ,Checking of ODU fan coil motor , Checking of IDU motor , checking of fans of ODU as well IDU, Cleaning of panel and emergency break down service as required complete in all respects and to the best satisfaction of Engineer-in-charge.					
2	Providing PVC drain pipe 25 mm dia as required complete in all respects.	40	250	Rs. Two hundred fifty only	per /mitr.	10000
	Total:-					**76500**

Draft Schedule of Quantity checked & Approved for Rs 76,500/-

Executive Engineer
Electrical Division
HPPWD Palampur