

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2026-27
To

5/4-16

Dated: - 23/04/2026


The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.


Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above



Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

- Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-
1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
 2. Copy to Notice board.


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

Certified that this division HPPWD,Haroli is out of Municipal council and the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2026-27- 51416 dated 23/04/2026 are required to be carried out immediately being emergent nature of work in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli Distt.Una HP).

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer Division H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/firms and PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: -
2. Date of issue/sale of tender forms against cash payment(non-refundable): -
3. Date of receipt of tenders: -
4. Date of opening of tenders: -

28/04/2026
29/04/2026
30/04/2026
30/04/2026

up to 10.30 (AM).
up to 3.00 PM
up to 10.30 AM
at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1.	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- Dismantling of old damaged CC Pavement at RD. 0/00 to 0/040 & C/O R/wall at RD. 0/010 to 0/022.60 RHS)	99426	2000/-	One Month	350/-	Class- C & D
2	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/330 to 0/340)(Under Deposit -SCCP)	99338	2000/-	One Month	350/-	Class- C & D
3	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- C/O R/wall at RD. 0/022.60 to 0/042.80 RHS)	98553	2000/-	One Month	350/-	Class- C & D
4	A/R & M/O on Una Rampur Palkwah Jaijon road km. 0/00 to 21/500(SH:-White washing on parapet walls and tree trunks etc. km. 10/00 to 15/500)	99624	2000/-	One Month	350/-	Class- C & D
5	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- C/O R/wall at RD. 0/063.10 to 0/083.30 RHS)	98553	2000/-	One Month	350/-	Class- C & D
6	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Providing & applying Apex paint on Retaining wall Front side of Traffic Park and Approach road)Deposit Work	99251	2000/-	One Month	350/-	Class- C & D
7	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- C/O R/wall at RD. 0/042.80 to 0/063.10 RHS)	99026	2000/-	One Month	350/-	Class- C & D
8	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/359 to 0/365)(Under Deposit -SCCP)	99950	2000/-	One Month	350/-	Class- C & D
9	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- Embankment filling at RD. 0/070 to 0/100 & P/L CC Pavement at RD. 0/00 to 0/016)	99740	2000/-	One Month	350/-	Class- C & D
10	Repair & restoration work on link road Pandoga Barrier to Panjwar km. 0/00 to 9/00(SH:-C/O Toe wall and RCC slab on drain at RD. 2/740 to 2/771-RHS)	99618	2000/-	One Month	350/-	Class- C & D

11	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- P/L CC Pavement at RD. 0/016 to 0/035.30)	98816	2000/-	One Month	350/-	Class- C & D
12	Repair & maintenance on Una Haroli Palkwah jaijon road km. 0/00 to 23/00(SH:-Repair of Berms at Various RDs km. 2/00 to 3/00-BHS)	98985	2000/-	One Month	350/-	Class- C & D
13	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/365 to 0/371.50)(Under Deposit -SCCP)	99779	2000/-	One Month	350/-	Class- C & D
14	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- C/O R/wall at RD. 0/083.30 to 0/100 & Embankment filling at RD. 0/040 to 0/70)	99147	2000/-	One Month	350/-	Class- C & D
15	Repair & maintenance of Rampur Bridge at RD. 3/080 to over swan river on Una , Haroli Palkwah, Polian Jaijon road km. 0/00 to 23/00-Phase-VIII)	99386	2000/-	One Month	350/-	Class- C & D
16	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/372 to 0/380.50)(Under Deposit -SCCP)	99753	2000/-	One Month	350/-	Class- C & D
17	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- P/L CC Pavement at RD. 0/074 to 0/093)	97280	2000/-	One Month	350/-	Class- C & D
18	A/R & M/O on Various roads under Haroli Sub-Division HPPWD (SH:-Supplying and fixing of sign boards & writing)	99885	2000/-	One Month	350/-	Class- C & D
19	Repair & maintenance on Una Haroli Palkwah jaijon road km. 0/00 to 23/00(SH:-Repair of Berms at Various RDs km. 3/00 to 4/00-BHS)	99066	2000/-	One Month	350/-	Class- C & D
20	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- P/L CC Pavement at RD. 0/054.70 to 0/074)	98816	2000/-	One Month	350/-	Class- C & D
21	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/340 to 0/347)(Under Deposit -SCCP)	99749	2000/-	One Month	350/-	Class- C & D
22	Repair & maintenance of Rampur Bridge at RD. 3/080 to over swan river on Una , Haroli Palkwah, Polian Jaijon road km. 0/00 to 23/00-Phase-VI)	99599	2000/-	One Month	350/-	Class- C & D
23	C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand Under MMSY (SH:- P/L CC Pavement at RD. 0/035.30 to 0/054.70)	99328	2000/-	One Month	350/-	Class- C & D
24	A/R & M/O on Various roads under Haroli Sub-Division HPPWD (SH:- writing letter on boards and bridges)	99894	2000/-	One Month	350/-	Class- C & D
25	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/347 to 0/353)(Under Deposit -SCCP)	99780	2000/-	One Month	350/-	Class- C & D
26	Repair & maintenance of Rampur Bridge at RD. 3/080 to over swan river on Una , Haroli Palkwah, Polian Jaijon road km. 0/00 to 23/00-Phase-VII)	99627	2000/-	One Month	350/-	Class- C & D
27	Construction of link road Chek Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80mm thick paver blocks, R/walls in Rd. 0/353 to 0/359)(Under Deposit -SCCP)	99610	2000/-	One Month	350/-	Class- C & D
28	Construction of Driving training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Landscaping, Beautification & Plantation work in Traffic Park campus) (Deposit Work)	99450	2000/-	One Month	350/-	Class- C & D
29	A/R & M/O on Una Rampur Haroli Palkwah Jaijon road km. 0/00 to 23/00 (SH:-Landscaping, Beautification & Plantation work at Polian Chowk at RD. 19/400)	99200	2000/-	One Month	350/-	Class- C & D

30	Repair & maintenance of Rampur Bridge at RD. 3/080 to over swan river on Una , Haroli Palkwah, Polian Jaijon road km. 0/00 to 23/00-Phase-IX)	99357	2000/-	One Month	350/-	Class- C & D
31	A/R & M/O PWD Non-residential building at Haroli (SH:- Painting of Division & Sub-Division Office etc.)Phase-I	98965	2000/-	One Month	350/-	Class- C & D
32	Repair & maintenance of Rampur Bridge at RD. 3/080 to over swan river on Una , Haroli Palkwah, Polian Jaijon road km. 0/00 to 23/00-Phase-V)	99665	2000/-	One Month	350/-	Class- C & D
33	Restoration of rain damages on link road to Saloh Nursery to Harijan Basti Saloh km. 0/00 to 2/700(SH:-Repair of rain cut at various RDs)	99504	2000/-	One Month	350/-	Class- C & D
34	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD. 5/904(SH:-P/L Cement concrete M-10 Down stream apron of Abutment A-1 to Pier P-5)	99288	2000/-	One Month	350/-	Class- C & D
35	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD. 5/904(SH:-P/L Cement concrete M-10 Down stream apron of Pier P-5 to Pier P-9)	99238	2000/-	One Month	350/-	Class- C & D
36	Repair & Restoration of link road Panoga Barrier to Panjvar km. 0/00 to 9/00(SH:-P/L CC Pavement to approach road, Dismantling of Chambers & Edge wall etc. in RD. 2/648 to 2/780 LHS)	99049	2000/-	One Month	350/-	Class- C & D
37	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD. 5/904(SH:-P/L Cement concrete M-10 Down stream apron of Pier P-9 to Pier P-14)	99742	2000/-	One Month	350/-	Class- C & D
38	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD. 5/904(SH:-P/L Cement concrete M-10 Down stream apron of Pier P-14 to Pier P-18)	99944	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
2. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
3. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
4. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
5. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
6. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK,

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-harolli-hp@hp.gov.in

On behalf of Governor of Himachal Pradesh

①

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand, Under MMSY		Estimated Cost: Rs	₹ 99,426			
		Time:-	One month			
[SH: Dismantling of old damaged CC Pavement at Rd. 0/00 to 0/040 & C/O R/wall at Rd. 0/010 to 0/022.60 Rhs]		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix 1/c equivalent design mix, including carriage of material within all leads including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Cum.	800.00	Rupees Eight Hundred Only	14400
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	153.70	Cum.	160.00	Rupees One Hundred Sixty Only	24592
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1-4-8) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	17.27	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	58734
4	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204 3.7 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	10.00	Each	170.00	Rupees One Hundred Seventy Only	1700
Total						99426
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

2

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,338		
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/330 to 0/340) (Under Deposit -SCCP)		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.03	Cum	170.00	Rupees One Hundred Seventy Only.	1535.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	3.75	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	10500.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	11.48	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	37884.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	51.00	Sqm	900.00	Rupees Nine Hundred Only.	45900.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.60	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	2700.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	170.00	Rupees One Hundred Seventy Only.	170.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.18	Cum	550.00	Rupees Five Hundred Fifty Only.	649.00
	Total					99338
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandanry by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Draft Schedule of quantity

Name of work:- C/O link road to Shamsan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY

(SH: C/O R/wall at Rd. 0/022.60 to 0/042.80 Rhs)

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.33	Cum.	160.00	Rupees One Hundred Sixty Only	1333
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1-4-8), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.69	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	94160
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	18.00	Each	170.00	Rupees One Hundred Seventy Only	3060
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) Z/02012 dated 07.08.2018				Total	98553
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)/A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)/A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Estimated Cost: Rs ₹ 98,553
Time:- One month
Earnest Money:- 2000

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

①


Schedule of Quantity						
			Estimated Cost: Rs.99624/-			
			Earnest Money: Rs. 2000/-			
			Time Limit: One Month			
Name of work: A/R & M/O on Una Rampur Palkwah Jajion road Km 0/00 to 21/500 (SH: White washing on parapet walls and tree trunks etc. Km 10/00 to 15/500)						
Sr. No.	Sub-Head and Items of work	Quantity	Unit	Rates in Words		Amount
				Figures		
1	2	3	6	4	5	7
1	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 19.15 complete as per direction of the Engineer-in charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, job tax, GST, labour cess or other taxes imposed by the Government.	3558.00	#REF!	28.00	Rupees twenty eight only	99624
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PW(B)00172/02212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PW(B)0311/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
Haroli Division,
HPPWD

(5)

Draft Schedule of quantity

Name of work:- C/O link road to Shamschan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY		Estimated Cost: Rs		Time:-	₹ 98,553	
(SH: C/O R/wall at Rd. 0/063.10 to 0/083.30 Rhs)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8),including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	8.33	Cum.	160.00	Rupees One Hundred Sixty Only	1333
2	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts, and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government	27.69	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	94160
3	Note 3) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018	18.00	Each	170.00	Rupees One Hundred Seventy Only	3060
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021				Total	98553
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Dist.

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 99,251		
(SH: Providing & applying Apex paint on Retaining wall Front side of Traffic park and Approach road) (Deposit work)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Berger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018	751.90	Sqm	132.00	Rupees One Hundred ThirtyTwo Only	99251
					Total	99251
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (H.P.)

7

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY		Estimated Cost: Rs		₹ 99,026		
(SH: C/O R/wall at Rd. 0/042.80 to 0/063.10 Rhs)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m. as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana toll tax,GST,labour cess or other taxes imposed by Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8);including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana toll tax,GST,labour cess or other taxes imposed by the Government.	8.37	Cum.	160.00	Rupees One Hundred Sixty Only	1340
2	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana toll tax,GST,labour cess or other taxes imposed by the Government	27.83	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	94626
3	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018	18.00	Each	170.00	Rupees One Hundred Seventy Only	3060
					Total	99026
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

(B)

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,950		
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/359 to 0/365) (Under Deposit-SCCP)		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO		Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.82	Cum	170.00	Rupees One Hundred Seventy Only.	2009.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	2.25	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	6300.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	17.53	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	57849.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.60	Sqm	900.00	Rupees Nine Hundred Only.	27540.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.36	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	1620.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg-per cm2 extending through the full width of the structures with slope of 1(y):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.00	Each	170.00	Rupees One Hundred Seventy Only.	1530.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.64	Cum	550.00	Rupees Five Hundred Fifty Only.	3102.00
	Total					99950
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (I) (17) 2/02012 dated 07.08.2018					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandantry by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.R.)


9

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY		Estimated Cost: Rs	Time:-	₹ 99,740		
[SH: - Embankment filling at Rd. 0/070 to 0/100 & P/L CC Pavement at Rd. 0/00 to 0/016]		Rate in words	Amount	One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	74.25	Cum.	240.00	Rupees Two Hundred Fourty Only	17820
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	8.40	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	21760
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by max in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	6.40	Cum.	1150.00	Rupees One Thousand One Hundred Fifty Only	7360
4	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802, 803, 1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	9.60	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	52800
					Total	99740
Note 1: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note :-Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.W.D. Division Haroli

12


SCHEDULE OF QUANTITY

Estimates cost:- 99618
Earnest Money:- 2000
Time Limit:- One Month.

Name of work :- Repair & restoration work on link road Pandoga Barrier to Panjagar km. 0/00 to 9/00 (SH: C/O Toe wall and RCC slab on drain at RD 2/740 to 2/771- RHS)

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.46	Per Cubic metre.	160.00	Rupees one hundred sixty only	1674
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	22.32	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	73656
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or hauling out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.09	Per Cubic metre.	3900.00	Rupees three thousand nine hundred only	8151

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
4	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg.(four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights' depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	0.99	Per Cubic metre.	5500.00	Rupees five thousand five hundred only	5445
5	Providing and laying mild steel medium tensile steel bars for steel (approved make) reinforcement for reinforced cement concrete work including bending, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana , toll tax, sale tax, sale tax , GST, labour cess or other taxes imposed by the Government.	118.80	Per Kg	90.00	Rupees ninety only	10692
	Total					99618
Note:-	1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B)A(31)/2020 dated 22.07.20					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 Haroli Division,
 HPPWD, Haroli

11

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY		Estimated Cost: Rs	Time:-	₹ 98,816	
(SH:- P/LCC Pavement at Rd. 0/016 to 0/035.30)		Earnest Money:-	Rate in words	2000	
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Amount
1	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8),including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.72	Cum.	3400.00	26248
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government	7.72	Cum.	1150.00	8878
3	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations/ cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal MIX 1 : 1.5:3. and as per Direction of Engineer-in-charge, including carriage of material within all leads including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll	11.58	Cum.	5500.00	63690
				Total	98816
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)31/2020 Dated 22.07.2020 & Govt. of Hp vide letter no. PBW (B/A)31/2020-1 Dated 07.10.2021					
Percentage quoted rate in figures					
Percentage quoted rate in words					
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

M

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

19

Schedule of quantity

Name of work: - Repair & maintenance on Una Haroli Palkwah Jainon road km 0/00 to 23/00 (Estimated Cost: Rs		₹ 98,985		
(SH: Repair of Berms at Various RDs km 2/00 to 3/00- BHS)		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903. The rate is including of octroi, royalty, GST,Malkana, toll tax , sale tax or other taxes imposed by the Government.	1799.72	Per Sqm	55.00	Rupees FiftyFive Only	98985
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018				Total:	98985
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

23

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,779
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/365 to 0/371.50) (Under Deposit-SCCP)		Time:-		One month
S.NO		DESCRIPTION		Earnest Money:-
Qty	Unit	T.Rate	Rate in words	Amount
11.60	Cum	170.00	Rupees One Hundred Seventy Only.	1972.00
2.44	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	6832.00
16.72	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	55176.00
33.15	Sqm	900.00	Rupees Nine Hundred Only.	29835.00
0.39	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	1755.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D- plast/Finolux having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	8.00	Each	170.00	Rupees One Hundred Seventy Only.	1360.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.18	Cum	550.00	Rupees Five Hundred Fifty Only.	2849.00
	Total					99779
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandanthy by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

TM

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand, Under MMSY		Estimated Cost: Rs	Time:-	₹ 99,147		
(SH: C/O R/wall at rd. 0/083.30 to 0/100 Rhs & Embankment filling at Rd. 0/040 to 0/70)		Amount	2000	One month		
S NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m. as directed by Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	6.89	Cum.	160.00	Rupees One Hundred Sixty Only	1102
2	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 902, 1202 and 1203 (CC 148) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	22.90	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	77845
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 30 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	14.00	Each	170.00	Rupees One Hundred Seventy Only	2380
4	Construction of embankment with approved material obtained at site from roadways cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	74.25	Cum.	240.00	Rupees Two Hundred Forty Only	17820
					Total	99147

Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) 6 (17) 2/02022 dated 07.08.2018

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B) (33) 2/02020 dated 22.07.2020 & Govt. of HP vide letter no. PBW (B) (33) 2/02020-1 Dated 07.10.2021

Percentage quoted rate in figures

Percentage quoted rate in words

Note- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected

M
 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

11



SCHEDULE OF QUANTITY

Name of work:- Repair & maintenance of Rampur bridge at RD 3/080 over swan river on Una, Haroli, Palkwah, Polian Jaijon road Km 0/00 to 23/000 - Phase-VIII

Estimated Cost 99386
Earnest Money 2000
Time limit One month

S No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	699.90	Per square metre	10.00	Rupees ten only	6999
2	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt. NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@172/0212 dated 7.8.2018	699.90	Per square metre	132.00	Rupees one hundred thirty two only	92387
					Total	99386
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


Executive Engineer
Haroli Division
HPPWD Haroli

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)

		Estimated Cost: Rs		₹ 99,753		
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/372 to 0/380.50) (Under Deposit-SCCP)		Time:-		One month		
S.NO	DESCRIPTION	Earnest Money:-				
		Qty	Unit	T.Rate	Rate in words	
		Amount				
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.57	Cum	170.00	Rupees One Hundred Seventy Only.	1967.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	3.19	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	8932.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	13.38	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	44154.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	43.35	Sqm	900.00	Rupees Nine Hundred Only.	39015.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.51	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	2295.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D- plast/Finolex having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.00	Each	170.00	Rupees One Hundred Seventy Only.	1190.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.00	Cum	550.00	Rupees Five Hundred Fifty Only.	2200.00
Total						99753
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandanry by the contractor, otherwise the tender will be rejected.						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

19

Schedule of quantity

Name of work: - Repair & maintenance on Una Haroli Palkwah Jainon road km 0/00 to 23/00 (Estimated Cost: Rs		₹ 99,066		
(SH: Repair of Berms at various RDs km 3/00 to 4/00- BHS)		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903. The rate is including of octroi, royalty, GST, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1801.20	Per Sqm	55.00	Rupees FiftyFive Only	99066
					Total:	99066
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

2

20

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY		Estimated Cost: Rs	Time:-	₹ 98,816			
(SH:- P/L CC Pavement at Rd. 0/054.70 to 0/074)		One month					
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	Rate in words	Amount
1	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8), including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	7.72	Cum.	3400.00		Rupees Three Thousand Four Hundred Only	26248
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government	7.72	Cum.	1150.00		Rupees One Thousand One Hundred Fifty Only	8878
3	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203, M 25 Nominal Mix 1 : 1.5:3, and as per Direction of Engineer -in -charge, including carriage of material within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government	11.58	Cum.	5500.00		Rupees Five Thousand Five Hundred Only	63690
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						Total	98816
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)/A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)/A(31)/2020-1 Dated 07.10.2021							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Executive Engineer,
P. B. W. D. Division, Haroli

Schedule of quantity

Name of work :- Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)							Estimated Cost: Rs	₹ 99,749
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/340 to 0/347) (Under Deposit-SCCP)							Time:-	One month
							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.52	Cum	170.00	Rupees One Hundred Seventy Only.	1618.00		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	2.63	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	7364.00		
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	16.39	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	54087.00		
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	35.70	Sqm	900.00	Rupees Nine Hundred Only.	32130.00		
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.42	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	1890.00		

17

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H))(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.00	Each	170.00	Rupees One Hundred Seventy Only.	850.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.29	Cum	550.00	Rupees Five Hundred Fifty Only.	1810.00
Total						99749
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandanbry by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

93

Draft Schedule of quantity

Name of work:- C/O link road to Shamshan Ghat in Village Gondpur Jaichand GP Gondpur Jaichand. Under MMSY		Estimated Cost: Rs	Time:-	₹ 99,328		
(SH: - P/L CC Pavement at Rd. 0/035.30 to 0/054.70)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1.4.8) including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,maikhana ,toll tax,CST,labour cess or other taxes imposed by the Government.	7.76	Cum.	3400.00	Rupees Three Thousand Four Hundred Only	26384
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401... including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,maikhana ,toll tax,CST,labour cess or other taxes imposed by the Government	7.76	Cum.	1150.00	Rupees One Thousand One Hundred Fifty Only	8924
3	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203 M 25 Nominal Mix 1 : 1.5:3, and as per Direction of Engineer-in-charge, including carriage of material within all leads including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,maikhana ,toll tax,CST,labour cess or	11.64	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	64020
					Total	99328
Note 1] All Type of material shall be arranged by the contractor vide Notification by Additional Secy:- to the Govt. of HP vide letter No. PBW (B) © [17] 2/02012 dated 07.08.2018						
2] The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.W.D. Division, Haroli
Distt. Una (H.P.)

25

Schedule of quantity

Name of work :- Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200		Estimated Cost: Rs		₹ 99,780
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/347 to 0/353) (Under Deposit-SCCP)		Time:-		One month
S.NO		DESCRIPTION		Earnest Money:-
Qty	Unit	T.Rate	Rate in words	Amount
11.82	Cum	170.00	Rupees One Hundred Seventy Only.	2009.00
2.25	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	6300.00
17.53	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	57849.00
30.60	Sqm	900.00	Rupees Nine Hundred Only.	27540.00
0.36	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	1620.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg.per cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	8.00	Each	170.00	Rupees One Hundred Seventy Only.	1360.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.64	Cum	550.00	Rupees Five Hundred Fifty Only.	3102.00
Total						99780
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandantary by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

27

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,610		
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/353 to 0/359) (Under Deposit-SCCP)		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.82	Cum	170.00	Rupees One Hundred Seventy Only.	2009.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	2.25	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	6300.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	17.53	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	57849.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.60	Sqm	900.00	Rupees Nine Hundred Only.	27540.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.36	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	1620.00

18

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe (D- plast/Finolex having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.00	Each	170.00	Rupees One Hundred Seventy Only.	1190.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.64	Cum	550.00	Rupees Five Hundred Fifty Only.	3102.00
Total						99610
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) ©						
(17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandantary by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

99

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 99,450		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Providing & planting of ornamental plants with fiber pots at site of work. Filling with mixture of screened manure, good earth and coco peat. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. One month maintenance	10.00	Each	900.00	Rupees Nine Hundred Only	9000
2	Providing & planting of ornamental Frostail palm tree 5-6 feet. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. One month maintenance	45.00	Each	750.00	Rupees Seven Hundred Fifty Only	33750
3	Providing & planting of ornamental plant Japanese date palm tree 3 feet including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. One month maintenance	45.00	Each	750.00	Rupees Seven Hundred Fifty Only	33750
4	Providing & planting of ornamental (Ficus Raport) plant 5 feet including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. One month maintenance	8.00	Each	1000.00	Rupees One Thousand Only	8000
5	Providing & planting of ornamental Grouldey cypress 5-6 feet including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. One month maintenance	13.00	Each	1150.00	Rupees One Thousand One Hundred Fifty Only	14950
					Total:	99450
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/2/20212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(3)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

99

Schedule of quantity

Name of work :- A/R & M/O On Una Rampur Haroli Palkwah Jaijon road km. 0/00 to 23/00		Estimated Cost: Rs		₹ 99,200		
(SH: Landscaping, Beautification & Plantation work at Polian Chowk at Rd. 19/400)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing & planting of ornamental plants with filter pots at site of work. Filling with mixture of screened manure, good earth and coco peat. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month maintenance	5.00	Each	900.00	Rupees Nine Hundred Only	4500
2	Providing & planting of ornamental Foxtal palm tree 5-6 feet. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month maintenance	20.00	Each	750.00	Rupees Seven Hundred Fifty Only	15000
3	Providing & planting of ornamental plant Japanese datepalm tree 3 feet. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month maintenance	20.00	Each	750.00	Rupees Seven Hundred Fifty Only	15000
4	Providing & planting of ornamental (Ficus Tapori) plant 5 feet. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month maintenance	8.00	Each	1000.00	Rupees One Thousand Only	8000
5	Providing & planting of ornamental Groudenyepress 5-6 feet. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month maintenance	10.00	Each	1150.00	Rupees One Thousand One Hundred Fifty Only	11500
6	Uprooting rank Vegetation weeds by digging the area to depth 10 cm removing all weedsand other growth with roots by farking repeatedly breaking clods,roughdressing.Flooding with water. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month	100.00	Each	100.00	Rupees One Hundred Only	10000
7	Mixing earth and sludge are measure in the required proportion og grassing area. Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government. One month maintenance	60.00	Each	100.00	Rupees One Hundred Only	6000

8	Providing and fixing Nilgiri, Maxicamgrass turfing with earth including carriage of material within all head and bills and other incidental. The rate includes sale tax octroi royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government. One month maintenance	100.00	Each	292.00	Rupees Two Hundred Ninety Two Only	29200
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@/(17)2/0212 dated 7.8.2018				Total:	99200
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

90

SCHEDULE OF QUANTITY

Estimated Cost 99357
Earnest Money 2000
Time limit One month

Name of work:- Repair & maintenance of Rampur bridge at RD 3/080 over swan river on Una, Haroli, Palkwah, Polian Jaijon road Km 0/00 to 23/000 - Phase-IX

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentials. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	699.70	Per square metre	10.00	Rupees ten only	6997
2	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentials. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	699.70	Per square metre	132.00	Rupees one hundred thirty two only	92360
					Total	99357
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haridwar

(5)

Schedule of quantity

Name of work :-A/R & M/O PWD Non residential building at Haroli.		Estimated Cost: Rs		₹ 98,965		
(Sub Head -Painting of Division & Sub Division Office etc.) Phase-I		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T Rate		
		Earliest Money:-		Rate in words		
				Amount		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1201.93	Sqm	11.00	Rupees Eleven Only	13221
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	120.19	Sqm	62.00	Rupees Sixty Two Only	7452
3	Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface. Water thinnable cement primer including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1201.93	Sqm	52.00	Rupees Fifty Two Only	62500
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour two coat including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	210.56	Sqm	75.00	Rupees Seventy Five Only	15792
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Sery to the Govt. of HP vide letter No-PBW(B)(17)2/2012 dated 7.8.2018.				Total:		98965
2) The bidder are requested to submit their bid as per notification issued by the Principal Socy. PW to the Govt. of HP vide letter No-PBW(B)(A3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
P.P.W.D. Division Haroli,
Distt. Una (H.P.)

32

SCHEDULE OF QUANTITY

Estimated Cost 99665
Earnest Money 2000
Time limit One month

Name of work:- Repair & maintenance of Rampur bridge at RD 3/080 over swan river on Una, Haroli, Palkwah, Polian Jaizon road Km 0/00 to 23/000 - Phase V

S No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	701.86	Per square metre	10.00	Rupees ten only	7019
2	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	701.86	Per square metre	132.00	Rupees one hundred thirty two only	92646
					Total	99665
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)/A(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli

33

SCHEDULE OF QUANTITY

Estimated Cost 99504
Earnest Money 2000/-
Time limit One month

Name of work : Restoration of rain damages on link road to Saloh Nursery to harizan basti Saloh Km 0/00 to 2/700(SH:-Repair of rain cut at various RDs)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Banking excavated earth in layers not exceeding 20 cm depth, breaking clods without rolling and watering, dressing up, in embankment for roads, flood banks, marginal banks and guide banks etc. upto any lead and lift as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malakhana, toll tax, GST, labour cess or other taxes imposed by the Government.	414.60	Per cubic metre	240.00	Rupees hundred only	99504
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018					99504
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					

Executive Engineer
Haroli Division
HPPWD

34

Schedule of Quantity

Estimated Cost :- Rs.

99288.00

Name of work:- Repair & Restoration of rain damage on Pandoga Bridge on Panjawaar Bathri road at RD 5/904.

Earnest Money :- Rs.

2000.00

Time limit :-

One Month

SH: P/L Cement concrete M-10 Down streame apron of Abutment A-1 to Pier P-5)

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Providing and laying (M-10 Grade)(M-Ten) Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification MORD 2014 Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .	19.70	Cum	5040.00	Rupees Five Thousand Forty and Paise Zero Only	99288
	Total					99288
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2019					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandantry by the contractor, otherwise the tender will be rejected.					

Executive Engineer
HPPWD Division Haroli
Distt. Una (HP)

95

Schedule of Quantity

Name of work:- Repair & Restoration of rain damage on Pandoga Bridge on Panjawar Bathri road at RD 5/904.

Estimated Cost :- Rs.
Earnest Money :- Rs.

99238.00
2000.00

SH: P/L Cement concrete M-10 Down stream apron of Pier P-5 to Pier P-9)

Time limit :-

One Month

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Providing and laying (M-10 Grade)(M-Ten) Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification MORD 2014 Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals.	19.69	Cum	5040.00	Rupees Five Thousand Forty and Paise Zero Only	99238
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2019					9923
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandantary by the contractor, otherwise the tender will be rejected.					

Executive Engineer
HPPWD Division Haroli
Distt. Una (HP)

36

Estimated Cost :- Rs. 99049.00

Earnest Money :- Rs. 2000.00

Schedule of Quantity

Line of work:- Repair & restoration of Link road Pandoga Barrier to Panjawaar KM 0/0 TO 9/0

Time limit :- One Month

Item: P/L CC Pavement to approach road, Dismantling of Chambers & Edge wall etc in RD 2/648 to 2/780 (HS)

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .	58.70	Cum	1000.00	Rupees One Thousand and Paise Zero Only	58700
2	Providing and laying cement concrete 1:4:8 (one cement: four sand:eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.76	Cum	3400.00	Rupees Three Thousand Four Hundred and Paise Zero Only	9384
3	Providing and laying reinforcement cement concrete work of grade M-25(M=twenty five)design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams,girders, bressumers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.63	Cum	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	30965
Total						99049

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2019

Percentage quoted rate in Figures

Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandantry by the contractor, otherwise the tender will be rejected.

Executive Engineer
HPPWD Division Haroli
Distt. Una (HP)

37

Schedule of Quantity

Estimated Cost :- Rs.

99742.00

Name of work:- Repair & Restoration of rain damage on Pandoga Bridge on Panjawaar Bathri road at RD 5/904.

Earnest Money :- Rs.

2000.00

SH: P/L Cement concrete M-10 Down streame apron of Pier P-9 to Pier P-14)

One Month

Time limit :-

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Providing and laying (M-10 Grade)(M-Ten) Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification MORD 2014 Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .	19.79	Cum	5040.00	Rupees Five Thousand Forty and Paise Zero Only	99742
	Total					99742
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2019					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandantry by the contractor, otherwise the tender will be rejected.					


Executive Engineer
HPPWD Division Haroli
Distt. Una (HP)

38

Schedule of Quantity

Estimated Cost :- Rs.

99994.00

Name of work:- Repair & Restoration of rain damage on Pandoga Bridge on Panjawar Bathri road at RD 5/904.

Earnest Money :- Rs.

2000.00

SH: P/L Cement concrete M-10 Down stream apron of Pier P-14 to Pier P-18)

Time limit :-

One Month

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Providing and laying (M-10 Grade)(M-Ten) Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification MORD 2014 Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .	19.84	Cum	5040.00	Rupees Five Thousand Forty and Paise Zero Only	99994
	Total					99994
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2019					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandantry by the contractor, otherwise the tender will be rejected.					

Executive Engineer
HPPWD Division Haroli
Distt. Una (HP)