



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP PWD, Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **25-04-2026** up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on **24-04-2026** up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on the same day from 3:00 P.M. to 5:00 P.M. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1.	A/R & M/O on Various Non Residential Buildings under HP PWD Division Joginder Nagar (SH:- Supply and Fixing various office under HPPWD Sub Division Lad Bharol).	Rs. 86,666/-	Rs. 1,700/-	Rs.350/-	Class "D"	Two Months
2.	Restoration of Rain Damges on various road under Joginder Division Sub Division HP PWD Joginder (Makriri Section) (ISH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc)	Rs. 49,530/-	Rs. 1,000/-	Rs.350/-	Class "D"	One Months
3.	Restoration of Rain damges on link road Dhelu Mod and Gian Chand House to Railway line km. 0/0 to 1/0 (SH - Construction of edge wall at km. 0/137 to 0/144.10) under SDF deposit SID:SDF/2025/1119	Rs. 74,642/-	Rs. 1,500/-	Rs. 350/-	Class "D"	Two Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2026-27- **730-79**

Dated- **08/04/26**

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

DNIT/DRAFT SCHEDULE OF QUANTITY

GIB E No. 425

Work : A/R & M/O on Various Non Residential Buildings under HPPWD Division Joginder Nagar
 and fixing office bench at Various Office Under HPPWD Sub Division Lad Bharol)

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Providing and fixing Carbon steel Rest Bench for Hospitals, office, Reception and Garden of size of 720 (W) x 580(D) x 790(H) (Seven hundred twenty by five hundred eighty by hundred ninety millimeter) (Chair type bench with back rest. The bench consist Seat & back processed with 1.2 mm (one point two millimeter) thickness cold rolled MS Sheet and furnished with power coating, Armrest processed with 1.6 mm (one point six millimeter) MS and furnished with powercoating, leg processed with 1.00 mm (one millimeter) sheet furnished with power coating, center support beam processed with 2mm (two millimeter) thickness MS Sheet and furnished with power coating including carriage of materials, with leads and lifts as per direction of the Engineer-in-Charge including carriage of material in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Each	17,333.25	Rupees Seventeen Thousand Three Hundred Thirty Three And Paise Twenty Five Only	86,666.00
Total					86,666.00

*Draft Schedule of Quantity approved for ₹ 86,666/-
 (Eight Six Thousand Six Hundred Sixty Six) only/-*

~~Executive Engineer~~
 B & R Division HP.PWD,
 Joginder Nagar

GIB

614

DNIT/DRAFT SCHEDULE OF QUANTITY

Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :
			Figures	Words	
			AMOUNT Rs. P		
Hiring of Hydraulic Excavator cum loader having 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debries and C/O road side katcha drains i/c cost of fuel oil lubricants and wages of operating staff, any pair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive all taxes including ST levy by the government time to time.	39.00	Per working hour	1,270.00	Rupees One Thousand Two Hundred Seventy Only	49,530.00 1,000.00 One Month
Total					49,530.00

Draft Schedule of Quantity approved for Rs 49,530/-
(Forty Nine Thousand Five Hundred Thirty) only/-

614

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

E.No. 439 - 29078. dt 02/02/20

(616)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on link road Dhelu Mod and Gian Chand house to railway line km 0/0 to 1/0 (Sub Head:-Construction of edge wall at Km. 0/137 to 0/144.10 under SDF deposit SID; SDF/2025/1119		Estimate Cost: 74,642.00		Earnest Money: 1,500.00		Time Limit : 12 Months
		Description of work		Rate	AMOUNT	
Sr. No.	No. or Qty.	Unit	Figures	Words	Rs.	P
1	2.91	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	1,886.00	
<p>Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.</p>						
2	10.65	Per cubic metre	5,987.35	Rupees Five Thousand Nine Hundred Eighty Seven And Paise Thirty Five Only	63,765.00	
<p>Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.</p>						

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	6.39	Per cubic metre	1,149.10	Rupees One Thousand One Hundred Forty Nine And Paise Ten Only	7,343.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Each	329.65	Rupees Three Hundred Twenty Nine And Paise Sixty Five Only	1,648.00
Total						74,642.00

*Draft Schedule of Quantity approved for 74,642/-
(Seventy four Thousand Six Hundred forty two)
(only) /-*

616

[Signature]
Executive Engineer
B & R Division HP.PWD,
Joginder Nagar