



Office of  
Executive Engineer B&R Division HP.PWD. Joginder Nagar

Himachal Pradesh Public Works Department, Mandi-175015  
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

**"NOTICE INVITING TENDER"**

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP PWD Joginder Nagar District Mandi (HP) from the eligible contractors of the appropriate class registered in HP PWD as per revised enlistment rules so as to reach in the office of under signed on **12.05.2026** up to 11 30 A M and will be opened on the same day at (12 00 noon) in the presence of intending contractors. The tender application will be received in this office on **8-05-2026** up to 10 00 A M to 12 00 P M and tender form can be had from this office on **11.05. 2026** from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F D R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contract or	Time
1	Restoration of rain damages on Siun Bhararpatt road km. 0/0 to 2/0 (SH- Construction of breast wall at km. 0/625 to 0/628.40 under NDF Deposit SID NDF/2023/95	Rs. 49,851/-	Rs. 1,000/-	Rs. 350/-	Class "D"	Three Months
2	Restoration of rain damages on Chhamb Kuthera Badhu road km. 0/0 to 2/0. (SH- Removal of formation deficiency at km. 0/410 to 0/470 NDF deposit SID NDF/2023/1346	Rs. 59,858/-	Rs. 1,200/-	Rs. 350/-	Class "D"	Two Months
3	R/O Removal of land slide slips on various road under Nagar Division in GP Baih (SH- Removal of slips land slide between km. 0/800 to 0/830 under NDF Deposit SID NDF/2023/100	Rs. 39,372/-	Rs. 8,00/-	Rs. 350/-	Class "D"	One Months
4	Construction of link road from main road Chanang to Mandwana km. 0/0 to 8/660 (SH- Providing & laying Kharanja soling and cement concrete pavement in km. 0/0 to 0/027 under SDP deposit SID SDP/2024	Rs. 97,504/-	RS. 2,000/-	Rs. 350/-	Class "D"	Two Months
5	Construction of link road Charonjh to Magru Nallah via Therarlya Devat Mandir to upper Charonjh (SH:- Construction of Toe wall D/S & U/S side for existing 900mm dia RCC hume pipe culvert at km. 0/180 under Deposit SID:SDP/2024/62.	Rs. 48,722/-	RS. 1,000/-	Rs. 350/-	Class "D"	Three Months
6	Construction of link road Mata Bhabori Mata Mandir (SH:- Providing & laying Kharanja soling and cement concrete pavement in km. 2/050 to 2/099 under Deposit SID:SDP/2024/62	Rs. 1,97,293/-	RS. 3,900/-	Rs. 350/-	Class "D"	Three Months
7	Construction of link road from Main road Pipli. (SH:- Construction of 900 mm dia RCC hume pipe Culvert at RD. 1/090 under SDP deposit SID:SDP 2024/213.	Rs. 99,769/-	RS. 2,000/-	Rs. 350/-	Class "D"	Three Months
8	Restoration of rain damages on Dol Raktal changehar road km. 0/0 to 8/660 in GP Langna (SH:- Providing & laying wearing grade -II & repair of pot holes in km. 0/0 to 3/00 under NDF deposit SID:NDF/2023/1342	Rs. 2,99,702/-	RS. 6,000/-	Rs. 350/-	Class "D"	Three Months
9	Construction of link road village Rangra Sahroon in GP Kolang (SH:- Providing & laying Kharanja soling & cement concrete pavement in km. 0/0 to 0/053 under BSP deposit SID: BSP/2024/63	Rs. 1,98,368/-	RS. 4,000/-	Rs. 350/-	Class "D"	Three Months
10	R/O Repair of pot holes on various road under Joginder Nagar Sub Division (Ladruhin Section) (SH- Supply and Stacking of Crushed stone aggregate 10 to 13.2 mm and sand) under NDF deposit SID NDF/2023/101	Rs. 39,975/-	Rs. 800/-	RS. 350/-	Class "D"	One Months
11	Construction of link road Bhet to Harizan Basti Saparu (SH:- Construction of 900 mm dia RCC hume pipe culvert at RD. 0/880 under BSP deposit SID:BSP/2024/460.	Rs. 48,264/-	Rs. 800/-	RS. 350/-	Class "D"	One Months
12	Construction of link road to village Bagdaina km. 0/00 to 1/000 (SH:- Construction of retaining wall /Pusta for protection of existing R/Wall at RD. 0/630 to 0/639.70).	Rs. 1,45,628/-	Rs. 1,100/-	RS. 350/-	Class "D"	Two Months
13	Restoration of Rain Damages on <b>Jalad Basalan Tanhotu road</b> km. 0/0 to 7/0 (SH- Providing and Fixing W Metal Beam Crash Barriers System at km. 1/450 to 1/470).	Rs. 93,932/-	Rs. 1,900/-	Rs. 350/-	Class "D"	Two Months
14	Construction of Retaining wall and Drainage system <b>Nichla Panjalag to Kanharag GP Kathon Tehsil Lad Bharol Distt Mandi (H P )</b> (SH- Construction of PCC Pusta for Retaining wall at RD. 0/258 to 0/303 SID MPR/2025/538	Rs. 2,95,832/-	Rs. 5,900/-	Rs. 350/-	Class "D"	Three Months

**Certified that tender of above works are being called of emergent nature in exigency of public interest**

Terms and conditions -

- 1 The contractor should be registered as dealer under H P GST Tax Act. 2018 and also produce the Tin number, H P sales Tax clearance certificate from the Excise and Taxation Department

- 2 The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD, Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- 3 For on behalf of Governor of Himachal Pradesh the Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- 4 In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- 5 Only two tenders form will be issued to the contractor/firm which may be noted.
- 6 Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- 7 The contractor shall be responsible for rectifying defects noticed within six months from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- 8 The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc. or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- 9 The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking he will get complete the works in hand before award of work with in schedule time.
- 10 All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- 11 The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar,  
District Mandi (HP) for on behalf of  
Governor of Himachal Pradesh  
Ph. 01908-222033.

No. PW-JND-B&R-EA-I/NIT/Press/2025-26-

1631-80

Dated:-

21-04-2026

- 1 Copy to the F C Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-Chief, HPPWD, Shimla
- 3 The Chief Engineer (MZ), HPPWD, Mandi
- 4 The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 All the Contractor working under this Division
- 7 Drawing Branch in this office
- 8 Account Branch in this office
- 9 Notice Board
- 10 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.

Job-1

**DNT/DRAFT SCHEDULE OF QUANTITY**

(2)

**Name of Work : R/O Restoration of rain damages on Siun Bhararpatti road km.0/0 to 2/0**  
**(SH: Construction of breast wall at km. 0/625 to 0/628.40 under NDF deposit SID: NDF/2023/95**

**Estimate Cost: 49,851.00**  
**Earnest Money: 1,000.00**  
**Time Limit : Three Months**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock ( where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	4.66	Per cubic metre	201.75	Rupees Two Hundred One And Paise Seventy Five Only	940.00
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	0.51	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	330.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size ) plums and curing complete including the cost of form work in <b>Retaining walls Breast walls</b> , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levied by the government time to time including GST	7.99	Per cubic metre	5,956.30	Rupees Five Thousand Nine Hundred Fifty Six And Paise Thirty Only	47,591.00
4	Providing <b>weep holes</b> in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	3.00	Each	329.95	Rupees Three Hundred Twenty Nine And Paise Ninety Five Only	990.00
<b>Total</b>						<b>49,851.00</b>

*Draft schedule of quantity approved for ₹ 49,851/- (Forty nine thousand eight hundred fifty one) only*

*(Signature)*  
Executive Engineer  
B & R Division HP.PWD,  
Joginder Nagar

7

Job-2

8

**DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of Work: R/O Restoration of rain damages on Chhamb Kuthera Kharsi Badhu road km.0/0 to 2/0 Removal of formation deficiency at km. 0/410 to 0/470 under NDF deposit SID: NDF/2023/1346		(SH)		Estimate Cost: 59,858.00		
				Earnest Money: 1,200.00		
				Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock ( where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 11.16cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	233.20	Per cubic metre	256.68	Rupees Two Hundred Fifty Six And Paise Sixty Eight Only	59,858.00
<b>Total</b>						<b>59,858.00</b>

*Draft schedule of quantity approved for E*  
*59,858/- (Fifty nine thousand eight hundred*  
*fifty eight) only*

8

~~Executive Engineer~~  
 B & R Division HP.PWD.  
 Joginder Nagar

Job-3

DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost:	
				Figures	Words	Earnest Money:	One Month Time Limit :
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification clause 302.3.5 and 1611. including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time including GST.	204.00	Per cubic metre	193.00	Rupees One Hundred Ninety Three Only	39,372.00	800.00
Total						39,372.00	

*Draft schedule of quantity approved for ₹ 39,372/- only (Thirty nine thousand three hundred & seventy two) only*

9

~~Executive Engineer~~  
B & R Division HP.PWD,  
Joginder Nagar

Job-4

**DNIT/DRAFT SCHEDULE OF QUANTITY**

Sr. No.		Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit : Two Months
					Figures	Words	
1		Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	12.76	Per Cubic metre	2,216.70	Rupees Two Thousand Two Hundred Sixteen And Paise Seventy Only	28,285.00
2		Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	8.51	Per Cubic metre	8,133.85	Rupees Eight Thousand One Hundred Thirty Three And Paise Eighty Five Only	69,219.00
<b>Total</b>							<b>97,504.00</b>

*Draft schedule of quantity approved for 297504/-  
(Twenty seven thousand five hundred four) only*

Executive Engineer  
B & R Division HP.PWD,  
Joginder Nagar

10

Job 5

(11)

Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT Rs. P
				Figures	Words

**DNIT/DRAFT SCHEDULE OF QUANTITY**

<b>Name of Work :</b> Construction of link road Charonjh to Magru Nallah via Therariya Devta Mandir to upper Charonjh (Sh:- Construction of Toe wall D/S & U/S side for existing 900mm dia RCC hume pipe culvert at Km 0/180. under Deposit SID: 2024/471		<b>Estimate Cost:</b> 48,722.00 <b>Earnest Money:</b> 1,000.00 <b>Time Limit :</b> Three Months				
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	1.04	Per cubic metre	6,653.90	Rupees Six Thousand Six Hundred Fifty Three And Paise Ninety Only	6,920.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	5.45	Per cubic metre	7,670.10	Rupees Seven Thousand Six Hundred Seventy And Paise Ten Only	41,802.00
<b>Total</b>						<b>48,722.00</b>

*Draft schedule of quantity approved ₹ 48722 only  
(Forty eight thousand seven hundred twenty two only)*

~~Executive Engineer~~  
B & R Division HP.PWD,  
Joginder Nagar

(11)

Job-6

12

**DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of Work : Construction of link road Mata Bhabori Mata Mandir (SH: Providing & laying kharanja soling and cement concrete pavement in km. 2/050 to 2/099 under BSP deposit SID: BSP/2024/62				Estimate Cost: 1,97,293.00 Earnest Money: 3,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	AMOUNT Rs. P
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	23.54	Per Cubic metre	2,505.90	Rupees Two Thousand Five Hundred Five And Paise Ninety Only	58,989.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	15.69	Per Cubic metre	8,814.80	Rupees Eight Thousand Eight Hundred Fourteen And Paise Eighty Only	1,38,304.00
<b>Total</b>						<b>1,97,293.00</b>

*Draft schedule of quantity approved for 1972/13/-  
(One lac ninety seven thousand two hundred  
ninety three) only*

Executive Engineer  
B & R Division HP.PWD,  
Joginder Nagar

12

Job-7

13

DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.		Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Figures	Words	
Name of Work : Construction of link road from Main road Pipili to Kanehtar Jon in GP Pipili 900mm dia RCC hume pipe culvert at RD 1/090 under SDP deposit SID: SDP/2024/213							
				Estimate Cost: Earnest Money: Time Limit :		99,769.00 2,000.00 Three Months	
1		Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	15.43	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	9,999.00
2		Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	1.53	Per cubic metre	6,653.90	Rupees Six Thousand Six Hundred Fifty Three And Paise Ninety Only	10,180.00
3		Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	6.24	Per cubic metre	7,670.10	Rupees Seven Thousand Six Hundred Seventy And Paise Ten Only	47,861.00
4		Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Per running metre	6,345.70	Rupees Six Thousand Three Hundred Forty Five And Paise Seventy Only	31,729.00
				Total			99,769.00

*Draft schedule of quantity approved for ₹ 99769/- only  
(₹ Ninety nine thousand seven hundred sixty nine) only*

13

Executive Engineer,  
B&R Division, H.P.P.W.D  
Joginder Nagar

Job-8

(14)

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Dol Raktal Changehar road km.0/0 to 8/660 in GP Langna (SH: Providing & laying wearing grade-II & repair of pot holes in km. 0/0 to 3/00 under NDF deposit SID: NDF/2023/1342		Estimate Cost:		AMOUNT Rs. P		
		Estimate Money:	Time Limit :			
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time including GST.	9.37	Per cubic metre	3,560.40	Rupees Three Thousand Five Hundred Sixty And Paise Forty Only	33,361.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 0.30 kg (zero point three kilogramme) per Sqm, 20 mm thick pre-mix carpet with Bitumen VG-10 @ 1.46 kg (One point four six kilogramme) per Sqm and seal coat type B with bitumen VG-10 @ 0.68 kg (zero point six eight kilogramme) per Sqm as per technical specification clause 1904.2, 503 and 508.1. The rate including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	624.92	Per square metre	426.20	Rupees Four Hundred Twenty Six And Paise Twenty Only	2,66,341.00
<b>Total</b>						<b>2,99,702.00</b>

Draft schedule of quantity approved for ₹ 2,99,702/- only  
(= Ninety nine thousand seven hundred two) only

(14)

Executive Engineer

B &amp; R Division HP.PWD,

Joginder Nagar

Job-9

Tullah  
(15)

**DNIT/DRAFT SCHEDULE OF QUANTITY**

Sr. No.		Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT Rs. P
					Figures	Words		
					Rate			
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	25.46	Per Cubic metre	2,344.70	Rupees Two Thousand Three Hundred Forty Four And Paise Seventy Only	59,696.00		
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	16.98	Per Cubic metre	8,166.80	Rupees Eight Thousand One Hundred Sixty Six And Paise Eighty Only	1,38,672.00		
<b>Total</b>							<b>1,98,368.00</b>	

*Draft schedule of quantity approved for  
₹ 198368/- only (Rupee 198 thousand 368 only)  
thousand three hundred sixty eight only*

(15)

*Executive Engineer*  
B & R Division HP.PWD,  
Joginder Nagar

266-10

18

**DNIT/DRAFT SCHEDULE OF QUANTITY**

Sr. No.		Description of work	No. or Qty.	Unit	Rate		Estimate Cost: 39,975.00 Earnest Money: 800.00 Time Limit : One Month
					Figures	Words	
					AMOUNT Rs. P		
1	Supplying and stacking of Crushed/broken stone aggregate 10 to 13.2 mm (thirteen point two to ten millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	13.50	Per cubic metre	2,250.00	Rupees Two Thousand Two Hundred Fifty Only	30,375.00	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Per cubic metre	2,400.00	Rupees Two Thousand Four Hundred Only	9,600.00	
<b>Total</b>						<b>39,975.00</b>	

*Draft schedule of quantity approved for ₹ 39975/- only (₹ Thirty nine thousand nine hundred seventy five)*

*[Signature]*

**Assistant Engineer**  
Sub-Division No.-II  
B & R Division HP.PWD,  
Joginder Nagar

**Executive Engineer**  
B & R Division HP.PWD,  
Joginder Nagar

16

Job-11

DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.		Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Figures	Words	
Name of Work : Construction of link road Bhet to Harizan basti Saparu Construction of 900mm dia RCC hume pipe culvert at RD 0/880 under BSP deposit SID: BSP/2024/460 (SIH: Estimate Cost: 48,264.00 Earnest Money: 1,000.00 Time Limit : one Months)							
1		Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	5.36	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	3,473.00
2		Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	0.43	Per cubic metre	6,653.90	Rupees Six Thousand Six Hundred Fifty Three And Paise Ninety Only	2,861.00
3		Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	1.33	Per cubic metre	7,670.10	Rupees Seven Thousand Six Hundred Seventy And Paise Ten Only	10,201.00
4		Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	5.00	Per running metre	6,345.70	Rupees Six Thousand Three Hundred Forty Five And Paise Seventy Only	31,729.00
Total							48,264.00

Draft schedule approved for E 48,264/- (Forty eight thousand two hundred sixty four) only  
 Executive Engineer  
 B&R Division, HPWD  
 Jaipur

E.N. 0-15

17

Job-12

**DNI/DRAFT SCHEDULE OF QUANTITY**

Name of work:- Construction of link road to Village Bagdaina km 0/00 to 1/000

(SH: Construction of Retaining wall / Pusta for protection of existing R/wall at RD 0/630 to 0/639.70) SDP/2021/160

Estimated Cost : RS. 145628.00

Earnest Money : Rs. 2900.00

Time : Two months

Sr. No.	Item Description	Quantity	Unit	Rate		Amount
				In fig.	In words	
1	2 Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	3 13.14	4 Per Cubic metre	648.00	5 Rupees six hundred forty eight only.	6 8,515.00
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size ) plums and curing complete including the cost of form work in <b>Retaining walls Breast walls</b> , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	22.40	Per cubic metre	6121.10		1,37,113.00
	<b>Total</b>					<b>1,45,628.00</b>

Draft schedule of quantity approved for 14.5628/-  
(Rs one lac forty five thousand and six hundred twenty eight only)

(2)

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.

Job-13

19

## DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
<b>Name of Work : Restoration of rain damages on Jalad Basalan Tanhotu road km 0/0 to 7/0 (SH: Providing and fixing "W" metal beam crash barrier system at km. 1/450 to 1/470)</b>						
<b>Estimate Cost: 93,932.00</b> <b>Earnest Money: 1,900.00</b> <b>Time Limit : Two Months</b>						
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	1.48	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	959.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.46	Per cubic metre	8,114.90	Rupees Eight Thousand One Hundred Fourteen And Paise Ninety Only	11,848.00

<p>3 Providing and erecting a "W" Metal Beam Crash Barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam guard rail 70cm (seventy centimetre). Above road/ ground level fixed on ISMC series channel vertical posts 150x75x5mm thick (one hundred fifty X seventy five X five millimetre) spaced 2.00 (two point zero) metre centre to centre 1.80 metre (one point eight zero) high 1.10 metre (one point one zero) below ground/ road level all steel parts and fittings to be galvanised by hot deep process, all fittings to confirm to IS: 1364, metal beam guard rail to be fixed on the vertical posts with a spacer of channel section 150x75x5mm (one hundred fifty x seventy five x five millimetre), 330mm (three hundred thirty millimetre) long complete as per clause 810 within all leads, lifts carriage of material and other incidentials and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time including GST.</p>	<p>20.00 Per Running Meter</p>	<p>4,056.25</p>	<p>Rupees Four Thousand Fifty Six And Paise Twenty Five Only</p>	<p>81,125.00</p>
<b>Total</b>				<p><b>93,932.00</b></p>

*Draft schedule of quantity approved for ₹ 93932 only (Ninety three thousand nine hundred thirty two) only*

*(19)*  
~~Executive Engineer~~  
 B & R Division HP.PWD,  
 Joginder Nagar

Job - 14

**DNIT/DRAFT SCHEDULE OF QUANTITY**

**Name of Work : Construction of Retaining wall and Drainage system Nichla Panjalag to kanharag GP Kathon Tehsil Lad Bharol Distt. Mandi (HP) (SH: Construction of PCC Pusta for Retaining wall at RD 0/258 to 0/303 SID :MPR/2025/538**

**Estimate Cost: 2,95,832.00**  
**Earnest Money: 5,900.00**  
**Time Limit : Three Months**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock ( where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	48.06	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	31,143.00
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size ) plums and curing complete including the cost of form work in <b>Retaining walls Breast walls</b> , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	43.20	Per cubic metre	6,004.85	Rupees Six Thousand Four And Paise Eighty Five Only	2,59,410.00
3	Providing <b>weep holes</b> in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	16.00	Each	329.95	Rupees Three Hundred Twenty Nine And Paise Ninety Five Only	5,279.00
<b>Total</b>						<b>2,95,832.00</b>

18  
 E.No - 19

*Draft schedule of quantity approved for  
 ₹ 295832/-only (295 lacs ninety five  
 thousand eight hundred thirty two) only*

*Executive Engineer,  
 B&R-Division, H.P.P.W.D  
 Jodhpur*