



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **18-04-2026** up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on **16-04-2026** up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on **17-04-2026** from 2.30 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of rain Damages on Majharnu Kundani Kufru road km. 0/0 to 6/0 (SH:- Construction of wire Crated Retaining wall at km. 2/975 to 2/980, 2/981 to 2/986 & 2/987 to 2/992 under SF Deposit SID: SDF/2025/313).	Rs. 2,99,233/-	Rs.6,000/-	Rs. 350/-	Class "D"	Three Months
2	Construction of Health Sub Centre Kas under Deposit (SH:- Construction of Breast Wall to protection the site at RD. 0/007 to 0/014 under deposit and Construction of link road Kumharda Gayol Kas road km. 0/0 to 0/700 (SH:- Formation Cutting in km. 0/360 to 0/450 under deposit SID.BSP/2021/843)	Rs. 2,89,051/-	Rs. 5,800/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2026-27-

Dated:-

- 36835-84
- 30-03-2026
1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
 2. The Engineer-in-Chief, HPPWD, Shimla.
 3. The Chief Engineer (MZ), HPPWD, Mandi.
 4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
 5. All the Assistant Engineer working under this Division.
 6. All the Contractor working under this Division.
 7. Drawing Branch in this office.
 8. Notice Board.
 9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

728

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Majharnu Kunduni Kufru road km.0/0 to 6/0 (Sh:- Construction of wire created retaining wall at Km. 2/975 to 2/980, 2/981 to 2/986 & 2/987 to 2/992 under SDF deposit
SID:SDF/2025/313)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
				Time Limit : Three Months		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	11.11	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	6,776.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre) into one hundred millimetre mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time including GST. Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time including GST.	70.29	Per Cubic metre	3,830.00	Rupees Three Thousand Eight Hundred Thirty Only	2,69,211.00
3		21.05	Per cubic metre	1,104.30	Rupees One Thousand One Hundred Four And Paise Thirty Only	23,246.00
Total						2,99,233.00

Draft Schedule of Quantity approved for ₹ (2,99,233) 233/- (Two-lacs Ninety nine Thousand two Hundred Thirty Three) only 7/-

Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

728

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of Health Sub Centre Kas under Deposit (SH: Construction of breast wall to protect the site at Rd 0/007 to 0/014 under deposit and construction of link road Kumharda Gayola Kas road km.0/0 to 0/700. (Sh:-Formation cutting in km. 0/360 to 0/450 (under Deposit SID:BSP/2021/843.))				Estimate Cost: Earnest Money: Time Limit :		AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	10.02	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	6,111.00	
2	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.The rate is inclusive all taxes levy by the government time to time including GST.	14.98	Per cubic metre	198.40	Rupees One Hundred Ninety Eight And Paise Forty Only	2,972.00	

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
3 Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	28.98	Per cubic metre	6,036.80	Rupees Six Thousand Thirty Six And Paise Eighty Only	1,74,946.00
4 Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	9.66	Per cubic metre	1,104.30	Rupees One Thousand One Hundred Four And Paise Thirty Only	10,668.00
5 Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	12.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	3,939.00
6 Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 17.73cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	360.32	Per cubic metre	250.93	Rupees Two Hundred Fifty And Paise Ninety Three Only	90,415.00
Total					2,89,051.00

*Draft Schedule of quantity approved for ₹ 2,89,051/-
(Two Lacs Eight nine Thousand Eighty one only) -*

*Executive Engineer
H & R Division HP.PWD,
Jogindar Nagar*

729