



Office of  
Executive Engineer B&R Division HP.PWD. Joginder Nagar  
Himachal Pradesh Public Works Department, Mandi-175015  
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **27-04-2026** up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on **24-04-2026** up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on **25-04-2026** from 2.30 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	C/O Road lower Chauntra to Malehar road km. 0/0 to 2/00 under MGNEREGA (SH:- Supply and Stacking of Crushed/ Broken Stone agg. 20mm and Sand.	Rs. 99,600/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
2	C/o A/R & M/O Dalana to Loan road km. 0/0 to 1/500, under MGNEREGA (SH:- Supplying and Stacking of crushed/ broken Stone aggregate 20mm and Sand).	Rs. 53,900/-	Rs. 1,100/-	Rs. 350/-	Class "D"	Two Months
3.	C/o A/R & M/O Dalana to Barto road km. 0/0 to 1/499 under MGNEREGA (SH:- Supplying and Stacking of crushed/ broken Stone agg. 20mm and Sand.	Rs. 54,110/-	Rs. 1,100/-	Rs. 350/-	Class "D"	Two Months
4.	C/O Link road Khali to Chount (Work code:- 1308002/RC/8000222626) 2025-26 (SH:- Supply and stacking of crushed / broken stone agg. 20mm, and sand). <i>Under MGNEREGA</i>	Rs. 99,960/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Three Months
5.	Repair of Hostel, Residential accommodation (Type-IV III & II) and Guest House in State Level Revenue Training Institute at Joginder Nagar Distt, Mandi (H.P.) (SH:- Providing and fixing aluminum door frame, cupboard, Glass panes etc. under Deposit).	Rs. 2,36,001/-	Rs. 4,700/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.  
District Mandi (HP) for on behalf of  
Governor of Himachal Pradesh  
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2026-27- *1479-1528* Dated:- *17/04/26*

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla
3. The Chief Engineer (MZ), HPPWD, Mandi
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar
5. All the Assistant Engineer working under this Division
6. All the Contractor working under this Division
7. Drawing Branch in this office
8. Notice Board
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder

661

J-1

Schedule of Quantity

Estimated 99600.00 ✓  
 Cost:-  
 Earnest 2000.00  
 Money:-  
 Time:- Two month

Name of work :- C/o road lower Chauntra to Malehar road 0/0 to 2/00 Under MGNREGA  
 Sub Head: Supplying and stacking of crushed/broken stone agg. 20mm and sand.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The Rat is inclusive all taxes levy by the government time to time including GST	30	2200	Rupees Two Thousand Two Hundred and Paise Nil ✓	Per cubic metre ✓	66000 ✓
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. he Rat is inclusive all taxes levy by the government time to time including GST	14	2400	Rupees Two Thousand Four Hundred and Paise Nil ✓	Per cubic metre	33600 ✓
Total:-						99600.00

*Shas JE*

Assistant Engineer,  
 B&R Sub Division No.II,  
 HP.PWD, Joginder Nagar

*Draft schedule of quantity checked & approved for 99,600/- (Ninety nine thousand six hundred only)*

*Executive Engineer*  
 B&R Division, HP.PWD  
 Joginder Nagar (H.P.)

635

Job-4

J-2

**Draft** Schedule of Quantity

Estimated Cost:- 54110.00  
Earnest Money:- 1100.00  
Time:- Two month

Name of work : C/O A/R M/O Dalana to Bario road km 0/0 to 1/499 under MGNREGA.

Job Head: Supplying and stacking of crushed/broken stone agg. 20mm and Sand)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The Rat is inclusive all taxes levy by the government time to time including GST.	7.49	2200.00	Rupees Two thousand Two hundred and paise nil only	Per cubic metre	16478.00
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect.he Rat is inclusive all taxes levy by the government time to time including GST	15.68	2400.00	Rupees two thousand four hundred and paise nil only	Per cubic metre	37632.00
<b>Total:-</b>						<b>54110.00</b>

*[Signature]*

Assistant Engineer,  
B&R Sub Division No.II,  
HP RWD, Joginder

*Draft Schedule of Quantity approved for ₹ 54110 only  
(₹ Fifty four thousand one hundred ten) only*

Executive Engineer  
B&R Division, HPPWD  
Joginder Nagab (H.P.)

Job-5

J-3

634

**Draft** Schedule of Quantity

Estimated Cost:- 53900.00  
Earnest Money:- 1100.00  
Time:- Two month

Name of work : C/O A/R M/O Dalana to Loan road km 0/0 to 1/500 under MGNREGA.

Sub-head: Supplying and stacking of crushed/broken stone agg. 20mm and Sand)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The Rat is inclusive all taxes levy by the government time to time including GST.	7.46	2200.00	Rupees Two thousand Two hundred and paise nil only	Per cubic metre	16412.00
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. he Rat is inclusive all taxes levy by the government time to time including GST	15.62	2400.00	Rupees two thousand four hundred and paise nil only	Per cubic metre	37488.00
<b>Total:-</b>						<b>53900.00</b>

*[Signature]*

Assistant Engineer,  
B&R Sub Division No.II,  
HP, PWD, Jodinder

*Draft schedule of quantity approved for ₹ 53900/- only  
(₹ Fifty three thousand nine hundred only)*

*[Signature]*  
Executive Engineer  
B&R Division, HPPWD  
Joginder Nagar (H.P.)

628

Draft Schedule of Quantity

Estimated Cost:- 99960.00  
Earnest Money:- 2000.00  
Time:- Three months

Name of work:- C/O Link road Khali to Chount (Work code:- 1308002/RC/8000222626) 2025-26  
Sub Head: Supplying and stacking of crushed/broken stone agg. 20mm, and sand

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect.	30.60	2200.00	Rupees Two thousand and Two hundred only	Per cubic metre	67320.00
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect.	13.60	2400.00	Rupees Two thousand and four hundred only	Per cubic metre	32640.00
					Total:-	99960.00

628

S. C. Choudhary

Assistant Engineer,  
B&R Sub Division No.II,  
HP.PWD, Joginder Nagar

Draft schedule of quantity approved for ₹ 99960.00/-only  
(₹ = Ninety nine thousand nine hundred sixty) only.

Executive Engineer  
B&R Division, HPPWD  
Joginder Nagar (H.P.)

6

## DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : Repair of Hostel, residential accommodation (Type-IV, III & II) and Guest House in State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (Sh:- Providing & fixing aluminium door frame, cupboard, Glass panes etc. under Deposit.)		Estimate Cost: 2,36,001.00 Earnest Money: 4,700.00 Time Limit : Three Months				
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions. i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket require (Fittings shall be paid for separately) for fixed portion Powder coated aluminium (minimum thickness of powder coating 50 (fifty micron) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	41.30	Per Kilogramme	480.45	Rupees Four Hundred Eighty And Paise Forty Five Only	19,843.00
2	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood Pre-laminated one side decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including priming coat on unexposed surface, with necessary fixing arrangement and screws etc. complete. 12mm (twelve millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	2.88	Per Square Meter	1,124.80	Rupees One Thousand One Hundred Twenty Four And Paise Eighty Only	3,239.00
3	Providing and fixing 250x16mm (two hundred fifty by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	2.00	Each	242.45	Rupees Two Hundred Forty Two And Paise Forty Five Only	485.00
4	Providing and fixing 300x16mm (three hundred by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	3.00	Each	269.50	Rupees Two Hundred Sixty Nine And Paise Fifty Only	809.00
5	Providing and fixing anodized aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 250x10mm (Two hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	2.00	Each	109.15	Rupees One Hundred Nine And Paise Fifteen Only	218.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 150x10mm (One hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	27.00	Each	83.30	Rupees Eighty Three And Paise Thirty Only	2,249.00
7	Providing and fixing anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete.100mm (one hundred millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.00	Each	58.50	Rupees Fifty Eight And Paise Fifty Only	234.00
8	Providing and fixing anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete.75mm (Seventy five millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	14.00	Each	48.30	Rupees Forty Eight And Paise Thirty Only	676.00
9	Providing and fixing 40 mm (forty millimetre) panelled or panelled and glazed shutters with 2nd class deodar wood for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.89	Per Square Metre	5,718.95	Rupees Five Thousand Seven Hundred Eighteen And Paise Ninety Five Only	10,809.00
10	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty with Float glass panes of nominal thickness 4 mm (four millimeter) (weight not less than 10kg/sqm)(ten kilogramme per square meter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	1.35	Per Square metre	673.00	Rupees Six Hundred Seventy Three Only	909.00
11	Providing and fixing 25mm (twenty five millimetres) thick ISI marked cup board shutter (for cupboard) including ISI marked nickel plated bright finished M.S.Piano hinges IS : 3818 marked with shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hardwood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	61.81	Per Square metre	2,961.20	Rupees Two Thousand Nine Hundred Sixty One And Paise Twenty Only	1,83,032.00
12	Painting on wood work with two or more coat applied @ 0.90 litre/ 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied @ 0.75 litre/ 10 sqm (seventy five liter per ten square meter) of approved brand and manufacture with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time including GST.	61.81	Per square metre	119.00	Rupees One Hundred Nineteen Only	7,355.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
13	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete, as per the direction and entire satisfaction of Engineer-in -Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	59.76	Per square metres	102.80	Rupees One Hundred Two And Paise Eighty Only	6,143.00
	<b>Total</b>					<b>2,36,001.00</b>

*Draft schedule of quantity approved for ₹ 236001 only  
(₹ Two Lacs thirty six thousand one) only*

(6)

*[Signature]*  
Executive Engineer  
B & R Division HP.PWD,  
Joginder Nagar

AGE 50  
ISE I  
Nagar