

**O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.**

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in) e-mail: [ee-karc-hp@nic.in](mailto:ee-karc-hp@nic.in) DDO KNR04-651 Phone No-01786-292897

No:- PW- BHNR-B&R-EA-I-Tender Notice/2026-27- 477

Registered  
Dated:- 18/9/2026

To

The Executive Engineer (IT Cell),  
Nigam Bihar, Himachal Pradesh Shimla-2.


**Subject:- Publication of Notice Inviting Tender.**

Sir,

I am enclosing herewith the "Notice Inviting Tender" alongwith "Schedule of Quantity" for uploading on Department website as per Notification No. PWD-B-A0(3)/1/2024-241828 dated 18.09.2025 issued by the Additional Chief Secretary (PW) to the Govt. of HP & circulated by the Engineer-in-Chief, HP.PWD., office letter No.PW/CTR/32-20/Genl Inst/ GCC/2025-10063-10163 dated 27.09.2025 for favour of information and necessary action. The works attached in list is very urgent nature. It is requested that the same may kindly be got published.

DA: - Notice Inviting Tender/Schedule of Quantity.

Yours Faithfully

  
Executive Engineer,  
Karchham Division,  
HP.PWD., Bhabanagar.



O/o the Executive Engineer, Karchham Division, HP.PWD: Bhabanagar 172115.

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), e-mail: [ee-karc-hp@nic.in](mailto:ee-karc-hp@nic.in) Phone No-01786-292897

### NOTICE INVITING TENDER

Sealed percentage tender(s) on PWD form No.6 & 8 are hereby invited by the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD in appropriate class to reach in this office on **25.04.2026** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **23.04.2026** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without earnest money or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur H.P. Ambiguous/ Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of form
1	R/R damages on jeepable road from Kafnoo Bazar to village Kafnoo Km. 0/00 to 0/620. (SH:- C/O R/wall at RD. 0/095 to 0/106.50).	497226.00	10000.00	Two months	350/-
2	Construction of 45.00 mtr. span steel truss bridge on Shong to Brua road at RD. 0/280. (SH:- Geotechnical Investigation).	284000.00	5700.00	One month	350/-
3	Construction of 30.00 mtr. span steel Composite Girder bridge on Chaura to Majhgaon road at RD. 19/770. (SH:- Geotechnical Investigation).	284000.00	5700.00	One month	350/-
4	Construction of 30.00 mtr. span steel Composite Girder bridge on Chaura to Majhgaon road at RD. 16/240. (SH:- Geotechnical Investigation).	284000.00	5700.00	One month	350/-
5	C/O link road from village Shango to Dutrang Km. 0/00 to 2/500 (SH:-Formation cutting 5/7 mtr. wide road between Km. 0/610 to 0/640 and C.C. Toe wall at RD. 0/610 to 0/625).	490609.00	9900.00	Two months	350/-
6	C/O link road from Kacharang to Gharshu via Rockcharang Km. 0/0 to 2/730.(SH:- Formation cutting 5/7 mtr. wide road at RD.0/285 to 0/300).	421176.00	8500.00	Two months	350/-

### SPECIAL CONDITIONS


1. The material shall be arranged by the contractor himself.
2. The detail of documents to be attached with the application is given below.
  - i Latest copy of renewal enlistment.
  - ii Copy of Pan Card.
  - iii Copy of GST No.
3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the office of the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractors are requested to quote percentage rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labour cess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
12. A contractors enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification.

13. The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.

14. Cement should be purchased from H.P. State Civil Supply Corporation.

15. GST will be deducted from each bill as per latest instruction of the Government.

16. The rates beyond over +5% will be rejected. Besides this the additional performance security will to borne @ 20 % and 30% for unbalanced bid. Additional Performance security of 20% will be borne for the unbalance bid of -10% to -20% and 30 % will be borne for the unbalance bid of below to the -20%, however the tender beyond the limit of -30% will also be accepted.

  
Executive Engineer,  
Karchham Division,  
HP.PWD., Bhabanagar.

No.PW/BHNR/B&R/EA-I-Tender Notice/2026-27- 414-23

Copy forwarded for information to the:-

1. The Engineer-in-Chief, HP.PWD, Shimla
2. The Chief Engineer (SZ) HP.PWD, Shimla-1
3. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD, Rampur
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.

Dated:- 18/04/2026

Executive Engineer,  
Karchham Division,  
HP.PWD., Bhabanagar.




*O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.*

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in) e-mail: [ee-karc-hp@nic.in](mailto:ee-karc-hp@nic.in) DDO KNR04-651 Phone No-01786-292897

**CERTIFICATE**

Certified that the tenders of the works invited vide this office  
NIT No.PW/BHNR/B&R/EA-I-Tender Notice/2026-27-414-23 Dated **18.04.2026** is urgent  
nature in exigency of Public interest.

  
Executive Engineer,  
Karchham Division,  
HP.PWD., Bhabanagar.

## Draft Schedule of Quantity

Estimated Cost:- 497226.00  
 Earnest Money:- 10000.00  
 Time:- Two Months

Name of work:- R/R damages on Jeepable road from Kafnoo Bazaar to village Kafnoo road Km 0/00 to 0/620  
 Sub Head:- C/o R/wall at RD 0/095 to 0/106.50)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto to any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	68.20	300	Rupees Three Hundred Only	Per cubic metre	20460.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	143.75	3218.8	Rupees Three Thousand Two Hundred Eighteen and Eighty Paises Only	Per cubic metre	462703.00
3	Back filling behind Retaining wall with granular material complete as per drawing and M.O.R.D. technical specification clause 1204.3.8. Including carriage of material within all lead and lifts and other incidentals.	14.49	970.5	Rupees Nine Hundred Seventy and	Per cubic metre	14063.00
					Total	497226.00

Draft schedule of quantity approved for amounting to Rs. 497226/- only *[Signature]*

Executive Engineer,  
 Karchham Division, HPPWD.,  
 Karchham at Bhaba Nagar

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of 45.00 Mtr Span Steel Truss Bridge On Shong To Brua Road At Rd 0/280. (SH- Geotechnical Investigation).

Estimated Cost : Rs 284000.00

Earnest Money : Rs 5700.00

Time Limit : One Month

S.No	Description of Item	Quantity		Rate		Unit	Amount
			In fig.	In word			
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work . The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as pe rthe direction of Engineer- in Charge.	40.00	7100.00	Ruppes Seven Thousand one hundred Only	Per Running metre	284000.00	
Total Amount in figures:-							284000.00

Draft schedule of quantity approved for amounting to Rs. 2,84,000/- only

Executive Engineer,  
Karham Division  
H.P.PWD. Karham


**DRAFT SCHEDULE OF QUANTITY**

**NAME OF WORK:-** Construction of 30.00 Mtr Span Steel Composite Girder Bridge On Chaura To Majhgoan At Rd 19/770. (SH- Geotechnical Investigation).

Estimated Cost : Rs 284000.00  
 Earnest Money : Rs 5700.00  
 Time Limit : One Month

S.No	Description of Item	Quantity		Rate		Unit	Amount
		In fig.	In word	In fig.	In word		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work . The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as pe rthe direction of Engineer-in Charge.	40.00	Rmt	7100.00	Rupees Seven Thousand one Hundred Only	Per Running metre	284000.00
<b>Total Amount in figures:-</b>							<b>284000.00</b>

*Draft schedule of quantity approved for amounting to Rs 284000/- only*

  
 Executive Engineer,  
 Kartham Division  
 H.P.PWD. Kartham


**DRAFT SCHEDULE OF QUANTITY**

**NAME OF WORK:-** Construction of 30.00 Mtr Span Steel Composite Girder Bridge On Chaura To Majhgoan At Rd 16/240. (SH- Geotechnical Investigation).

Estimated Cost : Rs 284000.00  
 Earnest Money : Rs 5700.00  
 Time Limit : One Month

S.No	Description of Item	Quantity		Rate		Unit	Amount
			In fig.	In word			
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work . The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as pe rthe direction of Engineer- in Charge.	40.00	7100.00	Ruppes Seven Thousand one hundred Only	Per Running metre	284000.00	
<b>Total Amount in figures:-</b>							<b>284000.00</b>

*Draft Schedule of Quantity approved for amounting to Rs 284000/-only*

  
 Executive Engineer,  
 Karhagam Division  
 H.P.PWD. Karhagam

(22)

**Draft Schedule of Quantity**

Estimated Cost:-  
Earnest Money:-  
Time:-

490609.00  
9900.00  
Two Months

26

Name of work:-C/o Link road Village from Shango to Dutrang 0/00 to 2/500 .  
Sub Head:- C/o F/C 5/7 mtr wide between Km 0/610 to 0/640 and cc toe wall at RD 0/610 to 0/625

Sr. No.	Description of item	Qty.	In Figure	Rate		Unit	Amount
				In Words			
1	Cutting in earth work in all depths and heights in hard rock with chiselling and wedging out of rock (where blasting is prohibited), or setting out to the required lines grades, side slopes, trimming of bottom and levels as shown on the drawing and as directed by the Engineer-in-charge at site according to the HPPWD specification of 1990 volume-1 and sorting of useful and unuseful materials and stacking the useful material along road side which shall not be less than 118.68 cubic metre falling which recovery @ Rs. 300/- per cubic metre shall be effected and transportation of the un useful material for filling in roadway embankments for grade improvement and level to required grades and then disposing off all surplus excavated material in acquired width of the road or on approved dumping site to be arranged by the contractor through all modes of transportations including head load, animal loads or mechanical means along with its levelling and fine dressing and carriage of all labour machinery, materials, tools, equipments and safety measured and other incidentals necessary to complete the work by mechanical means and or labor (if any required complete as per the direction of Engineer-in-Charge). Any loss to the public and private property during the course of execution and transportation of useful and un useful materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him to full extent complete in all respects and in all cases.	356.03	650.7	Rupees Six Hundred Fifty and Seventy Paises Only		Per cubic metre	231659.00
2	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	6.12	300	Rupees Three Hundred Only		Per cubic metre	1836.00
3	Supplying, fitting and placing TMT bar reinforcement in superstructure complete as per drawings and technical specifications Clauses 1000 and 1202 and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	111.15	103.95	Rupees One Hundred Three and Ninety Five Paises Only		Per Kg	11554.00
4	Providing and laying cement concrete 1:4:8 (One cement : four sand : eight graded stone aggregate 25mm (Twenty Five millimetre) nominal size) and curing complete including cost of form work in retaining walls/breast walls, as per drawing and technical specification clause 802, 803, 1202 & 1203 as per HPPWD specification within all leads and lifts and as per the direction of Engineer-in-charge.	43.20	5281	Rupees Five Thousand Two Hundred Eighty One Only		Per cubic metre	228139.00

5	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm. (One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (V) : 20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	30.00	260.1	Rupees Two Hundred Sixty and Ten Paises Only	Each	7803.00
6	Back filling behind Retaining wall with granular material complete as per drawing and M.O.R.D. technical specification clause 1204.3.8. Including carriage of material within all lead and lifts and other incidentals.	9.90	970.5	Rupees Nine Hundred Seventy and Fifty Paises Only	Per cubic metre	9608.00
					Total	490609.

*Draft schedule of quantity approved for amounting to Rs. 490609/- only*

Executive Engineer,  
Karchham Division, HPPWD,  
Karchham at Bhaba Nagari

Draft Schedule of Quantity

25

Estimated Cost:- 421176.00  
 Earnest Money:- 8500.00

Time:- Two Months

Name of work:- C/O link road from Kachrang to Gharshu via Rockcham Km 0/00 to 2/730.  
 Sub Head:- F/C 5/7 mtr wide road at RD 0/285 to 0/300.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Cutting in earth work in all depths and heights in hard rock with chiselling and wedging out of rock (where blasting is prohibited), or setting out to the required lines grades, side slopes, trimming of bottom and levels as shown on the drawing and as directed by by the Engineer-in-charge at site according to the HPPWD specification of 1990 volume-1 and sorting of useful and unuseful materials and stacking the useful material along road side which shall not be less than 249.12/- cubic metre failing which recovery @ Rs. 300/- per cubic metre shall be effected and transportation of the un useful material for filling in roadway embankments for grade improvement and level to required grades and then disposing off all surplus excavated material in acquired width of the road or on approved dumping site through all modes of transportations including head load, animal loads or mechanical means along with its levelling and fine dressing and carriage of all labour machinery, materials, tools, equipments and safety measured and other incidentals necessary to complete the work by mechanical means and or labor (if any required complete as per the direction of Engineer-in-Charge). Any loss to the public and private property during the course of execution and transportation of useful and un useful materials shall be absolute responsibility of the contractor which shall have to be dully compensated by him to full extent complete in all respects and in all cases.	1167.76	360.67	Rupees Three Hundred Sixty and Sixty Seven Paises Only	Per cubic metre	421176.00
	Total					421176.00

*Draft Schedule of quantity approved for amounting to Rs. 421176/- only*

Executive Engineer,  
 Karchham Division, HPPWD,  
 Karchham at Bhaba Nagar