

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

4559

Dated:- 10.04.26

To

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :-

Regarding publication of Tender on departmental site
(Short Term Notice).

With reference to the notification issued by the
Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024
dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed
please find herewith the copy of Notice Inviting Tender for the loading on
departmental web-site as

*Certified that the works mentioned in the Tender Notice are
urgent in nature and in coordination with the Disaster Management Act, 2005
Section 24 (i).*

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in
Notice inviting tender**

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **18.04.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 17.04.2026** for which the application should reach in this office **upto 1.00 PM 17.04.2026**.


The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	C/O Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Double curtain with curtain rod , G.I pipe and Sun board Etc.)	96,547	2,000/-	One Month	350/-
2	C/O Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and laying C.C 1:2:4, flex board and Polish in building)	84,554/-	1,700/-	One Month	350/-
3	C/O Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Granite slab in pantry ,painting and moulding Etc.)	94,513/-	1,900/-	One Month	350/-
4	C/O Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing frames and lining in the opening foe lifts etc.)	99,336/-	2,000/-	One Month	350/-

5	Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Curtain rod including Curtain in Session Court Room)	99,828/-	2,000/-	One Month	350/-
6	C/O Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Cupboard in Pantry room)	99,859/-	2,000/-	One Month	350/-
7	Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Curtain rod including Curtain in JMFC Court Room)	99,828/-	2,000/-	One Month	350/-
8	Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Cupboard in kitchen Room)	99,859/-	2,000/-	One Month	350/-
9	Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing fixing of 2mm thick pvc floor drawer slider, cullery organizer and plaster etc)	98,188/-	2,000/-	One Month	350/-
10	A/R & M/O Rest House at Karsog Tehsil Karsog Distt. Mandi H.P. (SH:- Cleaning of sewer line and septic Tank)	97,065/-	2,000/-	One Month	350/-
11	R/R damages on Salana to Mehandi via Noga Tikkri road KM. 0/00 to 4/500 (SH:- Removal of slips at various RDs)	98,682/-	2,000/-	One Month	350/-
12	R/R damages on Karsog Parlog road KM. 0/00 to 19/00 (SH:- Trimming of grass and weeds in various RDs)	97,000/-	1940/-	One Month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


 Executive Engineer
 B&R Division
 HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

4583-58

Dated:-

10.04.26

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

**Executive Engineer,
B&R Division,
HPPWD Karsog**

Percentage Schedule of Quantity

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Dist. Mandi (H.P) (Sh:- Providing and fixing Double curtain with curtain rod , G.I pipe and Sun board Etc.)

Estimated Cost 96547.00
Earnest Money 2000.00
Time One month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Providing and supplying of double Curtain rod with double curtain 8x1/2"x2x1/2"(eight into half into two into half as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	12.00	Each	4130.00	49560.00	Rupees Forty Nine Thousand Five Hundred Sixty and Paise Zero
2	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall : 32 mm (thirty two mili metre) nominal bore as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	36.00	Per Running Meter	805.20	28987.00	Rupees Twenty Eight Thousand Nine Hundred Eighty Seven and Paise Zero Only
3	Providing and fixing Sun board including writing as per approved from engoneer in charge size 0.30x0.10 mtrs (zero point thirty into zero point ten metre) as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	80.00	Each	225.00	18000.00	Rupees Eighteen Thousand and Paise Zero Only
Total in Figures					96547.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 84554.00
Earnest Money 1700.00
Time One month

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and laying C.C 1:2:4, flex board and Polish in building)
Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Providing and laying concrete for plain/reinforcement concrete 1:2:4 (one cement : two sand : four graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	4.88	Per Cubic Meter	7384.70	36037.00	Rupees Thirty Six Thousand Thirty Seven and Paise Zero Only
2	Providing and fixing 2 mm (two millimetre) thick teak ply of standard quality and of approved shade and design wall lining including fixing with approved adhesive, butt jointing and nails & screws complete and as per approved architectural drawings and the directions of Engineer- in - Charge including carriage of material within all leads, lifts and other incidentals.	15.60	Per Square Meter	1077.53	16809.00	Rupees Sixteen Thousand Eight Hundred Nine and Paise Zero Only
3	Providing and fixing flex board including ms square frame of 19mmx19mm (nineteen into nineteen millimetre) and writing etc. complete as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	8.10	Per Square Meter	1206.20	9770.00	Rupees Nine Thousand Seven Hundred Seventy and Paise Zero Only
4	Providing and polishing in high gloss/matt finish melamine clear polish on wood work in required colour/ wooden shade texture with process in the sequence as the surface to be polished is rubbed with sand paper 80/120 No. (eighty/one hundred twenty number) and then with sand paper of 160/180 nos (one hundred sixty/one hundred eighty numbers). Applying two coats of sealer with spray gun and allowing sufficient drying time for 1st (first) coat and 2nd (second) coat is allowed to dry for 8 to 12 hrs (eight to twelve hours). On drying of sealer coat, wet rubbing with emery cloth of finer grading with ample water to remove excess sealer layer and make the surface further smooth after this wet rubbing, then surface is applied with special grade melamine fillers to fill all the small and big holes/ grooves etc. Filler coat to be allowed to dry for 4 to 6 hrs (four to six hours) on which again a light wet rubbing is done this surface is further allowed to dry for 12 hrs (twelve hours). On this, 1st (first) coat of melamine polish is applied with spray gun using melamine clear polish and melamine thinner in required proportion. This 1st (first) coat is allowed to dry for 24 hrs (twenty four hours) then this dry surface is again fine wet rubbed smooth, which is further allowed to dry for 12 hrs (twelve hours). The final melamine polish is applied with compressor pressure spray gun using melamine clear polish and melamine thinner mixed in required proportion complete as per direction & satisfaction of Engineer-in-Charge. (Final coat to be done in 1 or 2 (one or two) layers without gap of time.) and as per approved architectural drawings and the directions of Engineer- in - Charge including carriage of material within all leads, lifts and other incidentals.	19.05	Per Square Meter	1151.60	21938.00	Rupees Twenty One Thousand Nine Hundred Thirty Eight and Paise Zero Only
Total in Figures					84554.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 94513
Earnest Money 1900
Time One Month

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Granite slab in pantry, painting and moulding Etc.)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (Eighteen Millimeter) thick stone slab over 20 mm (twenty millimeter) (average) thick base of cement mortar 1:4 (one cement : four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4.08	Per Square Meter	5778.85	23578.00	Rupees Twenty Three Thousand Five Hundred Seventy Eight and Paise Zero Only
2	Providing and fixing chromiuplated brass 100 mm (one hundred millimeter) mortice latch and lock with 6 lever sand apart of lever handles of approved quality with necessary screws etc. complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	30.00	Each	865.35	25961.00	Rupees Twenty Five Thousand Nine Hundred Sixty One and Paise Zero Only
3	Providing and fixing bright finished brass handles with screws etc. complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	20.00	Each	80.65	1613.00	Rupees One Thousand Six Hundred Thirteen and Paise Zero Only
4	Providing and applying white cement based putty of average thickness 1 mm, (one millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	37.29	Per Square Meter	142.05	5297.00	Rupees Five Thousand Two Hundred Ninety Seven and Paise Zero Only
5	Finishing walls with 100% weather proof exterior premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm (one point four three liter per ten square meter). Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (zero point nine zero liter per ten square meter) : New work (Two or more coats applied @ 1.43 litre/ 10 sqm (one point four three liter per ten square meter). Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (zero point nine zero liter per square meter) as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	218.44	Per Square Meter	128.55	28080.00	Rupees Twenty Eight Thousand Eighty and Paise Zero Only

6	Providing and fixing 2nd (second) class teak wood moulded beading size 50 x 12 mm (fifty into twelve millimeter) to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	69.00	Per Running Meter	144.70	9984.00	Rupees Nine Thousand Nine Hundred Eighty Four and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					94513.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99336
Earnest Money 2000

Time One Month

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing frames and lining in the opening for lifts etc.)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST in Words
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	0.19	Per Cubic Metre	151835.85	28849.00	Rupees Twenty Eight Thousand Eight Hundred Forty Nine and Paise Zero Only
2	Providing and fixing plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden/steel frame work, complete as per direction of Engineer-in- charge (Frame work shall be paid for separately). 9.140.1 12 mm (twelve millimeter) thick commercial ply conforming to IS 1328 BWR type as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	28.32	Per Square Metre	2488.95	70487.00	Rupees Seventy Thousand Four Hundred Eighty Seven and Paise Zero Only
Total in Figures					99336.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 00028.00
 Earnest Money 2000.00
 Time One month

Name of Work:-C/O Judicial court complex at Karnog Tehsil Karnog Distt. Mandi (I.L.P)Sh:- Providing and fixing Curtain road including Curtain InBersion court room)

Sl.No.	Sub-head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Providing and supplying of Curtain rod with curtain 8x1/2x2x1/2" (eight into half into two into half)as per direction of engineer in charge including cartage of materiale within all leads, lifts and other incidental	30.00	Each	2773.00	00028.00	Rupess Ninety Nine Thousand Eight Hundred Twenty Eight and Paise Zero Only
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
 Karnog Division,
 HPPWD, Karnog.

Percentage Schedule of Quantity

Estimated Cost 99859.00
Earnest Money 2000.00
Time One month

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Cupboard in Pantry room)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Providing and fixing 19mm(nineteen milli metre) thick water proof termite resistant HDMR/Ply board etc. wood conforming ply wood of ACTION TESA, GREENPLY box including shelves and shutters, the back side of cup board/cabinet shall be 19mm thick pre-laminated MDF board and all the cut portions of shelves and shutters shall be finished with 1mm (one milli metre) thick pre-lamination/ 4mm (four milli metre) thick veneer pasted over shutter to be polished. All internal and external surfaces of cup board shall be laminated with 1mm laminate sumnica of approved shade . All cut portion of the shelves shall be finished with Wood edging. The shutters of cup board from all sides shall be finished with PVC edging including piano hinges and magnetic catcher with in all accessories etc. complete as per given specification as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	6.75	Per Square Meter	14793.90	99859.00	Rupees Ninety Nine Thousand Eight Hundred Fifty Nine and Paise Zero Only
Total in Figures					99859.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99828.00
Earnest Money 2000.00
Time One month

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Distt. Mandi (H.P.) (Sh:- Providing and fixing Curtain road including Curtain in JMFC court room)

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Providing and supplying of Curtain rod with curtain 8x1/2x2x1/2' (eight into half into two into half) as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals	36.00	Each	2773.00	99828.00	Rupees Nine Thousand Eight Hundred Twenty Eight and Paise Zero Only
Total In Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Bill of Quantity

Estimated Cost 98188.00
Earnest Money 2000.00
Time One Month

Name of Work:- C/O judicial court complex at Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing of 2mm thick pvc floor drawer slider, cutlery organiser and plaster etc.)

Sr. No.	Sub-Head and item of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all Taxes including GST in RS. P	Total Amount With All taxes Including GST in Words
1	2 mm thick pvc/rubber tile flooring. plain, coloured, corbed, or mosaic or mottled finish. laid with approved adhesive on sub floor complete (sub- floor including damp proofing treatment to be measured separately for payment) as per direction of engineer in charge with in all lead and lift and other incidentals.	34.20	Per Square Metre	1269.90	43431.00	Rupees Forty three Thousand four hundred thirty one and Zero Paisa only
2	Providing and fixing drawer slider channel of harrison or its equivalent complete as per direction of engineer in charge. as per direction of engineer in charge with in all lead and lift and other incidentals.	12.00	Each	1250.00	15000.00	Rupees Fifteen Thousand and zero Paisa only
3	Providing and fixing PVC cutlery organiser for kitchen complete as per direction of engineer in charge. as per direction of engineer in charge with in all lead and lift and other incidentals.	3.00	Each	2250.00	6750.00	Rupees six Thousand seven hundred fifty and zero paisa only
4	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. as per direction of engineer in charge with in all lead and lift and other incidentals.	262.38	Per Square Metre	125.80	33007.00	Rupees Thirty three thousand seven and zero paisa only
	Total in Figures				98188.00	
	Quoted Rate in Figures					
	Quoted Rate in Words					

Bill of Quantity approved for Rs. 98188.00
Sr. No. For Years 2026-27

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Bill of Quantity

Estimated Cost 97065.00
 Earnest Money 2000.00
 Time One Month

Name of Work:- A/R & M/O Rest House at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Cleaning of sewer line and Septic Tank)

sr. No.	Sub- Head and item of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all Taxes including GST in RS. P	Total Amount With All taxes Including GST in Words
1	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm dia for all depths per direction of engineer in charge with in all lead and lift and other incidentals.	229.44	Rmtrs.	423.05	97065.00	Rupees Ninety Seven Thousand sixty five and Zero Paisa only
	Total in Figures				97065.00	
	Quoted Rate in Figures					
	Quoted Rate in Words					

Bill of Quantity approved for Rs. 97065.00
 Sr. No. For Years 2026-27


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Bill of Quantity

Estimated Cost 98682.00
Earnest Money 2000.00
Time One Month

Name of Work :- R.R Damages on Salana to Mehandi via noga Tikkri road Km 0/00 to 4/500 (Sh:- Removal of slips at Various Rd)

Sr. No.	Sub- Head and Item of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all Taxes including GST in RS. P	Total Amount With All taxes Including GST in Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 other incidentals, as per direction of engineer in charge with in all lead and lift and other incidentals.	822.35	Per Cubic metre	120	98682.00	Rupees Ninety Eighth Thousand six hundred eighty two and Zero Paisa only
	Total in Figures				98682.00	
	Quoted Rate in Figures					
	Quoted Rate in Words					

Bill of Quantity approved for Rs. 98682.00
Sr. No. For Years 2026-27

Executive Engineer
Karsog Division
HP PWD Karsog

Percentage Bill of Quantity

Estimated Cost 97000.00
Earnest Money 1940.00
Time One Month

Name of Work :- R.R Damages on Karsog Parlog Road km 0/00 to 19/000 (S.H. :- Trimming of Grass and weeds in various Rds)

Sr. No.	Sub- Head and item of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all Taxes including GST in RS. P	Total Amount With All taxes Including GST in Words
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 as per direction of engineer in charge with in all lead and lift and other incidentals.	20000	Sqm	4.85	97000.00	Rupees Ninety Seven Thousand and Zero Paisa only
	Total in Figures				97000.00	
	Quoted Rate in Figures					
	Quoted Rate in Words					

Bill of Quantity approved for Rs. 97000.00

Sr. No. For Years 2026-27


Executive Engineer
Karsog Division
HP PWD Karsog