

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

To

Dated:- 10-4-2024

432

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.


Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in
Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **23.04.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 22.04.2026** for which the application should reach in this office **upto 1.00 PM 22.04.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H:P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of JCb Rock Breaker for breaking/removal of rock/boulders in Km. 4/500 to 5/500)	99,000/-	2,000/-	One Month	350/-
2	R/R damages on Shilh to Tharmi via Pokhi road Km. 0/00 to 12/746 (SH:- Removal of slips & maintenance of berms in KM. 0/00 to 7/00) Job No. 2	98,409/-	2,000/-	One Month	350/-
3	R/r damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of JCB Rock Breaker for breaking/removal of rock/boulders in Km. 6/700 to 7/700)	99,000/-	2,000/-	One Month	350/-
4	R/R damages on Chamanpur to Sihni road Km. 0/00 to 2/00 (SH:- C/o B/wall at RD 0/680 to 0/700) Balance work from RD 0/698 to 0/700) Step-III	98,003/-	2,000/-	One Month	350/-
5	R/R damages on Shimla to Mandi via Tattapani road Km.55/500 to 90/00 (SH:- C/o B/wall at RD 87/00 to 87/007)	99,764/-	2,000/-	One Month	350/-
6	R/R damages on Rangan Ghaini Shaindhal road Km. 0/00 to 5/500 (SH:- Removal of slips at various RDs)	99,316/-	2,000/-	One Month	350/-

7	R/R damages on Kelodhar to Government Degree College Karsog Km. 0/00 to 3/00 (SH:- Removal of slips & maintenance of earthen shoulders at various RDs in KM. 0/00 to 1/500)	98,441/-	2,000/-	One Month	350/-
8	R/r damages on Balna to Naraina Behli KM. 0/00 to 3/00 (SH:- Removal of slips & maintenance of earthen shoulders at various RDs in KM. 0/00 to 1/500)	99,325/-	2,000/-	One Month	350/-
9	R/R damages on Alsindi Tattapani via Dhundan road KM. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 3/720 to 3/733) under PDNA 2023	4,98,291/-	10,000/-	One Month	350/-
10	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 4/330 to 4/340) and edge wall at RD 4/495 to 4/535) under PDNA 2023	4,97,138/-	10,000/-	One Month	350/-
11	R/R damages on Kotlu to kevidhar via Porla road in GP Teban KM. 0/00 to 6/120 (SH:- Removal of slips in Km. 0/00 to 5/00)	98,860/-	2,000/-	One Month	350/-
12	R/R damages on Kotlu Katanda road KM. 0/00 to 16/00 (SH:- Removal of slips, maintenance of berms & C/o unlined drain in KM. 0/00 to 16/00) under PDNA	99,846/-	2,000/-	One Month	350/-
13	R/R damages on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/00 (SH:- Removal of slips at RD 40/540 to 40/570, 40/710 to 40/770 & 41/060 to 41/130)	99,467/-	1,900/-	One Month	350/-
14	R/R damages on Katanda Pokhi road Km. 0/00 to 10/00 (SH:- Removal of slips at various RDs in Km. 5/00 to 7/500)	99,482/-	2,000/-	One Month	350/-
15	R/R damages on Kheel Pangna road Km. 0/00 to 11/600 (SH:- ROFD in narrow reaches at various RDs in KM. 8/00 to 10/540) under PDNA	4,80,447/-	9,700/-	Two Months	350/-
16	R/R damages on Kheel Pangna road Km. 0/00 to 11/600 (SH:- ROFD in narrow reaches at various RDs in Km. 2/585 to 8/045) under PDNA	4,90,682/-	9,900/-	Two Months	350/-
17	R/R damages on Mahota Bagshar road Km. 0/00 to 14/00 (SH:- Removal of slips at various RDs in between Km. 5/225 to 6/285) under PDNA	94,860/-	2,000/-	One month	350/-
18	R/R damages on Mahota Bagshar road Km. 0/00 to 14/00 (SH:- Removal of slips at various RDs in between Km. 0/00 to 0/285) under PDNA	99,064/-	2,000/-	One month	350/-
19	R/R damages on Mamail Mehendi road Km. 0/00 to 19/00 (SH:-ROFD at RDs 9/500 to 9/565, 9/845 to 9/900, 10/030 to 10/090, 10/530 to 10/605, 10/820 to 10/850) under PDNA 2023	4,88,186/-	9,800/-	One month	350/-
20	R/R damages on Karsog Bye Pass road KM. 0/00 to 1/300 (SH:- C/o embankment in Km. 0/570 to 0/725, 0/960 to 0/995 & 1/00 to 1/020) under PDNA 2023	4,87,906/-	10,000/-	Two months	350/-

21	R/R damages on Mahota Bagshar road Km. 0/00 to 14/000 (SH:- Removal of slips at various RDs in between 9/615 to 12/630) under PDNA 2023	97,488/-	2,000/-	One month	350/-
22	R/R damages on Karsog Kunhu road Km. 0/00 to 10/00 (SH:- C/o B/wall at RD 9/820 to 9/825)	99,368/-	2,000/-	Two months	350/-
23	R/R damages on Karsog Kunhu road Km. 0/00 to 10/00 (SH:- ROFD widening of road in Km. 8/940 to 9/00)	92,953/-	1,900/-	One month	350/-
24	R/R damages on Kotlu Nanj road Km. 0/00 to 6/120 (SH:- ROFD of road at various RDs in Km. 0/00 to 5/00) under PDNA	2,18,425/-	4,400/-	One month	350/-
25	R/r damages on Tattapani to Shakra road Km. 0/00 to 10/00 & Shakra Parlog upto village Bindla Km. 0/00 to 6/500 (SH:- Removal of slips, C/o unlined drain surface & maintenance of earthen shoulder at various RDs)	99,272/-	2,000/-	One month	350/-
26	R/R damages on Chindi to Bakhras road Km. 0/00 to 2/600 (SH:- C/o unlined surface drain and dressing of earthen shoulder etc)	99,944/-	2,000/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP, PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

Dated:-

16.4.26

No. PW-E-Tender-NIT/2025-26-

426-3T

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog


Percentage Schedule of Quantity

Estimated Cost 99000
Earnest Money 2000
Time One month

Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 5/00 (SH:- hiring of JCB Rock Breaker for breaking/removal of rock/boulders in Km. 4/500 to 5/500)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Hiring of JCB Breaker for breaking/removal of rock/boulders including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required locationk actual working will be accounted for payment and proper disposal of muck/debris will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer-in-Charge.	55.00	Per Hours	1800.00	99000.00	Rupees Ninety Nine Thousand and Paise Zero Only
Total in Figures					99000.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Assistant Engineer
Sub Division Karsog
HPPWD Karsog


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98409.00
Earnest Money 2000.00
Time One Month

Name of Work:- R/R Damages on Shilah to Therni via Pokhi road Km. 0/00 to 12/746(SH):- Removal of slips & Maintenance of berms in 0/00 to 7/00 Job No.2						
Sub-Head and items of works.						
Sr.No.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words	
1	591.00	Per Cubic Meter	120.00	70920.00	Rupees Seventy Thousand Nine Hundred Twenty and Paise Zero Only	
2	1155.00	Per Running Meter	23.80	27489.00	Rupees Twenty Seven Thousand Four Hundred Eighty Nine and Paise Zero Only	
Total in Figures						
Quoted Rate in Words						
98409.00						

Executive Engineer,
Karsog Division,
CHPWWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99000
 Earnest Money 2000
 Time One month
 Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- hiring of JCB Rock Breaker for breaking/removal of rock/boulders in Km. 6/700 to 7/700)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Hiring of JCB Breaker for breaking/removal of rock/boulders including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required locationk actual working will be accounted for payment and proper disposal of muck/debrns will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer-in-Charge.	55.00	Per Hours	1800.00	99000.00	Rupees Ninety Nine Thousand and Paise Zero Only
Total in Figures					99000.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
 Karsog Division,
 CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

98003.00
2000

Time

One Month

Name of Work:- R/R Damages on Chamainpur to Sihani road Km. 0/00 to 2/00 (SH:- C/O B/Wall at RD 0/680 to 0/700) (Balance work from RD 0/698 to 0/700)(Step-III).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with lift upto 1.50 mtr (one point fifty metre) and a lead upto 20 mtr (twenty metre) as per technical specification clause 1603.1 as per direction of engineer in charge within all leads and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	14.18	Per Cubic Meter	198.35	2813.00	Rupees Two Thousand Eight Hundred Thirteen and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.89	Per Cubic Meter	390.20	1518.00	Rupees One Thousand Five Hundred Eighteen and Paise Zero Only
3	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.81	Per Cubic Meter	5500.00	86955.00	Rupees Eighty Six Thousand Nine Hundred Fifty Five and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.00	Each	373.15	6717.00	Rupees Six Thousand Seven Hundred Seventeen and Paise Zero Only
Total in Figures					98003.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division.

Estimated Cost	99764.00
Earnest Money	2000
Time	One Month

Noted Rate in Figures	Noted Rate in Words
100%	100%
90%	90%
80%	80%
70%	70%
60%	60%
50%	50%
40%	40%
30%	30%
20%	20%
10%	10%
0%	0%

**Executive Engineer,
Karsog Division,
Karsog Division**

Percentage Bill Of Quantity

Estimated Cost
Earnest Money
Time

98441
2000
One Month


Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

99316
2000
One Month

Name of Work:- R/R Damages on Rangan Chaini Shaindhal Road Km. 0/00 to 5/500 (SH:- Removal of slips at various RD's).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including	Total Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	827.63	Per Cubic Metre	120.00	99316.00	Rupees Ninety Nine Thousand Three Hundred Sixteen and Paise Zero Only
Total in Figures					99316.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPWD, Karsog.


Percentage Schedule Of Quantity

Estimated Cost 98441
Earnest Money 2000

Time One Month

- Name of Work:- R/R Damages on Kelodhar to Government Degree College Karsog Km. 0/00 to 3/00 (SH:- Removal of slips & Maintenance of Earthen shoulders at various RD's in Km 0/00 to 1/500).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	724.58	Per Cubic Metre	120.00	86950.00	Rupees Eighty Six Thousand Nine Hundred Fifty and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	525.90	Per Square Metre	21.85	11491.00	Rupees Eleven Thousand Four Hundred Ninety One and Paise Zero Only
Total in Figures					98441.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
MPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99325
Earnest Money 2000
Time One Month

Time of Work:- R/R Damages on Balnato Naraina Behli Km. 0/00 to 3/00 (SH:- Removal of slips & Maintenance of Earthen shoulders at various RD's in Km 0/00 to 1/500).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	670.39	Per Cubic Metre	120.00	80447.00	Rupees Eighty Thousand Four Hundred Forty Seven and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	864.00	Per Square Metre	21.85	18878.00	Rupees Eighteen Thousand Eight Hundred Seventy Eight and Paise Zero Only
Total in Figures					99325.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsod Division,
AHPPWD, Karsod.

Percentage Schedule Of Quantity

Estimated Cost 498291.00
Earnest Money 10000.00
Time One Month

Name of Work:- R/R Damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:-Providing Retaining Wall at RD 3/720 to 3/733) under PDNA-2023.

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches, with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	50.12	Per Cubic Meter	390.20	19557.00	Rupees Nineteen Thousand Five Hundred Fifty Seven and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.96	Per Cubic Meter	5500.00	456280.00	Rupees Four Lakhs Fifty Six Thousand Two Hundred Eighty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	33.00	Each	373.15	12314.00	Rupees Twelve Thousand Three Hundred Fourteen and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204, 3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.45	Per Cubic Meter	1200.00	10140.00	Rupees Ten Thousand One Hundred Forty and Paise Zero Only
Total in Figures					498291.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
GHPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	497138.00
Earnest Money	10000.00
Time	One Month

Name of Work:- R/R Damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:-Providing Retaining Wall at RD 4/330 to 4/340 and Edge Wall at RD 4/495 to 4/535)
Under PDNA 2023.

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	32.90	Per Cubic Meter	390.20	12838.00	Rupees Twelve Thousand Eight Hundred Thirty Eight and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.43	Per Cubic Meter	5500.00	453365.00	Rupees Four Lakhs Fifty Three Thousand Three Hundred Sixty Five and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	62.00	Each	373.15	23135.00	Rupees Twenty Three Thousand One Hundred Thirty Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.50	Per Cubic Meter	1200.00	7800.00	Rupees Seven Thousand Eight Hundred and Paise Zero Only
Total in Figures					497138.00	
Quoted Rate in Figures						
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98860.00
 Earnest Money 2000.00
 Time One month

Name of Work:- R/R Damages on Kottu to Kevidhar via Porta road in GP Teban Km. 0/00 to 6/120(SH):- Removal of slips in Km. 0/00 to 5/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Toatal Amount with all taxes including GST in Rs. p	Toatal Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	823.83	Per Cubic Meter	120.00	98860.00	Rupees Niney Eight Thousand Eight Hundred Sixty and Paise Zero Only
Total in Figures					98860.00	
Quoted Rate in Figures						
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99846.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Kotlu Katanda road Km. 0/00 to 16/00 (SH:- Removal of slips, Maintenance of berms & C/O Unlined Drain in Km 0/00 to 16/00) Under PDNA.

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	648.80	Per Cubic Meter	120.00	77856.00	Rupees Seventy Seven Thousand Eight Hundred Fifty Six and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	300.00	Per Running Meter	23.80	7140.00	Rupees Seven Thousand One Hundred Forty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	675.00	Per Square Meter	22.00	14850.00	Rupees Fourteen Thousand Eight Hundred Fifty and Paise Zero Only
Total in Figures					99846.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
JHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99467
Earnest Money 1900
Time One Month

Name of Work:- R/R Damages on Bakhtrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Removal of slips at RD 40/540 to 40/570, 40/710 to 40/770 & 41/060 to 41/130).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	828.89	Per Cubic Meter	120.00	99467.00	Rupees Ninety Nine Thousand Four Hundred Sixty Seven and Paise Zero Only
Total in Figures					99467.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.


Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

99482
2000
One Month

Name of Work:- R/R Damages on Katanda Pokhi Road Km. 0/00 to 10/00 (SH:- Removal of slips at various RD's in Km 5/00 to 7/500).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	829.02	Per Cubic Metre	120.00	99482.00	Rupees Ninety Nine Thousand Four Hundred Eighty Two and Paise Zero Only
Total in Figures					99482.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
JHPWD, Karsog.


Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

480447
9700
Two months

Name of Work:- R/R Damages on Kheel Pangna Road km 0/00 to 11/600 (SH:- ROFD in narrow reaches at various RD's in km 8/00 to 10/540) under PDNA

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 79.56 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.23868/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1910.63	Per Cubic Metre	251.46	480447.00	Rupees Four Lakhs Eighty Thousand Four Hundred Forty Seven and Paise Zero Only
Total In Figures					480447.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 490682
Earnest Money 9900
Time Two months

Name of Work:- R/R Damages on Kheel Pangna Road km 0/00 to 11/600 (SH:- ROFD in narrow reaches at various RD's in Km 2/585 to 8/045) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 64.63 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.19389/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2058.23	Per Cubic Metre	238.40	490682.00	Rupees Four Lakhs Ninety Thousand Six Hundred Eighty Two and Paise Zero Only
Total in Figures					490682.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsod Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
94860
2000
One Month

me of Work:- R/R Damages on Mahota Bagshar Road Km. 0/00 to 14/00 (SH:- Removal of slips at various RD's in between 5/225 to 6/285). PDNA 2023.

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs., P	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	790.50	Per Cubic Metre	120.00	94860.00	Rupees Ninety Four Thousand Eight Hundred Sixty and Paise Zero Only
Total in Figures					94860.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
QHPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money


99064
2000

One Month

Time

ne of Work:- R/R Damages on Mahota Bagshar Road Km. 0/00 to 14/00 (SH:- Removal of slips at various RD's in between 0/00 to 0/285). Under PUNA 2023.

No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals.	825.53	Per Cubic Metre	120.00	99064.00	Rupees Ninety Nine Thousand Sixty Four and Paise Zero Only
Total In Figures					99064.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
Karsog, Karsog.

Percentage Schedule of Quantity

Estimated Cost 488186
Earnest Money 9800
Time One Month
80210/10/605, 10/820

Name of Work:- R/R Damages on Mamail Mehandi road Km. 0/00 to 19/00 (SH:- ROFD at RD's 9/500 to 9/565, 9/845 to 9/900, 10/030 to 10/090, 10/530 to 10/605, 10/820 to 10/850) Under PDNA 2023.

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs.	Total Amount with all taxes Including GST In Rupees Four Lakhs Eighty Eight Thousand One Hundred Eighty Six and Paise Zero Only
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 179.06 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 53718/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1557.46	Per Cubic Meter	313.45	488186.00	
Total in Figures					488186.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
AHPWD, Karsog.

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Karsog By Pass road Km. 0/00 to 1/300 (SH:- C/O embankment in Km 0/570 to 0/725, 0/960 to 0/995 & 1/00 to 1/020) Under PDNA 2023.

Estimated Cost	487906
Earnest Money	~~2000~~ 100000
Time	Two Months

Sl.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m (one point five metre) transforming to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m (one thousand metre) as per Technical Specification Clause 301.5 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	1453.00	Per Cubic Meter	321.05	466486.00	Rupees Four Lakhs Sixty Six Thousand Four Hundred Eighty Six and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in-charge with in all lead and lifts and other incidentals.	900.00	Per Running Meter	23.80	21420.00	Rupees Twenty One Thousand Four Hundred Twenty and Paise Zero Only
Total in Figures					487906.00	
Quoted Rate in Figures						
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 JHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 97488
 Earnest Money 2000
 Time One Month

Name of Work:- R/R Damages on Mahota Bagshar Road Km. 0/00 to 14/00 (SH:- Removal of slips at various RD's in between 9/615 to 12/630). ~~Worked PO NA~~

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Toatal Amount with all taxes including GST in Rs. P	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	812.40	Per Cubic Metre	120.00	97488.00	Rupees Ninety Seven Thousand Four Hundred Eighty Eight and Paise Zero Only
Total in Figures					97488.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
 Karsog Division,
 CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99368
Earnest Money 2000
Time Two Months

Name of Work:- R/R Damages on Karsog Kunhu road Km 0/00 to 10/00 (SH:- C/O B/wall at RD 9/820 to 9/825).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	21.00	Per Cubic Metre	390.20	8194.00	Rupees Eight Thousand One Hundred Ninety Four and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.17	Per Cubic Metre	5500.00	88935.00	Rupees Eighty Eight Thousand Nine Hundred Thirty Five and Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3, 7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	6.00	Each	373.15	2239.00	Rupees Two Thousand Two Hundred Thirty Nine and Paise Zero Only
Total In Figures					99368.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 92953
Earnest Money 1900
Time One month

Name of Work:- R/R Damages on Karsog to Kunhu Road Km.0/00 to 10/00 (Sh:- ROFD Widening of Road in Km 8/940 to 9/00).

Sr.N o.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 14.91 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 4473/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	372.75	Per Cubic Metre	249.37	92953.00	Rupees Ninety Two Thousand Nine Hundred Fifty Three and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					92953.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 218425.00
Earnest Money 4400.00
Time One Month

Name of Work:- R/R Damages on Kottu Nanj road Km. 0/00 to 6/120 (SH:- ROFD of road at various RD in Km 0/00 to 5/00) Under PDNA.

Sub-Head and items of works.

	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	833.30	Per Cubic Meter	262.12	218425.00	Rupees Two Lakhs Eighteen Thousand Four Hundred Twenty Five and Paise Zero Only
Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 41.66 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 12500/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.					
Total in Figures					
Quoted Rate in Figures					
Quoted Rate in Words					
				218425.00	


Executive Engineer,
Karsog Division,
HPPWD, Karsog,


Percentage Schedule of Quantity

Estimated Cost 99272.00
Earnest Money 2000.00

Time One month
Name of Work:- R/R Damages on Tattapani to Shakra road Km. 0/00 to 10/00 & Shakra Parlog upto village Bindla Km 0/00 to 6/500(SH):- Removal of slips, C/O unlined drain surface & Maintenance of earthen shoulder at various RD's).

Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3, 5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	596.65	Per Cubic Meter	120.00	71598.00	Rupees Seventy One Thousand Five Hundred Ninety Eight and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm/zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	405.00	Per Running Meter	23.80	9639.00	Rupees Nine Thousand Six Hundred Thirty Nine and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	819.75	Per Square Meter	22.00	18035.00	Rupees Eighteen Thousand Thirty Five and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					99272.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99944.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Chindi to Bakhras road Km 0/00 to 2/600 (SH:- C/O Unlined surface drain and dressing of earthen shoulder etc.

Sub-Head and items of works.		Total Amount with all taxes Including GST In Rs. P		Total Amount with all taxes Including GST In Words	
Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	2325.00	Per Running Meter	21.80	Rupees Fifty Thousand Six Hundred Eighty Five and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2270.00	Per Square Meter	21.70	Rupees Forty Nine Thousand Two Hundred Fifty Nine and Paise Zero Only
Total in Figures					
Quoted Rate in Figures					
Quoted Rate in Words					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.