

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

564

Dated:-

17 ⁴/₂₀₂₆

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.


Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog.

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229, E-mail : ee-kar-hp@nic.in
Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **25.04.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 24.04.2026** for which the application should reach in this office **upto 1.00 PM 24.04.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Kahnool to Prangan road Km. 0/00 to 9/500 and Balindi Kanda Kahnool road Km. 0/00 to 10/00 (SH:- Removal of slips, C/o unlined drain and maintenance of earthen shoulder at various RDs)	99,920/-	2,000/-	One Month	350/-
2	R/R damages on Dharmour to Ashni Mandir road KM. 0/00 to 4/00 and Bagshar to Mahunag via Serj road Km. 0/00 to 6/00 (SH:- Removal of slips, C/o unlined drain and maintenance of earthen shoulder at various RDs)	99,420/-	2,000/-	One Month	350/-
3	R/R damages on Ruhni to Manola road KM. 0/00 to 10/500 and Bhanol Kufri to Koli Kot road KM. 0/00 to 6/120 (SH:- Removal of slips, C/o unlined drain and maintenance of earthen shoulder at various RDs)	98,900/-	2,000/-	One Month	350/-
4	R/R damages on Kandhi Dharkandlu road KM. 0/00 to 6/150 (SH:- Removal of slips, C/o unlined drain and maintenance of earthen shoulder at various RDs)	98,820/-	2,000/-	One Month	350/-
5	R/o Shill Badhair Bean road KM. 0/00 to 2/500 (SH:- ROFD of road at RD 0/195 to 0/225)	99,264/-	2,000/-	One Month	350/-

6	R/R damages on Mahog Shakelar via Navidhar road KM. 0/00 to 9/00 (SH:- Removal of slips at various RDs in Km. 0/00 to 4/145) under PDNA	4,99,348/-	10,000/-	One Month	350/-
7	R/R damages on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of Air Compressor for Blasting & hiring of JCB Rock Breaker for Breaking/removal of rock/boulders at various RDs)	98,039/-	2,000/-	One Month	350/-
8	R/R damages on Narash to Bego via Bhiri in GP Chouridhar Km. 0/00 to 5/200 (SH:- Removal of slips, C/o unlined drain surface & maintenance of berm at various RDs)	98,872/-	2,000/-	One Month	350/-
9	R/R damages on link road Bakhedi Mandap to Dohnal Bhanu in GP Bagaila Km. 0/00 to 4/00 (SH:- Removal of slips in various RDs in Km. 0/00 to 4/00)	97,440/-	2,000/-	One Month	350/-
10	R/R damages on Khadargali to Somakothi road KM. 0/00 to 4/110 (SH:- Removal of slips at various RDs in Km. 0/00 to 4/010) under PDNA	4,98,967/-	10,000/-	One Month	350/-
11	R/R damages on Sursi kani Mandlah road Km. 0/00 to 4/500 (SH:- C/o unlined drain & maintenance of berm at various RDs)	98,093/-	2,000/-	One Month	350/-
12	R/R damages on Kao to Kajoun road Km. 0/00 to 4/500 (SH:- Removal of slips in various RDs in Km. 0/00 to 4/500)	98,860/-	2,000/-	One Month	350/-
13	R/R damages due to cloud burst on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Providing and laying of RCC Hume pipe 900mm dia NP2 and filling of local earth including ramming and watering)	96,527/-	2,000/-	One Month	350/-
14	R/R damages on Kheel Dharmour to Shaloti Nag road KM. 0/00 to 3/00 & Churag to Chamanpur road Km. 0/00 to 4/00 (SH:- C/o unlined drain surface and maintenance of earthen shoulder at various RDs between KM. 0/00 to 2/00 in Kheel Dharmour to Shaloti Nag road & 0/900 to 3/00) in Churag to Chamanpur road)	98,429/-	2,000/-	One Month	350/-
15	R/R damages on Pargagali to Reshtadhr road KM. 0/00 to 5/500 (SH:- C/o unlined drain surface and maintenance of earthen shoulder at various RDs between Km. 0/00 to 5/500)	99,297/-	2,000/-	One Month	350/-
16	R/R damages on Salani to Kandlu in GP Dabrot Km. 0/00 to 3/00 (SH:- Removal of slips, in various RDs in Km. 0/00 to 3/00)	99,120/-	2,000/-	One Month	350/-
17	R/R damages on Shakelar Mahog via Navidhar road Km. 0/00 to 9/00 (SH:- Removal of slips and maintenance of earthen shoulders & C/o unlined surface drain at various RDs in Km. 0/00 to 9/00) under PDNA	4,65,857/-	9,400/-	Two months	350/-
18	R/R damages on Teban Jae road Km. 0/00 to 3/300 (SH:- Removal of slips maintenance of berms & C/o unlined drain in KM. 0/00 to 3/300)	99,096/-	2,000/-	One Month	350/-

19	R/R damages on Sainj Sainjeli road Km. 0/00 to 5/00 (SH:- C/o R/wall at RD 0/390 to 0/400 and ROFD in varius stretches in Km. 4/00 to 5/00) under PDNA	4,86,143/-	9,800/-	Two months	350/-
20	C/o Judicial Court Complex at Karsog Tehsil Karsog Distt. Mandi H.P. (SH:- Providing and fixing inauguration plate mane by golden brass & black acrylic sheet remote perliment stand, generator rent & betray package, transportation and fitting charge)	67,201/-	1,400/-	One Month	350/-
21	C/o Judicial Court Complex at Karsog Distt. Mandi H.P. (SH:- Providing and fixing of door, closer, door catcher, two way angle cock etc)	98,190/-	2,000/-	One Month	350/-
22	C/o Judicial Court Complex at Karsog Distt. Mandi H.P. (SH:- Providing and finishing polish in dias and court room and steel plant in main gate) etc "	99,751/-	2,000/-	One Month	350/-
23	A/R & M/O Type-II quarter at Baral at Karsog Distt. Mandi H.P. (SH:- Cleaning of sewer line and septic tank),	96,218/-	2,000/-	One Month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be. Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. "Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

558-63

Dated:-

17/4/2020

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HPPWD Karsog

Schedule Percentage Bill Of Quantity

Estimated Cost Rs :- 99920/-

Earnest money:- 2000/-

Time :- One Months

Name of work :- RR Damages on Kahnoo to Pargan Road Km 0/0 to 9/500 and Balindi Kanda Kahnoo Road Km 0/0 to 10/0 (SH:-
Removal of Slips, C/O Unlined drain and Maintenance of earthen shoulder at Various RDs)

Sr. No.	Description's	Qty.	Rate In figure	Unit	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1.	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material within any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer-In-Charge including carriage of materials within all leads and lifts.	350	120.00	Per Cub Meter	42000 .00	Rupees Forty Two Thousand Only
2	Construction of unlined surface drain of average cross-section area 0.20 Sqm in soil specified lines grades, levels and dimension. Excavation material to be used in embankment with a lift upto any lead as per leads lifts and other incidentals. As per direction of Engineer-in-charges within all leads and lifts.	400	23.80	Per Running Meter	9520 .00	Rupees Nine Thousand five Hundred twenty Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead and lifts as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-In-Charge.	2200	22.00	Per Square meter	48400 .00	Rupees forty eight Thousand four Hundred Only
Total in Figures					99920 .00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paisa Zero Only	

Executive Engineer
Karsog Division
HPWD Karsog

Schedule Percentage Bill Of Quantity

Estimated Cost Rs :- 99420/-

Earnest money:- 2000/-

Time :- One Months

Name of work :- RR Damages on Dharmour to Ahsni Mandir Road Km 0/0 to 4/0 and Bagsar to Mahounag via Seri Road Km 0/0 to 6/0 (SH:- Removal of Slips, C/O Unlined drain and Maintenance of earthen shoulder at Various RDs)

Sr. No.	Description's	Qty.	Rate In figure	Unit	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1.	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer- In- Charge including carriage of materials within all leads and lifts.	300	120.00	Per Cub Meter	36000 .00	Rupees Thirty six Thousand Only
2	Construction of unlined surface drain of average cross-section area 0.20 Sqm in soil specified lines grades, levels and dimension .Excavation material to be used in embankment with a lift upto any lead as per leads lifts and other incidentals. As per direction of Engineer-in- charges within all leads and lifts.	400	23.80	Per Running Meter	9520 .00	Rupees Nine Thousand five Hundred twenty Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead and lifts as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-In-Charge.	2450	22.00	Per Square mitter	53900 .00	Rupees Fifty three Thousand nine Hundred Only
Total in Figures					99420 .00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paisa Zero Only	


Executive Engineer
Karsog Division
CHD PWD Karsog

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Ruhni to Manola road Km. 0/00 to 10/500 and Bhanol Kufri to Koli Kot road Km 0/00 to 6/120(SH:- Removal of slips, C/O unlined drain surface & Maintenance of earthen shoulder at various RD's).

Estimated Cost 98500.00
Earnest Money 2000.00
Time One month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance.-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	300.00	Per Cubic Meter	120.00	36000.00	Rupees Thirty Six Thousand and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts. and other incidentals.	500.00	Per Running Meter	23.80	11900.00	Rupees Eleven Thousand Nine Hundred and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2300.00	Per Square Meter	22.00	50600.00	Rupees Fifty Thousand Six Hundred and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					98500.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Schedule Percentage Bif Of Quantity

Estimated Cost Rs :- 98820/-
Earnest money:- 2000/-
Time :- One Months
C/O Unlined drain and

Name of work :- RR Damages on Kandhi Dharkandlu Road Km 0/0 to 6/1150 (SH:- Removal of Slips , C/O Unlined drain and Maintenance of earthen shoulder at Various RDS)

Sr. No.	Description's	Qty.	Rate In figure	Unit	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1.	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer- In- Charge including carriage of materials within all leads and lifts.	350	120.00	Per Cub Meter	42000 .00	Rupees Forty two Thousand Only
2	Construction of unlined surface drain of average cross-section area 0.20 Sqm in soil specified lines grades, levels and dimension .Excavation material to be used in embankment with a lift upto any lead as per leads lifts and other incidentals. As per direction of Engineer-in- charges within all leads and lifts.	400	23.80	Per Running Meter	9520 .00	Rupees nine Thousand five Hundred twenty Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead and lifts as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-In-Charge.	2150	22.00	Per Square mitter	47300 .00	Rupees forty seven Thousand three Hundred Only
Total in Figures					98820 .00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paisa Zero Only	


Executive Engineer
Karsog Division
DPPWD Karsog

Percentage Schedule of Quantity

Estimated Cost 99264
Earnest Money 2000
Time One Month

ie of Work:- R/O Shill Badehar to Shaloth Bean road Km 0/00 to 2/500 (SH:- R.O.F.D. of road at RD 0/195 to 0/225).
Sub-Head and items of works.

	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST In Words
1	265.22	Per Cubic Meter	374.27	99264.00	Rupees Ninety Nine Thousand Two Hundred Sixty Four and Paise Zero Only
Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, bludge and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 48.62 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 14586/- only, shall be done on pro rata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.					
Total in Figures				99264.00	
Quoted Rate in Figures					
Quoted Rate in Words					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 499348
Earnest Money 10000
Time One Month

Name of Work:- R/R Damages on Mahog Shakel via Navidhar road Km. 0/00 to 9/00 (SH:- Removal of slips at various RD's in Km 0/00 to 4/145) Under PDNA.						
Sr.No.	Sub-Head and Items of works.					
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
		3950.54	Per Cubic Meter	126.40	499348.00	Rupees Four Lakhs Niney Nine Thousand Three Hundred Forty Eight and Paise Zero Only
Total in Figures					499348.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98039
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of Air Compressor for Blasting & hiring of JCB Rock Breaker for breaking/removal of rock/boulders at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in upot any lead and technical specification clause 1603.1 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	340.00	Per Square Metre	198.35	67439.00	Rupees Sixty Seven Thousand Four Hundred Thirty Nine and Paise Zero Only
2	Hiring of JCB Breaker for breaking/removal of rock/boulders including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required locationk actual working will be accounted for payment and proper disposal of muck/debns will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer-in-Charge.	17.00	Per Hours	1800.00	30600.00	Rupees Thirty Thousand Six Hundred and Paise Zero Only
Total in Figures					98039.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98872.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Narash to Bego via Bhiro in G.P. Chouridhar Km. 0/00 to 5/200(SH:- Removal of slips, C/O unlined drain surface & Maintenance of berm at various RD's).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance: Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	665.43	Per Cubic Meter	120.00	79852.00	Rupees Seventy Nine Thousand Eight Hundred Fifty Two and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer-in-charge with in all lead and lifts and other incidentals.	300.00	Per Running Meter	23.80	7140.00	Rupees Seven Thousand One Hundred Forty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	540.00	Per Square Meter	22.00	11880.00	Rupees Eleven Thousand Eight Hundred Eighty and Paise Zero Only
Total in Figures					98872.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 97440.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Link road from Bakhedi Mandap to Dohnal Bhanu in G.P. Bagaila Km. 0/0 to 4/00 (SH:- Removal of slips in various RD's in Km. 0/00 to 4/00).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	812.00	Per Cubic Meter	120.00	97440.00	Rupees Ninety Seven Thousand Four Hundred Forty and Paise Zero Only
Total In Figures					97440.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 498967
Earnest Money 10000
Time One Month

Name of Work: R/R Damages on Khadargali to Somakothi road Km. 0/00 to 4/110(SH)- Removal of slips at various RD's in Km 0/00 to 4/010 Under PDNA.

Sub-Head and Items of works.

Sr.No.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	3947.52	Per Cubic Meter	126.40	498967.00	Rupees Four Lakhs Ninety Eight Thousand Nine Hundred Sixty Seven and Paise Zero Only
Total in Figures				498967.00	
Quoted Rate in Figures					
Quoted Rate in Words					

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98093.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Sursi to Kani Mandlah Road Km. 0/0 to 4/500(SH):- C/O unlined drain & Maintenance of berm at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm (zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer-in-charge with in all lead and lifts and other incidentals.	685.00	Per Running Meter	21.80	14933.00	Rupees Fourteen Thousand Nine Hundred Thirty Three and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	3780.00	Per Square Meter	22.00	83160.00	Rupees Eighty Three Thousand One Hundred Sixty and Paise Zero Only
Total in Figures					98093.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98860.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Kao to Kajaun road Km. 0/00 to 4/500(SH):- Removal of slips in various RD's in Km. 0/00 to 4/500).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	823.83	Per Cubic Meter	120.00	98860.00	Rupees Ninety Eight Thousand Eight Hundred Sixty and Paise Zero Only
Total in Figures					98860.00	
Quoted Rate in Figures						
Quoted Rate in Words						

[Signature]

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 96527.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages due to cloud burst on Bakhrot Sanarri Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Providing and laying of RCC Hume Pipe 900mm dia NP2 and filling of local earth including ramming and watering).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs., P	Total Amount with all taxes Including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs (three metre) depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.43	Per Cubic Meter	390.20	6411.00	Rupees Six Thousand Four Hundred Eleven and Paise Zero Only
2	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Meter	5447.50	40856.00	Rupees Forty Thousand Eight Hundred Fifty Six and Paise Zero Only
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	8.46	Per Cubic Meter	3702.35	31322.00	Rupees Thirty One Thousand Three
4	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km (five kilo metre) also including ramming and watering of the earth in layers not exceeding 20 cm (twenty centimetre) in trenches, plinth, sides of foundation etc. complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	66.34	Per Cubic Meter	270.40	17938.00	Rupees Seventeen Thousand Nine Hundred Thirty Eight and Paise Zero Only
Total in Figures					96527.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98429.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Kheel Dharmour to Shaloti Nag road Km 0/00 to 3/00 & Churag to Chamanpur road Km 0/00 to 4/00(SH:- C/O Unlined Drain surface and maintenance of earthen shoulder at various RD's between Km 0/00 to 2/00 in Kheel Dharmour to Shaloti Nag road & 0/900 to 3/00 in Churag to Chamanpur road).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1965.00	Per Running Meter	23.80	46767.00	Rupees Forty Six Thousand Seven Hundred Sixty Seven and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2348.25	Per Square Meter	22.00	51662.00	Rupees Fifty One Thousand Six Hundred Sixty Two and Paise Zero Only
Total In Figures					98429.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99297.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Paragagalli to Reshtadhar road Km 0/00 to 5/500 (SH:- C/O Unlined Drain surface and maintenance of earthen shoulder at various RD's between Km 0/00 to 5/500).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm/zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts. and other incidentals.	1980.00	Per Running Meter	23.80	47124.00	Rupees Forty Seven Thousand One Hundred Twenty Four and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2371.50	Per Square Meter	22.00	52173.00	Rupees Fifty Two Thousand One Hundred Seventy Three and Paise Zero Only
Total in Figures					99297.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

**Estimated Cost
Earnest Money**

**99120.00
2000.00
One month**

Name of Work:- R/R Damages on Salani to Kandlu in G.P. Dabrot Km. 0/0 to 3/00 (SH:- Removal of slips in various RD's in Km. 0/00 to 3/00).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	826.00	Per Cubic Meter	120.00	99120.00	Rupees Ninety Nine Thousand One Hundred Twenty and Paise Zero Only
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

(Signature)


**Executive Engineer,
Karsog Division,
HPPWD, Karsog.**

Percentage Schedule Of Quantity.

Estimated Cost 465857
Earnest Money 9400
Time Two Months

Name of Work:- R/R Damages on Shakelar Mahog via Navidhar road Km. 0/00 to 9/00 (SH:- Removal of slips and Maintenance of Earthen Shoulders & C/O unlined surface drain at various RD's in Km 0/00 to 9/00) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	2470.35	Per Cubic Meter	120.00	296442.00	Rupees Two Lakhs Ninety Six Thousand Four Hundred Forty Two and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in- Charge with in all leads and lifts and other incidentals.	5145.00	Per Square Meter	21.80	112161.00	Rupees One Lakh Twelve Thousand One Hundred Sixty One and Paise Zero Only
3	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	2698.00	Per Running Meter	21.30	57254.00	Rupees Fifty Seven Thousand Two Hundred Fifty Four and Paise Zero Only
Total in Figures					465857.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99096.00
Earnest Money 2000.00
Time One month

Name of Work:- R/R Damages on Teban Jae road Km. 0/00 to 3/300 (SH:- Removal of slips, Maintenance of berms & C/O Unlined Drain in Km 0/00 to 3/300)

Sub-Head and items of works.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	667.30	Per Cubic Meter	120.00	80076.00	Rupees Eighty Thousand Seventy Six and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	300.00	Per Running Meter	23.80	7140.00	Rupees Seven Thousand One Hundred Forty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	540.00	Per Square Meter	22.00	11880.00	Rupees Eleven Thousand Eight Hundred Eighty and Paise Zero Only
Total in Figures					99096.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
DPPWD, Karsog.

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Sainj Sainjal road Km 0/00 to 5/00 (SH:- C/o R/Wall at RD 0/390 to 0/400 and ROFD in various Stretches in KM 4/00 to 5/00) Under PDNA.

Estimated Cost
Earnest Money
Time
Two Months

S.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.10	Per Cubic Metre	390.20	12135.00	Rupees Twelve Thousand One Hundred Thirty Five and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802.803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	37.32	Per Cubic Metre	5500.00	205260.00	Rupees Two Lakhs Five Thousand Two Hundred Sixty and Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	27.00	Each	373.15	10075.00	Rupees Ten Thousand Seventy Five and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	13.20	Per Cubic Metre	1200.00	15840.00	Rupees Fifteen Thousand Eight Hundred Forty and Paise Zero Only
5	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 30.790 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.9237/- only, shall be done on pro-rata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1026.30	Per Cubic Metre	236.61	242833.00	Rupees Two Lakhs Forty Two Thousand Eight Hundred Thirty Three and Paise Zero Only
Total in Figures					486143.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
Jammu & Kashmir,
Karsog.

Percentage Schedule of Quantity

Estimated Cost 67201.00
Earnest Money 1400.00
Time One month

Name of Work:- C/O Judicial court complex at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing and fixing Inogration Plate made by golden Brass & Black Acrylic sheet,
Remote Pelimant stand, Generator rent & Batray Package, Transportation & Fitting charge).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Providing and fixing Inogration Plate made by golden Brass & Black Acrylic sheet, or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1.00	Each	17700.00	17700.00	Rupees Seventeen Thousand Seven Hundred and Paise Zero Only
2	Providing and fixing Remote Pelimant stand or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	56.00	Per Square Feet	566.40	31718.00	Rupees Thirty One Thousand Seven Hundred Eighteen and Paise Zero Only
3	Providing and fixing Generator rent & Batray Package as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	1.00	Each	7670.00	7670.00	Rupees Seven Thousand Six Hundred Seventy and Paise Zero Only
4	Transportation & Fitting charge as per approved architectural drawings and the directions of Engineer- in - Charge including carriage of material within all leads, lifts and other incidentals.	1.00	Each	10112.60	10113.00	Rupees Ten Thousand One Hundred Thirteen and Paise Zero Only
Total in Figures					67201.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
JHPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98190.00
Earnest Money 2000.00
Time One Month

Name of Work:- C/O judicial court complex at karsog Distt. Mandi (H.P.) (Sh:- Providing and fixing of door closer, Door catcher , two way angle cock etc.)

Sub-Head and Items of works.

	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Providing and fixing door closer as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	4.00	Each	2200.00	8800.00	Rupees Eight Thousand Eight Hundred and Paise Zero Only
2	Providing and fixing almirah lockas per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	36.00	Each	340.00	12240.00	Rupees Twelve Thousand Two Hundred Forty and Paise Zero Only
3	Provider and fixing door catcher for door as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	48.00	Each	270.00	12960.00	Rupees Twelve Thousand Nine Hundred Sixty and Paise Zero Only
4	Providing and fixing Cup Cutlery Set as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	4.00	Each	2400.00	9600.00	Rupees Nine Thousand Six Hundred and Paise Zero Only
5	Providing and fixing door mate 4'x2' (four into two) as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	20.00	Each	700.00	14000.00	Rupees Fourteen Thousand and Paise Zero Only
6	Providing and fixing door mate 6'x2' (six into two) as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	3.00	Each	2450.00	7350.00	Rupees Seven Thousand Three Hundred Fifty and Paise Zero Only
7	Providing and fixing Dust bane as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	4.00	Each	700.00	2800.00	Rupees Two Thousand Eight Hundred and Paise Zero Only
8	Providing and fixing two in one angle cock 15mm(fifteen millimetre) nominal dia as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	2.00	Each	2500.00	5000.00	Rupees Five Thousand and Paise Zero Only
9	Providing and fixing curtain for door 8'x4' (eight into four) as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	6.00	Each	2350.00	14100.00	Rupees Fourteen Thousand One Hundred and Paise Zero Only
10	Providing and fixing Union 25 mm (twenty five millimetre) dia as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	18.00	Each	630.00	11340.00	Rupees Eleven Thousand Three Hundred Forty and Paise Zero Only
Total in Figures					98190.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
a HPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money

99751.00
2000.00
One month

Time
all taxes including GST in main gate etc.

Name of Work:- C/O Judicial court complex at Karsog Distt. Mandi (H.P) (Sh:- Providing andFinishing Polish in dias and court room and steel paint in main gate etc.

Sl.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Providing and polishing in high gloss/matt finish melamine clear polish on wood work in required colour/ wooden shade texture with process in the sequence as the surface to be polished is rubbed with sand paper 80/120 No. (eighty/one hundred twenty number) and then with sand paper of 160/180 nos (one hundred sixty/one hundred eighty numbers). Applying two coats of sealer with spray gun and allowing sufficient drying time for 1st (first) coat and 2nd (second) coat is allowed to dry for 8 to 12 hrs (eight to twelve hours). On drying of sealer coat, wet rubbing with emery cloth of finer grading with ample water to remove excess sealer layer and make the surface further smooth after this wet rubbing, then surface is applied with special grade melamine fillers to fill all the small and big holes/ grooves etc. Filler coat to be allowed to dry for 4 to 6 hrs (four to six hours) on which again a light wet rubbing is done this surface is further allowed to dry for 12 hrs (twelve hours). On this, 1st (first) coat of melamine polish is applied with spray gun using melamine clear polish and melamine thinner in required proportion. This 1st (first) coat is allowed to dry for 12 hrs (twelve hours) then this dry surface is again fine wet rubbed smooth, which is further allowed to dry for 12 hrs (twelve hours). The final melamine polish is applied with compressor pressure spray gun using melamine clear polish and melamine thinner mixed in required proportion complete as per direction & satisfaction of Engineer-in-Charge. (Final coat to be done in 1 or 2 (one or two) layers without gap of time.) and as per approved architectural drawings and the directions of Engineer- in - Charge including carriage of material within all leads, lifts and other incidentals.	79.52	Per Square Meter	1148.30	91313.00	Rupees Ninety One Thousand Three Hundred Thirteen and Paise Zero Only
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/10 sqm (zero point ninety lit/ten square metre)over an under coat of primer applied @ 0.80 lit/10 sqm (zero point eighty lit/ten square metre)of approved brand and manufacture	47.67	Per Square Meter	110.50	5268.00	Rupees Five Thousand Two Hundred Sixty Eight and Paise Zero Only
3	Providing and fixing Toilet paper holder as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	3.00	Each	250.00	750.00	Rupees Seven Hundred Fifty and Paise Zero Only
4	Providing and fixing floor grating as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	3.00	Each	240.00	720.00	Rupees Seven Hundred Twenty and Paise Zero Only
5	Providing and fixing bib cock 15 mm (fifteen mili metre)nominal dia as per direction of engineer in charge including carriage of materials within all leads, lifts and other incidentals.	2.00	Each	850.00	1700.00	Rupees One Thousand Seven Hundred and Paise Zero Only
Total in Figures					99751.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 96218.00
Earnest Money 2000.00
Time One month

Name of Work:- A/R & M/O Type -II Qutar at Baral at Karsog Tehsil Karsog Distt. Mandi (H.P) (Sh:- Cleaning of sewer line and Septic Tank).							
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words	
1	Cleaning of choked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres (four thousand litre) suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm(one fifty milli metre) dia upto 300mm(three hundred milli metre) dia for all depth as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	227.44	Per Running Meter	423.05	96218.00	Rupees Ninety Six Thousand Two Hundred Eighteen and Paise Zero Only	
Total In Figures					96218.00		
Quoted Rate in Figures							
Quoted Rate in Words							


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.