

Himachal Pradesh
Public Works Department.

No. PW-KD- CTR- Tender-NIT/2025-2026-

1352-53

Dated:-

18-04-2026

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-


- | | |
|------------------------------------------------------|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 27-04-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 27-04-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 28-04-2026 . up to 10:30 AM |
| 4. Date of opening of tender:- | 28-04-2026 up to 11:00 AM |

Sr. No.	Name of Work	Estimate d cost	EMD(R s.)	Cost of Tender (Rs.)	Time Limit	Eligible clas of Contractor
1	Restoation of Rain Damges on Elysium to Devidhar road s in km. 0/00 to 17/300 (SH;- Providing and fixing M.S Steel railing at RD. 0/00 to 0/840).	98662/-	2000/-	350/-	30 days	Class-D
2	Restoatio of Rain Damages on Elysium to Devikdhar roads in km. 0/00 to 17/300 (SH;- Providing and fixing ZM.S steel Railing at RD. 0/840 to 0/860).	98906/-	2000/-	350/-	30 days	Class-D
3	A/R & M/O to various Residential QTrs under kasumpti sub Division Shimla (SH;- Supplying of material in sub Division No.VIII Mehli Section Shimla-9).	99783/-	2000/-	350/-	30 days	Class-D
4	A/R & M/O various Residential qtrs. Under kasumpti Sub Division Shimla (SH;- Supplying of material to sub Division No.VIII Parimahal section Shimla-9).	99235/-	2000/-	350/-	30 days	Class-D
5	A/R & M/O to various Residential Qtrs under kasumpti Sub Division Shimla -9 (SH;- Supplying of metial to Sub Division No. VIII kasumpti Sub Division Shimla-9).	99560/-	2000/-	350/-	30 days	Class-D
6	A/R & M/O varioius roads under Bharari section (SH;- Maintance /General maintenance on various RDs).	98749/-	2000/-	350/-	30 days	Class-D
7	Restoation of Rain Damages on kelti to Barmu road km. 0/00 to 3/00 (SH;- Maintenance of drain , Bush cutting and with washing in km. 0/00 to 3/00).	97623/-	2000/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.


Executive Engineer,
Division Kasumpti,
HPPWD. Shimla-3.


No.PW-SD-I/CB-Tender/2026-2027-

1354-69

Dated :- 18-04-2026

Copy forwarded to:-


1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.


Executive Engineer,
Division Kasumpti.,
HPPWD Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, HPPWD SHIMLA-3.						Estimated Cost:- 98,662.00	
NAME OF WORK:- -Restoration of Rain damages on Elysium to Devidhar roads in km. 0/00 to 17/300. (SH:- Providing and fixing M.S steel railing at Rd. 0/00 to 0/840.)						Earnest Money :-2000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Denolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	2.59	Cum	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Cubic Metre	3238.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand): four graded stone aggregate 20mm (Twenty millimeter) nominal	2.59	Cum	6600.00	Rupees Six Thousand Six Hundred Only	Per Cubic Metre	17094.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) in gratings, framed guards bars ladders, railing, brackets and similar work. .	746.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilogram	78330.00
						Total	98662.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G. Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer
 B&R Division Kasumpti,
 HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, HPPWD SHIMLA-3.							
NAME OF WORK:- -Restoration of Rain damages on Elysium to Devidhar roads in km. 0/00 to 17/300. (SH:- Providing and fixing M.S steel railing at Rd. 0/840 to 0/860.)						Estimated Cost:- 98,906.00	
						Earnest Money :- 2000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	2.26	Cum	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Cubic Metre	2825.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand): four graded stone aggregate 20mm (Twenty milimeter) nominal size).	2.26	Cum	6600.00	Rupees Six Thousand Six Hundred Only	Per Cubic Metre	14916.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work. .	773.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilogram	81165.00
	Quoted rates Percentage in figures					Total	98906.00
	Quoted rates Percentage in words						
						G. Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer,
 B&R Division Kasumpti,
 HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost Rs :-98,378.00		
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Mehli Section Shimla-9).					Earnest Money Rs :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate	Unit	Unit	Amount
				In figures			
1	Supplying of Black Nails size 20mm complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	5.00	Kgs.	350.00	Rupees Three Hundred Fifty Only	Per Kilo-gram	1750.00
2	C.P. iron sliding door bolt 200x16mm	12.00	Nos	330.00	Rupees Three Hundred Thirty Only	Each	3960.00
3	C.P iron sliding door bolt 250x 16mm	10.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	3800.00
4	C.P. iron sliding door bolt 300x 16mm	6.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	2700.00
5	Iron door spring	6.00	Nos	395.00	Rupees Three Hundred Ninety Five Only	Each	2370.00
6	Hydraulic door closer (Heavy)	6.00	Nos	1890.00	Rupees One Thousand Eight Hundred Ninety Only	Each	11340.00
7	Drawer lock (Godrej)	12.00	Nos	270.00	Rupees Two Hundred Seventy Only	Each	3240.00
8	C.P.Tel Mixer make ESS ESS	3.00	Nos	5760.00	Rupees Five Thousand Seven Hundred Sixty Only	Each	17280.00
9	PVC Seat Cover for EVOC.	4.00	Nos	897.00	Rupees Eight Hundred Ninety Seven Only	Each	3588.00
10	PVC Seat Cover for Anglo Indian with Hinges.	4.00	Nos	850.00	Rupees Eight Hundred Fifty Only	Each	3400.00
11	S.S. Greeting 110mm (Heavy) with frame	5.00	Nos	158.00	Rupees One Hundred Fifty Eight Only	Each	790.00
12	Gate Valve 25mm (Heavy)	8.00	Nos	1490.00	Rupees One Thousand Four Hundred Ninety Only	Each	11920.00
13	Glass Corner Shelf for Tuffon Glass with S.S. Railing & Brackets	8.00	Nos	1890.00	Rupees One Thousand Eight Hundred Ninety Only	Each	15120.00
14	PVC Tank Cover 18" tread, heavy duty	4.00	Nos	890.00	Rupees Eight Hundred Ninety Only	Each	3560.00

15	Brass wall cock 15 mm with rod	4.00	Nos	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	4600.00
16	PVC Spout flexible 18 " heavy duty	4.00	Nos	1090.00	Rupees One Thousand Ninety Only	Each	4360.00
17	Brass wall cock 15 mm with rod	4.00	Nos	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	4600.00
							98378.00
G.Total							

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Kasumpti Division
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							Estimated Cost Rs :-99,235.00	
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.							Earnest Money Rs :- 2000.00	
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Parimahal Section Shimla-9).							Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate In figures	Unit	Unit	Amount	
			Nos					
1	Sink mixer Heavy duty Make ESS(premium range)	4.00	Nos	4800.00	Rupees Four Thousand Eight Hundred Only	Each	19200.00	
2	Brass wall cock 15 mm with rod	4.00	Nos	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	4600.00	
3	PVC Spout flexible 18 " heavy duty	4.00	Nos	1090.00	Rupees One Thousand Ninety Only	Each	4360.00	
4	S.S connection 15x450 Viking	5.00	Nos	290.00	Rupees Two Hundred Ninety Only	Each	1450.00	
5	P.V.C. pipe linolex 100mm	8.00	Nos	1005.00	Rupees One Thousand Five Only	Each	8040.00	
6	P.V.C. pipe Finolex 90mm	8.00	Nos	900.00	Rupees Nine Hundred Only	Each	7200.00	
7	P.V.C door Tee 100mm	6.00	Nos	375.00	Rupees Three Hundred Seventy Five Only	Each	2250.00	
8	P.V.C door Tee 90mm	6.00	Nos	290.00	Rupees Two Hundred Ninety Only	Each	1740.00	
9	P.V.C Plain Bend 100 mm	6.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	1500.00	
10	P.V.C Plain Bend 90mm	6.00	Nos	184.00	Rupees One Hundred Eighty Four Only	Each	1104.00	
11	P.V.C Door Bend 100mm	6.00	Nos	275.00	Rupees Two Hundred Seventy Five Only	Each	1650.00	
12	P.V.C Door Bend 90mm	6.00	Nos	205.00	Rupees Two Hundred Five Only	Each	1230.00	
13	P.V.C Collar 100mm	6.00	Nos	225.00	Rupees Two Hundred Twenty Five Only	Each	1350.00	
14	P.V.C Collar 90mm	6.00	Nos	210.00	Rupees Two Hundred Ten Only	Each	1260.00	
15	P.V.C Floor Trap 90mm	6.00	Nos	330.00	Rupees Three Hundred Thirty Only	Each	1980.00	
16	C.P Waste 32mm	6.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	1500.00	
17	P.V.C Ball valve for cistern	6.00	Nos	350.00	Rupees Three Hundred Fifty Only	Each	2100.00	
18	Kit PVC for Cistern heavy duty	6.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	3300.00	

19	Acrylic shelf 450mm	6.00	Nos	630.00	Rupees Six Hundred Thirty Only	Each	3780.00
20	Gate Hook 150mm (Heavy)	6.00	Nos	171.00	Rupees One Hundred Seventy One Only	Each	1026.00
21	Spindle for bib cock/Mixer with washer./Disk	4.00	Nos	245.00	Rupees Two Hundred Forty Five Only	Each	980.00
22	G.I. Nipple 15x50mm Jindal Make	2.00	Nos	30.00	Rupees Thirty Only	Each	60.00
23	C.P. Sink Waste 100mm Diamond make	2.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	900.00
24	Iron Door Hinges 75mm (Heavy)	5.00	Nos	23.00	Rupees Twenty Three Only	Each	115.00
25	Brass sliding door bolt complete	4.00	Nos	1890.00	Rupees One Thousand Eight Hundred Ninety Only	Each	7560.00
26	Brass Non Return Valve 15mm	4.00	Nos	590.00	Rupees Five Hundred Ninety Only	Each	2360.00
27	Gate VALVE 25 MM	3.00	Nos	1490.00	Rupees One Thousand Four Hundred Ninety Only	Each	4470.00
28	PVC Ball Cock Long with Ball for Cistern	4.00	Nos	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
29	Aluminium Sheet Heavy Duty.	4.00	Sft	60.00	Rupees Sixty Only	Per Square fit	240.00
30	C.P. Bib Cock Make ESS ESS	2.00	Nos	1350.00	Rupees One Thousand Three Hundred Fifty Only	Each	2700.00
31	C.P. Angel Cock Make ESS ESS	4.00	Nos	1290.00	Rupees One Thousand Two Hundred Ninety Only	Each	5160.00
32	PVC Tank Cover 18" tread heavy duty	3.00	Nos	890.00	Rupees Eight Hundred Ninety Only	Each	2670.00
							99235.00
	G.Total						

CONDITION:-

- 1 Rates should be quoted for all heights including all leads and lifts.
- 2 Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer
Kasumpt. Division
HP PWU Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost Rs :-99,560.00		
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SI:- Supplying of material to Sub division no. VIII Kasumpti Section Shimla-9).					Earnest Money Rs :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate In figures	Unit	Unit	Amount
1	Screw 20,25,30,35mm	3.00	Packet	95.00	Rupees Ninety Five Only	Per Packet	285.00
2	White cement in packing	8.00	Kgs.	45.00	Rupees Forty Five Only	Per Kilo-gram	360.00
3	Powder coated pegs	5.00	Per Peg	55.00	Rupees Fifty Five Only	Per Pegs	275.00
4	Glass Pan 4mm plain frosted	20.00	Sft	120.00	Rupees One Hundred Twenty Only	Per Square fit	2400.00
5	C.P. Door Bolt	5.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	950.00
6	Curatin Bracket Powder coated	10.00	Nos	95.00	Rupees Ninety Five Only	Each	950.00
7	Wire mesh fly proof	30.00	Sqft	55.00	Rupees Fifty Five Only	Per Square fit	1650.00
8	C.P. curtain bracket any shape	20.00	Nos	48.00	Rupees Forty Eight Only	Each	960.00
9	P.V.C. royal Plough	10.00	Packet	69.00	Rupees Sixty Nine Only	Per Packet	690.00
10	Gate Valve 25 mm	5.00	Nos	1490.00	Rupees One Thousand Four Hundred Ninety Only	Each	7450.00
11	Brass stop cock 1/2" Heavy Range	6.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	2700.00
12	Brass Bib cock 1/2" Heavy range	6.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	2700.00
13	C.P. Pillar cock Long body Stainless steel ESS ESS	6.00	Nos	1460.00	Rupees One Thousand Four Hundred Sixty Only	Each	8760.00
14	C.P. Piller cock Make ESS ESS	6.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	5640.00
15	CP Angle cock Long body Make ESS ESS	6.00	Nos	1290.00	Rupees One Thousand Two Hundred Ninety Only	Each	7740.00
16	C.P Bib cock long body Make ESS ESS	6.00	Nos	1350.00	Rupees One Thousand Three Hundred Fifty Only	Each	8100.00

17	C.P Bib cock Make ESS ESS	6.00	Nos	1790.00	Rupees One Thousand Seven Hundred Ninety Only	Each	10740.00
18	PVC Tank Cover 18" tread heavy duty	5.00	Nos	890.00	Rupees Eight Hundred Ninety Only	Each	4450.00
19	Sink mixer Heavy duty Make ESS(premium range)	4.00	Nos	4800.00	Rupees Four Thousand Eight Hundred Only	Each	19200.00
20	Brass wall cock 15 mm with rod	4.00	Nos	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	4600.00
21	PVC Spout flexible 18 " heavy duty	4.00	Nos	1090.00	Rupees One Thousand Ninety Only	Each	4360.00
22	Brass wall cock 15 mm with rod	4.00	Nos	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	4600.00
	G.Total						99560.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Kasumpti Division
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:98,749.00		
Name of Work :-- A/A &M/O various roads underBharari Section.(SH:- Maintenance/General maintenance on various RDS.)					Earnest Money :-2000 .00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	The maintenance of drains include erosion, repair, clearing, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2150.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Meter	9890.00
2	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4500.00	Sqm	3.00	Rupees Three Only	Per Square Metre	13500.00
3	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	267.30	Sqm	29.40	Rupees Twenty Nine and Paise Forty Only	Per Square Metre	7859.00
4	Construction of unlined surface drains of average X-section area 0.40 sqm in ordinary rocks to specified lines, grades, levels and dimensions as per approved design amend technical specification clause 304 excavated material to be used in embankments at site including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (Mechanical Means).	2500.00	Rmt	27.00	Rupees Twenty Seven Only	Per Running Meter	67500.00
						Total	98749.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer
B&R Division Kasumpti,
HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							
Name of Work :-- Restoration of Rain damages on Kelti to Barmu road 0/00 to 3/00 (SH:- Maintenance of drain ,Bush cutting and white washing in km. 0/00 to 3/00)						Estimated Cost:97,623.00	
						Earnest Money :-2000 .00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Maintenance of Earthen shoulder(stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials in all leads and lifts as per directions of the Engineer-	1569.50	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Running Meter	66374.00
2	The maintenance of drains include erosion, repair, clearing, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2150.00	Rmt	4.60	Rupees Four and Paise Sixty Only.	Per Square Metre	9890.00
3	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/ berms, and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	4500.00	Sqm	3.00	Rupees Three Only	Per Square Metre	13500.00
4	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge	267.30	Sqm	29.40	Rupees Twenty Nine and Paise Forty Only	Per Running Meter	7859.00
	Quated rates Percentage in figures					Total	97623.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B&R Division Kasumpti,
 HPPWD, Winter Field Shimla-3