

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-MDI(P)E-Tender-NIT/2026-27- 90-125 Dated:- 4/4/26

To

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,  
Mandi Division No.I,  
HP. PWD. at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,  
Mandi Division No.I,  
HP. PWD. at Padhar

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**\*NOTICE INVITING TENDER\***

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 16.04.2026 up to 12:00 Noon and the same shall be opened on the same day at 12 30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 13.04.2026 upto 12:00 Noon Contractors in person or their authorized representatives.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Drang Basahi road Km 0/00 to 22/00. (PDNA-2023) (SH:- Construction of Breast wall at RD 21/030 to 21/045)	2,18,719.33	4400/-	350/-	One month
2	Restoration of rain damages on Cheli to Silhikhad road Km 0/00 to 10/800. (PDNA-2023) (SH:- Construction of Breast wall at RD 0/650 to 0/658.30)	99,765.00	2000/-	350/-	One month
3	Restoration of rain damages on Cheli to Silhikhad road Km 0/00 to 10/800. (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/710 to 0/717.80)	99,555.75	2000/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

**TERMS AND CONDITIONS:-**

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,  
Mandi Division No. I,  
HPPWD, at Padhar, Distt. Mandi (H.P.)  
on behalf of Governor of Himachal Pradesh

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 218719.33

Earnest Money Rs:- 4400.00

Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Drang Basahi road km. 0/00 to 22/00. (PDNA -2023). (Sub Head:- Construction of Breast wall at RD 21/030 to 21/045).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.65	Per cubic metre	522.50	16537.13	Rupees Sixteen Thousand Five Hundred Thirty Seven and Paise Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	3.63	Per cubic metre	4752.90	17253.03	Rupees Seventeen Thousand Two Hundred Fifty Three and Paise Three Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.74	Per cubic metre	4931.00	107199.94	Rupees One Lakh Seven Thousand One Hundred Ninety Nine and Paise Ninety Four Only
4	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification in cement mortar 1:6 (one cement : six coarse sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.98	Per cubic metre	5918.50	70903.63	Rupees Seventy Thousand Nine Hundred Three and Paise Sixty Three Only
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	284.40	6825.60	Rupees Six Thousand Eight Hundred Twenty Five and Paise Sixty Only
<b>Total in figure :</b>					<b>218719.33</b>	<b>Rupees Two Lakh Eighteen Thousand Seven Hundred Nineteen and Paise Thirty Three Only</b>
<b>Total in Words :</b>						<b>Rupees Two Lakh Eighteen Thousand Seven Hundred Nineteen and Paise Thirty Three Only</b>

Executive Engineer,  
Mandi Division No.1,  
HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 99765.00  
 Earnest Money Rs:- 2000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Cheli to Silhikhad road km. 00/00 to 10/800. (PDNA -2023). (Sub Head: Construction of Breast wall at Rds. 0/650 to 0/658.30).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.86	Per cubic metre	522.50	7241.85	Rupees Seven Thousand Two Hundred Forty One and Paise Eighty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	19.01	Per cubic metre	4765.30	90588.35	Rupees Ninety Thousand Five Hundred Eighty Eight and Paise Thirty Five Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.00	Each	276.40	1934.80	Rupees One Thousand Nine Hundred Thirty Four and Paise Eighty Only
<b>Total in figure :</b>					<b>99765.00</b>	<b>Rupees Ninety Nine Thousand Seven Hundred Sixty Five Only</b>
<b>Total in Words :</b>						<b>Rupees Ninety Nine Thousand Seven Hundred Sixty Five Only</b>

Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.

**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 99555.75  
 Earnest Money Rs:- 2000.00  
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
 Name of work :- Restoration of rain damages on Cheli to Silhikhad road km. 0/00 to 10/800. (PDNA -2023). (Sub Head: Construction of Retaining wall at Rds. 0/710 to 0/717.80).

Contract No. :

Bidder Name :

**SCHEDULE OF WORKS**

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.28	Per cubic metre	522.50	4848.80	Rupees Four Thousand Eight Hundred Forty Eight and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.86	Per cubic metre	4765.30	85108.26	Rupees Eighty Five Thousand One Hundred Eight and Paise Twenty Six Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	276.40	2764.00	Rupees Two Thousand Seven Hundred Sixty Four Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.52	Per cubic metre	1512.10	6834.69	Rupees Six Thousand Eight Hundred Thirty Four and Paise Sixty Nine Only
<b>Total in figure :</b>					<b>99555.75</b>	<b>Rupees Ninety Nine Thousand Five Hundred Fifty Five and Paise</b>
<b>Total in Words :</b>						<b>Rupees Ninety Nine Thousand Five Hundred Fifty Five and Paise Seventy Five Only</b>

Executive Engineer,  
 Mandi Division No.I,  
 HP. PWD. at Padhar.