

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender- Publication/2026-27- 181-90

Dated:- 9-4-2026

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject: -

Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest and Approved under PDNA-2023.

DA: - Notice Inviting Tender.
(09 Nos. Works) -


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Copy to Account Branch in this office.
Copy to Drawing Branch in this office.
Notice Board.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed **Percentage rate** tenders on form **"6&8"** are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **18.04.2026 upto 03.00 PM** and will be opened on the same day at **3.30 PM** in the presence of interested contractors or their authorized representatives who may like to be present. If it happen to be holiday on that day tender will be opened on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 18.04.2026** and tender form will be issued on **18.04.2026 upto 1:30 PM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	A/R & M/O non residential Buildings at SLBSGMC and Hospital Nerchowk, Distt. Mandi (HP) (SH: P/F viterous China E.W.C., C.P./ S.S. Jet and CPVC Pipe and its fittings etc.).	98675	2000	350	One Month	"D"
2	Restoration of rain damages on Samloun Manjhyali Chaihar Sapharu road Km 0/0 to 9/945 (Sub Head: Removal of slips at various R.D. & Construction of unline surface drain at RD 2/650 to 2/900 and 8/0 to 8/150).	96947	2000	350	One Month	"D"
3	Restoration of rain damages on Mandi Gagal Chailchowk road KM 0/0 to 16/190 (SH: Removal of balance slips at RD 0/0 to 0/900).	96511	2000	350	One Month	"D"
4	Restoration of rain damages on Bhangrotu Nauru Tikkari road KM 0/0 to 4/400 (SH: C/o B/wall at RD 1/450 to 1/462) under PDNA-2023.	221870	4500	350	Two Months	"D"
5	A/R & M/O SLBSGMC&H Nerchowk, Distt. Mandi (HP) (SH: Painting and distempering work in interior of incineration block building).	73585	1500	350	One Month	"D"
6	Restoration of rain damages on Ropa Behna Bari Dhar road (SH: Removal of balance slips at various RD's 0/0 to 0/900).	96511	2000	350	One Month	"D"
7	Restoration of rain damages on Tawan Kummi Sakroha Gagal road KM 0/0 to 10/300 (SH: C/o R/wall at RD 5/515 to 5/530) under PDNA-2023.	315480	6400	350	One Month	"D"
8	Restoration of rain damages on various roads under Chakkar Sub Division, HPPWD Nerchowk (SH: Providing dual directional delinators for road side with plastic head un breakable at neck) (Gagal Section).	98700	2000	350	One Month	"D"
9	A/R & M/O SLBSGMC&H Nerchowk, Distt. Mandi (HP) (SH: Painting and distempering work in Exterior of incineration block building).	99720	2000	350	One Month	"D"

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. Maximum two tenders shall be issued to each contractor.
4. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
5. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
6. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT Sr. No. 333 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O non Residential Buildings at SLBSGMC and Hospital Nerchowk, Mandi (HP) (SH:- P/F Vitreous China E.W.C., C.P./S.S. Jet and CPVC Pipe and its fittings etc.).				Estimated Cost:-	
				Earnest Money:-	2000.00
				Time:- One Month	
Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.	Amount
				In figure In words	
1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) ISI marked white solid plastic seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	5.00	Nos	4677.70 Rupees Four Thousand Six Hundred Seventy Seven and Paise	23389.00
2	Providing and fixing 8mm dia C.P./S.S. Jet with flexible tube upto 1metre long with S.S. triangular plate to European type W.C. of quality and make as approved including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	5.00	Nos	436.85 Rupees Four Hundred Thirty Six and Paise Eighty Five Only	2184.00
3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	146.00	Meter	410.29 Rupees Four Hundred Ten and Paise Twenty Nine Only	59902.00
4	Supplying and stacking Below Counter Wash Basin (Oval) 555*450*205 mm at site of work with in all leads, lifts and carriage of materials Cascade NEXT- C0407 white) - Parryware including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	2.00	Nos	3000.00 Rupees Three Thousand Only	6000.00
5	Supplying and stacking at site clean coarse sharp sand free from dirt, dust disintegrated pieces, detritious and organic matter in proper stacks at site including carriage of material with in all leads, lifts and other incidental as per direction of Engineer-in-Charge.	4.00	Per cum	1800.00 Rupees One Thousand Eight Hundred Only	7200.00
TOTAL:-					98675.00

draft schedule of quantity checked & approved for Rs. 98,675/- only
(Rs. Ninety Eight Thousand six hundred seventy five only).

Executive Engineer
Nerchowk Division
PPWD Nerchowk

DNIT SRNO (174) FOR THE YEAR 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain Damages on Samloun Manjhyall Chahar Saphru road Km 0/00 to 9/945 (Sub Head:- Removal of Slips at Various R.D. & Construction of Unline Surface drain at R.D. at 2/650 to 2/900 & 8/00 to 8/150)				Estimated Cost:- 96947.00		
				Earnest Money :- 2000.00		
				Time :- One Months		
Sr.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	In word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	638.45	101.10	Rupees One hundred One seven and paise Ten only.	Per Cubic Metre	64547.00
2	Construction of unlined surface drain of average cross-sectional area 0.40 sqm in ordinary rock to specified lines, grades, level and dimensions as per approved design and technical specification clause 307. Excavated material to be used in embankment at site. including carriage of material and other incidentals as per the direction of the Engineer-in Charge .	400.00	81.00	Rupees Eighty One and paise zero only.	Per Rmt	32400.00
					Total	96947.00

*Draft Schedule of Quantity approved for ₹ 96,947/- only
(Rs. Ninety Six Thousand Nine Hundred Forty Seven only)*

*Executive Engineer,
HPRAAD Division,
PPWD Nerchowki*

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Mandi Gagal Chailchowk road km. 0/0 to 16/150 (S.M.)

Removal of balance slips at RD. 0/0 to 0/900).

DRAFT SCHEDULE OF QUANTITY						
Name of work:- Restoration of rain damages on Mandi Gagai Chailchowk road km. 0/0 to 16/190 (SH:- Removal of balance slips at RD. 0/0 to 0/900).						Estimated Cost:-
						Earnest Money:-
						Time:- One Month
S. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any leads and lift as per technical specification 302.3.5 and 1611 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	923.55	104.50	Ruppes One Hundred Four and Paise Fifty only	Per cubic meter	96511.00
Total:-						96511.00

Proof schedule of quantity checked & approved for Rs. 96, (Rs. Ninety six thousand five hundred Eleven only).


 Executive Engineer
 Narechowk Division
 APPWD Narechowk

draft schedule of quarterly checks & approved for Rs. 9 (Rs. Ninety six thousand five hundred Eleven only).

5/11/115

Scanned with CamScanner

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhangrotu Nouru Mandal Tikkari road km. 0/0 to 4/400 (SH:- C/O B/wall at RD. 1/450 to 1/462) under PDNA-2023.

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5m and a lead upto 20m as per technical specification clause 1603.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	13.44	Per cubic metre	172.00	Rupees One Hundred SeventyTwo Only	2312.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	44.15	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred NinetyFive Only	216114.00
3	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.00	Nos.	287.00	Rupees Two Hundred EightySeven Only	3444.00
TOTAL:-						221870.00

Draft schedule of quantity checked & approved for Rs. 2,21,870/- only (Rs. Two lakh Twenty one thousand Eight hundred seventy only).

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNT Sr. No. ① for the year 2026-27

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O SLBSGMC&H Nerchowk, Mandi (HP) (SH:- Painting and distemping work in interior of incineration block building).

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-	
				Earnest Money:-	73585.00
				Time:- One Month	1500.00
				Rate with all taxes excluding GST in Rs. P.	Amount
				In figure In words	
1	Distemping on ceiling/ sloping surfaces with oil bound washable distemper of approved brand and manufacture to give an even shade: Old work (Two or more coats) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	156.27	Per Square metre	64.25 Rupees SixtyFour and Paise Twenty/Five Only	10040.00
2	Distemping on walls surfaces with oil bound washable distemper of approved brand and manufacture to give an even shade: Old work (Two or more coats) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	850.66	Per Square metre	59.30 Rupees FiftyNine and Paise Thirty Only	50444.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	100.70	Per Square metre	14.10 Rupees Fourteen and Paise Ten Only	1420.00
4	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	100.70	Per Square metre	116.00 Rupees One Hundred Sixteen Only	11681.00
		Total:-			73585.00

Day + Schedule of quantity checked & approved for Rs. 73,585/- only (Rs. Seventy Three Thousand Five Hundred Eighty Five only).

Executive Engineer
Nerchowk Division
PPWD Nerchowk

DNIT Sr.No. (14) for 2026-27

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ropa Behna Bari Dhar road (SH:- Removal of balance slips at various RD's 0/0 to 0/900)

Estimated Cost:-	96511.00
Earnest Money:-	2000.00
Time:- One Month	

S. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any leads and lift as per technical specification 302.3.5 and 1611 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	923.55	104.50	Rupess One Hundred Four and Paise Fifty only	Per cubic meter	96511.00
Total:-						96511.00

Draft Schedule of Quantity checked & approved for Rs. 96,511/- only (Rs. Ninety six Thousand Five Hundred Eleven only).


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT Sr. No. 77 dt. 2026-27

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Tawan Kummil Sakroha Gagal road km. 0/0 to 10/300
(SH:- C/o R/wall at RD. 5/515 to 5/530) under PDNA-2023.

Estimated Cost:-	315480.00
Earnest Money:-	6400.00
Time:- Two Months	

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.33	Per cubic metre	287.00	Rupees Two Hundred EightySeven Only	2390.71
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	60.00	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred NinetyFive Only	293700.00
3	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.00	Nos.	287.00	Rupees Two Hundred EightySeven Only	5740.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.38	Per cubic metre	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty	13648.95
TOTAL:-						315480.00

*Draw + Schedule of quantity checked & approved for Rs. 3,15,480/- only
(Rs. Three Lacs Fifty Four Thousand Four Hundred Eighty only).*

[Signature]
Executive Engineer
Nerchowk Division
BPPWD Nerchowk

DNT Sr. No. (243) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkar Sub Division, HPPWD Nerchowk
(SI:- Providing dual directional delinators for road side with plastic head un breakable at neck (Gagal Section).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Providing dual directional delinator made out of 18 gauge (Eighteen gauge) MS rectangular pipe of size 25x68mm (twenty five into sixty eight millimetres) and of length 600mm (six hundred millimetre). Pipes stove enamelled and baked to 120 C (one hundred twenty degree centigrade) or powder coated. Head made out of ABS plastic rectangular moulded with flat face provided with high intensity prismatic reflectors of colour white/yellow/red of size 100x125mm (one hundred into one hundred twenty five millimetres) with additional 2 (two) reflective strips of 20mm (twenty millimetres) wide make green light for road side with plast head unbreakable neck including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	94.00	Each	1050.00	Rupees One Thousand Fifty Only	98700.00
TOTAL:-						98700.00

*Draft schedule of quantity checked & approved for Rs. 98,700/-
(Rupees Ninety Eight Thousand Seven Hundred only).*

[Signature]
Assistant Engineer
Chakkar Sub-Division
H.P.P.W.D. Nerchowk

[Signature]
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DMIT sr. No. (3) for the year 2026-27.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O SLBSGMC&H Nerchowk, Mandi (HP) (SH:- Painting and distempering work in Exterior of incineration block building).

Name of Work:- A/R & M/O SLBSGMC&H Nerchowk, Mandi (HP) (SH:- Painting and distempering work in Exterior of incineration block building).						Estimated Cost:-	99720.00
						Earnest Money:-	2000.00
						Time:- One Month	
Sr. No.	Description of item	Quantity	Unit	Rate with all taxes excluding GST in Rs. P.		Amount	
				In figure	In words		
1	Finishing walls with Acrylic smooth exterior paint of required shade of approved i.e. Apex of Asian paints or equivalent : Old work (Two or more coat applied @ 1.67 ltr / 10 sqm) on existing cement paint surface for extra height upto 30 mts. including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	739.73	Per Square metre	128.3	Rupees One Hundred TwentyEight and Paise Thirty Only	94907.36	
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	36.99	Per Square metre	14.10	Rupees Fourteen and Paise Ten Only	521.56	
3	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	36.99	Per Square metre	116.00	Rupees One Hundred Sixteen Only	4290.84	
Total:-						99720.00	

Doft schedule of quantity checked & approved for Rs. 99,720 only (Rs. Ninety Nine Thousand Seven Hundred Twenty only).

Executive Engineer
Nerchowk Division
HPVD Nerchowk