

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender- Publication/2026-27-

19-27

Dated:- 2-4-2026

To

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject: -

Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest and Approved under PDNA-2023.


**DA: - Notice Inviting Tender.**  
**( 09 Nos. Works)**

  
Executive Engineer  
Nerchowk Division  
HPPWD Nerchowk

**Copy forwarded to for information:-**

Copy forwarded to the Superintending Engineer, 1<sup>st</sup> Circle, HP.PWD.,  
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.  
Copy to Account Branch in this office.  
Copy to Drawing Branch in this office.  
Notice Board.

  
Executive Engineer  
Nerchowk Division  
HPPWD Nerchowk.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDER"**


Sealed **Percentage rate** tenders on form "6&8" are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **13.04.2026 upto 03.00 PM** and will be opened on the same day at **3.30 PM** in the presence of interested contractors or their authorized representatives who may like to be present. If it happen to be holiday on that day tender will be opened on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 13.04.2026** and tender form will be issued on dated **13.04.2026 upto 1:30 PM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Additional work for C/o Lakhwanu Dahanu Hawanu Bhansot Rathol Andhreta Meramasit road KM 0/0 to 5/600. Under NABARD RIDF-XXVII. (SH:- Preparation of working estimate of additional work).	98500	2000	350	One Month	"D"
2	Repair of HPPWD Rest House Galma, Tehsil Balh, Distt. Mandi (HP) (SH: Plaster work and Painting work).	99271	2000	350	One Month	"D"
3	A/R & M/O Residential accommodation type-III qtr. Under HPPWD Division Nerchowk. (SH: Repair work in type-III qtr, WS & SI, plaster and painting work).	91077	1900	350	One Month	"D"
4	Construction of Play ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH: C/o wire crate R/wall at RD 0/035 to 0/045).	92522	1900	350	One Month	"D"
5	Annual repair and maintenance of Non-Residential building at SLBS Govt. Medical College & Hospital at Nerchowk, Mandi (HP)(SH: Supplying and stacking accessories items for repair and maintenance works).	99216	2000	350	One Month	"D"
6	Repair of HPPWD Rest House Galma, Tehsil Balh, Distt. Mandi (HP) (SH: Construction of Boundary wall, edge wall and Painting work).	97534	2000	350	One Month	"D"
7	Repair of Government Primary School Khakhriyana, Tehsil Balh, Distt. Mandi (HP) (SH: Construction of boundary wall).	99038	2000	350	One Month	"D"
8	Construction of Government High School Building at Behna, Tehsil Balh, Distt. Mandi (HP) (SH: Preparation of detail estimate for Government High School Behna).	35000	800	350	15 days	"D"
9	Construction of Play ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH: C/o wire crate R/wall at RD 0/045 to 0/055).	92522	1900	350	One Month	"D"
10	Restoration of rain damages on Shimla Mandi Tattapani road km 181/400 to 186/200. (SH:- C/o PCC U-shape drain at Statue of Martyr Sh. Tek Singh Mastana at Village Sayah, Post Office Lohara, Tehsil Balh Distt. Mandi HP).	63652	1300	350	One Month	"D"

**Note:- The Contractors/Firms should possess the following documents (Photo copy to be attached).**

- The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- Maximum two tenders shall be issued to each contractor.
- The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
- The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
- As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.

  
**Executive Engineer**  
**Nerchowk Division**  
**HPPWD Nerchowk**

DWT Sr. No. 206 for the year 2025-26

slab No.1.

**DRAFT SCHEDULE OF QUANTITY**

Name of work:- Additional Work for C/o Lakhwanu Dahannu Hawanu Bhansot Rathol Andhreta Meramasit road Km 0/000 to 5/600. Under NABARD RIDF-XXVII. (SH:- Preparation of working estimate of additional work)

Estimated Cost:- 98500.00  
 Earnest Money :- 2000.00  
 Time :- One Month

S.N o	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Job work for preparation of working estimate of additional work such as Cross-drainage work, Retaining Walls, Breast Walls & other necessary provision taken in the estimate, preparation of working estimate duly approved from the Circle Office & Chief Office. Three sets of working estimate and soft copies in the form of Compact Disc (C.D.) complete as per directions of Engineer in charge.	1	98500.00	Rupees Ninety Eight Thousand Five Hundred and paise zero only.	Per Job	98500.00
<b>Total</b>						<b>98500.00</b>

*Draft schedule of quantity checked & approved for Rs. 98,500/- only (Rs. Ninety Eight thousand five hundred only).*

*[Signature]*  
 Executive Engineer,  
 HPRWD Division  
 Perchowk

Lab No. 2

DNT Sr. No. (3) for the year 2026-27.

Name of Work:- Repair of HPPWD Rest House Galma, Tehsil Balh, Dist. Mandi (HP) (SH:- Plaster work & Painting work).		DRAFT SCHEDULE OF QUANTITY		Estimated Cost:-	99271.00	
				Earnest Money:-	2000.00	
				Time:- One Month		
Sr. No.	Description of item	Quantity	Unit	Rate with all taxes excluding GST in Rs. P.		Amount
				In figure	In words	
1	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement : 6 fine sand) including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	82.55	Per Square Meter	221.65	Rupees Two Hundred TwentyOne and Paise SixtyFive Only	18297.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	303.41	Per Square Meter	11.15	Rupees Eleven and Paise Fifteen Only	3383.00
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	142.89	Per Square Meter	111.65	Rupees One Hundred Eleven and Paise SixtyFive	15954.00

	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
i	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture.	131.91	Per Square Meter	99.40	Rupees Ninety/Nine and Paise Fourty Only	13112.00
ii	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture.	163.13	Per Square Meter	95.55	Rupees Ninety/Five and Paise Fifty/Five Only	15587.00
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	105.02	Per Square Meter	118.65	Rupees One Hundred Eighteen and Paise Sixty/Five Only	12461.00
6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	142.89	Per Square Meter	121.95	Rupees One Hundred Twenty/One and Paise Ninety/Five Only	17425.00

Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.00	Per Square Meter	1017.25	Rupees One Thousand Seventeen and Paise TwentyFive Only	3052.00
TOTAL:-					99271.00

*Draft schedule of quantity checked & approved for Rs. 99,271/- only (Rupees Ninety Nine Thousand Two Hundred Seventy one only).*

*[Signature]*  
 Executive Engineer  
 Nerchowk Division  
 P.P.V.D Nerchowk

Job No. 3

DRAFT Sr. No. (208) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O Residential accommodation type-III Qtr. Under HPPWD Division Nerchowk (SH:- Repair work in type-III Qtr., WS & SI, plaster and painting work).

Estimated cost:- 91077.00  
 Earnest Money Cost:- 1900.00  
 Time:- One Month

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in		Amount
				Rs. P.	In words	
				In figure		
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead Of area 3 sq. metres and below including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per sqm	156.25	One Hundred FiftySix and TwentyFive Only	305.00
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, with cement mortar 1:4 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.28	Per sqm	331.38	Rupees Three Hundred ThirtyOne and ThirtyEight Only	2412.00
3	Providing and fixing Stain less Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stain less steel plug 40mm, including painting of fittings and brackets, cutting and making good the walls wherever required kitchen sink of size 600x450x 250 mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	6077.75	Rupees Six Thousand SeventySeven and Paise SeventyFive Only	6078.00
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional Two coats wherever required to achieve even shade and colour including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	147.84	Per sqm	89.88	Rupees EightyNine and Paise EightyEight Only	13288.00
5	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	61.83	Per sqm	92.00	Rupees NinetyTwo Only	5688.00
6	Painting one coat (excluding priming coat) on previously painted wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping With enamel paint other than white including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	22.78	Per sqm	114.80	Rupees One Hundred Fourteen and Paise Eighty Only	2615.00

7	Providing and fixing 25 ltrs geyser in bathroom with all fixtures as per specification including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	7500.00	Rupees Seven Thousand Five Hundred Only	7500.00
8	Providing and fixing CP Brass fancy bib cock with spout no. 1391 of approved quality and colour including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	364.60	Rupees Three Hundred SixtyFour and Paise Sixty Only	365.00
9	Providing and fixing PVC Pipes complete with PVC Fittings and clamps including cutting and making good the walls etc. (Internal work) 15mm dia including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.00	Per Rmt	35.00	Rupees ThirtyFive Only	350.00
10	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete 75 mm dia including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	59.80	Rupees FiftyNine and Paise Eighty Only	120.00
11	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fitting with approved adhesive etc. including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.00	Per Rmt	165.00	Rupees One Hundred SixtyFive Only	1650.00
12	PVC water storage tank with cover and locking arrangement. 1000 litres net capacity tank including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	6202.00	Rupees Six Thousand Two Hundred Two Only	12404.00
13	Providing and laying in trenches 15mm nominal bore galvanised mild steel tubes (Medium grade), tube fittings (Earth work in trenches to be measured and paid for separately) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	25.00	Per Rmt	126.40	Rupees One Hundred TwentySix and Paise Fourty Only	3160.00
14	Providing and fixing CP Brass concealed stop cock of Prayag with flange of approved quality and colour including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	285.20	Rupees Two Hundred EightyFive and Paise Twenty Only	570.00
15	Providing & fixing 32 mm dia M.I. union for wash basin or sink including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	140.30	Rupees One Hundred Fourty and Paise Thirty Only	140.00
16	Providing & fixing 100 mm dia C.P. grating for floor or nahani / gully / floor trap including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	48.30	Rupees FourtyEight and Paise Thirty Only	48.00
17	Providing and fixing G.I. or M.I. Union of Following Sizes (where not Including the item) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	55.20	Rupees FiftyFive and Paise Twenty Only	110.00
18	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position sal wood including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.01	Per cum	95763.05	Rupees Thousand Seven Hundred SixtyThree and Paise Five Only	718.00

19	Demolishing stone rubble masonry manually/ by mechanical means recovery of useful stone 6.48 m <sup>3</sup> @ 300/- only per Cum including stacking of serviceable material and disposal of un-serviceable material within 50 metres in cement mortar including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.80	Per cum	1011.75	Rupees One Thousand Eleven and SeventyFive Only	10927.00
20	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of un-serviceable material within 50 metres including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.90	Per cum	1465.35	Rupees One Thousand Hundred SixtyFive and Paise ThirtyFive Only	1319.00
21	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres lead (wooden/concrete joists to be measured and paid for separately) For thickness of tiles upto 25mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.18	Per sqm	43.30	Rupees FourtyThree and Paise Thirty Only	441.00
22	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.18	Per sqm	2050.00	Rupees Two Thousand Fifty Only	20869.00
TOTAL:-						91077.00

*Draft schedule of quantity checked & approved for Rs. 91,077/- only (Rs. Ninety one Thousand and seventy seven only).*

  
 Executive Engineer  
 Nerchowk Division  
 P.P.W.D. Nerchowk

Net No. 4

DNIT Sr. No. 239 for the year 2025-26

**DRAFT SCHEDULE OF QUANTITY**

Name of Work:- Construction of Play ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH:- C/O wire crate R/wall at RD. 0/035 to 0/045).

Estimated cost:-	92522.00
Earnest Money Cost:-	1900.00
Time:- One Month	

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	29.50	Per Cum	287.00	Rupees Two Hundred EightySeven Only	8467.00
2	Providing and laying of boulder apron laid in wire crates with 3.15 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.34	Per Cum	3074.45	Rupees Three Thousand SeventyFour and FourtyFive Only	84055.00
TOTAL:-						92522.00

*Draft schedule of quantity checked & approved for Rs. 92,522/- only (Rupees Ninety Two Thousand Five Hundred Twenty Two only).*

*[Signature]*  
 Executive Engineer  
 Nerchowk Division  
 APPWD Nerchowk

DRAFT Sr. N. L. (39) for the year 2025-26

Job No. 5

**DRAFT SCHEDULE OF QUANTITY**

Name of Work :- Annual repair and maintenance of Non-Residential building at SLBS Govt. Medical College & Hospital at Nerchowk, Mandi (HP). (Sub Head:- Supplying and stacking accessories items for repair and maintenance works).

Estimated Cost:- 99216.00  
 Earnest Money :- 2000.00  
 Time :- One Month

S. No	Description of item	Quantity	Rate with all taxes excluding GST in Rs.		Unit	Amount
			In figure	In word		
1	Supplying and stacking of Vitrified Floor Tiles 600x600mm (six hundred into six hundred millimeter), approved brand (Somany/Kajaria etc.) and quality at site of work including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	152.64	650.00	Rupees Six Hundred Fifty Only	Per square meter	99216.00
<b>Total</b>						<b>99216.00</b>

*Draft schedule of quantity checked & approved for Rs. 99,216 only (Rs. Ninety Nine Thousand Two Hundred Sixteen only).*

*[Signature]*  
 Executive Engineer,  
 Nerchowk Division,  
 DIPPWD Nerchowk

DMIT Sr. No. ① for 2026-27

Vol 6

**DRAFT SCHEDULE OF QUANTITY**

Name of Work:- Repair of HPPWD Rest House Galma, Tehsil Balh, Distt. Mandi (HP) (SH:-  
Construction of Boundary wall, edge wall & Painting work).

Estimated Cost:-	97534.00
Earnest Money:-	2000.00
Time:- One Month	

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes excluding GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.45	Per cubic meter	265.90	Rupees Two Hundred SixtyFive and Paise Ninety Only	917.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.05	Per cubic meter	4734.75	Rupees Four Thousand Seven Hundred ThirtyFour and Paise SeventyFive Only	33380.00
3	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.06	Per square meter	543.25	Rupees Five Hundred FourtyThree and Paise TwentyFive Only	4379.00

	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 (Seven point five) in super structure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6 (one cement: six coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.23	Per cubic meter	8295.75	Rupees Eight Thousand Two Hundred NinetyFive and Paise SeventyFive Only	1867.00
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level Cement mortar 1:4 (1 cement :4 coarse sand) including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.00	Per square meter	998.40	Rupees Nine Hundred NinetyEight and Paise Fourty Only	10982.00
6	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement : 6 fine sand) including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.12	Per square meter	221.65	Rupees Two Hundred TwentyOne and Paise SixtyFive Only	6011.00
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.12	Per square meter	118.65	Rupees One Hundred Eighteen and Paise SixtyFive Only	3218.00

	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	41.06	Per square meter	229.25	Rupees Two Hundred TwentyNine and Paise TwentyFive Only	9413.00
9	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	6775.40	Rupees Six Thousand Seven Hundred SeventyFive and Paise Fourty Only	6775.00
10	Providing and fixing Viterols China Wash Basin CASCADE NXT C0404 Basin With Half Pedastal in White shade of Perryware/Jaguar/ hindware/ cera or equivalent including cutting holes & making good the same and carriage of material with in all leads and lifts- of superior quality as per direction of Engineer-charge	1.00	Each	4467.50	Rupees Four Thousand Four Hundred SixtySeven and Paise Fifty Only	4468.00
11	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete Semi rigid pipe 40mm dia including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	Each	88.65	Rupees EightyEight and Paise SixtyFive Only	89.00

	Providing and fixing C.P. brass long nose bib cock Cat no. OPP-15037PM Jaquar or equivalent single Control of approved quality conforming to IS standards. 15mm nominal bore including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	1877.35	Rupees One Thousand Eight Hundred SeventySeven and Paise ThirtyFive Only	3755.00
13	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931, 15mm nominal bore including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	1095.25	Rupees One Thousand NinetyFive and Paise TwentyFive Only	2191.00
14	Providing & Fixing Single Towel Rail Cat No. AQN-CHR-7711 of of Jaquar, or equivalent of superior quality including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.00	Each	2245.25	Rupees Two Thousand Two Hundred FourtyFive and Paise TwentyFive Only	6736.00
15	Providing and Fixing Soap Dish stainless steel CAN-113 IN of Jaquar or equivalent complete in all respect including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.00	Each	662.05	Rupees Six Hundred SixtyTwo and Paise Five Only	1986.00

	Providing and Fixing 8mm Dia C.P./S.S. jet with flexible tube up to 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer-In-Charge including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Each	260.90	Rupees Two Hundred Sixty and Paise Ninety Only	522.00
17	Providing and fixing uplasticised PVC connection pipe with brass unions: 45 cm length 15mm nominal bore including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.00	Each	84.50	Rupees EightyFour and Paise Fifty Only	845.00
TOTAL:-						97534.00

*Draft schedule of quantity checked & approved for Rs. 97,534/only  
(Rupees Ninety seven Thousand Five hundred Thirty four only).*

*[Signature]*  
Executive Engineer  
Nerchowk Division  
MPPWD Nerchowk

DRAFT Sr. No. 2 for 2026-27

Job No. 7

**DRAFT SCHEDULE OF QUANTITY**

Name of Work:- Repair of Government Primary School, Khakhriyana, Tehsil Balh, Distt.  
Mandi (HP) (SH:- Construction of boundary wall).

Estimated Cost:-	99038.00
Earnest Money:-	2000.00
Time:- One Month	

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Providing and laying cement concrete 1:5:10 (one cement: five coarse sand: ten graded stone aggregate 40 mm (forty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor all level, including the cost of centering, shuttering and finishing including carriage of materials. within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.05	Per cubic metre	5003.20	Rupees Five Thousand Three and Paise Twenty Only	15260.00
2	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 (Seven point five) in super structure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6 (one cement: six coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.63	Per cubic metre	9990.23	Rupees Nine Thousand Nine Hundred Ninety and Paise Twenty Three Only	66235.00
3	12 mm (twelve millimetre) cement plaster on the rough side of single or half brick wall of mix 1:4 (one cement: four fine sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	57.29	Per square metre	281.08	Rupees Two Hundred Eighty One and Paise Eight Only	16103.00

Providing and laying cement concrete 1:2:4 (one cement: two coarse sand: four graded stone aggregate 20 mm (twenty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.

TOTAL:-

0.21	Per cubic metre	6855.80	Rupees Six Thousand Eight Hundred FiftyFive and Paise Eighty Only	1440.00
				99038.00

*Draft schedule of quantity checked & approved for Rs. 99,038/- only (Rupees Ninety Nine Thousand Thirty Eight only).*

  
 Executive Engineer  
 Nerchowk Division  
 P.P.W.D. Nerchowk

Page No 8

DRAFT Sr. No. (245) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Construction of Government High School Building at Behna, Tehsil Ballh, Distt. Mandi (HP)  
(SH:- Preparation of detail estimate for Government High School Behna).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Job work for preparation of detail estimate and bill of quantity/ schedule of quantity including computer typing and necessary provision taken in the estimate and bill of quantity as per approved drawings and got approved / technical sanction from competent authority. If any correction/ amendments has desired, the same may be corrected as per direction of Engineer-in-Charge complete alongwith submission of soft copy of the approved estimate and bill of quantity.	1.00	Per Job	35000.00	Rupees ThirtyFive Thousand Only	35000.00
TOTAL:-						35000.00

Draft Schedule of quantity checked & approved for Rs. 35000/only (Rs. Thirty Five Thousand only).

Executive Engineer  
Nerchowk Division  
GHPWD Nerchowk

Lab No. 9

DMIT Sr. No. 244 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Construction of Play ground at GSSS Galma, Tehsil Balh, Distt. Mandi (HP) (SH:- C/O wire crate R/wall at RD. 0/045 to 0/055).

Estimated cost:- 92522.00  
Earnest Money Cost:- 1900.00  
Time:- One Month

Sr. No.	Description of Items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per Cum	287.00	Rupees Two Hundred EightySeven Only	8467.00
2	Providing and laying of boulder apron laid in wire crates with 3.15 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	27.34	Per Cum	3074.45	Rupees Three Thousand SeventyFour and FourtyFive Only	84055.00
TOTAL:-						92522.00

Draft schedule of quantity checked & approved for Rs. 92,522/00 (Rupees Ninety Two Thousand Five Hundred Twenty Two only).

  
Executive Engineer  
Nerchowk Division  
APPWD Nerchowk

DRAFT SR.No. 209 for the year 2025-26

slab No.10

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Shimla Mandi Tattapani road km. 181/400 to 186/200 (SH:- C/O PCC U-shape drain at Statue of Martyr Sh. Tek Singh Mastana at Village Sayah, Post Office Lohara, Tehsil Balh, Dist. Mandi (HP)).

Estimated cost:- 63652.00  
 Earnest Money Cost:- 1300.00  
 Time:- One Month

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	3014.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement : three sand : six graded, crushed stone aggregate 20mm (Twenty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	7.00	Per cubic meter	5247.00	Rupees Five Thousand Two Hundred Fourty Seven only	36729.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	187.96	Per KG	127.20	Rupees One Hundred Twenty Seven and Paise Twenty only	23909.00
<b>TOTAL:-</b>						<b>63652.00</b>

Draft schedule of quantity checked & approved for Rs. 63,652/- only (Rs sixty Three Thousand six Hundred Fifty Two only).

Executive Engineer  
 Nerchowk Division  
 P.P.W.D Nerchowk