

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2025/ 313-23

Dated/ 7-4-2026

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

~~Executive Engineer~~
~~Palampur Division~~
~~HPPWD Palampur~~

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 313-23
Dated 7/4/2026 are urgent in nature and in public interest.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT--
'NOTICE INVITING TENDERS'**

Sealed Item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **17.04.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 16.04.2026 up to 4.00 P.M and the application for issue of tender form shall be received 13.04.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Retaining Wall near land of Sh. Ram Saran Kumar Ward No. 9 (SW:- C/o R/Wall (MC Deposit))	Rs. 99,946.00	Rs. 2,000.00	Two Months
2	Dharamshala Yol Dadh Palampur road Km 28/00 to 38/00 (SW:- Hiring of JCB)	Rs. 98,900.00	Rs. 2,000.00	Two Months
3	Link road Cinema Hall Bye Pass road Km 0/00 to 1/500 (SW:- P/L Interlocking Tile works (DC Deposit))	Rs. 99,582.00	Rs. 2,000.00	Two Months
4	R/R Bindraban Morla to connect Menjha via Menjha Society Fatta Chimbhar road (SW:- C/o Breast Wall from RD 2/460 to 2/467.50)	Rs. 97,574.00	Rs. 2,000.00	Three Months
5	R/R Bindraban Morla to connect Menjha via Menjha Society Fatta Chimbhar road (SW:- C/o Breast Wall from RD 2/470 to 2/470.50)	Rs. 97,844.00	Rs. 2,000.00	Three Months
6	NH 154 to Govt. High School Tanda via S.C.V.B Degree College to connect S.C Basti Tanda KM 0/00 to 5/00 (SW:- Inter locking Paver from Km 4/650 to 4/672)	Rs. 99,759.00	Rs. 2,000.00	Three Months
7	NH 154 to Govt. High School Tanda via S.C.V.B Degree College to connect S.C Basti Tanda KM 0/00 to 5/00 (SW:- Inter locking Paver from Km 4/700 to 4/722)	Rs. 99,287.00	Rs. 2,000.00	Three Months
8	C/o Ambulance road from Sh. Anil Kumar House to Tuni to Badri Ward No. 1 GP Balla (SW:- P/L Interlocking Tiles and locking on both side (D.C Deposit))	Rs. 1,49,604.00	Rs. 3,000.00	Two Months
9	Development of Kand Gwaltikkar Ground Tehsil Palampur Distt. Kangra (SW:- P/L G-II & CC Pavement (MPLAD))	Rs. 1,49,247.00	Rs. 3,000.00	Two Months

10	Additionality to 1 st Floor of Panchayat Ghar GP Speru (SW:- Plaster work and Painting work (Deposit))	Rs. 1,99,551.00	Rs. 4,000.00	Three Months
11	R/R of Rain damage on Parour Lahla Chachian road Km 1/00 to 10/00 (SW:- C/o R/wall on RD 2/910 to 2/917(SDRF))	Rs. 99,701.00	Rs. 2,000.00	Two Months
12	R/R on Rain damage on link road from Arth to Ree Gidda Km 0/00 to 3/990 (SW:- C/o R/Wall on RD 0/430 to 0/440 (SDRF))	Rs. 98,842.00	Rs. 2,000.00	Two Months
13	Link road Chandpur to Speru (SW:- P/F W Metal beam Crash Barrier at RD 0/480 to 0/503.20)	Rs. 99,470.00	Rs. 2,000.00	Two Months
14	Link road Chandpur to Speru (SW:- P/F W Metal beam Crash Barrier at RD 0/530 to 0/533.10)	Rs. 99,075.00	Rs. 2,000.00	Two Months
15	C/o Jeep road at Shastri Nagar Ward No. 3 MC Palampur near house of Gurbaksh Singh to Pritam Chand House (SW:- F/C & R/Wall (MPLAD))	Rs. 3,94,904.00	Rs. 7,900.00	Three Months
16	Repair & C/O Rachiyara Speru Gehar Sungal and Awa Khad Samshan Ghat road (SW:- P/L Wearing G-II & CC Pavement at RD 0/00 to 0/060) (MPLAD)	Rs. 1,49,175.00	Rs. 3,000.00	Two Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

①

SCHEDULE OF QUANTITY						
Name of work:- C/o Retaining wall near land of Sh. Ram Sharan Kumar Ward No. 9. (SH:- C/o R/wall). M.C. Deposit						
		Estimated cost Rs.		99946.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.98			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.67			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	9.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.00			Per cubic metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur,

2

SCHEDULE OF QUANTITY

Name of work:- Dharamshala Yol Dadh Palampur road Km 28/00 to 38/00. (SH:- Hiring of JCB).

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage mttook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	98900.00
Total						2000.00
						Two Months

Executive Engineer,
Palampur Division
HP. PWD Palampur. *gn*

3

SCHEDULE OF QUANTITY

Name of work:- Link road Cinema Hall Bye Pass Road Km 0/00 to 1/500. (SH:- P/L Interlocking Tile Works). **DC Deposit**

Estimated cost Rs. 99582.00

Earnest Money Rs. 2000.00

Time Limits Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.47			Per cubic metre.	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	42.35			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.48			Per cubic metre.	
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

Draft Schedule of quantity

Work :- R/R Bindraban Morla to connect Manjha via Menjha society Fatta Chimbhalhar road.

Breast wall from R/D 2/460 to 2/467.50.

Estimate Cost :- 97574
 Earnest Money :- 2000

4

Time Limit :- Three Months

Quantity	Rate		Unit	Amount Rs.
	In figure	In Words		
16.20			Per Cubic metre	
21.26			Per Cubic metre	
6.00			Each	
Total :-				

Executive Engineer
 Palampur Division
 HP PWD Palampur

Draft Schedule of quantity

Name of Work :- R/R Bindrabhan Morla to connect Manjha via Menjha society Fatta Chimbahar road.

Estimate Cost :- 95844

Earnest Money : 2000

Time Limit :- Three Months

Sl. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental.	16.20			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.26			Per Cubic metre	
3	Providing weap holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structures with slop of 1 (v) : 20 (H) towards draing face complete as per drawing and technical specification clause 614, 709, 1204-307 including carriage of materials with in all leads, lifts and other incidental.	7.00			Each	
Total :-						


 Executive Engineer
 Palampur Division
 HP PWD Palampur

6

SCHEDULE OF QUANTITY

Name of work:-N.H. 154to Govt. high school tanda via S.C.V.B.Degree college to connect S.C. Basti tanda Km.0/00 to 5/000 (SW:- Inter locking paver From Km. 4/650 to 4/672)

Estimated cost Rs. 99759.00
Earrest Money Rs. 2000.00
Time Limits Three Months

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.84			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.98			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

7

SCHEDULE OF QUANTITY

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			Time Limits			
			In Figures	In Word		
Name of work: N.H. 154 to Govt. high school tанда via S.C.V.B. Degree college to connect S.C. Basti tанда Km. 0/00 to 5/000 (SW:- Inter locking paver From Km. 4/700 to 4/722)						
			Estimated cost Rs.			99287.00
			Earnest Money Rs.			2000.00
						Three Months
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.52			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.97			Per cubic metre.	
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

8

SCHEDULE OF QUANTITY

Name of work:- C/o Ambulance road from Sh. Anil Kumar House to Tuni to Babri ward No. 1 G.P. Balla. (SH:- P/L Interlocking tiles & Locking on both side). **DC Deposit 1.50 Lacs**

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			Estimated cost Rs.			
			In Figures	In Word		
			Earnest Money Rs.			149604.00
			Time Limits			3000.00
						Two Months
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	109.20			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.56			Per cubic metre.	
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

9

SCHEDULE OF QUANTITY						
Name of work:- Development of Kand Gwalikkar Ground Tehsil Palampur Distt. Kangra H.P. (SH:- P/L G-II & C.C. Pavement).			Estimated cost Rs.		149247.00	
MPLAD 1.50 Lacs			Earnest Money Rs.		3000.00	
Sr. No.	Description of Item	Quantity	Time Limits		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.00			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	18.69			Per cubic metre.	
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

10

Draft Schedule of Quantity

Name of Work :- **Additionalty to 1st floor of Pauchayat Ghar GP Spedu.**

Estimated Cost : Rupees 1,99,551/-
Earnest Money : Rupees 4000/-
Time limit : Three Months.

Sub Work :- **Plister work and Painting work. (Deposit 2.00 lacs)**

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and fixing 10mm thick anti skid water proof stain and impect resistant heavy duty vetrifired tiles Nitco or equivalent 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	20.01 Sqm			Per Square Meter	
2	6 mm Cement plaster in ceiling in Cement Mortar 1:3 (1 Cement:3 Sand) as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	91.73 Sqm			Per Square Meter	
3	15mm Cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in Cement Mortar 1:6 and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	110.25 Sqm			Per Square Meter	
4	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in Cement Mortar 1:6 and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	99.81 Sqm			Per Square Meter	
5	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge: 35mm thick 2nd class Kail and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	12.56 Sqm			Per Square Meter	
6	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured) Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : Float glass panes 4 mm thick (weight not less than 10 kg per sqm) and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	21.53 Sqm			Per Square Meter	
7	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 19 mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. Piano hinges IS : 3818 marked with necessary screws	7.69 Sqm			Per Square Meter	


(10)

8	Providing and fixing 250x16 mm size aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	4.00 Nos.	Each	
9	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	8.00 Nos.	Each	
(i)	150x10 mm size	19.00 Nos.	Each	
(ii)	100x10 mm size			
10	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	4.00 Nos.	Each	
(i)	125x10 mm size	19.00 Nos.	Each	
(ii)	100x10 mm size	19.00 Nos.	Each	
11	Providing and fixing 200 mm size bright finished brass hard drawn hooks and eyes. The rate inclusive toll tax, GST and any other taxes imposed by the government.; and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	4.00 Nos.	Each	
12	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	4.00 Nos.	Each	
13	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 15592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	43.11 Rmt.	Per Running Meter	

16

14	<p>Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government</p>				
(i)	Bend 87.5° 110 mm bend	12.00 nos.		Each	
(ii)	Shoe (Plain) 110 mm Shoe	6.00 nos.		Each	
15	<p>Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (cement : 4 coarse sand) and making good the wall etc. complete. 110 mm and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	36.00 nos.		Each	
16	<p>Applying Birla / JK white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	201.98 Sqm		Per Square Meter	
17	<p>Applying priming coats with primer of approved brand and manufacturer, having low VOC (Volatile Organic Compound) content With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	99.81 Sqm		Per Square Meter	
18	<p>Applying priming coat over new wood and wood based surfaces after and including preparing the surface by Thoroughly cleaning oil, grease, dirt and other foreign matter) sand papering and knotting. Ready mixed paint brushing with primer pink and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	77.73 Sqm		Per Square Meter	
19	<p>Painting two coats (excluding priming coat) on new wood and wood based surfaces, with ready mixed paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping ready mixed painted other then white and as per the entire satisfaction and direction of Engineer-in-Charge as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.</p>	77.73 Sqm		Per Square Meter	

Executive Engineer
Palampur Division
H.P.PWD Palampur



SCHEDULE OF QUANTITY

Name of work:- R/R of Rain Damage on Parour Lahla chachian road KM 1/00 to 10/000. (S.H :- C/o R/Wall On RD 2/910 to 2/917)SDRF		Estimated cost Rs.		99701.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. <small>Government of Himachal Pradesh</small>	9.45		Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government	22.05		Per cubic metre.		
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00		Each		
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

12

SCHEDULE OF QUANTITY

Sr. No.		Description of item	Quantity	Rate		Unit	Amount
				Time Limbs			
				In Figures	In Word		
Name of work:- R/R of Rain Damage on link road from Arth to Ree Gidda KM 0/00 to 3/990. (S.H :- C/o R/Wall On RD 0/430 to 0/440)SDRF							
				Estimated cost Rs.		98842.00	
				Earnest Money Rs.		2000.00	
				Time Limbs		Two Months	
1		Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	10.80			Per cubic metre.	
2		Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause. 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20			Per cubic metre	
3		Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre.	
4		Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total							

Executive Engineer,
Palampur Division
HP, PWD Palampur

13

SCHEDULE OF QUANTITY

Name of work:- Link road Chandpur to Speru. (SH:- P/F/W metal beam Crash Barrier at Rd 0/480 to 0/503.20)

Estimated cost Rs. 99470.00
 Earnest Money Rs. 2000.00
 Time Limits Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging or rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre.	
3	Prviding and erecting of "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post. 150x75x5 mm (one hundred fifty into seventy fiveinto five millimetre) spaced 2 mtr.(two metre) center to center, 108 Mtr.(one hundred eight metre) high, 1.10Mtr.(one point ten metre) below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fitting confirm to IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (one hundred fifty into seventy fiveinto five millimetre) long, complete clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.20			Per running metre	
Total						

Executive Engineer,
 Palampur Division
 HP, PWD Palampur

14

SCHEDULE OF QUANTITY

Name of work:- Link road Chandpur to Speru. (SH:- P/F W metal beam Crash Barrier at Rd 0/530 to 0/533.10)

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
			Estimated cost Rs.	99075.00		
			Earnest Money Rs.	2000.00		
			Two Months			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre.	
3	Providing and erecting of "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150x75x5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 mtr.(two metre) center to center, 108 Mtr.(one hundred eight metre) high, 1.10Mtr.(one point ten metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fitting confirm to IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (one hundred fifty into seventy five into five millimetre) long complete clause 810 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.10			Per running metre	
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

15

SCHEDULE OF QUANTITY					
Name of work:- C/o jeep road at Shastri Nagar ward No. 3 MC Palampur near house of Gurbaksh Singh to Pritam Chand house			Estimated cost Rs.		394904.00
Dist. Kangra H.P. (SH:- F/C & R/wall). MPLAD 4.00 Lacs			Earnest Money Rs.		7900.00
			Time Limits		Three Months
Sr. No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	445.76			Per cubic metre.
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	24.40			Per cubic metre
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	70.41			Per cubic metre.
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	23.00			Each
5	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	12.41			Per cubic metre
Total					


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur.

16

SCHEDULE OF QUANTITY					
Name of work:- Repair & C/o Rachiya Spedu Gehar Sungal and AvarKhad Samshah Ghat road. (SH:- P/L wearing G-II & C.C. Pavement at Rd 0/00 to 0/060). MPLAD 1.50 Lacs					
Sr. No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.70			Per cubic metre
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	19.50			Per cubic metre.
Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.