



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Telephone No: 01907-256827

E-mail: ee-seraj-hp@gov.in

No. PW-SRJ-CB-TA/2025-26-

456

Dated:- 13/04/2026

To

The Executive Engineer (I.T.) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject: -

**Regarding publication of the tender on
departmental site.**

Enclosed please find herewith the copies of notice
inviting tender for the up-loading on department web-site before 20.04.2026
as per notification issued by the Pr. Sec. (PW) to the Govt. of HP vide letter
No. PBW(B) A(3)1/2024 dated 03.01.2024 and No. PWD-B-A0(3)1/2024-
241828 dated 02.02.2026.

**Certified that the works mentioned in the tender
notice are urgent in nature and in co-ordination with the disaster
management Act. 2005.**

DA: - As Above.


Executive Engineer,
HPPWD Division,
Seraj at Janjehli.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Telephone No: 01907-256827

E-mail: ee-seraj-hp@gov.in

NOTICE INVITING TENDER

Sealed percentage rate short terms tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD Division, Seraj at Janjehli Distt. Mandi (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class, so as to reach in this office on 21.04.2026 upto 10.30 A.M. and will be opened on the same day at 11.00 A.M. In the presence of contractors or their authorised representative who wish to be present at that time. The application for obtaining the tender form will be received on 20.04.2026 between 10.00 A.M. to 01:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on 20.04.2026 between 11.00 AM to 05.00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, HP.PWD Division, Seraj at Janjehli Distt. Mandi H.P. must accompany with the tender form. Ambiguous/ Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. **The Executive Engineer, HP.PWD Division, Seraj at Janjehli reserve the right to reject/accept any offer of tender without assigning any reasons.**

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender	Time allowed
1	RRD in various roads under Janjehli Section-I under Janjehli Sub Division (SH:- Removal of slips & land slide in various roads).	4,99,622/-	10,000/-	350/-	Two months
2	RRD on Link road village Bassi KM 0/000 to 10/000 (SH:- C/o Embankment, removal of slips and Unlined drain in various Rds)	4,95,853/-	10,000/-	350/-	Two Months
3	RRD on Seri Khad to Majhwas road in GP Bhanthal KM 0/000 to 2/500 (SH:- Removal of Land Slide in various RDS Km 0/000 to 2/500)	4,71,147/-	10,000/-	350/-	Two Months
4	RRD on Janjehli Bhekhali Gadagusaini road Km 0/000 to 11/000 (SH:- C/o wire crate R/wall at Rd 0/535 to 0/563.80 and C/o embankment at various RDs)	4,97,673/-	10,000/-	350/-	Two Months
5	SDF/2025/1220 R/O (Repair of) Restoration of rain damage on Tapnali Khauli road in Km. 0/000 to 15/000 (SH:- Removal of slip in between Km. 11/045 to 13/300). SDF/2025/1222 R/O (Repair of) Restoration of rain damage on on Mehach Deori road in Km. 0/000 to 7/000. (SH:- C/o Retaining wall in wire crate at Rd. 0/900 to 0/904.35)	99,641/-	2000/-	350/-	Two Months
6	SDF/2025/1221 R/O (Repair of) Restoration of rain damage on Tapnali to Ghat road in Km. 0/000 to 18/000. (SH:- Removal of slip in between Km. 0/120 to 7/430. SDF/2025/1224 R/O (Repair of) Restoration of rain damage on Gadagusaini Thanwarigad Lababan road in Km. 0/000 to 7/000 (SH:- Removal of slip in between Km. 0/400 to 2/130).	99,350/-	2000/-	350/-	Two Months
7	RR Damages on various road under Chhatri Sub-Division (SH:- Removal of slip in various roads).	2,64,326/-	6000/-	350/-	Two Months
8	SDF/2025/1218 R/O (Repair of) Restoration of rain damage on Handel to Niharikhad road in Km. 0/000 to 7/465 (SH:- Removal of slip in between Km. 0/015 to 0/680). SDF/2025/1219 R/O (Repair of) Restoration of rain damage on Chhatri Gadagusain road in Km. 0/000 to 29/000 (SH:- Removal of slip in between Km. 14/200 to 17/315).	99,065/-	2000/-	350/-	Two Months
9	SDF/2025/1225 R/O (Repair of) Restoration of rain damage on Baryogi Thensar Magrugalla road in Km. 0/000 to 8/500 (SH:- Removal of slip in between Km. 5/550 to 6/480). SDF/2025/1217 R/O (Repair of) Restoration of rain damage on Chharti Magrugalla via Lassi road in Km. 0/000 to 8/500 (SH:- Removal of slip in between Km. 0/120 to 0/730).	99,580/-	2000/-	350/-	Two Months
10	SDF/2025/1227 R/O (Repair of) Restoration of rain damage on Baryogi Kakradhar road in Km. 0/000 to 4/000 (SH:- Removal of slip in between Km. 1/960 to 3/100). SDF/2025/1223 R/O (Repair of) Restoration of rain damage on Nagan Chhatri road in Km. 13/000 to 22/000 (SH:- Removal of slip in between Km. 13/405 to 15/300).	99,098/-	2000/-	350/-	Two Months
11	RR Damages on Janjehli Raigarh Shikarimata road km. 0/000 to 16/450 (SH:- Construction of Breast wall at Rds. 4/961 to 4/965 & 4/980 to 5/006)	4,92,736/-	10,000/-	350/-	Two Months

12	RR Damages on Ghumrala Jughand road km 0/000 to 3/500 (SH: Construction of Brest wall in wire crate at Rd 1/760 to 1/800)	4,23,870/-	9000/-	350/-	Two Months
13	RR Damages on Thunag Banyad Mandehalu road km 0/000 to 14/200 (SH: Removal of slips & Land slides at various Rds in km 4/00 to 10/800).	4,82,688/-	9,800/-	350/-	Two Months
14	RR Damages on various roads under Bagsaid Sub Division (SH:- Hiring of JCB for removal of slips, dressing of berms, repair of earthen road, construction of unlined drain in various roads in Bagsaid Sub Division) SDF/NDRF/BASP	4,94,400/-	10,000/-	350/-	Two Months
15	RR Damages on Bagsaid Thunag via Raingaloo road km 0/00 to 9/500 (SH:- Construction of Retaining wall in PCC 1:4:8 at Rds 0/505 to 0/513)	4,99,415/-	10,000/-	350/-	Two Months
16	RR Damages on Rilla-Chandi-Kurshali Road km 0/000 to 8/400 (SH:- Construction of Embankment/ filling at various Rds in km 0/240 to 0/400).	4,95,972/-	10,000/-	350/-	Two Months
17	RR Damages on Rilla-Chandi-Kurshali Road km 0/000 to 8/400 (SH:- Construction of Embankment/ filling at various Rds in km 0/400 to 0/540).	4,75,226/-	10,000/-	350/-	Two Months
18	RR Damages on various link roads under Janjehli Sub Division HPPWD Janjehli (SH:-Hiring of Hydraulic Excavator with rock breaker (210-Hyundai or its equivalent) 1.00/1.35 cum (one point zero/one point three five cubic meter) bucket capacity for removal of slips in various link road under Janjehli Section-II).	4,97,200/-	10,000/-	350/-	Two Months
19	RR Damages on various roads under Bagsaid Sub-Division (SH:-Removal of slips, Construction of embankment & Re-Construction of Unlined surface drain at various Rds in Bagsaid Section).	4,97,800/-	10,000/-	350/-	Two Months
20	RR Damages on Mandi Gagal Chail Janjehli Chhatri road km 0/00 to 82/000 (SH:-Removal of slips & land slides various Rds in km 73/000 to 80/000 & RR Damages on Janjehli Magrugalla road km 0/000 to 11/000 (SH:- Removal of slips & land slides various Rds in km 4/400 to 8/00)	4,93,690/-	10,000/-	350/-	Two Months
21	RR Damaged on various roads under Janjehli Sub Division (SH:- Hiring of Tipper for carriage of different material in various roads) Job No-II	96,000/-	2,000/-	350/-	Two Months
22	RR Damaged on various roads under Janjehli Sub Division (SH:- Hiring of Tipper for carriage of different material in various roads) Job No-I	99,200/-	2,000/-	350/-	Two Months
23	RR Damages on various road JE Section Bagachanogi under Sub Division Janjehli HPPWD Janjehli (SH:- Removal of slips and land slides at various Rds in Dhawas Chhodhar road km 0/000 to 2/500 & Shilibagi Deol Jainshla road km 0/000 to 10/000).	4,92,400/-	10,000/-	350/-	Two Months
24	RR damages on Mandi Gagal Chail Janjehli road KM 35/000 to 82/000 (SH:-Construction of Unlined Drain and Maintenance of Earthen Shoulder in various KM 35/000 to 63/000)	2,30,888/-	5,000/-	350/-	Two Months
25	RR Damages on Link Bagla via Damedhi Khad (Perm aka Gharat) Village Thanar in G.P. Gudah km 0/000 to 2/400 (SH:-Removal of slips & land slides at various Rds in km 0/500 to 2/400).	2,25,617/-	5,000/-	350/-	Two Months
26	RR Damages on Thachadhar Naloti Balwar Kilan Dawada road in km 0/000 to 8/000 (SH:- Construction of B/wall at Rds 6/380 to 6/405)	4,28,320/-	9,000/-	350/-	Two Months
27	RR Damages on Thachadhar Naloti Balwar Kilan Dawada road in km 0/000 to 8/000 (SH:- Removal of slips in between km 7/000 to 8/000).	2,99,632/-	6,000/-	350/-	Two Months
28	RR Damages on Bagsaid Thunag via Raingaloo road km 0/00 to 9/500 (SH:- Construction of Embankment at Rds 0/675 to 0/750 & Unlined surface Drain at various Rds).	2,90,630/-	6,000/-	350/-	Two Months
29	RR Damages on various road under Janjehli Sub Division (SH:- Construction of Unlined surface drain & maintenance of earthen shoulder at various Rds in various road under Bagachanogi Section).	99,594/-	2,000/-	350/-	Two Months
30	SDF/2024/60, R/O(Repair and Maintenance of Kainchi Mod Majhwal road km 0/00 to 1/500 (SH:- Removal of slips and land slides at various Rds in km 0/000 to 1/500)	97,781/-	2,000/-	350/-	Two Months

31	RR Damages on Gohar Kandha road in Km 0/000 to 16/000 (SH:- C/o B/wall in wire crate at Rd 14/420 to 14/440.50)	4,94,416/-	10,000/-	350/-	Two Months
32	RRD on Janjehli Magrugala Chhatri road in Km 0/000 to 11/200 (SH:- C/o R/wall at Rd 8/165 to 8/180)	4,10,249/-	10,000/-	350/-	Two Months
33	RRD on Mandi Gagal Chail Janjehli Chhatri road Km 0/000 to 82/000 (SH:- C/o Retaining wall at Rd 68/311 to 68/324)	4,74,367/-	9,500/-	350/-	Two Months
34	RRD on Nagan Chhari road in Km 19/000 to 22/000 (SH:- C/o Retaining wall at Rd in Km 17/847 to 17/857.30).	4,03,150/-	8,200/-	350/-	Two Months
35	RR Damages on Katyandi Tandi Thunag road Km. 0/000 to 6/525. (SH:- Construction of L-shape drain in Km. 2/090 to 2/400, 2/570 to 2/680.70, Retaining wall with Toe wall in PCC 1:4:8 at RD. 2/300 to 2/306).	4,99,405/-	10,000/-	350/-	Two Months
36	RRD on Bhanthal Sanarali Shankardehra Raigarh road Km. 0/000 to 14/000. (SH:- Construction of Retaining wall at RD 8/410 to 8/422).	4,51,937/-	10,000/-	350/-	Two Months
37	RR Damages on Lower Bhiyand to Upper Bhiyand road Km 0/000 to 2/500 (SH:- Removal of slips and land slides in various Rds in Km 0/000 to 2/000) Under MPLAD.	4,91,817/-	10,000/-	350/-	Two Months
38	Restoration Rain Damaged on Parala to Mandap road Km 0/000 to 3/900 (SH:- Construction of retaining wall with Toe wall in PCC 1:4:8 at Rd 2/008 to 2/018).	4,67,247/-	10,000/-	350/-	Two Months

Terms and conditions:-

1. The contractors/firms are required to quote their rates clearly percentage rate, failing which the tender is liable to be rejected.
2. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.
3. The contractor will produce show their enlistment/renewal documents at the time of obtaining tender.
4. Latest Income tax and GST tax clearance certificates as well as PAN Number and GST number must be attached with the application failing which tender documents will not be issued.
5. The rates shall be quoted by the bidder with all taxes including GST.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. As per Govt. Notification No. PW/CTR/32-20-General Isnt. CPWD/2020-37996-38095 dated 13.03.2023 the tender above 5% will be summarily rejected and tenders amount below 30% of amount put to tender will also be accepted.

Executive Engineer,
HPPWD Division
Seraj at Janjehli.

Dated:-

13/04/2026

No. PW-SRJ/NIT/2026-27:-

446-55

1. Copy to the Director, Information and publication Department HP Shimla for favour of publication in one regional newspaper and one National newspaper.
2. Copy to the superintending Engineer 1st Circle HPPWD Mandi for information please
3. Copy to Sub- Divisional office (Civil) Thunag Tehsil Thunag for information please.
4. Copy to Block Development office Janjehli Tehsil Thunag Distt. Mandi HP.
5. Copy to all the Assistant Engineer working under this Division.
6. Copy to Drawing Branch & Account Branch
7. Notice board of this office.

Executive Engineer,
HPPWD Division
Seraj at Janjehli.

BILL OF QUANTITY

Estimate Cost: 4,99,622.00 Only

Earnest Money: 10,000.00 Only

Time : Two months.

Name of Work:- RRD onvarious roads under Janjehli Section -I under Janjehli Sub Division (SH:- Removal of slips & Land slide in various roads).

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer - in-Charge including carriage of material within all leads, lifts and other incidental charges.	4230.50	Cum	118.10	4,99,622.00	Rupees Four Lakh(s) Ninety Nine Thousand Six Hundred Twenty Two Only
Total:-					4,99,622.00	

Bill of Qty approved
Rs. 4,99,622/only


Executive Engineer
H.P.W.D. Division
Seraj at Janjehli

BILL OF QUANTITY

Estimate Cost: 4,95,853.00 Only
 Earnest Money: 10,000.00 Only
 Time : Two Months.

Name of Work:- RR Damaged on Link road Village Bassi KM 0/000 to 10/000 (SH:- Construction of Embankment , Removal of Slips and Unlined Drain in Various RDs) Under PDNA 2023

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 including carriage of material in all leads and lifts and other incidentials complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1056.90	Cum	204.15	2,15,766.00	Rupees Two Lakh(s) Fifteen Thousand Seven Hundred Sixty Six Only
2.00	Construction of unlined surface drains of average cross-sectional area 0.30 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By Mechanical Means and direction of Engineer -in-Charge including carriage of material within all leads, lifts and other incidental charges.	2150.00	Per Running Meter	37.60	80,840.00	Rupees Eighty Thousand Eight Hundred Forty Only
3.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer -in-Charge including carriage of material within all leads, lifts and other incidental charges.	1687.10	Cum	118.10	1,99,247.00	Rupees One Lakh(s) Ninety Nine Thousand Two Hundred Forty Seven Only
Total:-					4,95,853.00	

Bill of qty approved
 for Rs. 4,95,853 only

[Signature]
 Executive Engineer,
 HPPWD Division
 Seraji at Janjehli

246

(3)

BILL OF QUANTITY

Estimate Cost: 4,71,147.00 Only

Earnest Money: 10,000.00 Only

Time : Two months.

Name of Work:- RRD on Seri Khad to Majhas road in GP Bhanthal KM 0/000 to 2/500 (SH:- Removal of slips & Land slide in various RDs KM 0/000 to 2/500).

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer - in-Charge including carriage of material within all leads, lifts and other incidental charges.	3989.39	Cum	118.10	4,71,147.00	Rupees Four Lakh(s) Seventy One Thousand One Hundred Forty Seven Only
Total:-					4,71,147.00	

Bill of Qty approved
for Rs. 4,71,147/only

Executive Engineer
H.P.W.D. Division
Seraj at Jagmudi

318

(4)

BILL OF QUANTITY						
Name of Work:- RR damages on Janjehli Bhekhali Gadagusaini road km 0/000 to 11/000 (SH:- Construction of crated R/wall at RD 0/535 to 0/563.80 and Construction of embankment at various Rds)				Estimated cost Rs. 4,97,673.00		
				Earnest Money cost Rs. 10,000.00		
				Time - Two Month		
	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	48.60	Per Cubic metre	552.35	26844.00	Rupees Twenty Six Thousand Eight Hundred & Fourty Four Only
2	Providing and laying concrete for plain /reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	25.92	Per Cubic metre	5236.10	135720.00	Rupees One Lakh Thirty Five Thousand Seven Hundred & Twenty Only
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS : 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	79.49	Per Cubic metre	3140.50	249638.00	Rupees Two Lakh Fourty Nine Thousand Six Hundred & Thirty Eight Only
4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	19.01	Per Cubic metre	1306.55	24838.00	Rupees Twenty Four Thousand Eight Hundred & Thirty Eight Only
5	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer -in-Charge. .	297.00	Per Cubic metre	204.15	60633.00	Rupees Sixty Thousand Six Hundred & Thirty Three Only
				Total	497673.00	

Bill of Quantity
Rs. 4,97,673.00

Approved for
Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY


Estimate Cost: Rs. 99,641.00 Only
 Earnest Money: Rs. 2,000.00 Only
 Time :- Two Months

Name of Work :- SDF/2025/1220 R/O (Repair of) Restoration of rain damage on Tapnali Khauli road in km 0/000 to 15/000 (SH:- Removal of slip in between km 11/045 to 13/300) SDF/2025/1222 R/O (Repair of) Restoration of rain damage on Mehach Deori road in km 0/000 to 7/000 (SH:- Construction of Retaining wall in wire crate at Rd 0/900 to 0/904.35)

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	422.1	Per Cubic metre	118.10	49850	Rupees Fourty Nine Thousand Eight Hundred & Fifty Only
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	6.53	Per Cubic metre	552.35	3607.00	Rupees Three Thousand Six Hundred & Seven Only
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G .I. wire conforming to IS : 280 and IS : 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.62	Per Cubic metre	3140.50	42774.00	Rupees Fourty Two Thousand Seven Hundred & Seventy Four Only

4	Back filling behind abutment , wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	2.61	Per Cubic metre	1306.55	3410.00	Rupees Three Thousand Four Hundred & Ten Only
				Total	99641.00	

Bill of Qty approved
for Rs. 99,641 only



Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: Rs. 99,350.00 Only
 Earnest Money: Rs. 2,000.00 Only
 Time :- Two Months

Name of Work :- SDF/2025/1221 R/O (Repair of) Restoration of rain damage on Tapnali to Ghat road in km 0/000 to 18/000
 (SH:- Removal of slip in between km 0/120 to 7/430) SDF/2025/1224 R/O (Repair of) Restoration of rain damage on
 Gadagusaini Thanwarigad Lababan road in km 0/000 to 7/000 (SH:- Removal of slip in between km 0/400 to 2/130)

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	841.24	Per Cubic metre	118.10	99350	Rupees Ninety Nine Thousand Three Hundred & Fifty Only
				Total	99350.00	

Bill of qty approved
 for Rs. 99,350/only

[Signature]
 Executive Engineer
 Seraj Division B&R
 HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 2,64,326 /- Only
Rs. 6,000/-Only
Two Months

Name of Work :- RR Damages on various road under Chhattri sub Division (SH:- Removal of slip in various roads).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2238.15	Per Cubic metre	118.10	264326.00	Rupees Two Lakh Sixty Four Thousand Three Hundred & Twenty Six Only
				Total	264326.00	

Bill of Quantity approved
for Rs. 2,64,326 Only

[Signature]
Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: Rs. 99,065.00 Only
Earnest Money: Rs. 2,000.00 Only
Time :- Two Months

Name of Work :- SDF/2025/1218 R/O (Repair of) Restoration of rain damage on Handel to Niharikhad road in km 0/000 to 7/465
(SH:- Removal of slip in between km 0/015 to 0/680) SDF/2025/1219 R/O (Repair of) Restoration of rain damage on Chhattri
Gadagusain road in km 0/000 to 29/000 (SH:- Removal of slip in between km 14/200 to 17/315)

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	838.82	Per Cubic metre	118.10	99065	Rupees Ninety Nine Thousand & Sixty Five Only
				Total	99065.00	

Bill of Qty approved
for Rs. 99,065/- only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: Rs. 99,580.00 Only
 Earnest Money: Rs. 2,000.00 Only
 Time :- Two Months

Name of Work :- SDF/2025/1225 R/O (Repair of) Restoration of rain damage on Baryogi Thensar Magrugalla road in km 0/000 to 8/500 (SH:- Removal of slip in between km 5/550 to 6/480) SDF/2025/1217 R/O (Repair of) Restoration of rain damage on Chhatri Magrugalla via Lassi road in km 0/000 to 8/500 (SH:- Removal of slip in between km 0/120 to 0/730)

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	843.18	Per Cubic metre	118.10	99580	Rupees Ninety Nine Thousand Five Hundred & Eighty Only
				Total	99580.00	

Bill of Qty approved
for Rs. 99,580/only

Executive Engineer
 Seraj Division B&R
 HRPWD Janjehli

BILL OF QUANTITY

Estimate Cost: Rs. 99,098.00 Only
Earnest Money: Rs. 2,000.00 Only
Time :- Two Months

Name of Work :- SDF/2025/1227 R/O (Repair of) Restoration of rain damage on Baryogi kakradhar road in km 0/000 to 4/000
(SH:- Removal of slip in between km 1/960 to 3/100) SDF/2025/1223 R/O (Repair of) Restoration of rain damage on Nagan
Chhatri road in km 13/000 to 22/000 (SH:- Removal of slip in between km 13/405 to 15/300)

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	839.1	Per Cubic metre	118.10	99098	Rupees Ninety Nine Thousand & Ninety Eight Only
				Total	99098.00	

Bill of Qty approved
for Rs. 99,098/only


Executive Engineer
Sera Division B&R
HPPWD Janjehi

(11)

BILL OF QUANTITY						
Name of Work:- RR Damages on Janjehli Raigarh Shikarimata road km 0/00 to 16/450 (SH:- Construction of Breast wall at Rds 4/961 to 4/965 & 4/980 to 5/006)					Estimated cost Rs. - 4,92,736.00	
					Earnest Money cost Rs. - 10,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any leads upto any height as per technical specification clause 1603.1 within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	24.67	Per Cubic metre	150.00	3701.00	Rupees Three Thousand Seven Hundred & One Only
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	25.73	Per Cubic metre	552.35	14212.00	Rupees Fourteen Thousand Two Hundred & Twelve Only
3	Random rubble Stone masonry in cement mortar 1:6 (one cement : six sand) for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	48.64	Per Cubic metre	5558.90	270385.00	Rupees Two Lakh Seventy Thousand Three Hundred & Eighty Five Only
4	Construction of dry rubble masonry for retaining walls , breast walls , revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clauses 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	51.36	Per Cubic metre	3980.50	204438.00	Rupees Two Lakh Four Thousand Four Hundred & Thirty Eight Only
				Total	492736.00	

Bill of Quantity approved
for Rs. 4,92,736/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY						
Name of Work:- RR Damages on Ghumrala Jughand road km 0/00 to 3/500 (SH:- Construction of Brest wall in wire crate at Rd 1/760 to 1/800)					Estimated cost Rs. -	4,23,870.00
					Earnest Money cost	9,000.00
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	56.68	Per Cubic metre	552.35	31307.00	Rupees Thirty One Thousand Three Hundred & Seven Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS : 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	125.00	Per Cubic metre	3140.50	392563.00	Rupees Three Lakh Ninety Two Thousand Five Hundred & Sixty Three Only
				Total	423870.00	

Bill of qty. approved for

Rs. 4,23,870.00 /- only

Executive Engineer
Seraf Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost:

Rs. 4,82,688.00 Only

Earnest Money:

Rs. 9,800.00 Only

Time :-

Two Months

Name of Work :- RR Damages on Thunag Banyad Mandehalu road km 0/00 to 14/200 (SH:- -Removal of slips & Land slides at various RDs in km 4/00 to 10/800).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	4087.11	Per Cubic metre	118.10	482688.00	Rupees Four Lakh Eighty Two Thousand Six Hundred & Eighty Eight Only
				Total	482688.00	

Bill of Qty approved
for Rs. 4,82,688 only


Executive Engineer
Sera Division B&R
HPPWD Janjehli

→

BILL OF QUANTITY

Estimate Cost: 4,94,400.00 Only
 Earnest Money: 10,000.00 Only
 Time : Two months.

Name of Work:- RR Damaged on various road under Bagsaid Sub Division (SH:- Hurring of JCB for removal of slips, dressing of berms , repair of earthen road , construction of unlined drain in various roads in Bagsaid Sub Division) SDF/NDRF/BASP

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Hiring of JCB /excavator for removal of snow /slips and boulder in all kinds of soil including rocky portion and saturated and disposing of all excavated earth or un - serviceable materials from the road surface up to any leads and lifts as per direction and entire satisfaction of Engineer- in charge. The machine /JCB (front end-loader) should work minimum 8.00 hours daily and remove at least 45.00 cum. Quantity of slips and loading of soil 100 cubic meter per hours . Any loss to the public/private property of any accident etc. happened during the course of hiring period execution shall be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases the fuel and operational staff for excavator will be provided by the owner , the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book	412.00	Per Hours	1200.00	4,94,400.00	Rupees Four Lakh(s) Ninety Four Thousand Four Hundred Only
Total:-					4,94,400.00	

Assistant Engineer
 Bagsaid Sub Division
 HPPWD Bagsaid

Executive Engineer,
 HPPWD Division
 Seraj at Janjehli

Bill of qty approved
 for Rs. 4,94,400.00 only

BILL OF QUANTITY						
Name of Work:- RR Damages on Bagsaid Thunag via Raingaloo road km 0/00 to 9/500 (SH:- Construction of Retaining wall in PCC 1:4:8 at Rds 0/505 to 0/513)					Estimated cost Rs. - 4,99,415.00	
					Earnest Money cost Rs. - 10,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	21.28	Per Cubic metre	552.35	11754.00	Rupees Eleven Thousand Seven Hundred & Fifty Four Only
3	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials, with in all leads .lifts as per direction of Engineer - in - charge .	90.00	Per Cubic metre	5236.10	471249.00	Rupees Four Lakh Seventy One Thousand Two Hundred & Fourty Nine Only
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	6.16	Per Cubic metre	1306.55	8048.00	Rupees Eight Thousand & Fourty Eight Only
7	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	21.00	Each	398.30	8364.00	Rupees Eight Thousand Three Hundred & Sixty Four Only
				Total	499415.00	

*Bill of Qty approved
for Rs. 4,99,415.00 only*

[Signature]
Executive Engineer
Seraf Division B&R
HRPWD Janjehli

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 4,95,972.00 Only
Rs. 10,000.00 Only
Two Months

Name of Work :- RR Damages on Rilla-Chandi-Kurshali Road km 0/000 to 8/400 (SH:- Construction of Embankment/ filling at various Rds in km 0/240 to 0/400).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	2429.45	Per Cubic metre	204.15	495972.00	Rupees Four Lakh Ninety Five Thousand Nine Hundred & Seventy Two Only
				Total	495972.00	

*Bill of Qty approved
for Rs. 4,95,972 only*

[Signature]
Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 4,75,226.00 Only
Rs. 10,000.00 Only
Two Months

Name of Work :- RR Damages on Rilla-Chandi-Kurshali Road km 0/000 to 8/400 (SH:- Construction of Embankment/ filling at various Rds in km 0/400 to 0/540).

S. No.	Sub Head and Item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	2327.83	Per Cubic metre	204.15	475226.00	Rupees Four Lakh Seventy Five Thousand Two Hundred & Twenty Six Only
				Total	475226.00	

*Bill of Qty approved
for Rs. 4,75,226/only*

[Signature]
Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 4,97,200.00 Only
Rs. 10,000.00 Only
Two Months

Name of Work :- RR Damages on various link roads under Janjehli Sub Division HP.PWD Janjehli (SH:- Hiring of Hydraulic Excavator with rock breaker (210-Hyundai or its equivalent) 1.00/1.35 cum (one point zero/one point three five cubic meter) bucket capacity for removal of slips in various link road under Janjehli Section -II).


S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Hiring of Hydraulic Excavator with rock breaker (210 Hyundai or its equivalent) 1.00/1.35 Cum (one point Zero / one point three five cubic metres) for breaking rock, loading in tippers and disposal with any lift , trimming bottom and side slopes in accordance with requirements of line , gaeds and cross - sections as per technical specification clause 302.3.5. including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor / owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor , only actual working hours will be accounted for the payment earth cutting / removal of slips excavation in all kinds of soil including loading in to tipper / trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer- in charge.	113.00	Per Hour	4400.00	497200.00	Rupees Four Lakh Ninety Seven Thousand Two Hundred Only
				Total	497200.00	

Bill of Qty approved
Rs. 4,97,200 only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY						
Name of Work:-RR Damages on various road under Bagsaid Sub- Division (SH:- Removal of slips, Construction of embankment & Re-Construction of Unlined surface drain at various Rds in Bagsaid Section).					Estimated cost Rs. - 4,97,800.00	
					Earnest Money cost Rs. - 10,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	518.75	Per Cubic metre	118.10	61264.00	Rupees Sixty One Thousand Two Hundred & Sixty Four Only
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site , spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	292.9	Per Cubic metre	204.15	59796.00	Rupees Fifty Nine Thousand Seven Hundred & Ninety Six Only
3	Construction of Unlined surface drains of average cross -section area .020sqm in soil to specified lines, grades, levels and dimensions. Excavated material to e used in embankmet with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307. By mechanical Means as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	13650.00	Per Running metre	27.60	376740.00	Rupees Three Lakh Seventy Six Thousand Seven Hundred & Fourty Only
				Total	497800.00	

Bill of Qty approved
for Rs. 4,97,800 only


Executive Engineer
Seraj Division B&R
HRPWD Janjehat

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 4,93,690 /- Only
Rs. 10,000/-Only
Two Months

Name of Work :- RR Damages on Mandi Gagal Chail Janjehli Chhatri road km 0/00 to 82/00 (SH:-Removal of slip & land slides various Rds in km 73/00 to 80/00 & RR Damages on Janjehli Magrugalla road km 0/00 to 11/00 (SH:- Removal of slip & land slides various Rds in km 4/400 to 8/00).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	4180.27	Per Cubic metre	118.10	493690.00	Rupees Four Lakh Ninety Three Thousand Six Hundred & Ninety Only
				Total	493690.00	

Bill of Qty approved
for Rs. 4,93,690 only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: 96,000.00 Only
 Earnest Money: 2,000.00 Only
 Time : Two months.

Name of Work:- RR Damaged on various roads under Janjehli Sub Division (SH:- Hurring of Tipper for carriage of different material in various roads) Job No-II

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Hiring of Tipper for carriage / disposal of debris to dumping site of work with lift to suitable place with in all leads and lifts to the entire satisfaction of the Engineer -in Charge . The Tipper should work minimum 9.00 AM to 5.00 PM daily any loss to the public / private property or any accident etc . happened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases the fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor /owner. The daily log book will be maintained at site which should be duly verified by the Engineer in charge.	30.00	Per Day	3200.00	96,000.00	Rupees Ninety Six Thousand Only
Total:-					96,000.00	

Bill of Quantity approved
 for Rs. 96,000/only.


 Executive Engineer,
 HPPWD Division
 Saraj at Janjehli

BILL OF QUANTITY

Estimate Cost: 99,200.00 Only

Earnest Money: 2,000.00 Only

Time : Two months.

Name of Work:- RR Damaged on various roads under Janjehli Sub Division (SH:- Hurring of Tipper for carriage of different material in various roads) Job No-I

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Hiring of Tipper for carriage / disposal of debris to dumping site of work with lift to suitable place with in all leads and lifts to the entire satisfaction of the Engineer -in Charge . The Tipper should work minimum 9.00 AM to 5.00 PM daily any loss to the public / private property or any accident etc . happened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases the fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor /owner. The daily log book will be maintained at site which should be dully verified by the Engineer - in charge.	31.00	Per Day	3200.00	99,200.00	Rupees Ninety Nine Thousand Two Hundred Only
Total:-					99,200.00	

Bill of Quantity approved for

Rs. 99,200/- only

Executive Engineer,
HPPWD Division
Seraj at Janjehli

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 4,92,400 /- Only
Rs. 10,000/-Only
Two Months

Name of Work :- RR Damages on various road JE Section Bagachanogi under sub division Janjehli HP.PWD Janjehli (SH:- Removal of slips and land slides at various Rds in Dhawas Chhoadhar road km 0/00 to 2/500 & Shillibagi Deol Jainshla road km 0/00 to 10/00).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	4169.35	Per Cubic metre	118.10	492400.00	Rupees Four Lakh Ninety Two Thousand Four Hundred Only
				Total	492400.00	

Bill of Qty approved
for Rs. 4,92,400.00 only


Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: 2,30,888.00 Only

Earnest Money: 5,000.00 Only

Time : Two months.

Name of Work:- RR Damages on Mandi Gagal Chail Janjehli road KM 35/000 to 82/000 (SH:- (SH:- Construction of Unlined Drain and Maintenance of Earthen Shoulder in various KM 35/000 to 63/000)

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Construction of unlined surface drains of average cross-sectional area 0.30 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By Mechanical Means and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	2850.00	Per Running Meter	37.60	1,07,160.00	Rupees One Lakh(s) Seven Thousand One Hundred Sixty Only
2.00	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material /irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment upto any lead as per technical specification Clause 1903 and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	1755.00	Per Square Meter	70.50	1,23,728.00	Rupees One Lakh(s) Twenty Three Thousand Seven Hundred Twenty Eight Only
		Total:-			2,30,888.00	

Bill of Quantity approved for
Rs. 2,30,888/- only
Executive Engineer,
HPP & D Division
Seraj at Janjehli

BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 2,25,617 /- Only
Rs. 5,000/-Only
Two Months

Name of Work :- RR Damages on Link Bagla via Damedhi Khad (Perma ka Gharat) Village Thanar in G.P. Gudah km 0/00 to 2/400
(SH:-Removal of slip & land slides at various Rds in km 0/500 to 2/400).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1910.39	Per Cubic metre	118.10	225617.00	Rupees Two Lakh Twenty Five Thousand Six Hundred & Seventeen Only
				Total	225617.00	

Bill of Qty approved
for Rs. 2,25,617/- only


Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY						
Name of Work:- RR Damages on Thachadhar Naloti Balwar Kilan Dawada road in km 0/00 to 8/00 (SH:- Construction of Brast wall at Rds 6/380 to 6/405)					Estimated cost Rs	4,28,320.00
					Earnest Money Rs	9,000.00
					Time - Two Months	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	57.00	Per Cubic metre	552.35	31,484.00	Rupees Thirty One Thousand Four Hundred & Eighty Four Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	75.18	Per Cubic metre	5236.10	3,93,650.00	Rupees Three Lakh Ninety Three Thousand Six Hundred & Fifty Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.00	Each	398.30	3,186.00	Rupees Three Thousand One Hundred & Eighty Six Only
				Total	4,28,320.00	

bill of qty approved
 Rs. 4,28,320/only


Executive Engineer
 Seraj Division B&R
 HPPWD Janjehli

BILL OF QUANTITY

Estimate Cost: Rs. 2,99,632.00 Only
 Earnest Money: Rs. 6000.00 Only
 Time :- Two Months

Name of Work :- RR Damages on Thachadhar Naloti Balwar Kilan Dawada road in km 0/00 to 8/00 (SH:- Removal of slip in between km 7/000 to 8/000).

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2537.10	Per Cubic metre	118.10	299632.00	Rupees Two Lakh Ninety Nine Thousand Six Hundred & Thirty Two Only
				Total	299632.00	

Bill of Qty approved
 for Rs. 29,99,632/only

 Executive Engineer
 Seraj Division B&R
 HPPWD Janjehli


BILL OF QUANTITY						
Name of Work:-RR Damages on Bagsaid Thunag via Raingaloo road km 0/00 to 9/500 (SH:-Construction of Embankment at Rds 0/675 to 0/750 & Unlined surface Drain at various rd's).					Estimated cost Rs. - 2,90,630.00	
					Earnest Money cost Rs. - 6,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 mtr, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 mtr as per Technical specification clause 301.5 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	460.35	Per Cubic metre	204.15	93980.00	Rupees Ninety Three Thousand Nine Hundred & Eighty Only
2	Construction of Unlined surface drains of average cross-section area .020sqm in soil to specified lines, grades, levels and dimensions. Excavated material to e used in embankmet with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307. By mechanical Means as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	7125.00	Per Running metre	27.60	196650.00	Rupees One Lakh Ninety Six Thousand Six Hundred & Fifty Only
				Total	290630.00	

Bill of Qty approved
for Rs. 2,90,630/only

Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY						
Name of Work:- RR Damages on various road under Janjehli Sub- Division (SH:- Construction of Unlined surface drain & maintenance of earthen shoulder at various Rds in various road under BagachanogI Section).					Estimated cost Rs. - 99,594.00	
					Earnest Money cost Rs. - 2,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of Unlined surface drains of average cross -section area .020sqm in soil to specified lines, grades, levels and dimensions. Excavated material to e used in embankmet with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307. By mechanical Means as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1800.00	Per Running metre	27.60	49680.00	Rupees Fourty Nine Thousand Six Hundred & Eighty Only
2	Maintenance of Earthen shouder (filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 mtr as per technical specification clause 1903including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	708.00	Per Sqm	70.50	49914.00	Rupees Fourty Nine Thousand Nine Hundred & Fourteen Only
				Total	99594.00	

Bill of Qty approved
 for Rs. 99,594.00 only

 Executive Engineer
 Seraj Division B&R
 HPPWD Janjehli


BILL OF QUANTITY

Estimate Cost:
Earnest Money:
Time :-

Rs. 97,781 /- Only
Rs. 2,000/-Only
Two Months

Name of Work :- SDF/2024/60,R/O(Repair and Maintenance of Kainchi Mod Majhwal road km 0/00 to 1/500 (SH:- Removal of slips and land slides at various Rds in km 0/000 to 1/500)

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto any lead as per technical specification 302.35 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	827.95	Per Cubic metre	118.10	97781.00	Rupees Ninety Seven Thousand Seven Hundred & Eighty One Only
				Total	97781.00	

Bill of Qty approved
for Rs. 97,781.00 only
[Signature]
Executive Engineer
Seraj Division B&R
HPPWD Janjehli

BILL OF QUANTITY						
Name of Work:- RR Damages on Gohar to Kandha road km 0/00 to 16/00 (SH:- Construction of Brast wall in wire crate at Rds 14/420 to 14/440.50)					Estimated cost Rs. - 4,94,416.00	
					Earnest Money cost Rs. - 10,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	48.59	Per Cubic metre	552.35	26839.00	Rupees Twenty Six Thousand Eight Hundred & Thirty Nine Only
3	Random rubble Stone masonry in cement mortar 1:6 (one cement : six sand) for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	40.34	Per Cubic metre	5558.90	224246.00	Rupees Two Lakh Twenty Four Thousand Two Hundred & Fourty
6	Construction of dry rubble masonry for retaining walls , breast walls , revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clauses 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	35.86	Per Cubic metre	3980.50	142741.00	Rupees One Lakh Fourty Two Thousand Seven Hundred & Fourty One Only
7	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS : 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	32.03	Per Cubic metre	3140.50	100590.00	Rupees One Lakh Five Hundred & Ninety Only
				Total	494416.00	

Bill of Qty approved
to Rs. 4,94,416/- only

Executive Engineer
Sera Division B&R
HPPWD Janjehli

32

Estimate Cost: 4,10,249.00 Only
 Earnest Money: 10,000.00 Only
 Time :Two months

Name of Work :- RRD on Janjehli Magarugala Chhatri road KM 0/000 to 11/200 (SH:- Construction of Retaining wall at RD 8/165 to 8/180) Under PDNA

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	19.65	Per Cubic metre	552.35	10,854.00	Rupees Ten Thousand Eight Hundred Fifty Four Only
2.00	Providing and laying mechanically mixed and vibrated cement concrete 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40 mm (twenty millimeter) size for plain / reinforced concrete in open foundation complete including form work as per drawings and technical specification clause 802,803,1202 & 1203 and curing complete including carriage of materials with in all leads and lifts as per the direction of Engineer -in-Charge.	22.50	Per Cubic Meter	6,085.00	1,36,913.00	Rupees One Lakh(s) Eighty Seven Thousand Two Hundred Ninety Six Only
3.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G.I wire conforming to I.S.280 and I.S. 4826 in 100mm x 100 (one hundred in to one hundred millimeters) in much (woven diagonally) including 10% extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads ,lifts of material and technical specification clause 1301. within all leads ,lifts and carriage of materials and other incidentals .	70.35	Per Cubic Meter	3,140.50	2,20,934.00	Rupees Two Lakh(s) Twenty Thousand Nine Hundred Thirty Four Only
4.00	Back filling with granular material behind abutment , wing wall and return wall complete as per drawings and technical specification clauses 1206.3 and 1604.7 complete including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	31.80	Per Cubic metre	1,306.55	41,548.00	Rupees Forty One Thousand Five Hundred Forty Eight Only
			Total:-		4,10,249.00	

Bill of Qty approved
 for Rs. 4,10,249/only

Executive Engineer
 H.P.P.W.D. Division
 Seraj at Janjehli

BILL OF QUANTITY

Name of Work:- RR Damages on Mandi Gagal Chail Janjehli Chhatri road km 0/000 to 82/000 (SH:-Construction of Retaining wall at RD 68/311 to 68/324)					Estimated cost Rs. - 4,74,367.00	
					Earnest Money cost Rs. - 9,500.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filing the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	35.25	Per Cubic metre	552.35	19470.00	Rupees Nineteen Thousand Four Hundred & Seventy Only
2	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	81.81	Per Cubic metre	5236.10	428365.00	Rupees Four Lakh Twenty Eight Thousand Three Hundred & Sixty Five Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.00	Each	398.30	7169.00	Rupees Seven Thousand One Hundred & Sixty Nine Only
4	Back filling behind abutment, wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	14.82	Per Cubic metre	1306.55	19363.00	Rupees Nineteen Thousand Three Hundred & Sixty Three Only
				Total	474367.00	

Bill of Qty approved
for Rs. 4,74,367.00 only

[Signature]
Executive Engineer,
HPPWD Division
Seraj at Janjehli

BILL OF QUANTITY

Estimate Cost: Rs 4,03,150.00 Only
 Earnest Money: 8,200.00 Only
 Time :- Two Months

Name of Work :- RR Damages on Nagan Chhatri road in km 19/00 to 22/00 (SH:- Construction of Retaining wall at Rds in km 17/847 to 17/857.30)
 UNDER PDNA

S. No.	Sub Head and item of work	Qty.	Unit	Estimated Rate (In Rs)	Total Amount with all Taxes including GST in Rs. P	Total Amount with all Taxes including GST in Word
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	24.21	per Cubic metre	552.35	13372.00	Rupees Thirteen Thousand Three Hundred Seventy Two Only
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C. nominal mix 1: 3: 6 (one cement : three sand :six graded stone aggregate 20mm (twenty millimeter) within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	60.95	per Cubic metre	6085.00	370881.00	Rupees Three Lakh(s) Seventy Thousand Eight Hundred Eighty One Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	15.00	Each	398.30	5975.00	Rupees Five Thousand Nine Hundred Seventy Five Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	9.89	per Cubic metre	1306.55	12922.00	Rupees Twelve Thousand Nine Hundred Twenty Two Only
			Total		4,03,150.00	

Bill of Qty approved
 Rs - 4,03,150/- only
 Executive Engineer
 Seraj Division (B&R)
 HPPWD, Janjehli

35

BILL OF QUANTITY						
Name of Work:- RR Damages on Katyandi Tandi Thunag road km 0/00 to 6/525 (SH:- Construction L- shape Drain in km 2/090 to 2/400 ,2/570 to 2/680 7, Retaining wall with T/wall in PCC 1:4:8 at Rd 2/300 to 2/306)					Estimated cost Rs. - 4,99,405.00	
					Earnest Money cost Rs. - 10,000.00	
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious material of disposal any lead and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil including carriage of material within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge. .	55.06	Per Cubic metre	552.35	30412.00	Rupees Thirty Thousand Four Hundred & Twelve Only
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C. nominal mix 1: 3: 6 (one cement : three sand : six graded stone aggregate 40mm (Forty millimeter) within all leads and lifts and other incidental and as per the direction of the Engineer-in-Charge.	32.51	Per Cubic metre	6085.00	197823.00	Rupees One Lakh Ninety Seven Thousand Eight Hundred & Twenty Three Only
3	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregate and curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	17.28	Per Cubic metre	5236.10	90480.00	Rupees Ninety Thousand Four Hundred & Eighty Only
4	Random rubble Stone masonry in cement mortar 1:6 (one cement : six sand) for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.33	Per Cubic metre	5558.90	101895.00	Rupees One Lakh One Thousand Eight Hundred & Ninety Five Only
5	Construction of dry rubble masonry for retaining walls , breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clauses 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	17.68	Per Cubic metre	3980.50	70375.00	Rupees Seventy Thousand Three Hundred & Seventy Five Only
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	4.92	Per Cubic metre	1306.55	6428.00	Rupees Six Thousand Four Hundred & Twenty Eight Only

7	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.00	Each	398.30	1992.00	Rupees One Thousand Nine Hundred & Ninety Two Only
				Total	499405.00	

Bill of qty approved for
Rs. 9,99,405/- only

[Signature]
Executive Engineer
Seraj Division B&R
HRPWD Janjehli

36

BILL OF QUANTITY

Estimate Cost: 4,51,937.00 Only

Earnest Money: 10,000.00 Only

Time :Two months

Name of Work :- RRD on Bhanthal Sanarali Shankardehra road Raigarh road KM 0/000 to 14/000 (SH:- Construction of Retaining wall at RD 8/410 to 8/422) Under PDNA

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	47.52	Per Cubic metre	552.35	26,248.00	Rupees Twenty Six Thousand Two Hundred Forty Eight Only
2.00	Providing and laying Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain / reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203 including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	8.64	Per Cubic metre	4,697.60	40,587.00	Rupees Forty Thousand Five Hundred Eighty Seven Only
3.00	Random rubble masonry work in cement mortar 1:6 (one cement : six sand)in foundation complete as per drawing and technical specification Clauses 702,704, 1202 & 1203. complete including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	32.68	Per Cubic metre	5,558.90	1,81,665.00	Rupees One Lakh(s) Eighty One Thousand Six Hundred Sixty Five Only
4.00	Providing and laying plain concrete 1:4:8(1 cement : 4 sand :8 graded stone aggregate 40mm nominal size) in open foundation complete as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	5.28	Per Cubic metre	5,236.10	27,647.00	Rupees Twenty Seven Thousand Six Hundred Forty Seven Only
5.00	Construction of dry rubble masonry for retaining walls , breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5. including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	41.76	Per Cubic metre	3,980.50	1,66,226.00	Rupees One Lakh(s) Sixty Six Thousand Two Hundred Twenty Six Only
6.00	Back filling with granular material behind abutment , wing wall and return wall complete as per drawings and technical specification clauses 1206.3 and 1604.7 complete including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	7.32	Per Cubic metre	1,306.55	9,564.00	Rupees Nine Thousand Five Hundred Sixty Four Only
Total:-					4,51,937.00	

Bill of Qty approved
for Rs. 4,51,937/only

Executive Engineer
H.P.W.D. Division
Seraj at Janjehti

310

37

BILL OF QUANTITY

Estimate Cost: 491,817.00 Only

Earnest 10,000.00 Only

Time : Two months.

Name of Work:- RR Damages on Lower Bhiyand to Upper Bhiyand road KM 0/000 to 2/500. (SH:- Removal of slips & Land slide in various Rd's in km. 0/000 to 2/000). Under MPLAD

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead as per technical specification 302.3.5 and 1611. and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental charges.	4164.41	Cum	118.10	491,817.00	Rupees Four Lakh(s) Ninety One Thousand Eight Hundred Seventeen Only
		Total:-			491,817.00	

Bill of Quantity approved
for Rs. 4,91,817 / only


Executive Engineer
HPPWD
Seraj at Janjehi

BILL OF QUANTITY

Estimate Cost: 467,247.00 Only
Earnest Money: 8,000.00 Only
Time : Two months

38

Name of Work :- Restoration and Rain Damaged on Parala to Mandap road KM 0/00 to 3/900. (SH:- Construction of Retaining wall with Toe wall in PCC 1:4:8 at Rd. 2/008 to 2/018).

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	33.70	Per Cubic metre	552.35	18,614.00	Rupees Eighteen Thousand Six Hundred Fourteen Only
2.00	Providing and laying plain concrete 1:4:8(1 cement : 4 sand :8 graded stone aggregate 25mm nominal size) in open foundation complete as per drawings and technical specification including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	28.80	Per Cubic metre	5,236.10	150,800.00	Rupees One Lakh(s) Fifty Thousand Eight Hundred Only
3.00	Random rubble masonry work in cement mortar 1:6 (one cement : six sand)in foundation complete as per drawing and technical specification Clauses 702,704, 1202 & 1203. complete including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	28.02	Per Cubic metre	5,558.90	155,760.00	Rupees One Lakh(s) Fifty Five Thousand Seven Hundred Sixty Only
4.00	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification Clauses 704.6 & 1302.5. including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	32.00	Per Cubic metre	3,980.50	127,376.00	Rupees One Lakh(s) Twenty Seven Thousand Three Hundred Seventy Six Only
5.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification clauses 1206.3 and 1604.7 complete including carriage of material within all leads and lifts and other incidentals and as per directions of Engineer-in-charge.	8.20	Per Cubic metre	1,306.55	10,714.00	Rupees Ten Thousand Seven Hundred Fourteen Only
6.00	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 within all leads , lifts and carriage of materials and other incidentals.	10.00	Each	398.30	3,983.00	Rupees Three Thousand Nine Hundred Eighty Three Only
			Total:-		467,247.00	

Bill of Quantity approved for
R. 4,67,247 / only

Executive Engineer
HPPWD Division
Seraj at Janjehi