



Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur, Distt. Kangra (H.P)-176206
e-mail id: ce-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Scaled percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **28-04-2026 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **27-04-2026 up to 4:30 P.M** and the application for issue of tender form shall be received on **25-04-2026 up to 12:00 Noon.**

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1.	Repair of Ayushman Arogya Mandir, sub Health centre Dodhamb in Tehsil Shahpur Distt Kangra (H.P). (Deposit Work). (SH:- Dismantling roofing, trusses, purlins and Steel work).	90238.00	2000.00	Two Month	350/-
2.	Up gradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No:- HP-04-435 in Distt. Kangra (HP) (SH:- Providing and laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line km 3/701/4/400)	99051.00	2000.00	One Month	350/-
3.	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Back & Ridge of main roof, Dormer, Porch & Back side stair Roof)	99434.00	2,000.00	One Month	350/-
4.	Up gradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No:- HP-04-435 in Distt. Kangra (HP) (SH:- Providing and laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line km 4/401 to 5/100)	99051.00	2000.00	One Month	350/-
5.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 18/00 to 18/400).	98,904.00	2,000.00	One Month	350/-
6.	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Dormer (1 st) (2 nd) & Porch)	99963.00	2,000.00	One Month	350/-
7.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 21/00 to 21/500).	98,649.00	2,000.00	One Month	350/-
8.	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Front side)	99897.00	2,000.00	One Month	350/-
9.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 23/00 to 24/00).	98,190.00	2,000.00	One Month	350/-
10.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 24/00 to 25/00).	98,461.00	2,000.00	One Month	350/-

11.	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- Dismantling of Roofing , Ceiling & P/F 6mm Thick Cement fiber Board Ceiling)	99960.00	2,000.00	One Month	350/-
12.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 21/500 to 22/00).	98,888.00	2,000.00	One Month	350/-
13.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 18/400 to 19/00).	99,068.00	2,000.00	One Month	350/-
14.	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 19/00 to 20/00).	99232.00	2,000.00	One Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GS No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 20/04/26

No.PWD/SD/Tender/NIT/2026-27/- 689 - 89

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. Notice Board

Executive Engineer
Shahpur Division
HP.PWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST : - ₹ 90238.00
 EARNEST MONEY : - ₹ 2000.00
 TIME LIMIT : - Two Months

NAME OF WORK :- Repair of Ayushman Arogya Mandir, Sub Health centre Dodhamb in Tehsil Shahpur Dist Kangra (H.P.). (Deposit Work).

SUB-HEAD :- Dismantling roofing,trusses, purlins and Steel work.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50. including stacking of useful materials near the site and disposal of unserviceable materials within all lead and lift and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	3	69 80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	5785.00
2	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead of Sectional Area Below 40 Square centimetres. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	97.20	12.50	Rupees Twelve And Paise Fifty Only	Per square metre	1215.00
3	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, complete as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	765.00	107.50	Rupees One Hundred Seven And Paise Fifty Only	Per Kilogram	82238.00
Total:-						90238.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99051.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- Upgradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No: HP-04-435 in Distt Kangra (H.P.)
SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 3/701 to 4/400.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of hot applied thermoplastic compound 2.5mm (Two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two decimal five millimetres) is exclusive of surface applied glass beads as per IRC-35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	144.60	685.00	Rupees Six Hundred Eighty Five Only	Per Square metre	99051.00
TOTAL :-						99051.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :-

₹ 99434.00

EARNEST MONEY :-

₹ 2000.00

TIME LIMIT :-

One Month


NAME OF WORK :-

Repair of Primary Health Centre at Lapiana Under Health Block Shahpur, District Kangra)

SUB-HEAD :-

P/F 0.60mm Thick Prepainted Sheet Roofing Front side & Ridge of Main Roof, Dormer, Porch & Back Side Stair Roof.

Sr. No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks, bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3	41.50	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	68479.00	
2	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty millimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.40	850.40	Rupees Eight Hundred Fifty And Paise Forty Only	Per running metre	30955.00	
		TOTAL :-					99434.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					


 Executive Engineer,
 Shahpur Division,


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99051.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- Upgradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No: HP-04-435 in Distt Kangra (H.P.)

SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 4/401 to 5/100.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of hot applied thermoplastic compound 2.5mm (two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two decimal five millimetres) is exclusive of surface applied glass beads as per IRC-35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	144.60	685.00	Rupees Six Hundred Eighty Five Only	Per Square metre	99051.00
TOTAL :-						99051.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer
 Shahpur Division,
 HPPWD Shahpur

9

18

14

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 98904.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: One Month

5

23

NAME OF WORK :- A/R and M/O Ranktal:32 mile Kotla road km 18/00 to 24/00. (Under NMSRRY 2025-26)
 SUB-HEAD :- Repair of Pot Hole / patch work between km 18/00 to 18/400).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	196.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	27773.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five Kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	223.40	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5027.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ the binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	223.40	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	66104.00
TOTAL :-		0				98904.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


20

51 (6)

ESTIMATED COST :- ₹ 99963.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)
SUB-HEAD :- P/F 0.60mm Thick Pre-painted Sheet Roofing Dormer (1st),(2nd) & Porch

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount	
			In fig	In words			
1	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick pre-painted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with pre-painted iron J or L hooks, bolts and nuts with pre-painted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government	60.58	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	99963.00	
TOTAL :-						99963.00	
		Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)	
		Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)	


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98649.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Rental 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 21/00 to 21/500).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	25.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3543.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	298.70	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6721.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/ per ten square meter aggregates using penetration grade bitumen @ 10% binders content @ 22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	298.70	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88385.00
TOTAL :-						98649.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shajpur Division,
 HPPWD Shajpur

7

214

SCHEDULE OF QUANTITY


21

ESTIMATED COST :- ₹ 99897.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Repair of Primary Health Centre at Lapiana Under Health Block Shahpur, District Kangra)

SUB-HEAD :- P/F 0.60mm Thick Prepainted Sheet Roofing Front side

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks, bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.54	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	99897.00
TOTAL :-						99897.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98190.00
 EARNEST MONEY :- ₹ 20000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotha road km 18/00 to 26/600. (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 23/00 to 24/00).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface/damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	27.25	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3861.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	296.26	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6666.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20 mm-thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	296.26	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87663.00
TOTAL :-						98190.00


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98461.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26)
 SUB-HEAD :- Repair of Pot Hole / patch work between km 24/00 to 25/00).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	23.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3259.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6728.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @ 0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ the binders content @ 22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88474.00
TOTAL :-						98461.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99960.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Repair of Primary Health Centre at Lapiana Under Health Block Shahpur, District Kangra)
SUB-HEAD :- P/F 6mm Thick Cement fiber Board Ceiling, Steel Work & Back Side Stair Roofing.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and fixing 6 mm thick plain multipurpose cement fibre board with suitable screws for cement particle board in ceiling etc complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3	810.00	Rupees Eight Hundred Ten Only	Per square metre	73224.00
2	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	152.00	107.50	Rupees One Hundred Seven And Paise Fifty Only	Per Kilogramme	16340.00
3	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks, bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.30	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	10396.00
TOTAL :-						99960.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur.

SCHEDULE OF QUANTITY


12

27

ESTIMATED COST :- ₹ 98888.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).
 SUB-HEAD :- Repair of Pot Hole / patch work between km 21/500 to 22/00).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	8077.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.21	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6417.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0.2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.21	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	84394.00
TOTAL :-						98888.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99068.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 19/00 to 20/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	36.50	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	5172.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.90	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6635.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer In Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.90	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87261.00
TOTAL :-						99068.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				


Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99232.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranitala 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).
 SUBHEAD :- Repair of Pot Hole / patch work between km 18/400 to 19/00.

Sl. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	425.10
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	267.60	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5999.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 KN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	267.60	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79183.00
TOTAL :-						99232.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur