



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- cc-sol-hp@nic.com

No.PW-SD/CB-Tender/-2025-26-

19606-10

Dated:- 28

03
26

To

The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer,
B&R Division,
HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Exigency

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:


Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	04.04.2026	Upto 3.00 P.M.
2	The last date sale of tender forms.	06.04.2026	Upto 4.00 P.M.
3	The date for receipt of tender forms.	07.04.2025	Upto 10.30 P.M.
4	The date of opening of tender	07.04.2026	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 07.04.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from the office of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost Form
1	Repair and maintenance of Rest House Building at HPPWD, sub-division at Kandaghat (SH: Providing and fixing wood work, painting work, water supply and sanitary fittings etc.)	499969/-	10000/-	Two Month	Rs.350
2	Repair and maintenance of Assistant Engineer's office at HPPWD sub-division Kandaghat Distt. Solan (SH: Providing and fixing cup board s and outer side paint etc.)	499969/- 4969361/-	10000/-	Two Month	Rs.350
3.	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain in Chhausha section)	488250/-	9800/-	One Month	Rs.350
4	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain in Mamligh section)	491400/-	9900/-	One Month	Rs.350
5	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain in Mamligh section) (Kufu region)	493500/-	9900/-	One Month	Rs.350
6	Repair and maintenance of EE residence of officer colony at Kotla Nallah at Solan (SH: Painting distempering and sanitary fittings etc.)	369609/-	7500/-	Two Month	Rs.350

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.



 Executive Engineer
 B&R Division
 HPPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No.PW-SD/CB-Tender/20025-26- **19606-10** Dated: **28/3/26** are of emergent nature of work and in public interest the as per the provision at Sr. No. 5(I to IV) of Govt. Notification No PBW(B) A(3)1/2020 dated 27.05.2021.

Dated:-

Place:- Solan


Executive Engineer
B&R Division
HPPWD, Solan

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in words	Amount
				Figures	
				Estimated Cost:-	499969.00
				Earnest Money:-	10000.00
				Time limit :-	Two Months

Job No. : 11

Name of work :- Repair and maintenance of Rest House Building at HPPWD Sub Division at Kandaghat (SH:- Providing and fixing wood work, Painting work, water supply and sanitary fitting etc.)

1	Providing and fixing 19 mm thick commercial board water proof shutter for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of material in all leads and lifts, including all incidental charges.	5.61	Per Square Meter	1350.00 Rupees Thousand Three Hundred Fifty Only	7574.00
2	Providing and fixing 19 mm thick commercial board water proof in shelves, lining, box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lifts, including all incidental charges.	5.04	Per Square Meter	1425.00 Rupees Thousand Four Hundred Twenty Five Only	7182.00
3	Providing and fixing 6 mm (six millimeter) thick water proof ply wood lining with butt jointing and nails (frame work and cover fillets to be measured and paid for separately) as per H.P. PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	5.04	Per Square Meter	600.00 Rupees Hundred Only	3024.00
4	Providing and fixing 100mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	31.26	Per Square Meter	850.00 Rupees Hundred Fifty Only	26571.00
5	Providing and fixing 125 mm (One hundred twenty five) millimeters size aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc complete as per HP.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	250.00 Rupees Hundred Fifty Only	500.00
6	Providing and fixing Triple strip vertical type magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	4.00	Each	39.05 Rupees Thirty Nine and Paise Five Only	156.00
7	Providing and fixing 30 mm bright finished brass cup board or wardrobe knob of approved quality with necessary screws as per HP.PWD) specification including carriage of all labour equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	2.00	Each	950 Rupees Nine Hundred Fifty Only	1900.00
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. Complete as per HP.PWD. Specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	72.20 Rupees Seventy Two and Paise Twenty Only	144.00
8.1	150*10 (One hundred fifty into Ten millimeters)				
9	Providing and fixing square edge cover fillets (beadings) in hard wood (90*90) Section into Six millimeters including mitring at joints with wood screws and mull complete as per condition of the Engineer-in-Charge and HP.PWD Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	52.00	Per Running meter	110.00 Rupees One Hundred Ten Only	5720.00

10	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor level. Masonry work (first sort), incementmortar 1:6 (1 cement : 6 coarse sand) and H.P.P.W.D. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.16	Per Cubic Meter	6550.90	Rupees Thousand Five Hundred Fifty and Paise Ninety Only	Six	14150.00
11	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	4.32	Per Square meter	774.05	Rupees Hundred Seventy Four and Paise Five Only	Seven	3344.00
12	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer in Charge and as per HP.P.W.D. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	374.00	Per Square Meter	8.50	Rupees Eight and Paise Fifty Only		3179.00
13	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.P.W.D. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	374.00	Per Square Meter	85.10	Rupees Eighty Five and Paise Ten Only		31827.00
14	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacturer as per HP.P.W.D. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	101.46	Per square meter.	94.30	Rupees Ninety Four and Paise Thirty Only		9568.00
15	Finishing walls with textured exterior paint of required shade. New work Two or more coats applied 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm as per HP.P.W.D. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	220.61	Per Square Meter	196.05	Rupees Hundred Ninety Six and Paise Five Only	One	43251.00
16	Distemping with oil bound washable distemper of approved brand and manufacturer to give an even shade. New work (two or more coats) over and including water thinnable priming coat with cement primer complete as per direction of Engineer in Charge and as per HP.P.W.D. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	374.00	Per Square Meter	96.85	Rupees Ninety Six and Paise Eighty Five Only		36222.00
17	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacturer as per HP.P.W.D. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	86.43	Per Square Meter	106.25	Rupees Hundred Six and Paise Twenty Five Only	One	9183.00
18	Dismantling of flushing cistern of all types (C.I./PVC/iron/China) including stacking of useful materials near the site and disposal of un serviceable materials within 50 metres lead and lift, including all incidental charges.	7.00	Each	421.85	Rupees Hundred Twenty One and Paise Eighty Five Only	Four	2953.00
19	Providing and fixing White Vitreous China Wash-basin size 550x400 mm with C.I. brackets, 15 mm dia CP Brass single hole-basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required as per HP.P.W.D. specification including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Each	3972.55	Rupees Thousand Hundred Seventy Two and Paise Five Only	Three	11918.00

20	Providing and fixing 32 mm (thirty two millimeters) dia P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	3.00	Each	87.70	Rupees Eighty Seven and Paise Seventy Only	263.00
21	Providing and fixing 100 mm sand cast Iron grating for gully trap as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	3.00	Each	44.60	Rupees Forty Four and Paise Sixty Only	134.00
22	Providing and fixing 600mmx450mm (six hundred into four hundred fifty millimeter) beveled edge mirror of superior glass mounted on 6mm(six millimeters) thick A.C. sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Each	1009.90	Rupees Thousand Nine and Paise Ninety Only	3030.00
23	Providing and fixing 600x120x5 mm (six hundred into one hundred twenty into five millimeter) Acrylic Shelf with C.P. Brass bracket and guard rail complete, with 40 mm long screws, rawl plugs etc or equivalent as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	3.00	Each	2000.00	Rupees Thousand Only	6000.00
24	Providing and fixing vitreous china wash, down water closet (European type W.C pan) with Integral P or S trap including jointing the trap including jointing the trap with soil pipe in cement mortar 1:1 (One Cement: one sand) seat and cover to be paid for separately as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	7.00	Each	19267.00	Rupees Nineteen Thousand Two Hundred Sixty Seven Only	134869.00
25	Providing and fixing 8 mm dia C.P./S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Each	297.55	Rupees Two Hundred Ninety Seven and Paise Fifty Five Only	892.65
26	Providing and fixing 15 mm nominal dia CP Brass Single lever telephonic wall mixer of quality & make as approved by Engineer in charge	3.00	Each	6113.60	Rupees Six Thousand One Hundred Thirteen and Paise Sixty Only	18341.00
27	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm or 340x410x265 mm sizes respectively.	3.00	Each	1045.95	Rupees One Thousand Forty Five and Paise Ninety Five Only	3138.00
28	Providing and fixing toilet paper holder C.P. brass as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charge	3.000	Each	479.75	Rupees Four Hundred Seventy Nine and Paise Seventy Five Only	1439.00
29	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour weighing not less than 88 gms.	2.00	Each	950.00	Rupees Nine Hundred Fifty Only	1900.00
30	Providing and fixing 600 mm long Guard rail with total length of 645 mm, width 75 mm and effective height of 88 mm, weighing not less than 190 gms- PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Each	1500.00	Rupees One Thousand Five Hundred Only	4500.00

	Providing and fixing Acrylic soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with sealed firing arrangements, weighing not less than 06 gms as per HP.PWD specification including carriage of labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	6.000	Each	940.00	Rupees Hundred Forty Only	Nine	5640.00
	Providing and fixing Stainless steel Kitchen sink with drain board 610 x 510mm with bowl depth 200 mm as per PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	3261.05	Rupees Thousand Hundred Sixty One and Paise Five Only	Three Two	6522.00
	Providing and fixing uplasticised PVC connection pipe 45 cm length 15 mm nominal bore with brass unions as per PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	8.00	Each	83.00	Rupees Three Only	Eighty	664.00
	Providing and fixing Exhaust fan of ULTINO - PRO Supper Delux 8 inch (200)mm exhaust fan for kitchen, through with strong Air Suction, Rust proof body and dust protection shutter 5 years as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	4000.00	Rupees Thousand Only	Four	8000.00
	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms as per HP.PWD specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	8.00	Each	618.80	Rupees Hundred Eighteen and Paise Eighty Only	Six	4950.00
	Providing and fixing 15 mm (fifteen millimeters) nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	10.00	Each	532.00	Rupees Hundred Two Only	Five Thirty	5320.00
	Providing and placing on terrace (at all floor levels) 1000 litre Capacity polyethylene water storage tank, IS - 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2500.00	Per Liter	8.80	Rupees Eight and Paise Eighty Only		22000.00
8	Providing and fixing Ceiling fan of Usha/ Bajaj/ Havells brand including all lead and lift through all mode of transportation.	2.00	Each	12500.00	Rupees Thousand Hundred Only	Twelve Five	25000.00
39	Providing and fixing water heater Gyser of capacity 20litrs. including all lead and lift through all mode of transportation.	2.00	Each	11000.00	Rupees Thousand Only	Eleven	22000.00
40	Providing and fixing instant water heater Gyser of capacity 5 litrs. including all lead and lift through all mode of transportation.	2.00	Each	3500.00	Rupees Thousand Hundred Only	Three Five	7000.00
	Total:-						499969.00
	Quoted Percentage rate upto Three Digits :-		(+) / (-)				
	Rupees Four Lakhs Ninety Nine Thousand Nine Hundred Sixty Nine Only						

T.S. No. 319 for the 2025-26
Sl. No. 518 for the year 2025-26

Executive Engineer
B&R Division, H.P.PWD, Solan.

Schedule of Quantity

Job No. 29

Name of work :- Repair and maintenance of Assistant Engineer's Office at HPPWD Sub Division Kandaghat Distt. Solan (SH.- Providing and fixing cup boards and outer side paint etc.)

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Estimated Cost:-		496936.00
				Earnest Money:-		10000.00
				Time limit :-		Two Months
1	Providing and fixing 19 mm thick commercial board water proof shutter for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of material in all leads and lifts, including all incidental charges.	43.00	Per Square Meter	1350.00	Rupees One Thousand Three Hundred Fifty Only	58050.00
2	Providing and fixing 19 mm thick commercial board water proof in shelves, lining, box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lifts, including all incidental charges.	107.37	Per Square Meter	1425.00	Rupees One Thousand Four Hundred Twenty Five Only	153002.00
3	Providing and fixing 9mm thick ply wood in panelling/ lining/ ceiling fixing with nails or screws etc. complete including carriage of all lateral with in all leads and lifts as per the direction of Engineer-in-charge.	56.00	Per Square Meter	1017.00	Rupees One Thousand Seventeen Only	56952.00
4	Providing and fixing 12mm thick imported pine wood ceiling/ panelling with tongued and grooved jointing of standard quality ISI mark and approved shade and color complete i/c carriage of material within all leads and lifts.	56.00	Per Square Meter	1787.00	Rupees One Thousand Seven Hundred Eighty Seven Only	100072.00
5	Providing and fixing 6 mm (six millimeter) thick water proof ply wood lining with butt jointing and nails (frame work and cove filets to be measured and paid for separately) as per H.P. PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	40.39	Per Square Meter	600.00	Rupees Hundred Only	24234.00
6	Providing and fixing 1.00mm thick coloured or plain lamination sheet (summita) on boards/ply wood sheets with approved adhesive and nails etc complete as per HP PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	52.41	Per Square Meter	850.00	Rupees Eight Hundred Fifty Only	44549.00
7	Providing and fixing chromium plated brass handles with necessary screws etc. complete:	22.00	Each	223.95	Rupees Two Hundred Twenty Three and Paise Ninety Five Only	4927.00
7.1	125 mm		Each	196.75	Rupees One Hundred Ninety Six and Paise Seventy Five Only	11018.00
7.2	100 mm		Each	39.05	Rupees Thirty Nine and Paise Five Only	3163.00
8	Providing and fixing magnetic material of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	81.00	Each			

9	Providing and fixing Size 75 mm special quality chromium plated brass cup board locks with six levers of approved quality including necessary screws etc. complete.	24.00	Each	278.55	Rupees Two Hundred and Seventy Eight and Paise Fifty Five Only	6685.00
10	Providing and fixing aluminium 150*10 (One hundred fifty into Ten millimeters) tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. Complete as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	20.000	Each	72.20	Rupees Seventy Two and Paise Twenty Only	1444.00
11	Providing and fixing square edge cover fillets (beading) in hard wood 19*6 (Nineteen into Six) millimeters including mitering at junctions with wood screws and nails complete as per direction of the Engineer-in-Charge and H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	198.50	Per Running meter	110.00	Rupees One Hundred Ten Only	21835.00
12	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	116.70	Per square meter.	94.30	Rupees Ninety Four and Paise Thirty Only	11005.00
Total:-						496936.00
Rupees Forty Four Thousand Five Hundred Forty Nine Only						
Quoted Percentage rate upto Three Digits :-						

T/S No. for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

3

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 4,88,250.00
EARNEST MONEY ₹ 9,800.00
TIME ALLOWED One Months

Name of Work :- Restoration of rain damages on various roads under Kandaghat Sub Division (SH :- Hiring of Excavator cum loader for removal of debris, slips, clearance of unlined drain in Chhausha Section)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow, removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator, POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	465.00	1050.00	Rupees One Thousand Fifty Only	Rupees per Hour	488250.00
TOTAL						Rs. 488250.00
Total in Words :-		Rupees Four Lakhs Eighty Eight Thousand Two Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

Sr. No. 5/3 for the year 2025-26

Executive Engineer
B&R HPPWD Division
Solani

24

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 4,91,400.00
EARNEST MONEY ₹ 9,900.00
TIME ALLOWED One Month

Name of Work :- Restoration of rain damages on various roads under Kandaghat Sub Division (SH :- Hiring of Excavator Cum Loader for removal of debris, slips, clearance of unlined drain in Manligh Section)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow, removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator. POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	468.00	1050.00	Rupees One Thousand Fifty Only	Rupees per Hour	491400.00
TOTAL						Rs. 491400.00
Total in Words :-		Rupees Four Lakhs Ninety One Thousand Four Hundred Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

Sr. No. 514 for the year 2025-26

Executive Engineer
B&R HPPWD Division
Solani

5

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 4,93,500.00
EARNEST MONEY ₹ 9,900.00
TIME ALLOWED One Month

Name of Work :- Restoration of rain damages on various roads under Kandaghat Sub Division (SH :- Hiring of Excavator Cum Loader for removal of debris, slips, clearance of unlined drain in Manligh Section) (Kufthu region)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator, POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	470.00	1650.00	Rupees One Thousand Fifty Only	Rupees per Hour	493500.00
TOTAL						Rs. 493500.00
Total in Words :-		Rupees Four Lakhs Ninety Three Thousand Five Hundred Only				
Quoted Percentage rate upto Three Digits :-		(+)/(-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

Sr. No. S/5 for the year 2025-26

Executive Engineer
B&R HPPWD Division
Solani

Schedule of Quantity

Sr. No.	Description of work.	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (2)				Estimated Cost :-		369609.00
				Earnest Money :-		7500.00
				Time limit :-		Two Months

Name of work :- Repair and maintenance of EEE Residence of Officer colony Kotla Nallah at Solan (SH:- Painting, distemping and Sanitary fitting etc.)

1	Providing and fixing 18mm thick skirting with Pre-laminated (one side decorative and other side balancing lamination) 1st pressed 3 layer or graded particle board (medium density) Grade I, Type II, IS :12823 marked, with necessary fixing arrangements and screws, including drilling necessary holes for rawl plugs etc. and priming coat on unexposed surface complete as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	25.25	Per Square Meter	1775.65	Rupees One Thousand Seven Hundred Seventy Five and Paise Sixty Five Only	44835.00
2	Providing and fixing 25 mm thick ISI marked flush door shutters conforming to IS : 2902 (Part I) decorative type, core of birch board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters M.S. Piano hinges . (for cupboard) including ISI marked nickel plated bright finished IS : 3818 marked with necessary screws as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	3.78	Per square meter.	2473.28	Rupees Thousand Four Hundred Seventy Three and Paise Twenty Eight Only	9349.00
3	Providing and fixing 150mm (One hundred twenty five) millimeters size aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per HP.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	8.00	Each	71.10	Rupees Seventy One and Paise Ten Only	569.00
4	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	12.00	Each	60.00	Rupees Sixty Only	720.00
5	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts.	667.67	Per square meter.	11.15	Rupees Eleven and Paise Fifteen Only	7445.00
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	667.67	Per Square Meter	99.50	Rupees Ninety Nine and Paise Fifty Only	66433.00
7	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacturer, including applying additional coat where ever required to achieve even shade and colour as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	667.67	Per Square Meter	131.15	Rupees One Hundred and Thirty One and Paise Fifteen Only	87565.00
8	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturer's specification on setting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 lit/sq.m over an under coat of primer applied @0.75 lit/sq.m of approved brand and manufacturer as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	262.50	Per square meter.	118.40	Rupees One Hundred Eighteen and Paise Only	31050.00

9	French spirit polishing Two or more coats on new works including a coat of wood filler as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	25.39	Per Square Meter	208.55	Rupees Hundred Eight and Paise Fifty Five	Two	5295.00
10	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	472.3	Per square metre	151.95	Rupees Hundred Fifty One and Paise Nine Five Only	One	71766.00
11	Providing and fixing 15 mm nominal dia CP Brass Single lever telephonic wall mixer of quality & make as approved by Engineer in charge	2.00	Each	6113.60	Rupees Thousand and Hundred Thirteen	Six One	12227.00
12	Providing and fixing 15 mm (fifteen millimeters) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	8.000	Each	650.00	Rupees Hundred Fifty Only	Six	5200.00
13	Providing and fixing W.C. pan with ISI marked white solid plastic seat and lid white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	2.00	Each	5150.00	Rupees Thousand Hundred Fifty Only	Five One	10300.00
14	Providing and fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. complete as per directions of Engineer- in-charge.	12.00	one set	339.75	Rupees Hundred Nine and Paise Seventy Five Only	Three Thirty Paise	4077.00
15	Providing and fixing 600mmx450mm (six hundred into four hundred fifty millimeter) beveled edge mirror of superior glass mounted on 6mm(six millimeters thick A.C. sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	1124.10	Rupees Thousand Hundred Twenty Four and Paise Ten Only	One One	2248.00
16	Providing and placing on terrace (at all floor levels) 1000 Lite Capacity polyethylene water storage tank. IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1000.00	Per Liter	10.50	Rupees Ten and Paise Fifty Only		10500.00
Total:-							369609.00
Rupees Three Lakhs Sixty Nine Thousand Six Hundred Nine Only							
Quoted Percentage rate upto Three Digits :-							
				(+)/(-)			

T/S No. 315 for the 2025-26

Sr. No. 510 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD, Solan.