

Himachal Pradesh
Public Works Department

NO.PW.THHD/CB-tender/2025-26- 17/60-73

Dated:- 30/3/2026

To


✓ The Executive Engineer, (IT Cell)
O/O Engineer-in- Chief,
H.P.P.W.D., NirmnBhawan, Shimla-2

Subject:- Publication of Tender notice.

Sir,

I am enclosing herewith Notice Inviting Tender for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW (B) A (3) 1/2020 dated 16th July 2021.

As the work mentioned in the tender notice are urgent in nature and in public interest.


Executive Engineer,
TheogDivision,B&R,
H.P.P.W.D.,Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- The Deputy Commissioner, Shimla Distt. Shimla H.P
- The Superintending Engineer, 4th circle H.P.P.W.,D , Shimla-3.
- The Sub-divisional officer© Theog.
- The municipal Council Theog.
- Block development officer, Theog block.
- All the Assistant Engineer working under this division
- Superintendent Gr-II (Estt.) in this division.
- Drawing branch in this office.
- Notice Board


Executive Engineer,
TheogDivision,B&R,
H.P.P.W.D.,Theog

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No PW/TMC/C&I/ender/2020/26 12/02/23 @ 30/07/2023 are of emergent nature in exigency of public interest.

Examiner Engineer,
ThengDing B&R,
H. P. P. W. L. Theng

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **08.04.2026** up to 11.00 A.M. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **07.04.2026** up to 4.00 P.M. and the application for issue of tender form shall be received on **06.04.2026** up to 4.00 P.M.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	EMD (Rs.)	Cost of form (Rs)	Time Allowed
1	2	3	4	5	6	7
1	R/R Damages on Sainj Deha Chopal Road Km 0/0 to 20/740 (SH:- Providing & Laying Granular sub Base (G5B) in Km 10/000 to 20/740)	Theog	3,42,052/-	6,850/-	350/-	One Month
2	R/R Damages on Beon Jarai Road Km 0/ to 5/500 (SH :- C/O wire Create R/wall at RD 4/450 to 4/470)	Theog	3,14,363/-	6,300/-	350/-	One Month
3	R/R Damages on Sandhu Bago Talsh Road Km at RD 0/0 to 3/200 (SH:- C/O B/wall at RD 0/965 to 0/991)	Theog	4,92,560/-	9,800/-	350/-	One Month
4	C/O Forest Rest House Gadha Kufer, Tehsil Theog, District Shimla(HP) (SH:- Preparation Structural Drawings and Vetting Drawings from Competent authority)	Theog	4,00,000/-	8,000/-	350/-	One Month
5	R/R Damages on Sandhu Bago Talash Road Km at RD 0/0 to 3/200 (SH:- C/O B/wall at RD 2/435 to 2/456)	Theog	4,92,125/-	9,800/-	350/-	One Month
6	R/R Damages on Forest Colony to Chikhar Pump House Km at RD 0/0 to 6/400 (SH:- C/O B/wall at RD 2/405 to 2/420)	Theog,	2,50,831/-	5,000/-	350/-	One Month
7	R/R Damages on Dhamandri Jais Road Km 0/0 to 7/0 (SH:- C/O B/wall at RD 5/350 to 5/378)	Theog,	4,88,667/-	10,000/-	350/-	One Month
8	R/R Damages on Various Road under Sub-Division Theog (SH:- Hiring of Excavator-cum-Loader for removal of slips and surface dressing in various roads under Theog Sub-Division)	Theog	99,750/-	2,000/-	350/-	One Month
9	R/R Damages on Various Road under Sub-Division Theog (SH:- Hiring of Excavator-cum-Loader for removal of slips and surface dressing in various roads under Theog Sub-Division Section Sandhu)	Theog,	2,99,250/-	6,000/-	350/-	One Month
10	Detail estimate for the A/R & M/O to Sub Judge Office Building at Theog (SH:- Painting & Distempering, Flooring in Retiring room and court Room.) at Tehsil Theog Distt Shimla HP)	Theog	2,13,062/-	4,300/-	350/-	One Month
11	R/R Damages on Kuthar to Banaya Kalgaon Road Km 0/0	Theog	2,40,581/-	4,800/-	350/-	One

	to 10/685 (SH:- C/O PCC B/wall at RD 7/765 to 7/787)					Month
12	R/R of Rain Damages on Chhailla Sainj Neripul Yash want Nager Solan Road Km 0/0 to 18/435 (SH:-C/O Wire Crates B/wall at Rd 3/458 to 3/488)	Theog,	2,86,521/-	5,750/-	350/-	One Month
13	R/R of Rain Damages on Chhailla Sainj Neripul Yash want Nager Solan Road Km 0/0 to 18/435 (SH:-C/O PCC B/wall at Rd 2/045 to 2/060)	Theog	2,06,846/-	5,000/-	350/-	One Month
14	A/R & M/O Meha Dandi Road Km 0/0 to 4/930 (SH:- C/O B/wall & U-shape drain at RD 3/880 to 4/000)	Theog	3,75,906/-	7,550/-	350/-	One Month
15	C/O Double lane Bridge at Lelu over Giri Khad on Sainj Chopal Fediz Pul Road under Theog Division (SH:- Preparation of Hydraulic data and Geotechnical Investigation)	Theog	4,85,000/-	9,700/-	350/-	One Month
16	R/R of Rain Damages on Kargoli Nallah to Deha Road Km 0/0 to 8/00 (SH:- Removal of slips in Km 0/0 to 3/000)	Theog	4,99,950/-	10,000/-	350/-	One Month
17	R/R of Rain Damages on Kargoli Nallah to Deha Road Km 0/0 to 8/00 (SH:- Removal of slips in Km 0/0 to 5/000)	Theog	3,35,810/-	6,750/-	350/-	One Month
18	R/R of Rain Damages on Matiana Mohari Road Km 0/0 to 24/500 (SH:- C/O B/wall at Rd 14/225 to 14/250)	Theog	2,83,653/-	6,000/-	350/-	One Month
19	Extention of Ground by Providing R/walla and fencing over wall in Govt Degree College at Theog (SH:- C/O R/wall & Fencing over it)	Theog	2,33,310/-	4,700/-	350/-	One Month
20	R/R Damages on Chhailla Ghoond Banari Road Km 0/0 to 20/615 (SH:- C/O PCC B/wall at RD 15/736 to 15/751) 15 mtr.	Theog	2,17,540/-	4,400/-	350/-	One Month
21	R/R Damages on Matiana Mahori Guthan road Km 16/0 to 24/0 (SH:- C/O PCC B/wall at RD 20/970 to 20/993)	Theog	2,73,056/-	5,500/-	350/-	One Month
22	R/R Of Rain Damages on Chhailla Sainj Neripul Yashwant Nager Solan Road km 0/0 to 18/435(SH:-C/O B/Wall at RD 6/345 to 6/360)	Theog	4,97,556/-	10,000/-	350/-	One Month
23	R/R Of Rain Damages on Chhailla Sainj Neripul Yashwant Nager Solan Road km 0/0 to 18/435(SH:-C/O B/Wall at RD 6/375 to 6/390)	Theog	4,97,556/-	10,000/-	350/-	One Month

- The contractors are required to be produce a copy of their PAN No. GST and should also produce a copy of enlistment /renewal letter.
- Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act,1952 at the time of tender. Failure to observe this condition shall render the tender of contractor liable to summary rejection.


 Executive Engineer,
 Theog Division B&R,
 H.P.P.W.D Theog.

Schedule of Quantity

①

Estimated Cost 342052/-
Earnest Money: 6850/-
Time One month

Name of Work:- R/O Rain damages on Sainj Deha Chopla Road km 0/0 to 207/40(SH:- Providing & Laying Granular sub base(GSB) in km 10/000 to 207/40)

Sr. No.	Description of Items	QTY.	Rate	Unit	Amount	
1	Construction of granular sub base by providing well graded materials,spreading in uniform layers with tractor mount grader on prepared surface, mixture by mix in placement hood with renovator at OMC, and compacting with smooth wheel 80-10 K statick roller to achieve the desired density, complete as per MORD 2014 1 As per technical specification Clause 401 and leads and lifts as per direction of the Engineer-in-Charge.	194.16	1761.70 in feg	in words Rupees One Thousand Seven Hundred Sixty One and Paise Seventy Only	P/cum	342052.00
			% above/Below/ as per DNIT amount			
			Quoted Rate(In/Fig)			
			Quoted Rate(In/Words)			
			Total:-		342052.00	


 Executive Engineer
 Theog Division
 HP PWD Theog

3

SCHEDULE OF QUANTITY

Estimated Cost 492560/-
Earnest Money: 98000.00
Time: One Month

Name of work :- R/R Damages on Sandhu Bago Talsh Road KM at RD 0/0 to 3/200 (SH:- C/O B/wall at RD 0/965 to 0/991

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lifts as per the direction of the Engineer- in Charge	43.68	148.95	Rupees One Hundred Forty Eight and Paise Ninety Five Only	P/Cum	6506.14
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	31.46	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	6735.59
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge .(1:4:8)	95.16	4900.00	Rupees Four Thousand Nine Hundred Only	P/Cum	466284.00
4	Providing weepholes in brick masonry/ stone masonry , plin RCC abutment , B/wall. R/wall with 100 mm dia PVC pipe approved brand i/c all leads and lifts as per directions of the Engineer - in Charge .	52.00	250.65	Rupees Two Hundred Fifty and Paise Sixty Five Only	Each	13033.80
				Quoted rate in figer + /.(%.....)		
				Quoted rate in words		
						492560.00


Executive Engineer,
Theog Division,
HP.PWD. Theog

(5)


Estimated Cost :	400000.00
Earnest Money :	8000
Time Limit :	Two Months

SCHEDULE OF QUANTITY

Name of Work : Construction of Forest Rest House Gadhla Kufer, Tehsil Theog, District Shimla (HP).

(Sub-Head: - Preparation Structural Drawings and Vetting Drawings from Competent authority)

Sr. No.	Item Description	Quantity	Units	Rate		Amount
				In Figures	In Words	
1	Structural design of Building and Preparation of working drawings including obtaining approval of structural design and drawings from HP.PWD. and submission of soft copy of approved design and drawings of the same in hard copy complete in 2 no. Copies as per direction of Engineer-in-charge.	1	Job	250000.00	Rupees Two Lakh Fifty Thousand Rupees Only /-	250000.00
2	Consultancy services for Proof checking of Structural drawings of Construction of Govt. Sr. Sec. School at Kiar Koti, Distt. Shimla (HP) from competent authority such as NIT/IIT/PEC/NITTR in all respect and submitting the same to higher office for approval.	1	Job	150000.00	Rupees One Lakh Fifty Thousand Rupees Only /-	150000.00
Total						400000.00
				Quoted Rate (In Fig)	% above/below/at par	
				Quoted Rate (In Words)		


Executive Engineer
Theog Division
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time: One Month

492125/-
9800.00

Name of work :- R/R Damages on Sandhu Bago Talsh Road KM at RD 0/0 to 3/200 (SH:- C/O B/wall at RD 2/435 to 2/456)

Sr. No.	Description of Item	QTY	Rate in Rs.	Rate		Unit	Amount
				Rate in words			
1	Removal of land slide slip clearance: Removal of slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of sloop and disposal of cut materials with in lift up to 1.50 mtr and lift up 1000 mtrs. As per technical specification 302. 305 and 1611. including all leads and lifts	79.80	85.00	Rupees Eighty Five Only		P/Cum	6783.00
2	Excavation in soil in hilly area by manual means including cutting and trimming of slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lifts as per the direction of the Engineer- in Charge	47.25	148.95	Rupees One Hundred Forty Eight and Paise Ninety Five Only		P/Cum	7037.89
3	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge	39.69	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		P/Cum	8497.63
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge	13.23	4725.00	Rupees Four Thousand Seven Hundred Twenty Five Only		P/Cum	62511.75
5	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204Random rubble masonry in cement mortar 1:6.including all leads and lifts or as per the direction of Engineer- in Charge	86.31	4597.00	Rupees Four Thousand Five Hundred Ninety Seven Only		P/Cum	396767.07
6	Providing weepholes in brick masonry/ stone masonry, plin RCC abutment, B/wall. R/wall with 100 mm dia PVC pipe approved brand w/c all leads and lifts as per directions of the Engineer - in Charge.	42.00	250.65	Rupees Two Hundred Fifty and Paise Sixty Five Only		Each	10527.30
				Quoted rate in words			
				Quoted rate in Rs. / (%.....)			
							492125.00

Executive Engineer,
Theog Division,
HP.PWD. Theog

6

SCHEDULE OF QUANTITY

Estimated Cost 250831/
Earnest Money 50000.00
Time: One Months

Name of work :- R/R Damages on Forest Colony to Chikhar Pump House Km at RD 0/0 to 6/400 (SH:- C/O B/wall at RD 2/405 to 2/420)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Removal of land slide slip clearance: Removal of slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of sloop and disposal of cut materials with in lift up to 1.50 mtr and lift up 1000 mtrs. As per technical specification 302, 305 and 1611, including all leads and lifts or as per the direction of Engineer - in Charge	48.75	75.00	Rupees Seventy Five Only	P/Cum	3656.25
2	Excavation in soil in hilly area by manual means including cutting and trimming of slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lifts as per the direction of the Engineer- in Charge	61.95	148.95	Rupees One Hundred Forty Eight and Paise Ninety Five Only	P/Cum	9227.45
3	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge	11.25	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	2408.63
4	Wire crates made of G.I wire filled with boulders with square cut faces against wire (Boulder filling to be measured and paid for separately) G.I wire 4mm thick 15 cm X 15 cm mesh.	70.31	3350.00	Rupees Three Thousand Three Hundred Fifty Only	P/Cum	235538.50
				Quoted rate in fig+/- (%.....)		
				Quoted rate in words		
						250831.00


Executive Engineer,
Theog Division,
HP.P.W.D. Theog

SCHEDULE OF QUANTITY

Estimated Cost 488667/-
 Earnest Money 100000.00
 Time One Months

Name of work:- R/R Damages on Dhmandri Jais Road Km 0/0 to 7/0 (SH:- C/o B/wall at RD 5/350 to 5/378)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate		Unit	Amount
				Rate in words			
1	Excavation in soil in hilly area by manual means including cutting and trimming of slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical specification clause 1603.2 with in all leads and lifts as per the direction of the Engineer-in-Charge	44.80	180.00	Rupees One Hundred Eighty Only		P/Cum	8064.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	33.60	214.10	Rupees Two Hundred Fourteen and Paise Ten Only		P/Cum	7193.76
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge . (1:4:8)	8.68	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only		P/Cum	38004.51
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 .random rubble masonry In cement mortar 1:6 including all leads and lifts as per the direction of the Engineer - in Charge (1:6)	93.24	4597.00	Rupees Four Thousand Five Hundred Ninety Seven Only		P/Cum	428624.28
5	Providing weepholes in brick masonry/ stone masonry . plain reinforcement concrete abutment . wing wall . R/wall with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing with in all leads and lifts as per directions of the Engineer-in-Charge)	28.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only		Each	6780.20
<p align="center">Quoted rate in fig* /-(%.....)</p> <p align="center">Quoted rate in words</p>							488667.00


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

8

SCHEDULE OF QUANTITY

Estimated Cost Rs . 99750
Earnest Money 2000 00
Time One Month

Name of work :- R/R Damages on Various Roads under Sub-Division (SH:- Hiring of Excavator-cum-Loader for removal of slips and surface dressing in various roads under Theog Sub-Division)

Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
				in words		
1	Hiring of JCB excavator to be deployed for removal of slips dressing of surface i/c cost of fuel oil, lubricants waggas of operational staffs any repair breaks during operation will be carried out by the owner at his risk and cost i/c shifting of machineries from one place to other at required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in all leads and lifts as per direction of Engineer-in-Charge Excavator-cum-Loader	95.00	1050.00	Ruppes One Thousand Fifty Only	Per /Hour	99750.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

(9)

Estimated Cost Rs - 299250/-
 Earnest Money 6000 00
 Time One Month

Name of work :- R/R Damages on Various Roads under sub-Division Theog (SH:- Hiring of Excavator-cum -Loader for removal of slips and dressing in various roads under Theog Sub -Division Section Sandhu)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB excavator to be deployed for removal of slips dressing of surface i/c cost of fuel oil, lubricants waggas of operational staffs any repair breaks during operation will be carried out by the owner at his risk and cost i/c shifting of machineres from one place to other at required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in all leads and lifts as per direction of Engineer-in-Charge Excavator-cum-Loader	285.00	1050.00	Rupees One Thousand Fifty Only	Per /Hour	299250.00
			Quoted rate in figer+/-(%-----)			
			Quoted rate in words			
						299250.00


Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 213062/-
Earnest Money: 4300 00
Time: One Months

Name of Work:- Detail estimate for the A/R & M/O to Sub Judge Office Building at Theog (SH:- Painting & Distempering, Flooring in Retiring room and court Room,)at Theog Tehsil Theog Dist. Shimla HP

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete.	371.92	115.00	Rupees One Hundred Fifteen Only	Sqm	42770.80
2	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	371.92	105.00	Rupees One Hundred Five Only	Sqm	39051.60
3	Painting two coats(excluding coat) on wood and wood based surface with enamel paint to give an even shade including cleaning the surface of all dirt,dust and other foreign matter,sand papering & stoping With white enamel paint including all leads and lifts as per the direction of Engineer-in-Charge.	109.36	110.00	Rupees One Hundred Ten Only	Sqm	12029.60
4	Painting two coats(excluding priming coat on new concrete masonry/plaster surfaces with ready-mixed paint brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required with Paint other than white including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	26.48	115.00	Rupees One Hundred Fifteen Only	Sqm	3045.20
5	Painting two coats (excluding priming cost on new steel and other metal surfaces with enamel paint brushin to give an even shade including cleaning the surface of all dirt,dust and other foreign matters Enamel paint other than white including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	85.46	95.00	Rupees Ninety Five Only	Sqm	8118.70

6	2 mm thick pvc/rubber tiles flooring plain, coloured, corbed or mosaic or matted finish, laid with approved adhesive on sub floor damp proofing treatment (to be measured separately) for payment.	25.68	900.00	Rupees Nine Hundred Only	Sqm	23112.00
7	Supplying and fixing Glass panes i/ removal of old broken glass with putty and nails wherever necessary including racking out the old putty:	43.32	950.00	Rupees Nine Hundred Fifty Only	Sqm	41154.00
8	Polishing with French polish Two or more coat i/c preparing the surface free from mortar drops and other foreign matter with sand paper clean i/c all leads and lifts.	103.01	425.00	Rupees Four Hundred Twenty Five Only	Sqm	43779.25
			Quoted rate in words	Quoted rate in figer + /-(%.....)		213062.00


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 240581/-
Earnest Money: 4800.00

Time: One Month

Name of work :- R/R Damages on Kuthar to Baneya Kalgaon Road Km 0/0 to 10/685 (SH:- C/O PCC B/wall at RD 7/765 to 7/787)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	55.80	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	11946.78
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203, including all leads and lifts or as per the direction of Engineer - in Charge (1:4:8) 20 mm Nominal size)	52.40	4178.40	Rupees Four Thousand One Hundred Seventy Eight and Paise Forty Only	P/Cum	218948.16
3	Providing and fixing weapholes in brick masonry plain RCC abument, B/wall & R/wall with 100 mmm dia (4 Kg Cm ² pressure) PVC pipe i/c all leads and lift as per directions of the Engineer - in Charge.	40.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9686.00
Quoted rate in words						240581.00
Quoted rate in figer +/- (%-----)						240581.00


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost 286521/-
Earnest Money 5750/-

Time One month

Name of Work -R/R Of Rain Damages on Chhailia Sainji Neripul Yash want Nager Solan Road km 0/0 to 18/435 (SH - (SH -C/O Wire

Crates B/Wall at RD3/458 to 3/488)

Sr. No.	Description of Items	QTY.	Rate	In words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge (Ordinary Soil)	46 65	214 10	Rupees Two Hundred Fourteen and Paise Ten Only	P/cum	9988 00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including in all leads and lifts as per direction of Engineer-in- Charge	93 74	2950 00	Rupees Two Thousand Nine Hundred Fifty Only	P/cum	276533 00
Total:-						286521 00
		Quoted Rate in Fig		% above/below/as per DNIT amount		
		Quoted Rate in Words				


 Executive Engineer
 Theog Division
 HP PWD Theog

SCHEDULE OF QUANTITY

Estimated Cost 206846/-
Earnest Money 5000.00

Time One Months

Name of work :- R/R Damages on Chhaila Saini Neripul Yashwant Nager Solan Road Km 0/0 to 18/435 (SH:- C/O PCC B/wall at RD 2/045 to 2/060)

Sr. No.	Description of Item	QTY	Rate in fig	Rate in words	Unit	Amount
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	37.27	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	7979.51
2	Providing and laying concrete 1:4:8 (1 cement : 4sand : 8 graded stone aggregate 40 mm Nominal size) in open foundations complete as per drawing & technical specification clause 802 , 803 , 1202 and 1203,including all leads and lifts or as per the direction of Engineer - in Charge	39.30	4900.00	Rupees Four Thousand Nine Hundred Only	P/Cum	192570.00
3	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 100 mm dia (4 Kg Cm2 pressure) PVC pipe approved brand i/c all leads and lift as per directions of the Engineer - in Charge.	26.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	6295.90
Quoted rate in words						206846.00
Quoted rate in figer+/- (%.....)						


 Executive Engineer,
 Theoog Division,
 HP.PWD. Theoog

15

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Double lane Bridge at Lelu over Giri Khad on Sany Chopal Fediz Pul Road under Theog Division
(SH- Preparation of Hydraulic data and Geotechnical Investigation).

S.No	Description of Item	Quantity	JOB	In fig.	Rate		Unit	Amount
					In word	Time Limit		
1	Preparation of Hydraulic data complete in all respect in manuscript form and submission of the same in higher office for approval. if any correction/amendment has desired by the head office, the same may be corrected as desired and directed by the Engineer-in-Charge and higher office; complete in all respect. After approval of the hydraulic data from the higher office, the same will be submitted in fair shape to this office in two numbers of copies.	1.00	JOB	120000.00	Rupees One Lakh Twenty Thousand Only	9700.00	Per Job	120000.00
2	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of N _v Size 75 mm dia for investigation of soil rock conditions at site of work. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in-Charge.	50.00	Rmt	7300.00	Rupees Seven Thousand Three Hundred Only	One Month	Per Running Metre	365000.00
Total Amount in figures:-								485000.00



Executive Engineer,
 Theog Division
H.P.P.O. Theog

Schedule Of Quantity

Estimated Cost 283653/-
Earnest Money: 6000 /-
Time: One month
18

Name of Work:-R/R Rain Damages on Matiana Mohari Road km 0/0 to 24/500(SH-C/O B/Wall at RD 14/225 to 14/250)

Sr. No.	Description of Items	QTY.	Rate	in words	Unit	Amount
1	Excavation in Hilly areas in soil by mechanical means excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1 including in all leads and lifts as per direction of Engineer-in-Charge.	27.25	180.00	Rupees One Hundred Eighty Only	P/cum	4905.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	16.75	220.00	Rupees Two Hundred Twenty Only	P/cum	3685.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge (1.6, 12) 40 mm nominal size	7.15	4000.00	Rupees Four Thousand Only	P/cum	28600.00
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar 1.6 including all leads and lifts as per direction of the Engineer-in-Charge (1.6)	61.75	3800.00	Rupees Three Thousand Eight Hundred Only	P/cum	234650.00
4	Back Filling behind abutment wing wall/and R/wall complete as per drawing & technical specification clause 1204.3.8	11.25	1050.00	Rupees One Thousand Fifty Only	P/cum	11812.50
				Total:-		283653.00
		Quoted Rates (In Fig)		(% above/below / at Par)		
		Quoted Rates (In Words)				


 Executive Engineer
 Theog Division
 HP PWD Theog

Schedule Of Quantity

19


Estimated Cost 233310/-
Earnest Money: 4700 /-

Time One month

Name of Work:-Extension of Ground by Providing R/Wall and fencing over Wall in Govt Degree College at Theog (SH -C/O R/Wall & Fencing

Sr. No.	Description of Items	QTY.	Rate	in words	Unit	Amount
1	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 and 1203 including all leads and lifts as per direction of the Engineer-in-Charge. (1:4:8) 25 mm nominal size	15.00	5000.00	Rupees Five Thousand Only	P/cum	75000.00
2	Steel work welded in built sections . trusses and framed work including cutting . hosting fixing in position and applying a promeg coat of red lead paint . In gratings framed guard bars, ladders, railing brackets and smilar works including carriage of material with in all leads and lifts as per direction of the Engineer-in-Charge	1029.50	105.00	Rupees One Hundred Five Only	P/Kg	108097.50
2	Supplying and fixing expended metal to wood or steel members in partitions etc including all leads and lifts as per direction of the Engineer-in-Charge	82.80	525.00	Rupees Five Hundred Twenty Five	P/Sqm	43470.00
3	Cement concrete flooring 1:2:4 (1 Cement : 2 Sand : 4 graded stone aggergate 20 mm nominal) size laid on one layer finished with floating coat of neat cement . including all leads and lifts as per direction of the Engineer-in-Charge)	3.20	425.00	Rupees Four Hundred Twenty Five Only	P/cum	1360.00
4	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushin to give an even shade i/c cleaning the surface all dirt, dust and other foregin matter enamel paint other than white including carriage of materials with in all leads and lifts as per the direction of the Engineer- in Charge	82.80	65.00	Rupees Sixty Five Only	Each	5382.00
Total:-						233310.00

Quoted Rates (in Fig) _____ (% above/below / at Par)
Quoted Rates (in Words) _____


 Executive Engineer
 Theog Division
 HP PWD Theog

20

SCHEDULE OF QUANTITY

Estimated Cost 217540/-
Earnest Money 4400 00
Time: One Months

Name of work:- R/R Of Rain Damages on Chhaila Ghoond Banari Road Km 0/0 to 20/615 (SH:- C/O PCC B/wall at RD 15/736 to 15/751.) 15 mtr.

Sr. No.	Description of Item	QTY	Rate	Unit	Amount	
			Rate in fig			Rate in words
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	56.85	220.00	Rupees Two Hundred Twenty Only	P/Cum	12507.00
2	Providing and laying concrete 1:4:8 (1 cement : 4sand : 8 graded stone aggregate 40 mm Nominal size) in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203 including all leads and lifts or as per the direction of Engineer - in Charge .	43.46	4550.00	Rupees Four Thousand Five Hundred Fifty Only	P/Cum	197743.00
3	Providing and fixing weapholes in brick masonry plain RCC abument, B/wall & R/wall with 100 mm dia (4 Kg Cm2 pressure) PVC pipe approved brand i/c all leads and lift as per directions of the Engineer - in Charge.	27.00	270.00	Rupees Two Hundred Seventy Only	Each	7290.00
					Quoted rate in words	
					Quoted rate in figer+/(%-----)	217540.00

Executive Engineer,
Theog Division,
HP.PWD. Theog

21

SCHEDULE OF QUANTITY

Estimated Cost 273056/-
Earnest Money 5500.00
Time One Months

Name of work:- R/R Of Rain Damages on Matiana Mohari Guthan Road Km 16/0 to 24/0 (SH:- C/O PCC B/wall at RD 20/970 to 20/993)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of slope and disposing of cut material with lift upto 1.50 mtr. and lead upto 20 mtr. as per technical specification clause 1603.1 with in all leads and lifts as per the direction of the Engineer- in Charge	50.60	170.00	Rupees One Hundred Seventy Only	P/Cum	8602.00
2	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	32.20	220.00	Rupees Two Hundred Twenty Only	P/Cum	7084.00
3	Providing and laying concrete 1:4:8 (1 cement : 4sand : 8 graded stone aggregate 40 mm Nominal size) in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge .	55.20	4550.00	Rupees Four Thousand Five Hundred Fifty Only	P/Cum	251160.00
4	Providing and fixing weapholes in brick masonry plain RCC abument , B/wall & R/wall with 110 mm dia (4 Kg Cm ² pressure) PVC pipe approved brand i/c all leads and lift as per directions of the Engineer - in Charge.	23.00	270.00	Rupees Two Hundred Seventy Only	Each	6210.00
			Quoted rate in figer+/(%-----)			273056.00
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

29

SCHEDULE OF QUANTITY

Estimated Cost 497556/-
Earnest Money 10000.00
Time: One Months

Name of work:- R/R Of Rain Damages on Chhaila Saini Neripul Yashwant Nager Solan Road Km 0/0 to 18/435(SH:-C/O B/Wall at RD 6/345 to 6/360)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	78.15	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	16731.92
2	Providing and laying concrete 1:4:8 (1 cement : 4sand : 8 graded stone aggregate 40 mm Nominal size) in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203.including all leads and lifts or as per the direction of Engineer - in Charge	96.20	4900.00	Rupees Four Thousand Nine Hundred Only	P/Cum	471380.00
3	Providing and fixing weapholes in brick masonry plain RCC abument, B/wall & R/wall with 100 mm dia (4 Kg Cm2 pressure) PVC pipe approved brand i/c all leads and lift as per directions of the Engineer - in Charge.	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9443.85
Quoted rate in words						
Quoted rate in figer+/(%-----)						497556.00


Executive Engineer,
Theog Division,
HP.PWD. Theog

23

SCHEDULE OF QUANTITY

Estimated Cost 497556/-
Earnest Money 100000.00

Time: One Month

Name of work:- R/R Of Rain Damages on Chhaila Sainj Neripul Yashwant Nager Solan Road km 0/0 to 18/435 to protect the existing palace campus (SH:-C/O PCC B/Wall at RD 6/360 to 6/375)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig	Rate in words		
1	Earth work in excavation for structure as per drawing & technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and back filling in trenches with suitable material including all leads and lifts or as per the direction of Engineer - in Charge (Ordinary Soil)	78.15	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	P/Cum	16731.92
2	Providing and laying concrete 1:4:8 (1 cement : 4sand : 8 graded stone aggregate 40 mm Nominal size) in open foundations complete as per drawing & technical specification clause 802, 803, 1202 and 1203; including all leads and lifts or as per the direction of Engineer - in Charge .	96.20	4900.00	Rupees Four Thousand Nine Hundred Only	P/Cum	471380.00
3	Providing and fixing weapholes in brick masonry plain RCC abument, B/wall & R/wall with 100 mm dia (4 Kg Cm2 pressure) PVC pipe approved brand /ic all leads and lift as per directions of the Engineer - in Charge.	39.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	9443.85
Quoted rate in figer +/- (%-----)						497556.00
Quoted rate in words						


Executive Engineer,
Theog Division,
HP.PWD. Theog