

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-MDI(P)E-Tender-NIT/2026-27- 1096-1100 Dated:- 18/4/26

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 27.04.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 25.04.2026 upto 12:00 Noon Contractors in person or their authorized representatives. The application will not be accepted without Earnest Money & Cost of tender form.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Sakrog to Tikker road Km 0/00 to 3/720 (PDNA-2023) (SH:- Repair of Pot Holes in Km 0/00 to 3/720)	4,96,956.94	9500/-	350/-	One month
2	Restoration of rain damages on Balh to Ropa road Km 0/00 to 5/100 (PDNA-2023) (SH:- Repair of Pot Holes in Km 0/00 to 2/500)	4,94,544.56	9900/-	350/-	One month
3	Restoration of rain damages on Kunnu Baridhar via Gagoun road Km 0/00 to 6/500 (PDNA-2023) (SH:- Construction of wire crate cause way at RD 5/030 to 5/350)	4,99,642.37	10000/-	350/-	One month
4	Restoration of rain damages on Kunnu Baridhar via Gagoun road Km 0/00 to 6/500 (PDNA-2023) (SH:- Providing and Laying Kharanja Soling M-20 and Construction of unlined drain at RD 0/150 to 0/240 & 0/300 to 0/310)	4,97,217.00	9900/-	350/-	One month
5	Restoration of rain damages on Urla Nausa road Km 0/00 to 5/700 (PDNA-2023) (SH:- Removal of formation deficiency in Km 2/255 to 2/330 & 5/600 to 5/690)	2,11,197.00	4200/-	350/-	One month
6	Restoration of rain damages on Urla Nausa road Km 0/00 to 5/700 (PDNA-2023) (SH:- Construction of Retaining wall at RDs 2/300 to 2/311 & 2/315 to 2/326.26)	4,71,482.64	9400/-	350/-	One month
7	Restoration of rain damages on Urla Nausa road Km 0/00 to 5/700 (PDNA-2023) (SH:- Construction of Retaining wall at RDs 3/195 to 3/208)	4,66,732.86	9300/-	350/-	One month
8	Restoration of rain damages on Surahan Siun road Km 0/00 to 3/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/440 to 0/450 and 1/100 to 1/120)	4,97,965.44	10000/-	350/-	One month

9	Annual Repair and maintenance of Padhar Nahuli road Km 0/0 to 14/500. (Under PDNA) (SH:- Repair of pot holes in Km 5/500 to 10/00)	3,71,070.00	7400/-	350/-	One month
10	Annual Repair and maintenance of Padhar Nahuli road Km 0/0 to 14/500. (Under PDNA) (SH:- Repair of pot holes in Km 10/00 to 14/500)	3,71,070.00	7400/-	350/-	One month
11	NDF/2025/20, R/O (Repair of) Restoration of Rain damages on Surahan Siun road Km 0/00 to 13/00 Mohal (SH:- Hiring of earth cutting/ excavating machine for removal of slips/ debris for opening of roads etc.)	49,500.00	1000/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/ Firm should be enlisted with the HP.PWD & Registration/ Renewal copy attached.
2. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/ undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


 Executive Engineer,
 Mandi Division No. I,
 HPPWD, at Padhar Distt. Mandi (H.P.)
 on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 496956.94
 Earnest Money Rs:- 9500.00
 Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of Work:- Restoration of Rain damages on Sakrog to Tikker road Km 0/00 to 3/720 (PDNA-2023). (Sub Head:- Repair of Pot Holes in Km 0/00 to 3/720).
 Contract No:-
 Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling, with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	25.87	Per cubic metre	2266.00	58621.42	Rupees Fifty Eight Thousand Six Hundred Twenty One and Paise Forty Two Only
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer in-Charge.	1304.57	Per Square metre	336.00	438335.52	Rupees Four Lakh Thirty Eight Thousand Three Hundred Thirty Five and Paise Fifty Two Only
Total in figure :					496956.94	Rupees Four Lakh Ninety Six Thousand Nine Hundred Fifty Six and Paise Ninety Four Only
Total in Words :					Rupees Four Lakh Ninety Six Thousand Nine Hundred Fifty Six and Paise Ninety Four Only	

Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 494544.56
 Earnest Money Rs:- 9900.00
 Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of Work:- Restoration of Rain damages on Balh to Ropa road Km 0/00 to 5/100 (PDNA-2023). (Sub Head:- Repair of Pot Holes in Km 0/00 to 2/500).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	45.56	Per cubic metre	2266.00	103238.96	Rupees One Lakh Three Thousand Two Hundred Thirty Eight and Paise Ninety Six Only
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer in-Charge.	1164.6	Per Square metre	336.00	391305.60	Rupees Three Lakh Ninety One Thousand Three Hundred Five and Paise Sixty Only
Total in figure :					494544.56	Rupees Four Lakh Ninety Four Thousand Five Hundred Forty Four and Paise Fifty Six Only
Total in Words :					Rupees Four Lakh Ninety Four Thousand Five Hundred Forty Four and Paise Fifty Six Only	

Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar

3

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 499642.37
 Earnest Money Rs:- 10000.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.
 Name of work :- Restoration of rain damages on Kunnu Baridhar Via Gajoun road km. 0/00 to 6/500. (PDNA -2023), (Sub Head:- Construction of wire crate causeway at RD 5/030 & 5/350).
 Contract No. :
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.00	Per cubic metre	491.80	17704.80	Rupees Seventeen Thousand Seven Hundred Four and Paise Eighty Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	82.36	Per cubic metre	2409.00	198405.24	Rupees One Lakh Ninety Eight Thousand Four Hundred Five and Paise Twenty Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.00	Per cubic metre	1472.70	39762.90	Rupees Thirty Nine Thousand Seven Hundred Sixty Two and Paise Ninety Only
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.36	Per cubic metre	979.80	15049.73	Rupees Fifteen Thousand Forty Nine and Paise Seventy Three Only
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement: three sand: six graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	9.00	Per cubic metre	5180.30	46622.70	Rupees Forty Six Thousand Six Hundred Twenty Two and Paise Seventy Only
6	Providing and Laying reinforced cement concrete in substructure complete as per drawing and technical specifications clause 802, 804, 805, 806, 807, 1202 and 1204 Plain cement concrete nominal mix 1:1.5:3 (one cement : one point five sand : three graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Per cubic metre	6069.90	182097.00	Rupees One Lakh Eighty Two Thousand Ninety Seven Only
Total in figure :					499642.37	Rupees Four Lakh Ninety Nine Thousand Six Hundred Forty Two and Paise Seven Only
Total in Words :						Rupees Four Lakh Ninety Nine Thousand Six Hundred Forty Two and Paise Thirty Seven Only

Executive Engineer,
 Mandi Division No. I,
 HP, PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 497217.00
 Earnest Money Rs:- 9900.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Kunnu Baridhar Via Gajoun road km. 0/00 to 6/500. (PDNA -2023). (Sub Head:- Providing and Laying Kharanja Soling M-20 and Construction of unlined drain at RD 0/150 to 0/240 & 0/300 to 0/310).

Contract No.:

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combing including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	67.20	Per cubic metre	979.80	65842.56	Rupees Sixty Five Thousand Eight Hundred Forty Two and Paise Fifty Six Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:2:4 (one cement: two sand: four graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	58.80	Per cubic metre	5761.30	338764.44	Rupees Three Lakh Thirty Eight Thousand Seven Hundred Sixty Four and Paise Forty Four Only
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero point four zero square metre) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m (three metre) and lead of 50m (fifty metre) (average lead 25m) (twenty five metre) as per Technical specification clause 307. Excavated material to be used in embankment at site surface drains in hard rock materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	250.00	Per running metre	150.60	37650.00	Rupees Thirty Seven Thousand Six Hundred Fifty Only
4	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero point four zero square metre) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m (three metre) and lead of 50m (fifty metre) (average lead 25m) (twenty five metre) as per Technical specification clause 307. Excavated material to be used in embankment at site surface drains in ordinary rock materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1200.00	Per running metre	45.80	54960.00	Rupees Four Thousand Nine Hundred Sixty Only
Total in figure :					497217.00	Rupees Four Lakh Ninety Seven Thousand Two Hundred Seventeen
Total in Words :						Rupees Four Lakh Ninety Seven Thousand Two Hundred Seventeen Only

Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar, 4

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 211197.00
 Earnest Money Rs:- 4200.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.

Name of work :- Restoration of rain damages on Urla Nausa road km. 0/00 to 5/700. (PDNA -2023). (Sub Head: - Removal of formation deficiency in Km 2/255 to 2/330 & 5/600 to 5/690).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly areas in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper, blasting work (both in soft and hard rock), chiselling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required, setting out to the required lines, grades, side slopes, width, camber, super elevation and levels as shown on the drawings and as directed by Engineer-in-Charge at site according to technical specifications clauses 1603.1 & 1603.2, sorting out useful/ unuseful materials and stacking the same in all leads and lifts and transportation of useful materials for filling in roadways, embankments for grade improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its levelling, fine dressing and including all labour, machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respects including all leads and lift of materials as per direction of Engineer-in-Charge.	1124.63	Per cubic metre	220.95	248487.00	Rupees Two Lakh Forty Eight Thousand Four Hundred Eighty Seven Only
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No,1	62.15	Per cubic metre	600.00	-37290.00	Rupees Thirty Two Hundred Ninety Only.
Total in figure :					211197.00	Rupees Two Lakh Eleven Thousand One Hundred Ninety Seven Only

Total in Words :

Rupees Two Lakh Eleven Thousand One Hundred Ninety Seven Only

Executive Engineer,
 Mandi Division No-1,
 HP. PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 471482.64
 Earnest Money Rs:- 9400.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP, PWD. at Padhar.

Name of work :- Restoration of rain damages on Uria Nausa road km. 0/00 to 5/700. (PDNA -2023). (Sub Head: - Construction of Retaining wall at Rds. 2/300 to 2/311 & 2/315 to 2/326.26).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	60.28	Per cubic metre	522.50	31494.73	Rupees Thirty One Thousand Four Hundred Ninety Four and Paise Seventy Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	81.72	Per cubic metre	4851.70	396480.92	Rupees Three Lakh Ninety Six Thousand Four Hundred Eighty and Paise Ninety Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	279.90	6717.60	Rupees Six Thousand Seven Hundred Seventeen and Paise Sixty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.33	Per cubic metre	1512.10	36789.39	Rupees Thirty Six Thousand Seven Hundred Eighty Nine and Paise Thirty Nine Only
Total in figure :					471482.64	Rupees Four Lakh Seventy One Thousand Four Hundred Eighty Two
Total in Words :						Rupees Four Lakh Seventy One Thousand Four Hundred Eighty Two and Paise Sixty Four Only

Executive Engineer,
 Mandi Division No.1,
 HP, PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 466732.86
 Earnest Money Rs:- 9300.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Urla Nausa road km. 0/00 to 5/700. (PDNA -2023). (Sub Head: - Construction of Retaining wall at Rds. 3/195 to 5 to 3/208).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	37.44	Per cubic metre	522.50	19561.20	Rupees Nineteen Thousand Five Hundred Sixty One and Paise Twenty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	86.76	Per cubic metre	4851.70	420933.49	Rupees Four Lakh Twenty Thousand Nine Hundred Thirty Three and Paise Forty Nine Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	279.90	5598.00	Rupees Five Thousand Five Hundred Ninety Eight Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.65	Per cubic metre	1512.10	20640.17	Rupees Twenty Thousand Six Hundred Forty and Paise Seventeen Only
Total in figure :					466732.86	Rupees Four Lakh Sixty Six Thousand Seven Hundred Thirty Two and Paise Eighty Six Only
Total in Words :						Rupees Four Lakh Sixty Six Thousand Seven Hundred Thirty Two and Paise Eighty Six Only

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 497965.44
 Earnest Money Rs:- 10000.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of work :- Restoration of rain damages on Surahan Siun road km. 0/00 to 3/00. (PDNA -2023) (Sub Head:- Construction of Retaining wall at RD 0/440 to 0/450 and 1/100 to 1/120).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS


Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	51.20	Per cubic metre	522.50	26752.00	Rupees Twenty Six Thousand Seven Hundred Fifty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	90.87	Per cubic metre	4785.40	434849.30	Rupees Four Lakh Thirty Four Thousand Eight Hundred Forty Nine and Paise Thirty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	32.00	Each	275.90	8828.80	Rupees Eight Thousand Eight Hundred Twenty Eight and Paise Eighty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.21	Per cubic metre	1512.10	27535.34	Rupees Twenty Seven Thousand Five Hundred Thirty Five and Paise Thirty Four Only
Total in figure :					497965.44	Rupees Four Lakh Ninety Seven Thousand Nine Hundred Sixty Five and Paise Forty Four Only
Total in Words :						Rupees Four Lakh Ninety Seven Thousand Nine Hundred Sixty Five and Paise Forty Four Only

Executive Engineer
 Mandi Division No 1
 Executive Engineer
 H.F.W.V. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 371070.00
Earnest Money Rs:- 7400.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Annual repair and maintenance of Padhar Nahuli road Km. 0/0 to 14/500. (UNDER PDNA) (Sub Head:- Repair of pot holes in Km. 5/500 to 10/00).						
Contract No. :						
Bidder Name :						
<u>SCHEDULE OF WORKS</u>						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	1050.00	Per square metre	353.40	Rupees Three Lakh Seventy One Thousand Seventy Only	Rupees Three Lakh Seventy One Thousand Seventy Only
Total in figure :					371070.00	Rupees Three Lakh Seventy One Thousand Seventy Only
Total in Words :		Rupees Three Lakh Seventy One Thousand Seventy Only				

Executive Engineer,
Mandi Division No-1,
HP. PWD, at Padhar


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 371070.00
Earnest Money Rs:- 7400.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
Name of work :- Annual repair and maintenance of **Padhar Nahuli** road Km. 0/0 to 14/500. (UNDER PDNA) (Sub Head:- Repair of pot holes in Km. 10/00 to 14/500).
Contract No. :
Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	1050.00	Per square metre	353.40	371070.00	Rupees Three Lakh Seventy One Thousand Seventy Only
Total in figure :					371070.00	Rupees Three Lakh Seventy One Thousand Seventy Only

Total in Words : Rupees Three Lakh Seventy One Thousand Seventy Only

Executive Engineer,
Mandi Division No-I,
HP. PWD, at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost:- 49500.00
 Earnest Money:- 1000.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No.1 HP.PWD. at Padhar.
 Name of work: - NDF/2025/20, R/O (Repair Of) Restoration of Rain Damages on Surahan Siun road km 0/0 to 13/00Mohal. (Sub Head:- Hiring of earth cutting /excavating machine for removal of slips/debris for opening of roads etc.)

Contact No.:

Bidder Name:

SCHEDULE OF WORKS

Sr. No.	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes including GST in Rs. P.	Total Amount with all taxes including GST in words
1	Hiring of earth cutting/ excavating machineries to be deployed for earth cutting / excavating/ removal of slips, boulders including cost of fuel Oil, Lubricants and wages of operating staff any repair/ breakage during operation will be carried out by the contractor at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the contractor only. Actual working hours will be accounted for the payment. Earth cutting removal of slips, boulder Excavation in all kinds of soils, including loading in to tipper/trucks and disposed of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in -Charge.	45.00	Per Hours	1100.00	49500	Rupees Forty Nine Thousand Five Hundred Only
Total In figure :					49500	Rupees Forty Nine Thousand Five Hundred Only
Total In Words :						Rupees Forty Nine Thousand Five Hundred Only

Conditions :- Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Executive Engineer
 Mandi Division no 1
 HPPWD at Padhar