

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2025/ 175-88

Dated/ 4/4/26

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pardesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 175-88
Dated 4-4-2026 are urgent in nature and in public interest.

Executive Engineer
Palampur Division
PWP/D Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed Item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **13.04.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 10.04.2026 up to 4.00 P.M and the application for issue of tender form shall be received 09.04.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Retaining Wall on link road from Chardu (MC Palampur) to HPSEBL Rest House via Badami Lal Sohan Lal near house of Sh. Kuldeep at Ward No. 1 Lohna Palampur (SW:- C/o Retaining Wall at RD 0/060 to 0/068.10 (MC Deposit)	Rs. 96,510.00	Rs. 2,000.00	Two Months
2	C/o Retaining Wall on link road from Chardu (MC Palampur) to HPSEBL Rest House via Badami Lal Sohan Lal near house of Sh. Kuldeep at Ward No. 1 Lohna Palampur (SW:- C/o Retaining Wall at RD 0/070 to 0/078.10 (MC Deposit)	Rs. 96,510.00	Rs. 2,000.00	Two Months
3	Dharamshala Yol Dadh Palampur road KM 28/00 to 33/00 (SW:- Hiring of JCB)	Rs. 98,900.00	Rs. 2,000.00	Two Months
4	Minor repair work of combined office building (Mini Secretariat) Palampur Distt. Kangra (HP) (SW:- Repair of Entrance Porch & Repair of Interlocking Paver Block back side of building)	Rs. 78,523.00	Rs. 1,600.00	Two Months
5	C/o approach road through Civil Hospital Palampur via Dental Residence (SW:- C/o R/Wall (MC Deposit)	Rs. 96,754.00	Rs. 2,000.00	Two Months
6	Link road Chandpur to Speru (SW:- P/F W Metal beam Crash Barrier at RD 0/430 to 0/453.25)	Rs. 99,668.00	Rs. 2,000.00	Two Months
7	A/R & M/O Chachian to Darati Mathred road Km 0/00 to 3/900 (SH:- C/o Rising of existing drain walls (Road side) at RD 1/420 to 1/480 and Kuhal Crossing (Iron Grating at RD 3/770)	Rs. 99,439.00	Rs. 2,000.00	Two Months

8	C/o Interlocking Tile work at Housing Board Colony Bindraban (SW:- P/L Interlocking Tiles) (MC Deposit)	Rs. 99,778.00	Rs. 2,000.00	Two Months
9	C/o Interlocking Tile work from Main road Dharamshala Yol Dadh Palampur Towards the of Mehta (SW:- Providing and laying Interlocking Tile work (MC Deposit)	Rs. 99,675.00	Rs. 2,000.00	Two Months
10	C/o Interlocking Tile work from main road Dharamshala Yol Dadh towards Health Sub-Centre Bindraban (SW:- Providing and laying Interlocking Tile works (MC Deposit)	Rs. 98,793.00	Rs. 2,000.00	Two Months
11	C/o Interlocking Tile work from Main road Dharamshala Yol Dadh Towards the house of Colonel Chamaru Ram (SW:- Providing and laying Interlocking Tile (MC Deposit)	Rs. 99,423.00	Rs. 2,000.00	Two Months
12	C/o Interlocking Tile work for Path main road Differpatt towards the house of Sh. Guddu Ram & Mangi(SW:- P/L Interlocking Tiles (MC Deposit)	Rs. 74,402.00	Rs. 1,500.00	Two Months
13	Link road Bandla to Surdi Km 0/00 to 5/820 (SH;- C/o R/Wall at RD 0/660 to 0/668.10)	Rs. 96,538.00	Rs. 2,000.00	Two Months
14	C/o link road Banuri to Main Bazar Odder Km 0/00 to 3/500 (SW:- C/o 900 MM Dia Hume pipe culvert at RD 3/250)	Rs. 99,153.00	Rs. 2,000.00	Three Months
15	C/o Culvert towards house of Sh. Vinod Kumar and others at village Matehar (Banuri) (SW:- C/o Hume Pipe culvert (MC Deposit)	Rs. 99,989.00	Rs. 2,000.00	Two Months
16	Repair of road from Dharamshala Dadh Palampur Holta Chadiyar Sandhole road Km 15/00 to 27/00 (SW:- C/O R/Wall at RD 22/132 to 22/142 (DC Deposit)	Rs. 97,496.00	Rs. 2,000.00	Two Months
17	C/o U-Shape drain near House of Sh. Joginder Chauhan, Milap Chand Lohna (SH:- C/o U-shape drain (MC Deposit)	Rs. 99,792.00	Rs. 2,000.00	Two Months
18	C/o Retaining Wall at Bindraban Chowk near the house of Sh. Ashok Naryal & Others (SW:- C/o R/Wall (MC Deposit)	Rs. 98,076.00	Rs. 2,000.00	Two Months
19	C/o Interlocking Tile work from Pardeep Kumar House towards Jagdish House on Saurabh Kalia road (SW:- P/L Interlocking Tiles (MC Deposit)	Rs. 99,578.00	Rs. 2,000.00	Two Months
20	C/o link road from HPSEBL Rest House Lohna to Vijay Sharma & Other house Km 0/00 to 0/160 (SW:- Improvement of Grade & C/O R/Wall and CC Pavement (MC Deposit)	Rs. 97,152.00	Rs. 2,000.00	Two Months
21	C/o road to house of D.S Pathania & others in MC Ward No. 13 Palampur (SW:- C/o R/Wall (MC Deposit)	Rs. 99,831.00	Rs. 2,000.00	Two Months
22	C/o U-shape drain from Chopati to Santoshi Mata Chowk (SW:- Demolition & P/L 1:3:6 & Grating (MC Deposit)	Rs. 98,161.00	Rs. 2,000.00	Two Months

23	C/o U-Shape drain near Dhobi Ghat Maranda on Maranda to Khalet road (SW:- C/o U-shape drain alongwith grating Km 0/480 to 0/675 (MC Deposit)	Rs. 97,952.00	Rs. 2,000.00	Two Months
24	C/o Aanganwadi Surd Ward No. 7 GP Nachir (Palampur) (SW:- Cement Plaster (Outer Side) & C/o Toilet i/c Sanitary work etc)	Rs. 99,818.00	Rs. 2,000.00	Three Months
25	C/o link road Band Vihar towards Jitender Bhuria House (SW:- P/L G-II & G-III (MC Deposit)	Rs. 99,099.00	Rs. 2,000.00	Two Months

Terms & Conditions:-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
M.P.W.D. Palampur

1

SCHEDULE OF QUANTITY

Sr. No.		Description of Item	Quantity	Rate		Unit	Amount
				In Word			
				In Figures			
Name of work:- C/o Retaining wall on Link road from Chardu (MC Palampur) to HPSEBL Rest House Via Badami Lal Sohan Lal near house of Sh. Kuldeep at Ward No. 1 Lohna Palampur. (SH:- C/o Retaining wall at Rd 0/060 to 0/068.10). MC Deposit							
Estimated cost Rs. 96510.00 Earnest Money Rs. 2000.00 Time Limits Two Months							
1		Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deteriorous materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.26			Per cubic metre	
2		Providing and laying, mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	20.45			Per cubic metre.	
3		Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	14.00			Each	
4		Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.65			Per cubic metre	
Total							

Executive Engineer,
Palampur Division
HP PWD Palampur

2

SCHEDULE OF QUANTITY						
Name of work:- C/o Retaining wall on Link road from Chardu (MC Palampur) to HPSEBL Rest House Via Badami Lal Sohan Lal near house of Sh. Kuldeep at Ward No. 1 Lohna Palampur. (SH:- C/o Retaining wall at Rd 0/070 to 0/078.10). MC Deposit			Estimated cost Rs.		96510.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.26			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government	20.45			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V) 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government	14.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.65			Per cubic metre	
Total						

Executive Engineer,
Palampur Division
HP, PWD Palampur

3

SCHEDULE OF QUANTITY

Name of work:- Dharamshala Yol Dadh Palampur road Km 28/00 to 33/00. (SH:- Hiring of JCB).

Sr. No.	Description of Item	Quantity	Rate		Unit	Two Months Amount
			In Figures	In Word		
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-servicable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage mtook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

4

SCHEDULE OF QUANTITY

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
Name of work:- Minor repair work of Combined office building (Mini Secretariat) Palampur Distt. Kangra (H.P.). (SH:- Repair of entrance porch & Repair of interlocking paver block back side of building).						
		Estimated cost Rs.		78523.00		
		Earnest Money Rs.		1600.00		
				Two Months		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.66			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.01			Per cubic metre.	
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	59.49			Per square metre	
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point nine litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seven five litre per ten square metre) of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.60			Per square metre	
Total						

Executive Engineer,
Palampur Division
HP, PWD Palampur.

5

SCHEDULE OF QUANTITY

Name of work:- C/o Approach road through Civil Hospital Palampur via Dental Residence, (SH:- C/o R/wall), MC Deposit

Estimated cost Rs.
96754.00
Earnest Money Rs.
2000.00
Time Limits
Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.66		Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	20.65		Per cubic metre.		
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	11.00		Each		
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.77		Per cubic metre		
Total						

Executive Engineer,
Palampur Division
HP. PWD Palampur.

16

SCHEDULE OF QUANTITY

Name of work:- Link road Chandpur to Speru. (SH:- P/F W metal beam Crash Barrier at Rd 0/430 to 0/453.25)

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			Time Limits			
			In Figures	In Word		
			Estimated cost Rs.	99668.00		
			Earnest Money Rs.	2000.00		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre.	
3	Providing and erecting of "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post. 150x75x5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 mtr.(two metre) center to center, 108 Mtr.(one hundred eight metre) high, 1.10Mtr.(one point ten metre) below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fitting confirm to IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm (one hundred fifty into seventy five into five millimetre) long complete clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.25			Per running metre	
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

5

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chachian to Drati Mathred road Km 0/00 to 3/900. (SH:- C/o Rising of existing drain walls (road side) at rd 1/420 to 1/480 and kahal crossing (iron grating at Rd 3/770).		Estimated cost Rs.		99439.00		
		Earneest Money Rs.			2200.00	
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.20			Per cubic metre	
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	90.00			Per Kilogram	
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	12.00			Per cubic metre.	
4	Steel work welded in built up sections Trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	353.50			Per Kilogram	
Total						

Executive Engineer,
Palampur Division
HP, PWD Palampur

18

SCHEDULE OF QUANTITY

Name of work:- C/o Interlocking tile work at Housing Board Colony Bindraban, (SH:- P/L interlocking tiles), MC Deposit

Estimated cost Rs. 99778.00

Earneest Money Rs. 2000.00

Time Limits Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.76			Per cubic metre.	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.00			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.66			Per cubic metre.	
Total						

Executive Engineer
Palampur Division
HP PWD Palampur

9

SCHEDULE OF QUANTITY

Name of work:-C/o Interlocking Tile works from main road Dharamshala Yol Dadh Palampur towards the house of Mehta. (SH:- P/L interlocking Tile works). MC Deposit

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Estimated cost Rs. Earnest Money Rs. Time Limits			99675.00 2000.00 Two Months
1	Demolishing cement concrete manually/ by mechanical means Nominal concrete 1:3:6 or richer mix(1/c equivalent design mix) including disposal of material within 50 metres lead as per direction of Engineer - in - charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.57			Per cubic metre	
2	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802.803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.30			Per cubic metre.	
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45.00			Per square metre	
4	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.56			Per cubic metre.	
5	Steel work welded in built up sections Trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	243.44			Per Kilogram	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Sr. No.		Description of item	Quantity	Rate		Unit	Amount
				In Word			
				In Figures			
Name of work:- C/o Interlocking Tile works from main road Dharamshala Yol Dadh towards Health Sub Centre Bindraban. (SH:- P/L interlocking Tile works). MC Deposit							
				Estimated cost Rs.		98793.00	
				Earnest Money Rs.		2000.00	
				Time Limits		Two Months	
1		Providing, laying, Soling 90 to 45mm (Ninety to forty five milimetre) nominal size Grading-I, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.68			Per cubic metre	
2		Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802.803.1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.68			Per cubic metre.	
3		Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	46.80			Per square metre	
4		Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.49			Per cubic metre.	
Total							

Executive Engineer,
Palampur Division
HP.PWD Palampur

11

SCHEDULE OF QUANTITY

Sr. No.		Description of Item	Quantity	Rate		Unit	Amount
				Time Limits			
				In Figures	In Word		
Name of work:- C/o interlocking tile work from main road Dharamshala Yol Dadh towards the house of colonel Chamaru Ram. (SHI- P/L interlocking tile), M.C. Deposit							
				Estimated cost Rs.		99423.00	
				Earnest Money Rs.		2000.00	
				Time Limits		Two Months	
1		Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802, 803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.80			Per cubic metre.	
2		Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	57.60			Per square metre	
3		Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.65			Per cubic metre.	
Total							

Executive Engineer,
Palampur Division
HP. PWD Palampur

<p align="center">SCHEDULE OF QUANTITY</p> <p>Name of work:- C/o Interlocking Tiles work for path main road differpat towards the house of Sh. Guddu Ram & Mangi (SH:- P/L Interlocking tiles) M.C. Deposit</p>						
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
				Estimated cost Rs.		74402.00
				Earnest Money Rs.		1500.00
				Time Limits		Two Months
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 15/04 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	53.50			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M:20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.94			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

(13)

SCHEDULE OF QUANTITY

Name of work:- Link road Bandla to Surdi Km 0/00 to 5/820. (SHI:- C/o R/wall at Rd 0/660 to 0/668.10)

Estimated cost Rs. 96538.00

Earnest Money Rs. 2000.00

Time Limits Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1) and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.36		Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	20.45		Per cubic metre.		
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	14.00		Each		
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.65		Per cubic metre		
Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

14

SCHEDULE OF QUANTITY

Work:-/C/O link road Banuri to main bazar odder 0/00 to 3/500 (SW:-/C/O 900 mm dia hume pipe culvert at RD 3/250)

No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Estimated cost Rs. Earnest Money Rs. Time Limits			
1	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	3.15			Per cubic metre	99153.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in Sub Structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.43			Per cubic metre.	2000.00
3	Providing and laying (to level or slope) 900 mm (Nine hundred milimetre) diameter reinforced cement concrete non pressure pipe I.S Class NP2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding the cost of excavation, protection works, backfilling, concrete and masonry work in head walls and parapets as per drawing and technical specifications clause 1101 and as per the direction of the Engineer -in-Charge including carriage of materials within all leads and lift and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.00			Per running metre.	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	18.00			Per cubic metre.	
Total						

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Culvert towards house of Sh. Vinod Kumar and others at village Matchar (Banuri). (SH.- C/o Hume Pipe Culvert). MC Deposit		Estimated cost Rs.		99889.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	36.74			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arriisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	3.08			Per cubic metre.	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arriise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.21			Per cubic metre	
4	Providing and laying (to level or slope) 900 mm (Nine hundred millimetre) diametre reinforced cement concrete non pressure pipe LS Class NP3 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding the cost of excavation, protection works, backfilling, concrete and masonry work in head walls and parapets as per drawing and technical specifications clause 1101 and as per the direction of the Engineer -in-Charge including carriage of materials within all leads and lift and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.50			Per Running metre	
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

16

SCHEDULE OF QUANTITY

Name of work:- Repair of road from Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 15/00 to 27/00. (SH:- C/o R/wall at Rd 22/132 to 22/142). DC Deposit 10.00 Lacs		Estimated cost Rs.		Unit	Amount
		Earnest Money Rs.			
		Time Limits			
Sr. No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60		Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00		Each	
Total					

Executive Engineer
Palampur Division
HP.PWD Palampur

19

SCHEDULE OF QUANTITY

Name of work:- C/o U-Shape Drain near House of Sh. Joginder Chauhan , Millap Chand Lohna. (SH:- C/o U-Shape Darin). M.C. Deposit		Estimated cost Rs. Earnest Money Rs. Time Limits		99792.00 2000.00 Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseled / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	28.24			Per cubic metre
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government	19.55			Per cubic metre.
Total					

Executive Engineer,
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Retaining wall at Bindraban chowk near the house of Sh. Ashok Naryal & Others. (SH:- C/o R/wall). M.C.

Estimated cost Rs. 98076.00

Earnest Money Rs. 2000.00

Time Limits Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.81			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement : five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental, complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.02			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.84			Per cubic metre	
Total						

Executive Engineer,
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY						
Name of work:- C/o Interlocking Tile work from Pardeep Kumar House towards Jagdish House on Saurabh Kalia road. (SH:- P/L Interlocking Tiles). MC Deposit						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
				Estimated cost Rs.		99578.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
1	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials with imposed all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre.	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm. as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	64.00			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M:Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.66			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from HPSEBL Rest House Lohna to Vijay Sharma & others house Km 0/00 to 0/160. (SH:- Improvement of grade & C/o R/wall & C.C Pavement). MC Deposit

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures			
			In Word			
			Estimated cost Rs.	97152.00		
			Earnest Money Rs.	2000.00		
			Time Limits	Two Months		
1	Demolishing Nominal cement concrete 1:3:6 or richer mix (1/2 equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.28			Per cubic metre	
2	Stone soling property hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading, watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	5.28			Per cubic metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.28			Per cubic metre.	
4	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of sumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.99			Per cubic metre	
5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	11.52			Per cubic metre.	
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	3.00			Each	
7	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
	Total					

21

SCHEDULE OF QUANTITY						
Name of work:- C/o road to House of D.S. Pathania & Others in MC ward No. 13 Palampur. (SH:- C/o R/wall). MC Deposit						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
				Estimated cost Rs.		99831.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.93			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement: Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arriisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	20.13			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
	Total					

Executive Engineer
Palampur Division
HP:PWD Palampur.

21

SCHEDULE OF QUANTITY						
Name of work:- C/o road to House of D.S. Pathania & Others in MC ward No. 13 Palampur. (SH:- C/o R/wall). MC Deposit						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
				Estimated cost Rs.		99831.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.93			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arriren at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	20.13			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
	Total					

Executive Engineer
Palampur Division
HP:PWD Palampur.

22

Name of work:- C/o U-Shape Drain from Chopati to Santoshi Mata Chowk. (SHI:- Demolition & P/L 1:3.6 & Grating). MC						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
Estimated cost Rs.						98161.00
Earnest Money Rs.						2000.00
Time Limits						Two Months
1	Demolishing Nominal cement concrete 1:3.6 or richer mix (i/c equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.12			Per cubic metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of sumps and other deteriorous materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials in the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including cleaning of within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	9.05			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arriisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	5.36			Per cubic metre.	
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	719.10			Per Kilogram	
Total						

Executive Engineer
Palampur Division
HP-PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o U-Shape Drain Near Dhobi Chat Maranda on Maranda to Khalet. SH:- C/o U- Shape darin alongwith Grating
 Km 0/480 to 0/675). MC Deposit

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
						Estimated cost Rs. 97952.00 Earnest Money Rs. 2000.00
1	Demolishing Nominal cement concrete 1:3:6 or richer mix (i/c equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.11			Per cubic metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chisealing / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 3051 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting, and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	9.03			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arriisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government	5.35			Per cubic metre.	
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	717.57			Per Kilogram	
	Total					

Executive Engineer
 Palampur Division
 HP PWD Palampur.

24

SCHEDULE OF QUANTITY									
Name of work :- C/O Aanganwadi Surad Ward No. 7 G.P. Nachir (Palampur) (SW :- Cement Plaster (outer side) & C/O Toilet including sanitary Works etc.)									
Sr. No	Description of Item	Quantity	Rate		Unit	Amount	Estimated cost Rs.		
			In Figures	In Word			Earnest Money Rs.		
							Time Limits		
1	15 mm cement plaster on rough side of single or half brick wall of mix : 1:6 (one cement isto six coarse sand). The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	83.23			Per square metre	99818.00			
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 75 mm diameter. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.00			Per running metre	2000.00			
3	Providing and fixing W.C. pan with ISI marked white solid plastic seat and lid of white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00			Each				
4	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00			Each				
5	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each				
6	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.00			Each				
7	Providing and fixing 15 mm nominal bore brass bib cock of approved quality including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.00			Each				
8	Providing and fixing 15mm nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS-8931. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.00			Each				
9	Providing and fixing 15 mm nominal bore C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS-8931, including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Each				
10	Providing and fixing 100 mm nominal dia with 25 mm waste hole PTMT grating of approved quality and colour. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.00			Each				
11	Providing and fixing 15 mm nominal bore ball valve (brass) of approved quality, High or low pressure, with plastic floats complete. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00			Each				
12	Providing and fixing 110 mm dia PVC pipe including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.00			Per running metre				

13	Providing and fixing PTMT shelf 440 mm long, 124 mm width and 36 mm height of approved quality and colour, weighing not less than 300 gms. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government	1.00	Each
14	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 Per Kilogram/ sqm including grinding the joints with white cement and matching pigments etc., complete size of tile 600*600mm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.98	Per square metre
15	Providing and fixing ISI quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government	25.43	Per square metre
16	Providing and fixing 15 mm nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	50.00	Per Running metre
17	Providing and fixing 110 mm dia high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. complete. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government	30.00	Per Running metre
18	Providing and fixing 75 mm dia high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. complete. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government	27.00	Per Running metre
19	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete 110 mm dia. as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government	2.00	Each
20	Providing and fixing PVC collars 110 mm dia ISI marked including fixing with approved adhesive etc. complete. as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government	2.00	Each
21	Providing and fixing PVC collars 75 mm dia ISI marked including fixing with approved adhesive etc. complete. as per the direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government	2.00	Each
22	Providing and fixing 110 mm PVC plain bend ISI marked including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government	5.00	Each
23	Providing and fixing 75 mm PVC plain bend ISI marked including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government	5.00	Each
Total			

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY
Name of work:- C/o Link road Band Vihar towards Jitender Bhuria House. (Sh.- P/L G-II & G-III). MC Deposit

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
						99099.00
						2000.00
						Two Months
						Estimated cost Rs.
						Earnest Money Rs.
						Time Limits
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.78			Per cubic metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	21.78			Per cubic metre	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur.