

Himachal Pradesh
Public Works Department

No. PW-SD-I-CTR- Tender-NIT/2021-22-10868-70 Dated:- 23/08/2021

To

The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2020 dated Shimla-2 the 16th July 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .
2. The Computer cell O/O Executive Engineer (IT) cell Nigam Bihar Shimla-2.


Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|---------------------------|
| 1. Date of receipt of application for tender forms:- | 31-08-2021 |
| 2. Dated of Issue /sale of tender forms:- | 01-09-2021. |
| 3. Date of receipt of tender:- | 02-09-2021 up to 10:30 AM |
| 4. Date of opening of tender:- | 02-09-2021 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O on Kanda to Mulkoti road km., 4/00 to 13/240 (SH;- Repair of pot Holes between RD. 11/00 to 13/240)(Balance work).	387853/-	7800/-	350/-	30 days	Class-D
2	A/R & M/O on Kanda to Mulkoti road km. 4/00 to 13/240 (SH;- Repair of pot Holes between Rd. 8/00 to 10/00).	481927/-	9700/-	350/-	30 days	Class-D
3	Construction/Improvement on Circular road in Shimla Town via Lakkar Bazar at Rd. 147/825 to 153/075 (SH;- C/O R.C.C. Breast wall at Rd. 147/900 to 147/930).	499171/-	10000/-	350/-	60 days	Class-D
4	A/R & M/O to various residence qtrs at Kasumpti Shimla-9 (SH;- Providing and fixing pine wood pandling wooden door cup board in type-VI set No. 2 and painting work in type-V set No.11,12,17 at Kasumpti Shimla-9).	94317/-	1900/-	350/-	30 days	Class-D
5	A/R & M/O to various non residence building and minor repair work in HPPWD sub Division No.VIII at Kasumpti Shimla-9).	91969/-	1900/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

- The valid enlistment/Registration of contractor in Appropriate Class.
- Permanent account No. (PAN NO).
- G.S.T No.
- Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
- The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form . The application received without earnest money & cost of tender form shall summarily be rejected.
- The officer of the tender shall remain valid up to 75 days after the opening of tender.
- Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
- Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
- If the date given above happens to be holiday the same shall be processed on next working day.
- The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
- The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
- One contractor shall not have more than two major works in hand at a time.
- Work should be completed by the contractor within stipulated period.

Executive Engineer,
Shimla Division No-I,
HPPWD, Shimla-3.

No.PW-SD-I/CB-Tender/21-22-

10871-99

Dated :- 23-8-2021

Copy forwarded to :-

- Copy to the Deputy Commissioner Shimla Distt. Shimla.
- The Superintending Engineer, 4th Circle, HPPWD ., Shimla-3 for information please.
- Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
- Copy to the Sub Divisional Magistrate (U) Shimla.
- Copy to the Sub Divisional Magistrate (R) Shimla.
- Copy to Municipal committee Shimla Distt. Shimla.
- Copy to Block Development officer Mashobra Distt. Shimla.
- All the Assistant Engineers under this Division, HPPWD Shimla-3.
- Superintendent / HDM /DAO.
- Copy to all concerned contractor,
- Notice Board.

Executive Engineer,
Shimla Division No-I,
HPPWD., Shimla.

SCHEDULE OF QUANTITY

Name of work: -A/R & M/O on Kanda to Mulkoti Road Km. 4/00 to 13/240 (SH:-Repair of Pot Holes Between RD. 11/00 to 13/240) (Balance Work)

Estimated Cost: -Rs.387853/- only
Earnest Money : Rs.7800/-Only
Time - One Month

S.N o.	Sub head and items of work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3			6	7
1	Repair to Pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904, 2, 503 and 508. 1. including Carriage of Materials with in all leads and lifts as per direction of Engineer -In - Charge.	2272.13	Sqm.		Per Square metre	
					Total	

Executive Engineer,
Shimal Division No.1
HP,PWD, Shimla

SCHEDULE OF QUANTITY

Name of work: -A/R & M/O on Kanda to Mulkoti Road Km. 4/00 to 13/240 (SH:-Repair of Pot Holes Between RD. 8/00 to 10/00)

Estimated Cost -Rs. 481927- only
 Earnest Money : Rs.9700/-Only
 Time - One Month

S.N o.	Sub head and items of work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3			6	7
1	Repair to Pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904, 2, 503 and 508.1. including Carriage of Materials with in all leads and lifts.as per direction of Engineer -In - Charge.	2823.24	Sqm.		Per Square metre	
					Total	

Executive Engineer,
 Shimla Division No.1
 MHP,PWD, Shimla-3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 4,99,171.00	
Name of Work :- Construction /Improvement on Circular road in Shimla Town via Lakkar Bazar at RD.147/825 to 153/075 (SH: C/O R.C.C. Breast Wall at RD.147/900 to 147/930)					Earnest Money :- 10,000.00	
					Time:- 60 Days.	
Sr. No	Description of Work / Item (S)	No. of Qty.	Estimated Rate		Unit	Amount
			In figures	In words		
1	Earth work in rough excavation, banking excavated earth in layers not exceeding 20cm(Twenty centimetre) in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and topmost layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) All kinds of soil	67.50	Cum		Per Cubic Metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty milimetre) nominal size)	10.35	Cum		Per Cubic Metre	
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : three coarse sand) : Six graded stone aggregate 20 mm (Twenty milimetre) nominal size)	37.80	Cum		Per Cubic Metre	
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Mild steel and Medium Tensile steel bars	1587.60	Kgs.		Per Kilogram	
5	Centering and shuttering including strutting, propping etc. and removal of form work for (i) Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	108.00	Sqm		Per Square Metre	

6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred millimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	35.00	Nos				Each	
							Total	


 Executive Engineer,
 Shimla Division No.1,
 HP PWD Shimla-3.



SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.				Estimated Cost:-94,317.00		
Name of Work :- A/R & M/O to various residence quarter at Kasumpti Shimla-9 (SH: Providing and fixing Pine wood paneling, wooden door , cup board in type-VI set no.2 and Painting work in Type-V set No.11,12,17 at Kasumpti Shimla-9)				Earnest Money :- 1,900.00		
				Time:- 30 Days.		
Sr. No	Description of Work / Item (S)	No. of Qty.	Estimated Rate		Unit	Amount
			In figures	In words		
1	Providing and fixing Pine wood readmade plain framed panelling with necessary screws priming coat on unexposed surface etc. complete with pine wood including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.35	Sqm		Per Square Metre	
2	Applying spirit or oil stains (any colour)on wood and wood based surfaces to given an even surfaces including cleaning the surfaces of all dirt,dust and sand papering so as to produce a smooth dry and matt surface including stopping & knotting including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.35	Sqm		Per Square Metre	
3	Applying three coat of sealar filling on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt,dust and sand papered smooth and inncluding a coat of wood filler including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.35	Sqm		Per Square Metre	
4	Polishing two coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt,dust and sand papered smooth and including a coat of wood filler including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.35	Sqm		Per Square Metre	
5	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarlied on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	300.00	Sqm		Per Square Metre	
6	Painting one coat (excluding priming coat) on previously painted wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	50.00	Sqm		Per Square Metre	
	b) With enamel paint other than white	50.00	Sqm		Per Square Metre	
7	Extra over item No. 6 for every subsequent coat of paint on previously painted wood and wood based surfaces with enamel paint brushing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	25.00	Sqm.		Per Square Metre	

	b) With enamel paint other than white.	25.00	Sqm.			Per Square Metre	
8	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint	50.00	Sqm			Per Square Metre	
9	Extra for every subsequent coat of paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. i) With white enamel paint	25.00	Sqm			Per Square Metre	
10	Removing old paint or polish from wood and wood based surfaces with paint remover of approved brands and manufacture and making the surface even with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. i) Caustic soda	50.00	Sqm			Per Square Metre	
11	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	200.00	Sqm			Per Square Metre	
12	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	150.00	Sqm			Per Square Metre	
13	Applying priming coat on new concrete/masonry/asbestos cement/plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Ready mixed primer	150.00	Sqm			Per Square Metre	
14	Painting two coats (excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stopping including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	50.00	Sqm			Per Square Metre	
15	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.80	Sqm			Per Square Metre	
16	Providing and fixing 19mm thick commercial board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.16	Sqm			Per Square Metre	

17	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.16	Sqm			Per Square Metre
18	a) 6mm thick. Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.16	Sqm			Per Square Metre
19	Providing and fixing square edges cover fillets (beading) 19mmx6mm section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) 1st class deodar wood.	30.00	Rmt			Per Running Metre
20	Providing and fixing bright finished brass handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. i) 100mm	15.00	Nos			Each
21	Providing and fixing magnetic Catchers ISI marked with necessary screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	15.00	Nos			Each
22	Providing and fixing chromium plated brass 50 mm cup board or wardrobe knobs with nuts complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.00	Nos			Each
23	Applying priming coat over new wood and wood based surfaces after and i/c preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Ready mixed paint brushing wood primer pink.	50.00	Sqm			Per Square Metre
24	Painting two coats (excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stopping including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	50.00	Sqm			Per Square Metre
25	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	50.00	Sqm			Per Square Metre
26	Providing and fixing E aluminium Channel for glass shutter sliding complete as per direction of Engineer-in-Charge.	2.50	Rmt			Per Running Metre
27	Supplying and fixing glass panes in E aluminium channel including rehu roller for sliding smoothly and stickers complete in all respect (E channel paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Plain Glass :5mm thick	0.36	Sqm			Per Square Metre

28	Providing and fixing 4mm thick teak ply of standard quality and of approved shade & design wall lining including fixing with approved adhesive butt jointing and nails & screws complete (Brass frame work to be measured & paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.16	Sqm				Per Square Metre	
29	Providing and fixing aluminium slider channel top and Bottom with rolling balls 1.50 mtr. length for heavy door complete with all accessories including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Sqm				Per Square Metre	
30	Providing and fixing 100mm bright finished brass floor door stopper with rubber cushion screws etc. to suit shutter thickness complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	5.00	Nos				Each	
31	Providing and fixing S.S. curtain rod complete with accessories including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	23.00	Rmt				Per Running Metre	
32	Providing and fixing paneled glazed or paneled and glazed shutters for doors windows and clerestory windows including black enameled iron butt hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a)40mm thick i)2nd Class Deodar Wood.	2.16	Sqm				Per Square Metre	
							Total	

Executive Engineer,
Shimla Division No.1,
HP PWD Shimla-3.

[Signature]

SCHEDULE OF QUANTITY

Estimated Cost:- 91,969.00
Earnest Money :- 1,900.00
Time:- 30 Days.

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.
Name of Work :-A/R & M/O to various non residence buildings at Kasumpti Shimla-9 (SH: Providing and fixing Cup board and Minor repair work in HPPWD Sub-Division No.VIII at Kasumpti Shimla-9)

Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	58.41	Sqm			Per Square Metre	
2	Providing and fixing 19mm thick commercial board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	25.71	Sqm			Per Square Metre	
3	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 6mm thick.	22.74	Sqm			Per Square Metre	
4	Providing and fixing 1.00mm thick coloured or plain lamination sheet (summica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	17.14	Sqm			Per Square Metre	
5	Providing and fixing square edges cover fillets (beading) 19mmx6mm section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 1st class deodar wood	98.10	Rmt			Per Running Metre	
6	Providing and fixing bright finished brass handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. i) 100mm	70.00	Nos			Each	
7	Providing and fixing magnetic Catchers ISI marked with necessary screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	60.00	Nos			Each	
8	Providing and fixing chromium plated brass 50 mm cup board or wardrobe knobs with nuts complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	5.00	Nos			Each	
9	Applying priming coat over new wood and wood based surfaces after and i/c preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Ready mixed paint brushing wood primer pink.	56.08	Sqm			Per Square Metre	

10	Painting two coats (excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stopping including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	56.08	Sqm			Per Square Metre
11	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	50.00	Sqm			Per Square Metre
12	Providing and fixing E aluminium Channel for glass shutter sliding complete as per direction of Engineer-in-Charge.	3.40	Rmt			Per Running Metre
13	Supplying and fixing glass panes in E aluminium channel including rehu rollar for sliding smoothly and stickers complete in all respect (E channel paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Plain Glass :5mm thick	2.72	Sqm			Per Square Metre
						Total


 Executive Engineer,
 Shimla Division No.1,
 HP PWD Shimla-3.

