



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22
To

6498-6508

Dated 31-08-2021

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **09.09.2021** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **08.09.2021** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF** failing which no tender form will be issued to him.

Work No.:-1

Improvement of black spots on Wazir Bowali Nirmand Arsu Sarahan road Km. 0/00 to 34/00. (SH:- Improvement of curve in Km. 6/255 to 7/045, 7/250, 7/510 to 7/540, 7/660, 7/690, 7/795 to 7/825 and 8/210 to 8/300). Jio deposit. Estimated cost: Rs. 4,65,705/- Earnest money Rs.:- 9400/- time one month Cost of form:-350/-

Work No.:-2

A/R & M/O Various roads under Brow Sub-Division. (SH:- Supplying and stacking of dual directional delineators and supplying and fixing dual directional retro reflective plastic road studs/cat eyes). Estimated cost: Rs. 4,81,200/- Earnest money Rs.:- 10000/- time one month Cost of form:-350/-

Work No.:-3

Increase in height of boundry wall and fancing work at GSS School Samej. (SH:- C/o Protection wall from Rd 0/090 to 0/105) under deposit work. Estimated cost: Rs. 4,92,716/- Earnest money Rs.:- 10000/- time ,one month Cost of form:-350/-

Work No.:-4

Improvement of black spots on Wazir Bowali Nirmand Arsu Sarahan road Km. 0/00 to 34/00. (SH:- Improvement of curve in Km. 10/015 to 10/075). Jio deposit. Estimated cost: Rs. 4,92,830/- Earnest money Rs.:- 9900/- time one month Cost of form:-350/-


Work No.:-5

Construction of link road from Village Shalog to Dugha via Lahut Km. 0/00 to 1/700 under BASP. (SH:- Formation cutting 5/7 mtr wide road in Km. 0/360 to 0/705). Estimated cost: Rs. 4,97,471/- Earnest money Rs.:- 10000/- time one month Cost of form:-350/-

Work No.:-6


A/R & M/O Various roads under Dalash Sub-Division. (SH:- Supplying and stacking of dual directional delineators and supplying and fixing dual directional retro reflective plastic road studs/cat eyes). Estimated cost: Rs. 4,12,400/- Earnest money Rs.:- 10000/- time one month Cost of form:-350/-

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh


Certificate

Certified that the tenders called vide this Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 6498-6508 dated 31.08.2021 is very urgent nature. So may be uploaded on Departmental website in public interest please.


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh

Schedule of quantity

Name of Work: Improvement of identified black spots on Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 . (SH:- Improvement of narrow curves at RD. 6/255 to 6/330, 6/970 to 7/045, 7/250 to 7/280, 7/510 to 7/540, 7/660 to 7/690, 7/795 to 7/823 and 8/210 to 8/300)					Estimated cost:-		465707.00
					Earnest Money		10000
					Time		One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT
					Words		
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract ot achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 264.67 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2006.32	Cubic Metre				
Total in Figures							


 Executive Engineer
 Outer Sero Division
 H.P.W.D. Nimand

Schedule of Quantity

Name of work: - A/R & M/O various roads under Brow Sub-Division. (SH:-Supplying and stacking of dual directional delineators and Supplying and fixing dual directional retro reflective plastic road studs/cat-eyes.)

Estimated cost:- 481200.00

Earnest money:- 10000.00


Time:- One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Supplying and stacking of approved brand and manufacture dual directional delineators of size 39mmX39mm having 2 (two) feet height made of high quality rounded reflector fixed on both sides to make it highly visible in poor light condition. The rates are inclusive all taxes and including carriage of materials in all leads and lifts as per direction of the Engineer-In-Charge complete.	600 Nos.	Each			
2	Supplying and fixing of approved brand and manufacture dual directional retro reflective plastic road studs/cat-eyes studs Art No. C-1210 with dimensions 100mmX100mm and 20mm thickness in yellow, white and red colours (two way acrylic presmetic reflector). The rates are inclusive all taxes and including carriage of materials in all leads and lifts as per direction of the Engineer-In-Charge complete	200 Nos.	Each			

Executive Engineer,
Outer Serai Division,
HP.PWD, Narnand.

Schedule of quantity

Name of Work:- Increase in height of boundary wall and fencing work at GSS School Sumej. (SH:- C/O Protection Wall from RD. 0/090 to 0/105) under deposit work							Estimated cost:-		492716.00
							Earnest Money		10000
							Time		One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
				Words					
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	40.37	Cubic Metre						
2	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.27	Cubic Metre						
3	Providing and Laying cement concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 40 mm (forty millimetre) nominal size) with 15% plums and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, the size of plum should be 150 to 300 mm as per drawing and HP.PWD technical specifications including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	87.75	Cubic Metre						
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.40	Cubic Metre						
Total in Figures									


 Executive Engineer
 Gutter Seral Division
 HP.PWD, Noida

Signature of Tenderer with seal

Schedule of quantity						
Name of Work: Improvement of identified black spots on Wazir Bowali Nirmand Arsu Sarahan road km. km. 0/00 to 34/00 . (SH:- Improvement of narrow curves at RD. 10/015 to 10/075)				Estimated cost:- Earnest Money		492820.00
				Time		10000
				One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract of achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 368.21 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1262.41	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Serai Division
 HPWD, Jalandhar

Schedule of quantity

Schedule of quantity								
Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/360 to 0/705)				Qty.	Unit	Figures	Estimated cost:-	497471.00
							Earnest Money	10000
							Time	One month
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT	
					Words			
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract of achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 200.57 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2005.77	Cubic Metre					
Total in Figures								


Executive Engineer
 Outer Sarai Division
 HPPWD, Mirmand

Signature of Tenderer with seal

Schedule of Quantity


Name of work: - A/R & M/O various roads under Dalash Sub-Division. (SH:-Supplying and stacking of dual directional delineators and Supplying and fixing dual directional retro reflective plastic road studs/cat-eyes.)

Estimated cost:- 412400.00

Earnest money:- 10000.00

Time:- One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Supplying and stacking of approved brand and manufacture dual directional delineators of size 39mmX39mm having 2 (two) feet height made of high quality rounded reflector fixed on both sides to make it highly visible in poor light condition. The rates are inclusive all taxes and including carriage of materials in all leads and lifts as per direction of the Engineer-In-Charge complete.	320 Nos.	Each			
2	Supplying and fixing of approved brand and manufacture dual directional retro reflective plastic road studs/cat-eyes studs Art No. C-1210 with dimensions 100mmX100mm and 20mm thickness in yellow, white and red colours (two way acrylic presmetic reflector). The rates are inclusive all taxes and including carriage of materials in all leads and lifts as per direction of the Engineer-In-Charge complete	400 Nos.	Each			


 Executive Engineer,
 Outer Serai Division,
 HP.PWD, Nirmand.