

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT -Executive Engineer, Tauni Devi Division HP:PWD,
Tenders for the following works:-

Sealed item rate tenders on form No. 6 & 8 are hereby invited works shown below:- Date of receipt of Applications for tender forms:- 27.09.2021. upto 1.00 PM. Date of issue/sale of Tender forms 28.09.2021- 2:00 P.M. to 5.00 PM 3. Date of receipt of Tender:- 28.09.2021 at 11.00 AM 4. Date of opening of Tender:- 28.09.2021 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time
1.	C/O link road from Bhalana to Chaleji km. (SH:- R/wall at RD 1/860 to 1/869).	469153.00	9500.00	Two Months.
2.	R/R damages on Hamirpur to Sujanpur road Km. 2/600 to 18/300 (SH:- C/o R/wall at RD 3/850 to 3/858).	372666.00	7500.00	Two Months.
3.	C/o link road Chamiana to Bhadeen via Taryamali Km.0/0 to 2/765 (C/o R/wall at RD 0/364 to 0/369)	149807	3000.00	Two Months.
4.	C/o 4.60 mtr span RCC slab culvert on Radha Swami satsang beas centre at karot (SH:- C/o 4.60mtr span RCC slab culvert)	455575.00	9200.00	Two Months.
5.	R/R damages on Ree Saluhi road Km. 0/0 to 2/0 (SH:- R/wall at RD 0/035 to 0/042)	148881.00	3000.00	Two Months.
6.	C/o missing C.D. on Hamirpur Sujanpur road Km.0/0 to 24/785 (SH:- C/o 900 mm dia hume pipe culvert at RD 18/375).	93606.00	2000.00	Two Months.
7.	C/o L/R from Dulwana to Lambehra via Dhangota Brahmana Dhangota Lohakhrian Km. 0/0 to 4/0 (SH:- C/o GSB, WMM from RD 0/405 to 0/865 & V-shape drain in Km. 0/405 to 0/855).	425103.00	8500.00	Two Months.
8.	C/o L/R from Dulwana to Lambehra via Dhangota Brahmana Dhangota Lohakhrian Km. 0/0 to 4/0 (SH:- C/o RCC hume pipe culvert 900 mm dia at RD 0/610,0/695,0/765,0/824 i/c PCC wing wall 3.00 mtr both side).	413622.00	8500.00	Two Months.
9.	C/o Jeepable road from Mahila Mandir Bhawan upto house of Smt. Bimla Devi and others in Rakrial G.P. Bassi Jhanyara Km.0/0 to 0/050 (SH:- M/T work at RD 0/0 to 0/050) Under Minor works).	99661.00	2000.00	Two Months.
10.	C/o Jeepable road from Mahila Mandir Bhawan upto house of Smt. Bimla Devi and others in Rakrial G.P. Bassi Jhanyara Km.0/0 to 0/050 (SH:- C/o Edge wall at RD 0/0 to 0/022) Under Minor works).	327059.00	6500.00	Two Months.

TERMS AND CONDITIONS:-

NOTE:- The tender documents shall be issued only to those contractors/firms who fulfill the criteria and submit the documents with the application as required. Terms and condition same as previous /Notice Board.

And Gill
Executive Engineer
Tauni De. i
H.P.P.W.D. Tauni De. i

Schedule of Quantity

Estimated Cost:- 469153.00
Earnest Money:- 9500.00
Time:- Two Months.

NAME OF WORK:- C/O link road from Bhalana to Chaleli km. 0/0 to 2/00. (SH:- C/O R/Wall at RD. 1/860 to 1/869). (Under SCSP).

Sr. No.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m,(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	38.34			Per Cum.	
2.	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	85.08			Per Sqm.	
3.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	71.62			Per Cum.	
4.	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm (one hundred ten millimeters) diameter, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	20.00			Each	
					Total:-	

And
Executive Engineer,
Tauni Devi Division,
HP-PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 372666.00
Earnest Money:- 7500.00
Time:- Two Months.

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujanpur road km. 2/600 to 18/300. (SH:- C/O R/Wall at RD. 3/850 to 3/858).
(Deposit work).

Sr.N o.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m.(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	25.36			Per Cum.	
2.	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	61.55			Per Sqm.	
3.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	57.39			Per Cum.	
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	20.00			Each	
					Total:-	


 Executive Engineer,
 Jauni Devi Division,
 HP:PWD., Jauni Devi

Schedule of Quantity

DESCRIPTION OF WORK:- Construction of proposed 4.60mtr. Span R.C.C slab culvert on approach road to Radha Swami
 g Beas centre at Karot Distt. Hamirpur (H.P). (SH:- C/O 4.60mtr. Span R.C.C slab culvert) (Deposit Work)

Estimated Cost:- Rs.455575.00

Earnest Money:- Rs.9200.00

Time:- Two Months

Description of Items	Qty.	Rate		Unit	Amount
		In Fig.	In Words		
Earth work in excavation for all types of road structures such as retaining walls, breast walls, Culverts, drains and parapets etcetera in all types of classification of soil comprising of ordinary soil, ordinary rock , hard rock , chiseling/wedging out or rock (where blasting in prohibited) as per drawing and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and black filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an strutting and pumping and bailing out water up to any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	53.37			Per cubic metre	
Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1, 1603.2 including entire carriage of material with in all leads and lifts.	28.30			Per cubic metre	
Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202&1203 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts. Nominal mix 1:4:8(one cement: four sand : eight graded stone)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	3.03			Per cubic metre	
Providing and laying mechanically mixed cement concrete 1:3:6 (one cement : three sand : six graded crushed stone aggregate on ground for under water and curing comeplete including pumping or bailing out water, dewatering removal of slushy as required at site which may arise at the time of laying under water complete for all heights and depths including cost to form work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals.	11.70			Per cubic metre	

Schedule of Quantity

5

Estimated Cost:- 148881.00
Earnest Money:-3000.00
Time:- Two Months.

NAME OF WORK:- Restoration of rain damages on Ree Saluhi road km. 0/0 to 2/0.(SH:- C/O R/Wall at RD. 0/035 to 0/042).(Deposit work).

Sr.N o.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m.(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	9.87			Per Cum.	
2.	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	36.18			Per Sqm.	
3.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	22.08			Per Cum.	
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204 3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	9.00			Each	
					Total:-	

Anil Chaur
Executive Engineer,
Tauni Devi Division,
H.P.PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 93606.00
Earnest Money:- 2000.00
Time:- Two Months

Line of work:- C/O missing CD on Hamirpur Sujjanpur road Km 0/00 to 24/785.

(SH:- C/O 900mm dia hume pipe culvert at RD 18/375) (Near Bhaaleth Bridge)

No	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
	Excavation in soil in hilly area by mechanical means including cutting trimming of side slopes and disposing of excavated earth with a lift upto 1.5mtr. And a lead upto 20 mtr. as per technical specification plc jumper work as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents	2.52			Per cubic metre	
	Earth work in excavation for all types of road structures such as retaining walls, breast walls, Culverts, drains and parapets etcetera in all types of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawing and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and black filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an strutting and pumping and balling out water up to any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.	54.45			Per cubic metre	
	Providing and laying mechanically mixed cement concrete 1:3:6 (one cement : three sand : six graded crushed stone aggregate on ground for under water and curing complete including pumping or bailing out water, dewatering removal of slushy as required at site which may arise at the time of laying under water complete for all heights and depths including cost for work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals.	2.68			Per cubic metre	
	Providing and laying cement concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation complete as per drawing and technical specification clause 802,803,1202& 1203. PCC grade M-15(M-Fifteen) nominal mix 1:2.5:5(one cement : two point five sand: five graded crushed stone aggregate) 40mm (forty millimeters) nominal size as per direction of Engineer-in-Charge including entire.	18.08			Per cubic metre	
	Providing and laying cement concrete mechanically mixed and vibrated 1:5:10 (one cement: five sand : ten graded crushed stone aggregate) curing complete including the cost of form work for plain/reinforced concrete in retaining walls, breast walls without plumb as per drawing and HP.PWD., technical specifications clause 802,803,1202,1203 as per direction of Engineer-in-Charge including entire carriage of material in all leads and lifts.	1.00			Per cubic metre	

Schedule of Quantity

Estimated Cost:- 425103.00
Earnest Money:- 8500.00
Time:- Two Months.

NAME OF WORK:- C/O link road from Dulwana to Lambhara via Dhangota Brahmana Dhangota Lohakhrian km. 0/0 to 4/0.(SH:- C/O GSB, WMM from RD. 0/405 to 0/865 & V-shape drain in km. 0/405 to 0/855). (Under SCSP).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1	Compacting original ground supporting sub-grade including loosening of the ground upto a level of 300mm(three hundred millimeters) below the sub-grade level, watered, graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub-grade construction as per technical specification clause 303.5.2 and as per direction of Engineer-in-Charge.	316.58			Per cubic metre.	
2	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub-grade to be paid for separately) depending upon the classification of soil completed as per HP-PWD., specification and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	1582.88			Per Square metre	
3.	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP-PWD., specifications and as per direction of Engineer-in-Charge.	1582.88			Per Square metre	
4	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site upto lead of 1000m (one thousand metre) spreading in uniform layers with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per technical specification clause 401 for grading-III material, as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.	237.44			Per cubic metre.	
5	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred)weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.	144.11			Per cubic Metre.	
6	Construction of V-Shape drain with cement concrete 1:3:6 (one cement: three sand: six graded crushed stone aggregate 20mm (twenty millimeters nominal size) with thickness of concrete 10cm (ten centimeters) and size of drain 45x25 cm(forty five into twenty five centimeters) including cost of from work with steel plate excavation in earth work in all kind of soil and curing complete as per drawing and technical specification as per direction of Engineer-in-Charge including entire carriage of material in all leads and lifts.	40.00			Per running metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Arif Chav
Executive Engineer,
Taun Devi Division,
HP-PWD., Tauni Devl.

Schedule of Quantity

Estimated Cost- 413622.00

Earnest Money:- 8500.00

Time- Two Months.

NAME OF WORK:- C/O link road from Dulwana to Lambehra via Dhangota Brahmana Dhangota Lohakhrian km. 0/0 to 4/0 (SH:- C/O RCC hume pipe type culvert 900mm dia at RD.0/610, 0/695, 0/765, 0/824 i/c PCC wing wall 3.00mtr. both side). (Under SCSP)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	185.76			Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802, 803, 1202 and 1203 P.C.C. grade 1:4:8 (one cement four sand: eight graded crushed stone aggregate) nominal mix as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.90			Per cubic metre	
3	Providing and laying mechanically mixed concrete 1:3:6 (one cement three sand: six graded crushed stone aggregate) on ground for under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	59.11			Per cubic metre	
4	Providing and laying mechanically mixed and vibrated cement concrete 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls/breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	56.42			Per cubic metre	
5	Backfilling behind abutment, wing wall and return wall with granular material complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals.	17.42			Per cubic metre	
6	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900mm(nine hundred millimeters) dia. as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	30.00			Per running meter	
7	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastiflex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (IV): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals.	40.00			Each	
8	Providing and laying mechanically mixed cement concrete 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803, 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals.	1.10			Per cubic metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HP-PWD., Tauni Devi.

Schedule of Quantity

Estimated Cost:- 99661.00

Earnest Money:- 2000.00

Time:- Two Months.

Name of Work:- C/O Jeepable road from Mahila Mandal Bhawan upto house of Smt. Bimla Devi and others in Rakrial G.P. Bassi Jhanyara km. 0/0 to 0/050. (SH:- M/T work at RD. 0/0 to 0/050). (Under Minor Works).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in surface excavation not exceeding 30 cm (thirty centimeter) in depth but exceeding 1.5 m (One point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth upto 50 m (fifty metre) and lift upto 1.5 m (one point five metre) as directed by Engineer-in-Charge All kinds of soil as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	135.00			Per square metre	
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. With material conforming to Grade-II (size range 53 mm to 0.075 mm)(Fifty three millimeter to zero point zero seven five millimeter) having CBR Value-25 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	14.17			Per cubic metre	
3	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)(fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.	9.37			Per cubic metre	
4	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.70-1.0 kilogram (zero point seven zero to one point zero kilogram per square meter) using mechanical means as per technical specification clause -502 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	120.00			Per square metre	
5	Providing and applying tack coat using bitumen emulsion conforming to IS 8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. On W.B.M / W.M.M. @ 0.4kg/sqm (zero point four kilogram per square metre), as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	120.00			Per square metre	
6	2 cm (two centimeter) premix carpet surfacing with 1.8 cum(one point eight cubic metre) and 0.90 cum (zero point nine cubic metre) of stone chippings of 13.2 mm (thirteen point two millimeter) size and 11.2 mm (eleven point two millimeter) size respectively per 100 sqm (one hundred square metre) and 52 kg (fifty two kilogram) and 56 kg (fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm (thirteen point two millimeter) and 11.2 mm (eleven point two millimeter) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 10 heated and then mixed with solvent at the rate of 70 grams per kg of asphalt as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	120.00			Per square metre	
7	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm (two point thirty six millimeter) and retained on 100 micron sieve) with bitumen using 128 kg (one hundred twenty eight kilogram) of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum (zero point six zero cubic metre) of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete. as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	120.00			Per square metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 W.P.P.W.D. Tauni Devi

Schedule of Quantity

Estimated Cost:- 99951.00
Earnest Money:- 2000.00
Time:- Two Months.

Name of Work:- C/O Jeepable road from Mahila Mandal Bhawan upto house of Smt. Bimla Devi and others in Rakrial G.P. Bassi Jhanyara km. 0/0 to 0/050. (SH:- C/O Edge wall at km. 0/00 to 0/022). (Under Minor Works).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m,(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	7.92			Per Cum.	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	15.84			Per Cum.	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ veculus pipe having pressure 4kg.per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	20.00			Rmt.	
Terms and Condition:-					Total:-	

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HP-PWD, Tauni Delhi

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

No.PW- TDD/GA-N.I.T/2021-2022- 9520-21

Dated:- 20-09-2021

To

The Executive Engineer (IT cell),
Nigam Bihar, Shimla-2.

Subject: - Publication of tender Notice.

Jai Hind!

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr.Secy (PW) to the Govt of H.P. letter No. PBW(B)A(3) 1/2020 dated Shimla -2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/Notice Inviting Tender & Schedule of Quantity and Certificate.

Amit Gola
Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi.

Copy forwarded to the Computer Cell o/o Executive Engineer (IT cell), Nigam Bihar, Shimla-2. For information and further necessary action please.

Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi

**HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT -Executive Engineer, Tauni Devi Division HP:PWD,
Tenders for the following works:-**

Sealed item rate tenders on form No. 6 & 8 are hereby invited works shown below:- Date of receipt of Applications for tender forms:- 27.09.2021. upto 1.00 PM. Date of issue/sale of Tender forms 28.09.2021- 2:00 P.M. to 5.00 PM 3. Date of receipt of Tender:- 28.09.2021 at 11.00 AM 4. Date of opening of Tender:- 28.09.2021 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time
1.	C/O link road from Bhalana to Chaleli km.(SH:- R/wall at RD 1/860 to 1/869).	469153.00	9500.00	Two Months.
2.	R/R damages on Hamirpur to Sujampur road Km. 2/600 to 18/300(SH:- C/o R/wall at RD 3/850 to 3/858).	372666.00	7500.00	Two Months.
3.	C/o link road Chamiana to Bhadeen via Taryamali Km.0/0 to 2/765 (C/o R/wall at RD 0/364 to 0/369)	149807	3000.00	Two Months.
4.	C/o 4.60 mtr span RCC slab culvert on Radha Swami satsang beas centre at karot (SH:- C/o 4.60mtr span RCC slab culvert)	455575.00	9200.00	Two Months.
5.	R/R damages on Ree Saluhi road Km. 0/0 to 2/0 (SH:- R/wall at RD 0/035 to 0/042)	148881.00	3000.00	Two Months.
6.	C/o missing C.D. on Hamirpur Sujampur road Km.0/0 to 24/785 (SH:- C/o 900 mm dia hume pipe culvert at RD 18/375).	93606.00	2000.00	Two Months.
7.	C/o L/R from Dulwana to Lambehra via Dhangota Brahmana Dhangota Lohakhrian Km. 0/0 to 4/0 (SH:- C/o GSB ,WMM from RD 0/405 to 0/865 & V-shape drain in Km. 0/405 to 0/855).	425103.00	8500.00	Two Months.
8.	C/o L/R from Dulwana to Lambehra via Dhangota Brahmana Dhangota Lohakhrian Km. 0/0 to 4/0 (SH:- C/o RCC hume pipe culvert 900 mm dia at RD 0/610,0/695,0/765,0/824 i/c PCC wing wall 3.00 mtr both side).	413622.00	8500.00	Two Months.
9.	C/o Jeepable road from Mahila Mandir Bhawan upto house of Smt. Bimla Devi and others in Rakrial G.P. Bassi Jhanyara Km.0/0 to 0/050 (SH:- M/T work at RD 0/0 to 0/050) Under Minor works).	99661.00	2000.00	Two Months.
10.	C/o Jeepable road from Mahila Mandir Bhawan upto house of Smt. Bimla Devi and others in Rakrial G.P. Bassi Jhanyara Km.0/0 to 0/050 (SH:- C/o Edge wall at RD 0/0 to 0/022) Under Minor works).	327059.00	6500.00	Two Months.

TERMS AND CONDITIONS:-

NOTE:- The tender documents shall be issued only to those contractors/firms who fulfill the criteria and submit the documents with the application as required. Terms and condition same as previous /Notice Board.

Amir Ghill
Executive Engineer
Tauni De.vi
H.P.P.W.D. Tauni De.vi