

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **28.9.2021** up to 11.30 AM and shall be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 10.30 AM on **28.9.2021**.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Nahan Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	A/R & M/O Old Circuit House at Nahan.(SH:- Distempering, painting, plastering & other Misc. repair works).	4,92,078/-	9,850/-	02 Month	350/-
2	A/R & M/O Old Circuit House at Nahan.(SH:- Distempering, painting & other finishes etc.)	4,99,031/-	10,000/-	02 Month	350/-

CERTIFICATE:- It is certified that the tenders of above works are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must submit their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any HP PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No.PBW(B)A(3)1/2020 dated.Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

For & on behalf of Governor of Himachal Pradesh.

No. PWN/CB/Tender/2020-21-

4741-50

Dated:- 21.09.21

Copy forwarded to the following for information & further necessary action:-

1. The Engineer-in-Chief, HP.PWD., Shimla please.

2. The Chief Engineer(SZ), HP.PWD., Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. at Nahan please.
4. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
5. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD., Shimla-2 for uploading of Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please..
9. All the Assistant Engineers under this division to display on their respective Notice Boards.
10. The Notice Board.

Executive Engineer,
Nahan Division,
HPPWD Nahan.


SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Old Circuit House at Nahan (SH:-Distempering, painting,plastering & other miscellaneous repair works)

Estimated cost :- Rs :- 4,92,078/-only
Earnest Money:- Rs. 9,850/-only
Time:- Two Months.

Sr.No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including t thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metling the surface.including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1133.00	Per square metre			
2	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1718.36	Per Square metre			
3	Applying priming with cement primer coat on new concrete/Masonry/ asbestors cement /plastered surface and including preparing the surface by thoroughly cleaning oil,grease,dirt and other foreign matter and sand papering as required with : Ready Mixed primer including carriage of materials with in all leads and other incidental complete as per entire satisfaction of the Engineer-in-Charge.	1718.36	Per square metre			
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1718.36	Per square metre			
5	Finishing wall with weather proof exterior grade emulsion of approved design (apexultima) or its equarlied on undecorated wall surface (two coats) to give an even shade and final finish after throughly cleaning the surface to remove all dir, dust and other foreign matter etc including sand paper smooth complete .including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	672.46	Per Square metre			
6	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping With enamel paint other than white .including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	399.77	Per square metre			
7	Painting two coats (excluding priming coat)on new steel and other metal surface under coat with ready mixed paint brusing to give an even shade including cleaning the surface all dirt,dust and other foreign matter With white readymixed paint .including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	42.70	Per Square metre			
8	P/F pvc peneling approved qualty in ceiling with tongued and grooved jointjng and screws (frame work and cover filt to be measurd paid for separatly) including carriage of meatirls in all respect .including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	12.60	Per square metre			

9	Providing and fixing vitreous china wash down water closet squatting pan (Indian type W.C. pan) size 580mm (Earth work, bed concrete, foot rest and trap to be measured and paid for separately). Orissa pattern including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1.00	Each			
10	Demolition above G.L. upto floor two level including disposal of unserviceable material within 20 metres lead..including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.65	Per Cubic metre			
11	Providing and fixing 10mm thick anti skid water proof stain and impet resistant heavy duty vetrified tiles Nitco or equivalant 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings fixed with approved adhesive jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	7.20	Per square metre			
12	Providing and laying Duro stone vetrified tiles (300x300mmx8mm) in grey/ coloured of required shade in skirting risers of steps and dados on 12mm thick cement mortar 1:3 (1 cement : 3 sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete.	12.42	Per square metre			
13	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement :3 sand) and jointed with cement slurry..including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	64.00	Per Square Metre			
14	Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with:- Cement Mortar 1:5 (1 Cement : 5 Sand) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	66.00	Per square metre			
	Total :-					


 Executive Engineer,
 Nahan (B&R) Division,
 HP, PWD, Nahan.

SCHEDULE OF QUANTITY

Name of work:- A/R &M/O New Circuit House at Nahan (SH:-Distempering, painting & other finishes etc.)

Estimated cost :- Rs :- 4,99,031/-only

Earnest Money:- Rs. 10,000/-only

Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1810.00	Per Square metre			
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1810.00	Per square metre			
3	Applying priming with cement primer coat on new concrete/Masonry/ asbestors cement/plastered surface and including preparing the surface by thoroughly cleaning oil,grease,dirt and other foreign matter and sand papering as required with : Ready Mixed primer including carriage of materials with in all leads and other incidental complete as per entire satisfaction of the Engineer-in-Charge.	1810.00	Per square metre			
4	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including t horoughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metling the surface including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1810.00	Per square metre			
5	Finishing wall with weather proof exteriior grade emulsion of approved design (apexultima) or its equarlied on undecorated wall surface (two coats) to give an even shade and final finish after throughly cleaning the surface to remove all dir, dust and other foreign matter etc including sand paper smooth complete including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	756.00	Per Square metre			
6	Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with:- Cement Mortar 1:5 (1 Cement : 5 Sand) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	53.13	Per square metre			
7	Demolition above G.L. upto floor two level including disposal of unserviceable material within 20 metres lead.including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.84	Per Cubic metre			
8	Providing and laying Duro stone vetrified tiles (300x300mmx8mm) in grey/ coloured of required shade in skirting risers of steps and dados on 12mm thick cement mortar 1:3 (1 cement : 3 sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete.	10.08	Per square metre			

9	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement :3 sand) and jointed with cement slurry.including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	36.80	Per Square Metre			
10	Providing and fixing C.P. brass bib tap with captain head 15mm dia including all leads,lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	5.00	Each			
11	Providing and fixing vitreous china wash basin with single hole for pillar tap with C.I. or M.S brackets painted white including cutting holes & making good the same but excluding fittings 630mm x 450mm (six hundred thirty into four hundred fifty milimetre) including all leads,lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	3.00	Each			
12	Providing and fixing cup board 60 cm deep with 19mm thick prelaminated board in vertical back side of cup board and in cup board shutter and in horizontal, top bottom, sides shelves with hard wood edging including fittings such as alluminium handles, piono hinges for fixing shutter and locking arrangment etc. including stasfaction of Enginer Charge.	3.08	Per Square Metre			
13	Providing and fixing P.V.C connection with brass unions :- 300/450mm length :- 15mm nominal bore including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	10.00	Each			
14	Providing and fixing. Brass angle valve 15mm (fifteen milimetres) without nuts and pipe including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.00	Each			
15	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (Medium grade) tube fittings and clamps including making good the wall,ceiling and floor 15 mm(Fifteen milimeter) nominal bore. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.00	Per Running metre			
16	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping With enamel paint other than white including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	67.50	Per square metre			
	Total :-					

Executive Engineer,
Nahan (B&R) Division,
HP,PWD, Nahan.