

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PW-MD-II/CB/NIT (off line) /20-
To

10037

Dated:- 21/9/2021

The Superintending Engineer,
1st circle, HPPWD Mandi

Subject: - Tender notice in **emergent covered** approval thereof.

Sir,

Enclosed please find herewith the copy of tender notice schedule to be opened on dated 30.09.2021 for information and issue of necessary certificate please.

DA:-As above.

Executive Engineer,
Mandi Division No-II,
H.P.P.W.D. Mandi

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

The sealed item rate tender in emergent condition on form 6 & 8 are invited on behalf of Governor of Himachal Pradesh for the following works covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or before 30.9.2021 Up to 11.30 A.M. and will be opened on the same day at 3.30 P.M. in the presence of interesting contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto 1.00PM & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on 29.9.2021

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No.II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with quotation. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr.No	Name of work	Estt cost	E/Money	Cost of tender form	Time limit
1	R/R damages on Madan ka Ghar Samrahan road km 0/0 to 7/200 (SH:- C/O PCC R/wall at RD 0/900 to 0/908)	Rs.442777/-	Rs.8900/-	Rs.350	One month
2	R/R damages on Madan ka Ghar Samrahan road km 0/0 to 7/200 (SH:- C/O PCC R/wall at RD 0/860 to 0/867)	Rs.174620/-	Rs.3500/-	Rs.350	One month
3	R/R damages on Madan ka Ghar Samrahan road km 0/0 to 7/200 and Kushada to Samrahan road km 0/0 to 3/200 (SH:- Removal of land slide slips)	Rs.249816/-	Rs.5000/-	Rs.350	One month
4	C/O Baggi to Sain road km 0/00 to 6/00 (SH:- C/O PCC R/wall at RD 2/260 to 2/265)	Rs.229535/-	Rs.4600/-	Rs.350	One month
5	RRD MDR-57 Shandhapatan Bharol Bangora Harproi Kalang Traible Basahi Drubble Banwar kun ka Tar Mandokhar Bhargaon Kotli road km 70/600 to 85/00 (SH:- C/O R/wall at RD 80/767.50 to 80/775)	Rs.344957/-	Rs.6900/-	Rs.350	One month
6	RRD on Anna Kanchi Kushmal road km 0/00 to 8/300 & Roda Nallah Karkoh Arthi road km 0/00 to 12/500 (SH:- Removal of land slide slips)	Rs.250031/-	Rs.5000/-	Rs.350	One month
7	RRD on Ganpati Kun Ka Tar road km 0/00 to 21/500 (SH:- Removal of slips at RD 0/920 to 0/948) Valley side	Rs.491918/-	Rs.9900/-	Rs.350	One month

GENERAL CONDITIONS:-

- 1 The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- 2 The contractors whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to compete in tendering for four months.
- 3 The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking that he is not having more than two works in hand must be recorded in the application.
- 4 The rates shall be within the limit of -10% and + 5% otherwise the tenders for these will be rejected

No.PW-MDII-CB-NIT (off line) /2019-

Copy forwarded to the following for information and necessary action-

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt.Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt.Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
6. The Distt.Panchyat officer Mandi Distt.Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt.Mandi HP
8. All A.E.S/Contractors under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies

Executive Engineer
Mandi Division No.II
HP.PWD Mandi

Dated:- 21/09/2021

Executive Engineer
Mandi Division No.II
HP PWD Mandi

CERTIFICATE

CERTIFIED THAT THE TENDER AS CALLED OF THIS OFFICE
LETTER NO.PW/MDII/CB/NIT/2019-¹⁰⁰⁰⁰⁻¹⁰⁰³⁶ DATED ^{21/9/2021} IS OF URGENT
NATURE OF WORK AS THE SITE HAS BECOME DANGEROUS DUE TO HEAVY
RAIN. THE R/WALL AS WELL AS REMOVAL OF SLIPS IS URGENTLY REQUIRED
TO PROTECT THE ROAD SURFACE/OPENING OF ROADS FOR VEHICULAR
TRAFFIC DURING RAINY SEASON.

2
Executive Engineer
Mandi Division No.II
MP.PWD Mandi

SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Madan Ka Ghar Samrhan Road Km 0/00 to 7/200.
(SH:- C/O PCC R/Wall at RD 0/900 to 0/908)

Estimated Cost Rs. 4,42,777/-
Earnest Money Rs. 8900/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals.	28.08			Per Cubic Metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials with in all leads, lifts and other incidentals.	101.87			Per Square Metre	
3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm (forty millimetre) nominal size/in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials with in all leads, lifts and other incidentals.	63.80			Per Cubic Metre	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	18.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.40			Per Cubic Metre	
					Total	

Executive Engineer,
Mandla Division No-21,
HP, PWD, Mandla.

Name of work :- R.R.D. on Madhan -Ka Ghar Samrhan Road km 0/0 to 7/200. (SH:- C/O PCC R/Wall wall at RD 0/860 to 0/867)

SCHEDULE OF QUANTITY

Estimated Cost Rs. 1,74,620/-
Earnest Money Rs. 3500/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals.	3 14.84	4	5	6 Per Cubic Metre	7
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials with in all leads, lifts and other incidentals.	60.49			Per square metre	
3	Providing and having 1:5:10 (1 cement : 5 coarse sand: 10 graded stone aggregate 40 mm (forty millimetre) nominal size) in position cement concrete of specified grade, excluding the cost of centering and shuttering - All work up to plinth level with in all leads, lifts and other incidentals.	29.42			Per Cubic Metre	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 110mm (one hundred ten millimetre) PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	12.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	2.94			Per Cubic Metre	
	Total					


Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Madan Ka Ghar Samrahan road Km. 0/00 to 7/200 and Kushada to Samrahan road Km. 0/00 to 3/200 (SH:- Removal of land slide slips).

Estimated Cost Rs. 2,49,816/-
Earnest Money Rs. 5,000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with lift up to any lead as per technical specification including carriage of materials with in all leads, lifts and other incidentals.	2778.82			Per Cubic Metre	
					Total	


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Name of work :- C/O Baggi to Sain road Km 0/00 to 6/00.
(SH: C/O PCC R/wall at RD 2/260 to 2/268).

SCHEDULE OF QUANTITY

Estimated Cost Rs. 2,29,535/-
Earnest Money Rs. 4,600/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals.	3.60			Per Cubic Metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials with in all leads, lifts and other incidentals.	58.32			Per Square Metre	
3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm (forty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials with in all leads, lifts and other incidentals.	32.33			Per Cubic Metre	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	12.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.20			Per Cubic Metre	
					Total	


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

SCHEDULE OF QUANTITY

At : R.R.D. MDR-57 Shandhapattan Bharol Bangora Hardopri Kalang Traimbil Basahi Drubble Banwar
Kun-Ka-Tar Mandokhar Bhargaon Kotli Road Km. 70/600 to 85/00. (SH:- C/O R/wall at
RD. 80/767.50 to 80/775).

Estimated Cost Rs. 3,44,957/-
Earnest Money Rs. 6,900/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals.	31.62			Per Cubic Metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials with in all leads, lifts and other incidentals.	80.10			Per Square Metre	
3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm (forty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials with in all leads, lifts and other incidentals.	50.07			Per Cubic Metre	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	6.52			Per Cubic Metre	
	Total					

Executive Engineer,
Mandi Division No-II,
HAWD, Mandi-
*

SCHEDULE OF QUANTITY

of work :- R.R.D. MDR-57 Shandhapattan Bharol Bangora Hardropri Kalang Traimbli Basahi Drubble Banwar
Kun-Ka-Tar Mandokhar Bhargaoon Kotli Road Km. 70/600 to 85/00. (SH:- C/O R/wall at
RD. 80/767.50 to 80/775).

Estimated Cost Rs. 3,44,957/-
Earnest Money Rs. 6,900/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals.	31.62			Per Cubic Metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including carriage of materials with in all leads, lifts and other incidentals.	80.10			Per Square Metre	
3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm (forty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials with in all leads, lifts and other incidentals.	50.07			Per Cubic Metre	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	6.52			Per Cubic Metre	
	Total					

Executive Engineer,
Mandi Division No-II,
H.R.D. Mandi

SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Anna Kenchi Kushmal Road Km. 0/00 to 8/300 and Roda Nallah Karkoh Arthi road
Km. 0/00 to 12/500. (SH:- Removal of land slide slips).

Estimated Cost Rs. 2,50,031/-
Earnest Money Rs. 5,000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with lift up to any lead as per technical specification including carriage of materials with in all leads, lifts and other incidentals.	2781.21			Per Cubic Metre	
					Total	


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

SCHEDULE OF QUANTITY

Work :- R.R.D. on Ganpati Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- Removal of slips at RD 0/920 to 0/948). Velly side

Estimated Cost Rs. 4,91,918/-
Earnest Money Rs. 9,900/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Removal of slips in all kind of soil including saturated soil but excluding boulder and rocky portion requiring blasting upto any lead disposing of un-serviceable material stacking serviceable material and neatly dressing surface including carriage of materials with in all leads, lifts and other incidentals.	1901.50			Per Cubic metre	
					Total	

Engineer,
Main Division No-II,
HP. PWD, Mandi