

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2021-22

14730-32

Dated:- 21-9-2021

To,

The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 04.10.2021 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above (in triplicate)


Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

1. Copy along with N.I.T. to the Chief Engineer Mandi Zone HP.PWD . Mandi for information please.
2. Copy along with N.I.T. to the Superintending Engineer 1st Circle, HP.PWD. Mandi for information please.


Executive Engineer,
Sarkaghat Division
HP.PWD. Sarkaghat.

Himachal Pradesh
Public Works Department
"Notice Inviting Tender"

Sealed item rate tender are hereby invited in form No. 6&8 by the Executive Engineer B&R Division, HP.PWD, Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968.The important dates of tender are as under:-

The last date and time of receipt of application for tender form 04.10.2021 up to 4.00 P.M.

The last date for sale of tender is up to 05.10.2021 at 4.00PM.

The tender shall be received up to 11:00 AM on 06.10.2021 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 06.10.2021 The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	A/R & M/O on Duṛgapur Kathogan Thona Rissa Road Km. 0/0 to 24/0 (SH:- Construction of Retaining wall in PCC 1:5:10 at RD 11/700 to 11/709)	497691	10000	350	One Month
2.	Diversion of Land on Pounta Hari Benha Nabahi Km. 0/0 to 7/0 (SH:- P/L WBM G-I & C/O R/wall PCC 1:4:8 at RD 0/855 to 0/873 , 0/915 to 0/930 and 0/855 to 0/930)	261275	5000	350	One Month
3.	A/R & M/O Kalthari Tikkari Ropa Thathar Batail Road Km.0/0 to 7/300 (SH:- Construction of Retaining wall in PCC 1:5:10 at RD 11/700 to 11/709)	497691	9950	350	Two Months
4.	R/R Damages on Banoha Batail Road Km. 0/0 to 8/0 (SH:- Construction of R/wall in PCC 1:4:8 at RD 4/0 to 4/010)	498269	10000	350	One month

TERMS AND CONDITIONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
4. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
5. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
6. The earnest money for the above works should be required at the time of sale of tender's forms.
7. All the required documents should be submitted with the application others wise single application may be rejected.
8. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.
9. Cost of tender for the above works may be deposited with application.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

Dated:

21-9-2021

No. PW-SKT-CB-Tender/2021-22

14722-29

1. The Engineer in Chief HPPWD Shimla for information please.
2. The Chief Engineer (MZ) HPPWD Mandi for information please.
3. Copy to Superintending Engineer 1st Circle HPPWD Mandi for information Please.
4. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
5. Copy to Drawing Branch of this office for information.
6. Notice Board.

Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O on Durgapur Kathogan thona Rissa road Km 0/0 to 24/0 (SH:- Construction of retaining wall in PCC 1:5:10 at RD 11700 to 11709).

Rs. 4,97,691/-

Estimated cost :-

Rs. 10000/-

Earnest Money:-

One month

Time Limit

Sr.N o	Description of item/Sub Head	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kind of soil . with in all lead and lift and as per the direction of Engineer -in -charge.	15.30			Per cubic metre	0
2	Centering and shuttering including strutting, propping etc. and removal of form work for .Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets,kerbs and steps etc.with in all lead and lift and as per the direction of Engineer -in -charge.	147.30			Per square metres	0
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) with in all lead and lift and as per the direction of Engineer -in -charge.	95.85			Per cubic metre	0
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge.	24			Each	0
5	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	15.75			Per cubic metre	0
					Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE QUANTITY

Name of Work:- Diversion of Land on Pounta Hari Behna Nabahi Road km 0/0 to 7/00 (Sh:- P/L WBM G-I & C/O R/wall PCC 1:4:8 at RD 0/855 to 0/873, 0/915 to 0/930 and 0/855 to 0/930).						
				Estimated cost :-		Rs. 261275 /-
				Earnest Money:-		Rs. 5000 /-
				Time Limit:-		One month
Sr. No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Earth work in excavation in all kind of classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause -305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and direction of Engineer-in-charge complete.	27.09			Per cubic metre	
2	Providing and laying cement concrete plain/ reinforced concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 including form work for plain/ reinforced concrete work as per drawing and HP,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in-Charge.	96.75			Per cubic metre	
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	30.00			Each	
4	Providing, laying, spreading and compacting stone aggregates of 90 to 45mm (Ninety to forty five millimetre) size to water bound macadam specification including spreading in uniform thickness hand packing and rolling with three wheel roller 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening type-B at the rate 0.27cum(Zero point two seven cubic metre) and binding materials at the rate 0.08 cum (Zero point zero eight cubic metre) per 10 Sqm (Ten square metre) of road surface to fill-up the interstices of coarse aggregate watering and compacting to the required density grading 1 as per Technical Specification by manual mean including carriage of materials within all leads and lifts and other incidentals.	25.13			Per cubic metre	
					Total :-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE QUANTITY						
Name of Work:- Diversion of Land on Pounta Hari Behna Nabahi Road km 0/0 to 7/00 (SH:- P/L WBM G-I & C/O R/wall PCC 1:4:8 at RD 0/855 to 0/873, 0/915 to 0/930 and 0/855 to 0/930).						
Sr. No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Earth work in excavation in all kind of classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause -305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and direction of Engineer-in-charge complete.	27.09			Per cubic metre	
2	Providing and laying cement concrete plain/ reinforced concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size in open foundation complete as per drawing and technical specification cluse 802,803,1202 and 1203 including form work for plain/ reinforced concrete work as per drawing and HP.PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in-Charge.	96.75			Per cubic metre	
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	30.00			Each	
4	Providing, laying, spreading and compacting stone aggregates of 90 to 45mm (Ninety to forty five millimetre) size to water bound macadam specification including spreading in uniform thickness hand packing and rolling with three wheel roller 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening type-B at the rate 0.27cum(Zero point two seven cubic metre) and binding materials at the rate 0.08 cum (Zero point zero eight cubic metre) per 10 Sqm (Ten square metre) of road surface to fill-up the interstices of coarse aggregate watering and compacting to the required density grading 1 as per Technical Specification by manual mean including carriage of materials within all leads and lifts and other incidentals.	25.13			Per cubic metre	
Total :-						


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O on Durgapur Kathogan thona Rissa road Km 0/0 to 24/0 (SH:- Construction of retaining wall in PCC 1:5:10 at RD 11/700 to 11/709).

Rs. 4,97,691/-

Estimated cost :-

Rs. 10000/-

Earnest Money:-

One month

Time Limit

Sr.N	Description of item/Sub Head	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan); including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kind of soil . with in all lead and lift and as per the direction of Engineer -in -charge.	15.30			Per cubic metre	0
2	Centering and shuttering including strutting, propping etc. and removal of form work for :Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets,kerbs and steps etc.with in all lead and lift and as per the direction of Engineer -in -charge.	147.30			Per square metres	0
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) with in all lead and lift and as per the direction of Engineer -in -charge.	95.85			Per cubic metre	0
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge.	24			Each	0
5	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	15.75			Per cubic metre	0
					Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.