

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDER**

Sealed items rate tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractors enlisted in HPPWD, so as to reach in this office on **29.10.2021** up to 11:30 AM and shall be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non-refundable) up to 10.30 AM on **29.10.2021**.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer, HPPWD (B&R) Division, Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	Improvement of black spots Nahan Dadahu Haripurdhar road Km.0/0 to 36/0.(SH:-P/L thermoplastic compound & fixing of cautionary, mandatory & informatory sign boards at various location in Km.34/0 to 36/0)	4,98,500/-	10,000/-	01 Month	350/-

**CERTIFICATE:-** *It is certified that the tenders of above works are exigency/emergent nature and in public interest.*

**Terms & Conditions:-**


1. The Contractors/Bidders must submit their Permanent Income Tax Account Number/ GST Number on the tender along with copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof along with application.
7. The tender documents shall be issued to only those contractors who do not have more than two works in hand in any HP PWD Circle/Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid up to 75 days.
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated Shimla-2 the 22<sup>nd</sup> July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
11. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reason.

Executive Engineer  
B & R Division  
HPPWD Nahan

**For & on behalf of Governor of Himachal Pradesh**

Copy forwarded to the following for information & further necessary action:-

1. The Engineer-in-Chief, HP.PWD., Shimla please.
2. The Chief Engineer(SZ), HP.PWD., Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. at Nahan please.
4. The Superintending Engineer, 12<sup>th</sup> Circle, HP.PWD, Nahan please.
5. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD., Shimla-2 for uploading the Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please.
9. All the Assistant Engineers under this division to display on their respective Notice Boards.
10. The Notice Board.

  
Executive Engineer  
B & R Division  
HPPWD Nahan

**SCHEDULE OF QUANTITY**

Name of work :-Improvement of black spots Nahar Dadahu Haripurdhar road Km 0/0 to 36/0(SH :-Providing and laying thermoplastic compound & fixing of cautionary,mandatory and informatory sign boards at various location in Km 34/0 to 36/0)

Estimated cost :- Rs. 4,98,500/- only  
Earnest Money :- Rs. 10,000/- only.  
Time allowed :- One month.

S. No.	Sub-head & item of works	Quantity	Unit	Rate		Amount
				Words	Figure	
1	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250gms per sign area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC : 35. The finished surface to be level uniformly and free from streaks and holes including carriage of all labour equipments and materials to various location through all leads,lifts and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	100.00	Per square meter			
2	Providing and installation of delinators (road way indicators hazard makers , object markers 80-100 cm high above ground level , painted black and white in 15 cm wide strips, fitted with 80 x100 mm rectangular of 75 mm dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 and the drawings including carriage of all labour equipments and materials to various location through all leads,lifts and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	100.00	Each			
3	Providing and fixing plastic road studs/ cat eyes of 3 m series to 290/ art No. C 1210 in yellow/ wide /red colour( two way acrylic reflector/ micro prismatic lense) as per astm 4280 type H or equivalent fixed at site with suitable epoxy as per PWD Specification to including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	520.00	Each			
4	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 50 mm x 50mm x 5 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801. including carriage of all labour equipments and materials to various location through all leads,lifts and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge(1) 800 mm x 600 mm rectangular.	2.00	Each			
5	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 50 mm x 50mm x 5 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 including carriage of all labour equipments and materials to various location through all leads,lifts and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge(1) 600 mm equilateral triangle.	2.00	Each			
Total :-						

Executive Engineer,  
HP.PWD., Division  
Nahan.