

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDER**

Sealed items rate tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractors enlisted in HPPWD, so as to reach in this office on **27.10.2021** up to 11:30 AM and shall be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non-refundable) up to 10.30 AM on **27.10.2021**.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer, HPPWD (B&R) Division, Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.


Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	Fixing of 40.00 meter Span Temporary Steel Foot Bridge over Giri River for Shri Renuka Ji Fair at Dadahu	4,95,000/-	9,900/-	01 Month	350/-
2	Restoration of Rain Damages on Khajurna to Malonwala Road Km. 0/0 to 2/765 (SH:- C/o Retaining Wall at RD 2/610 to 2/630 & Village Road 2/604 to 2/622)	4,30,661/-	8,700/-	02 Months	350/-
3	Restoration of Rain Damages on Khajurna to Malonwala Road Km. 0/0 to 2/765 (SH:- C/o Retaining Wall at RD 2/742 to 2/760)	4,15,527/-	8,400/-	02 Months	350/-
4	Restoration of Rain Damages on Link Road under Gram Panchayat Nauni Jamta (SH:- Hiring of Excavator cum Loader for removal of slips and maintenance of Road) under DC Deposit	94,500/-	1,900/-	01 Month	350/-

**CERTIFICATE:-** It is certified that the tenders of above works are exigency/emergent nature and in public interest.

**Terms & Conditions:-**

1. The Contractors/Bidders must submit their Permanent Income Tax Account Number/ GST Number on the tender along with copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof along with application.
7. The tender documents shall be issued to only those contractors who do not have more than two works in hand in any HP PWD Circle/Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid up to 75 days.
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated Shimla-2 the 22<sup>nd</sup> July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.

11. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reason.

  
Executive Engineer  
CB & R Division  
HPPWD Nahan


For & on behalf of Governor of Himachal Pradesh

No. PWN/CB/Tender/2020-21- 5781-62

Dated:- 9/10/2024

Copy forwarded to the following for information & further necessary action:-

1. The Engineer-in-Chief, HP.PWD., Shimla please.
2. The Chief Engineer(SZ), HP.PWD., Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. at Nahan please.
4. The Superintending Engineer, 12<sup>th</sup> Circle, HP.PWD, Nahan please.
5. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD., Shimla-2 for uploading the Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please.
9. All the Assistant Engineers under this division to display on their respective Notice Boards.
10. The Notice Board.

  
Executive Engineer  
B & R Division  
HPPWD Nahan

**Schedule of Quantity**

Name of work:-Fixing of 40.00 metre span temporary steel foot bridge over Giri river for Renuka ji fair at Dadahu.

Estimated Cost:- Rs.4,95,000/- Only

Earnest money:- Rs.9,900/- Only

Time:- One Month.

Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Repairing,maintenance including painting etc.& fixing of 40.00 metre span temporary steel foot bridge at site of work and making surface smooth including all leads and lifts as per direction of Engineer-in- Charge.	1.00	Job			

Opened By Me .....  
 Cutting .....  
 Over Writing .....  
 Erasing .....  
 Condition .....

Executive Engineer,  
 Nahar (B&R) Division,  
 HP,PWD, Nahar.



3

Schedule of Quantity

Name of work:- Restoration of rain damages on Khajurna to Malon wala road Km 0/0 to 2/765(SH :-C/O R/Wall at RD 2/610 to 2/630 & village road 2/604 to 2/622)

Estimated Cost:-4,30,661/-only  
Earnest Money:-8,700/- only  
Time allowed:- Two months

Sr. No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead,dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	60.26	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 ( one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	105.55	Per Cubic metre			
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	33.00	Each			
4	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	22.68	Per Cubic metre			
	Total:-					

Opened By Me .....  
Cutting .....  
Over Writing .....  
Erasing .....  
Condition .....

Executive Engineer,  
HP.PWD., Division  
Nahan.

3

Schedule of Quantity

Name of work:- Restoration of rain damages on Khajurna to Malon wala road Km 0/0 to 2/765(SH :-C/O R/Wall at RD 2/742 to 2/760)

Estimated Cost:-4,15,527/-only  
Earnest Money:-8,400/- only  
Time allowed:- Two months

Sr. No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead,dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	43.20	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 ( one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	105.30	Per Cubic metre			
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	24.00	Each			
4	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	14.58	Per Cubic metre			
	Total:-					

Opened By Me .....  
Cutting .....  
Over Writing .....  
Erasing .....  
Condition .....

Executive Engineer,  
HP.PWD., Division  
Nahan.



# Schedule of Quantity

Name of work:- Restoration of rain damages on link road under Gram Panchayat Nauri Jamta (SH:- Hiring of excavator cum loader for removal of slips & maintenance of road) under DC deposit

Estimated Cost:- Rs.94,500/- Only  
Earnest money:- Rs.1,900/- Only  
Time:- One Month.

Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Hiring of Excavator Cum loader for formation cutting/ excavation of earth work in all kinds of soil/ removal of slips in all depths and heights including saturated soil and disposal of surplus soil with in all leads and lifts as per direction of the Engineer-in- Charge and making surface smooth including P.O.L. Charges and other expences etc also including carriage of machinery and Labour upto all leads, lifts etc.	105.00	Per hour			

Note :- The cost of P.O.L. charges wear and tear of machinery salary and livery charges of operator and cleaner and repair of machinery etc, shall be born by the contractor himself and nothing will be paid for the same.

Executive Engineer,  
Nahan (B&R) Division,  
HP,PWD, Nahan.

Checked By Me .....  
Cutting .....  
Over Writing .....  
Erasing .....  
Condition .....