

A certificate of exigencies /emergencies

It is certified that following works are in exigency/ emergency situation and as per in public interest / demands require immediate action uploaded in HPPWD website:-

C/O link road from Barara to Bakkar Khad to Guwardoo via Harizan Basti Kaswar. (SH:- C/O R/Wall at RD. 1/120 to 1/130).

Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- Imp. of blind curves at RD.1/540 to 1/630 & 2/405 to 2/450).


Executive Engineer
Tauni Devi
H.P.P.W.D. Tauni Devi

Himachal Pradesh
Public Works Department

CORRIGENDUM

The Offline Works -1) at Sr. No. 17. C/O link road from Barara to Bakkar Khad to Guwardoo via Harizan Basti Kaswar. (SH:- C/O R/Wall at RD. 1/120 to 1/130) (**Under SCSP**). E/cost-125588.00 2) at Sr. No. 18. Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- Imp. of blind curves at RD.1/540 to 1/630 & 2/405 to 2/450) E/Cost-483330.00 have also been invited and opened on dated 11.10.2021 in addition to the works invited vide this office letter No.PW/TDD/GA-NIT/2021-22-~~14614-65~~ dated ~~3-11-2021~~

Other terms and conditions for the said tender shall remain unchanged.

Amo 44
Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi.

No.PW/TDD/GA/N.I.T./2021-22 *14848-873*

Dated:- *06-11-2021*

Copy forwarded for information & necessary action to:-

1. The Superintending Engineer, 8th Circle, HP:PWD,
2. The Executive Engineer (IT cell), Nigam Bihar, Shimla-2.for for uploading of corrigendum on the Departmental website please.
3. Computer Cell o/o Executive Engineer (IT cell), Nigam Bihar, Shimla-2.
4. All the Assistant Engineers working under this Division.
5. Accounts Branch/ Drawing Branch/ Notice Board.
6. Lok Mitra, Tauni Devi.
7. Various Contractors/ Firms.

Amo 44
Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi

Schedule of Quantity

Estimated Cost:- 125588.00
 Earnest Money:- 2500.00
 Time:- Two Months.

NAME OF WORK:- C/O link road from Barara to Bakkar Khad to Guwardoo via Harizan Basti Kaswar. (SH- C/O RWall at RD. 1/120 to 1/130) (Under SCSP).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structling and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	26.70			Per cubic metre	
	Providing and laying mechanically mixed and vibrated cement concrete 1:5:10 (one cement : five sand : ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	52.86			Per cubic metre	
	Backfilling behind abutment, wing wall and return wall with granular material complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals.	13.50			Per cubic metre	
	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	25.00			Each	
					Total:-	

Terms and Condition:-

Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HP-PWD, Tauni Dept.

Schedule of Quantity

Estimated Cost:- 483330.00
Earnest Money:- 10000.00
Time:- Two Months.

Name of Work:- Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- Imp. of blind curves at RD.1/540 to 1/630 & 2/405 to 2/450). *(C Budget under SCSPT)*.

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation for road way in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal with a lift upto 1.50mtr. (one point fifty metre) and lead upto 1000mtr. (one thousand metre) trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections as per technical specification clause 302.3.5 (Mechanical means) as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals .	1497.77			Per cubic Metre.	
					Total:-	

Note:- No creditable material i.e. stone received from cutting work because this road is conglomerate.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HP-PWD., Tauni Dev