

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender

Form a/w requisite documents: -

23.11.2021 upto 5.00 PM.

2 Date of issue /sale of tender forms against

Cash payment (Non-refundable):-

25.11.2021 upto 4.00 PM.

3. Date of receipt of tenders: -

25.11.2021 upto 10.30 AM.

4. Date of opening of tenders: -

25.11.2021 at 11.00 AM.

Sr.No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	A/R & M/O on U.A.M. Road in km 36/00 to 38/00. (SH:- Making up loss material on shoulders & Unlined Drain from km 36/00 to 38/00.)	99933/-	2000/-	One month	350/-	Class-D
2	A/R & M/O on Tehi Bijlighar to Chaplah road km 0/0 to 4/00. (SH:- Removal of slide in km 36/00 to 38/00. (SH:-Removal of Land slid & Unlined Drain from km 0/0 to 4/0.).	99961/-	2000/-	One month	350/-	Class-D
3	A/R & M/O on Tutru Kitpal Bhiambi road km 0/0 to 4/00. (SH:-Removal of Land slid & Unlined Drain from km 0/0 to 4/0.).	99961/-	2000/-	One month	350/-	Class-D
4	A/R & M/O on link road from Dangera Jole to Takka via Chalber Haler km 0/0 to 11/030. (SH:- Repair of berms in km 5/0 to 8/0).	99987/-	2000/-	One month	350/-	Class-D
5	A/R & M/O on link road Una Takka to Mohalla Haler Mohalla Biasian upto Himotkarsh Collage 0/0 to 3/225. (SH:- Repair of berms in km 0/0 to 3/0.)	99987/-	2000/-	One month	350/-	Class-D
6	(i) A/R & M/O on Bahdala Chattara Pirnigah road. (SH:- P/L 25 mm thick mastic asphalt over Chhatara Khad. (ii) A/R & M/O link road to Chhatara Basoli. (SH:- P/L 25 mm thick mastic asphalt over Basoli Khad)	416401/-	8400/-	Two month	350/-	Class-D
7	(i) A/R & M/O link road to Bonde Mahadev. (SH:- P/L 25 mm thick mastic asphalt over Bridge Chhatara Khad) (ii) A/R & M/O Handola Jagat Khansa road. (SH:- P/L 25 mm thick mastic asphalt over Tanoli Khad) (iii) A/R on Ghandwal Batuhi Dhamandri Road km 0/0 to 3/0. (SH:- P/L 25 mm thick mastic asphalt over Bridge (14.40 metre) at RD 1/300) (iv) A/R & M/O Teuri Golpanga road (SH:- P/L 25 mm thick mastic asphalt over Bridge at RD 0/490)	458926/-	9200/-	Two month	350/-	Class-D
8	A/R & M/O on Handola Jagat Khana road km 0/0 to 3/340. (SH:- P/L 25 mm thick mastic asphalt over Handola Bridge at RD 0/030)	211693/-	4300/-	Two month	350/-	Class-D



9	A/R & M/O on Ambehra Dhamandri road km 0/0 to 5/500. ( SH:- C/O R/wall in km 2/090 to 2/108.50).	105486/-	2200/-	Two month	350/-	Class-D
---	--	----------	--------	-----------	-------	---------


The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand.The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

  
Executive Engineer  
Bangana Division  
HPPWD Bangana.


No.PW/BGN/CB/T-1/2020-21-

9008-9028

dated 15/11/2021


Cop forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD. Nirman Bhawan Shimla.
2. All the Chief Engineer in HPPWD.
3. The Superintending Engineer, 15th Circle, HPPWD., Una.
4. All the Assistant Engineer, working under this Division.
5. The B.D.O. Bangana
6. Accounts Branch.
7. Drawing Branch.
8. Various Contractors working under this Division
9. Notice Board.

  
Executive Engineer,  
Bangana Division,  
HPPWD Bangana.

## Certificate

Certified that the tenders called vide this office letter No. PW/BGN/CB/T-1/2020-21-9008-9028 dated 15.11.2021 is emergent nature and in public interest.



Executive Engineer,  
HPPWD Division  
Bangana.



# Schedule of Quantity

Job no. 1

Circular of Quantity							Job no. 1
Name of work:- A/R & M/O on U.A.M. Road in km 36/00 to 38/00. (Sh:- Making up loss material on shoulders & Unlined Drain from km 36/00 to 38/00.)			Estimated Cost: `		99933/-		
			Earnest Money: `		2000/-		
S.No.	Description of item	Quantity	Unit	Time Limit:		One month	
				Figure	Rates in Word		Amount
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1800	Per Square metre				
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1350	Per Running metre				
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2939	Per Running metre				

Executive Engineer,  
Bangana Division,  
HPPWD, Bangana



# Schedule of Quantity

Job no. 2

S.No.	Name of work:- A/R & M/O on Tehi Bijlighar to Chaplah road km 0/0 to 4/00. (SH:- Removal of slide in km 36/00 to 38/00. (SH:-Removal of Land slid & Unlined Drain from km 0/0 to 4/0.).	Estimated Cost: `			99961/-	
		Earnest Money: `			2000/-	
		Time Limit:			One month	
	Description of item	Quantity	Unit	Figure	Rates in	Amount
					Word	
	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in all leads and lifts. Selected earth obtained from the slips may be filled on the berms and should be compacted with power road roller to the required camber and gradient as per technical specification 302.3.5 and 1611 the entire satisfaction of the Engineer – in Charge.	729.54	Per cubic meter			
	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1900	Per Running metre			

Executive Engineer,  
Bangana Division,  
HPPWD, Bangana



# Schedule of Quantity

Job no. 3

Schedule of Quantity							Job no. 3	
Name of work:- A/R & M/O on Tutru Kripal Bhiambi road km 0/0 to 4/00. (SH:-Removal of Land slid & Unlined Drain from km 0/0 to 4/0.).		Estimated Cost: `		99961/-				
		Earnest Money: `		2000/-				
		Time Limit:		One month				
S.No.	Description of item	Quantity	Unit	Rates in		Amount		
				Figure	Word			
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts. Selected earth obtained from the slips may be filled on the berms and should be compacted with power road roller to the required camber and gradient as per technical specification 302.3.5 and 1611 the entire satisfaction of the Engineer – in Charge.	729.54	Per cubic meter					
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1900	Per Running metre					

Executive Engineer,  
Bangana Division,  
HPPWD, Bangana



# Schedule of Quantity

Job no. 4

Schedule of Quantity						Job no. 4
	Name of work:- A/R & M/O on link road from Dangera Jole to Takka via Chabbar haler Km 0/0 to 11/030.. (SH:- Repair of berms in km 5/00 to 8/00.)	Estimated Cost: `	99987/-			
S.No.	Description of item	Earnest Money: `	2000/-			
		Time Limit:	One month			
		Rates in	Amount			
		Figure	Word			
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3810.00	Per Square metre			
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1886.00	Per Running metre			

Executive Engineer,  
Bangana Division,  
HPPWD, Bangana



# Schedule of Quantity

Job no. 5

Name of work:- A/R & M/O on link road Una Takka to Mohalla Biasan upto Himotkarsh Collage 0/0 to 3/225. (SH:- Km 0/0 to 11/030. (SH:- Repair of berms in km 0/00 to 3/00.)						Estimated Cost: `		99987/-
						Earnest Money: `		2000/-
S.No.	Description of item	Quantity	Unit	Time Limit:		Rates in Word	One month Amount	
				Figure				
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3810.00	Per Square metre					
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1886.00	Per Running metre					

Executive Engineer,  
Bangana Division,  
HPPWD, Bangana



# Schedule of Quantity

Job no. 6

Name of work:-(i) A/R & M/O on Bahdala Chhattara Pirmighah road. (SH:- P/L 25 mm thick mastic asphalt over Chhatara Khad. (ii) A/R & M/O link road to Chhatara Basoli. (SH:- P/L 25 mm thick mastic asphalt over Basoli Khad)				Estimated Cost:	
				Earnest Money:	416401/-
S.No.	Description of item	Quantity	Unit	Time Limit:	8400/-
				Figure	Word
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.275 kg-per sqm (Zero point two hundred seventy five kilogram) per square metre, on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification .clause 503 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	469.80	Per Square metre		
2	Providing and laying bituminous concrete 30mm (thirty millimetre) thick 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, as per table 500.13 & 500.15 of MORD technical specification 2014, premixed with bituminous VG-30 (Viscosity Grade) binder minimum 5% (five percent) as per table 500.16 of MORD technical specification 2014, of mix and filler as per table 500.14 of MORD technical specification 2014, transporting the hot mix to work at site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORD specification 2014 clause 509 and table 500.17 complete in all respect. including entire carriage of material with in all leads and lifts and other incidental as directed by the Engineer-in-charge. The rates are inclusive of all taxes, malikhana and royalty imposed by the government.	11.75	Per cubic metre		
3	Providing and laying 25 mm thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoat finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 100°C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515, including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. The Hot Mix Plant should be situated with in the distance of 30 km (Thirty Kilometer) from work site.	469.80	Per Square metre		



# Schedule of Quantity

Job no. 7

Name of work:- (i) A/R & M/O link road to Bonde Mahadev. (SH:- P/L 25 mm thick mastic asphalt over Bridge Chhatara Khad) (ii) A/R & M/O Handola Jagat Khansa road. (SH:- P/L 25 mm thick mastic asphalt over Tanoli Khad) (iii) A/R on Ghandwal Batuli Dhamandri Road km 0/0 to 3/0. (SH:- P/L 25 mm thick mastic asphalt over Bridge (14.40 metre) at RD 1/300) (iv) A/R & M/O Teuri Golpanga road (SH:- P/L 25 mm thick mastic asphalt over Bridge at RD 0/490)							Estimated Cost:-	458926/-
							Earnest Money:-	9200/-
							Time Limit:-	One month
S.No.	Description of item	Quantity	Unit	Rates in		Amount		
				Figure	Word			
1	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.275 kg.per sqm (Zero point two hundred seventy five kilogram) per square metre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification .clause 503 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	543.82	Per Square metre					
2	Providing and laying bituminous concrete 30mm (thirty millimetre) thick 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, as per table 500.13 & 500.15 of MORD technical specification 2014, premixed with bituminous VG-30 (Viscosity Grade) binder minimum 5% (five percent) as per table 500.16 of MORD technical specification 2014, of mix and filler as per table 500.14 of MORD technical specification 2014, transporting the hot mix to work at site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORD specification 2014 clause 509 and table 500.17 complete in all respect. including entire carriage of material with in all leads and lifts and other insidental as directed by the Engineer-in-charge. The rates are inclusive of all taxes,malkhana and royalty imposed by the government.	10.80	Per cubic metre					
3	Providing and laying 25 mm thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoated finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515.including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.The Hot Mix Plant should be situated with in the distance of 30 km (Thirty Kilometer) from work site.	543.82	Per Square metre					

Executive Eng  
Bongana Divn.H  
SANGANA



## Schedule of Quantity

Job no. 8

S.No.	Description of item	Quantity	Unit	Estimated Cost:	
				Earnest Money:	208676/-
				Time Limit:	4200/-
				Rates in	One month
				Figure	Word
					Amount
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg.per sqm (Zero point two hundred seventy five kilogram) per square metre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification clause 503 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	225.00	Per Square metre		
2	Providing and laying bituminous concrete 30mm (thirty millimetre) thick 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, as per table 500.13 & 500.15 of MORD technical specification 2014, premixed with bituminous VG-30 (Viscosity Grade) binder minimum 5% (five percent) as per table 500.16 of MORD technical specification 2014, of mix and filler as per table 500.14 of MORD technical specification 2014, transporting the hot mix to work at site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORD specification 2014 clause 509 and table 500.17 complete in all respect. including entire carriage of material with in all leads and lifts and other incidental as directed by the Engineer-in-charge. The rates are inclusive of all taxes, malkhana and royalty imposed by the government.	6.75	Per cubic metre		
3	Providing and laying 25 mm thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoat finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515, including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. The Hot Mix Plant should be situated with in the distance of 30 km (Thirty Kilometer) from work site.	225.00	Per Square metre		



# SCHEDULE OF QUANTITY

Job No. 9

Name of work:- RRD on Ambhebra Dhamandri road Km 0/000 to 5/500 (SH:-C/O R/wall in Km 2/090 to 2/108.50).

Estimated Cost Rs 105  
Earnest Money Rs 220  
Time Limit: Tw

Sr. No.	Description of work	Quantity	Unit	RATE		A
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including setting out construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.24	Per cubic metre			1
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and technical specification clause 800, & 1200 for nominal mix 1 : 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths and the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	43.66	Per cubic metre			
3	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	8.51	Per Cubic Metre			
4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex, ) working pressure not less than 4.5 (four point five) kg/cm² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	34.00	Each			
Total Rs.						

Executive Engineer  
Bangana Division  
P.P.W.D. Bangana