

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO: PW.CHD.CB.E-9(Tender)/2020-21 11550-11649 Dated- 11/11/21
To


✓ The Superintending Engineer,
4th Circle, HPPWD., Shimla
District Shimla, H.P.

Subject:- **Publication of tender Notice.**

With reference of the Principal (PW- to the Government of Himachal Pradesh PBW(B) 1/2020 Dated 27th May 2021 and PBW (B) A (3) 1/2020 Dated 16th July 2021 enclosed please find herewith the Tender notice for approval and displayed the notice board of your good office.

It is therefor, requested that tender notice approval may kindly be granted in favour of this Division and tender notice also display on the notice board due to urgency to work please.

DA/As above.


Executive Engineer
Chopal Division
HPPWD Chopal



NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited by the Executive Engineer, Chopal Division HPPWD Chopal in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HP.PWD. the tender shall be opened in the presence of the contractors/ firms of their representative who wish to be present.

TIME SCHEDULE OF TENDER

- | | |
|--|--------------------------------|
| 1. Date and time of receipt of application for tender form:- | 23.11.2021 11:00 AM to 4:00 PM |
| 2. Date and time of issue of tender form:- | 23.11.2021 11:00 AM to 4:00 PM |
| 3. Date and time of receipt of tenders:- | 24.11.2021 11:00 AM |
| 4. Date and time of opening of tender:- | 24.11.2021 11: AM |

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for this purpose.

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	A/R & M/O on Kiarnu Koti Sarain road Km. 0/0 to 7/00 (SH:- C/O B/wall wire crated between Km. 0/770 to 1/810, 1/825 to 1/840 and 1/870 to 1/890)	474000/-	9500/-	Two Months	350/-	Class D
2	A/R & M/O on Kiarnu Koti Sarain road Km. 0/0 to 7/00 (SH:- C/O B/wall at between Km. 1/780 to 1/796)	473900/-	9500/-	Two Months	350/-	Class D
3	A/R & M/O on on Sainj Chopal Nerwa Feduj road Km. 20/00 to 90/00 (SH:- C/O Protection wall between Km. RDS. 9/345 to 9/405)	473000/-	9500/-	Two Months	350/-	Class D
4	A/R & M/O Various roads under Shamtha section PIU Sub Division (SH:- Removal of slips in different Roads)	147000/-	3000/-	Two Months	350/-	Class D
5	A/R & M/O Various roads under Feduj section PIU Sub Division (SH:- Removal of slips in different Roads)	145000/-	3000/-	Two Months	350/-	Class D
6	A/R & M/O Various roads under Kuthar section PIU Sub Division (SH:- Removal of slips in different Roads)	140000/-	2800/-	Two Months	350/-	Class D
7	A/R & M/O Various roads under Pulbhal section Chopal Sub Division (SH:- Removal of slips in different Roads)	475100/-	9500/-	Two Months	350/-	Class D
8	Balance work of Sub Health center at Kiarnoo P.O Podia Tehsil Nerwa Distt Shimla (SH:- Providing and Fixing Dors and Windows and Fittings)	101026/-	2000/-	Two Months	350/-	Class D

TERMS AND CONDITIONS:-

- Division HP.PWD Chopal must be accompanied with the application for receipt of tender form along with cost of form. Tender application received without earnest money .
2. The contractors/ firms should possess the following documents (photo copy to be self attached with application for obtaining the tenders documents):-
 - (xxii) Latest enlistment/ renewal orders with application for obtaining the tenders documents.
 - (xxiii) GST Number issued by the sale Tax Department.
 - (xxiv) PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
 3. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reasons (S)
 4. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
 5. The work will be completed by the contractor within the stipulated period.
 6. The contractor/ firms are required to insert the rate of each item in wards as well as in figures failing which Executive Engineer reserves the right to accept/rejects any overall tender.
 7. The tender shall be issued to only those contractor firms who are eligible suitable and competent
 8. The tender fors shall be issued to eligible contractors depending upon their past performance and work experience which shall be duly evaluated by the technical evaluation committee.
 9. The contractor/firm having necessary documents and past adequate experience shall be preferred
 10. The contractor who has failed to start/complete the work already allotted in his favour with in stipulated period shall not be issued tender forms.
 11. A contractor enlisted in a particular class be eligible to tender for his own class and one step blow.
 12. Only two No. tender form will be issued to the eligible contractor.
 13. If happens to be holiday the tender shall be opened on next working day at 11:30 A.M
 14. GST will be deducted as per rates fixed by the Govt.

Certificate

Certificate that tender for the above works are urgently required please.

No-PW-CSD-Tender /200/21

11550-11649

Dated 11/11/2021



Executive Engineer
Chopal Division
HPPWD Chopal

Copy forwarded to the :-

1. The Chief Engineer, Shimla Zone HPPWD Shimla
2. The Superintending Engineer 4th Circle HP, PWD. Shimla
3. All The Assistant Engineer working under this Division
4. All the Contractors/ Firms working under Chopal
5. The Deputy Commissioner Shimla
6. The Sub Divisional Magistrate Chopal
7. The Block Development Officer Chopal
8. The Tehsildar Chopal
9. Notice Board, Drawing Branch, Accounts Branch.

Executive Engineer
Chopal Division
HPPWD Chopal

SCHEDULED OF QUANTITY.

Name of work:- A/R & M/O on Kiarnu Koti Sarain road Km. 0/0 to 7/00 (SH:- C/O B/wall wire crated between Km. 0/770 to 1/810, 1/825 to 1/840 and 1/870 to 1/890)

		Job No		1	
		Estimated Cost		Rs. 4,74,000/-	
		Earnest Money		Rs. 9,500/-	
Sr No	Description Of Items	Quantity	Rate	Time	Amount
				Rate (in words)	
1	Earth work in excavation in ordinary rock using manual means including loading in truck and carrying of excavated materials to embankment site with a lift up to 1.50 metre and lead including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	98.45			Per Cubic metre
2	Earth work in Excavation of structure as per drawing & technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material & including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts ordinary soil (i) up to 3 metre depth..	54.60			Per Cubic metre
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and IS:4826 in 100x100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	218.99			Per Cubic metre
4	Back filling behind abutment wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 (i) Granular material including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts	10.50			Per Cubic metre
					Total

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.

Name of work :- A/R & M/O on Kiarnu Koti Sarain road Km. 0/0 to 7/00 (SI:- C/O B/wall at between Km. 1/780 to 1/796)

Job No **2**

Sr No	Description Of Items	Quantity	Rate	Estimated Cost		Unit	Amount
				Earnest Money	Time		
1	Earth work in excavation in ordinary rock using manual means including loading in truck and carrying of excavated materials to embankment site with a lift up to 1.50 metre and lead including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	166.40		Rs. 4,73,900/-	3 Months	Per Cubic metre	
2	Earth work in Excavation of structure as per drawing & technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material & including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts ordinary soil (i) up to 3 metre depth..	18.24				Per Cubic metre	
3	Providing and laying cement concrete 1:4:8 (1 cement 4 Sand 8 graded stone aggregate 25 mm nominal size) and curing complete including the cost of form work for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HPPWD technical specifications. including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	104.07				Per Cubic metre	
4	Providing weep holes in plain concrete wall 100mm dia PVC pipe extending through the width of the structure with slope of 1:20 towards dry face complete as per drawing and technical specification clause 614 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	30.00				Per running metre	
						Total	

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.

Name of work :- A/R & M/O on on Saini Chopal Nerwa Feduj road Km. 20/00 to 90/00 (SH-C/O Protection wall between Km. RDS/345 to 9/405)

SCHEDULED OF QUANTITY.							Job No	3
Name of work :- A/R & M/O on on Saini Chopal Nerwa Feduj road Km. 20/00 to 90/00 (SH- C/O Protection wall between Km. RDS/9/345 to 9/405)							Estimated Cost	Rs. 4,73,000/-
							Earnest Money	Rs. 9,500/-
							Time	3 Months
							Rate (in words)	Unit
Sr No	Description Of Items	Quantity	Rate	Rate (in words)	Unit	Amount		
1	Earth work in excavation in ordinary rock using manual means including loading in truck and carrying of excavated materials to embankment site with a lift up to 1.50 metre and lead including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol I and as per direction of Engineer in Charge at site in all leads and lifts	72.00			Per Cubic metre			
2	Earth work in Excavation of structure as per drawing & technical specification Clause 305 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal up to a lead of 50 meter dressing of sides and bottom and back filling in trenches with excavated suitable material & including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol I and as per direction of Engineer in Charge at site in all leads and lifts ordinary soil (i) up to 3 metre depth..	20.00			Per Cubic metre			
3	Providing and laying P.C. C. in 1:5:10 (one cement : 5 sand 10 graded stone) and curing complete including the cost of form work for plain/reinforced concrete in retaining walls, breast walls as per drawing and HPPWD technical specification including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol I and as per direction of Engineer in Charge at site in all leads and lifts.	111.46			Per Cubic metre			
4	Providing weep holes in plain concrete wall 100mm dia PVC pipe extending through the width of the structure with slope of 1:20 towards dry face complete as per drawing and technical specification clause 614 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol I and as per direction of Engineer in Charge at site in all leads and lifts.	19.43			Per running metre			
5	Back filling behind abutment wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 (i) Granular material including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol I and as per direction of Engineer in Charge at site in all leads and lifts	8.80			Per Cubic metre			
					Total			

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.

Name of work :- A/R & M/O Various roads under Shantha section PTU Sub Division (SH:- Removal of slips in different Roads)

Sr No	Description Of Items	Quantity	Rate	Job No	
				4	
				Estimated Cost	
1	Removal of slips in all kinds of soil including saturated soil but excluding boulder and rocky portion required blasting up to distance of 20 mtr disposing of un-serviceable material stacking serviceable material and neatly dressing the surface including including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	1336.36		Earnest Money	Rs. 1,47,000/-
				Time	Rs. 3,000/-
				Rate (in words)	1 Months
				Unit	Amount
				Per Cubic metre	
				Total	

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.	
Name of work :- A/R & M/O Various roads under Feduj section Ptu Sub Division (Sh:- Removal of slips in different Roads)	

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.

SCHEDULED OF QUANTITY.									
Name of work :- A/R & M/O Various roads under Kuthar section PIU Sub Division (SH:- Removal of slips in different Roads)							Job No	6	
Sr No	Description Of Items	Quantity	Rate	Rate (in words)	Estimated Cost	Job No	6		
					Earnest Money	Rs. 1,40,000/-	Rs. 2,800/-		
					Time	1 Months	Unit	Amount	
1	Removal of slips in all kinds of soil including saturated soil but excluding boulder and rocky portion required blasting up to distance of 20 mtr disposing of un-serviceable material stacking serviceable material and neatly dressing the surface including including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol. II and as per direction of Engineer in Charge at site in all leads and lifts.	1272.73					Per Cubic metre		
							Total		

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.

Name of work :- A/R & M/O Various roads under Pulbhal section Chopal Sub Division (SH:- Removal of slips in different Roads)

Sr No	Description Of Items	Quantity	Rate	Estimated Cost	Job No	7
				Earnest Money Time	Rs. 4,75,100/- Rs. 9,500/-	
1	Removal of slips in all kinds of soil including saturated soil but excluding boulder and rocky portion required blasting up to distance of 20 mtr disposing of un-serviceable material stacking serviceable material and neatly dressing the surface including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	4319.09		Rate (in words)	Unit	Amount
					Per Cubic metre	
					Total	

Executive Engineer
Chopal Division
HP PWD Chopal

SCHEDULED OF QUANTITY.

Name of work :- Balance work of Sub Health center at Kiarnoo P.O Podia Tehsil Nerwa Dist Shimla
(SH:- Providing and Fixing Dors and Windows and Fittings)

Sr No	Description Of Items	Quantity	Rate	Estimated Cost		Unit	Amount
				Time	Rate (in words)		
				Earnest Money	Rs. 1,01,026/-		
1	Providing and fixing pandelled glazed shutters for doors and windows and clerestory windows including black enamelled iron hinges with necessary screws 40mm thick 1st class kail wood	18.00				Per square metre	
2	Supplying and fixing glass panes with putty and nils including removal of broken glass panes wherever necessary plain glass 4mm thick	7.04				Per square metre	
3	Providing and fixing aluminium tower bolts (berrel type) anodized transparent of dyed to required shades and colour with screws etc. complete						
	150x10mm	6.00				Each	
	100x10mm	38.00				Each	
4	Providing and fixing aluminium handles anodized transparent of dyed to required shades and colour with screws etc. complete						
	125mm	4.00				Each	
	75mm	28.00				Each	
5	Providing and fixing anodized aluminium sliding door bolt anodized shades and colour with bolts and nuts screws etc. complete.						
	300x16mm	1.00				Each	
						Total	

Executive Engineer
Chopal Division
HP PWD Chopal