

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item rates tender are hereby invited by the Executive Engineer, Ghumarwin Division, HP-PWD, Ghumarwin for the following works from the registered contractors of appropriate class enlisted in HP-PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act. 1968. The important date of tender are as under:-

Date of application
Date of sale of tender.

2411/2021
25/11/2021

The tender shall be received up to 11:00A.M. on 26/11/2021 and will be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 225/11/2021.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Ghumarwin Division, HP-PWD, Ghumarwin must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

Sr.	Name of work	Estimated Cost	Earnest Money	Time Period	Tender Cost
1	C/o Pachrani to Badhwin road km 0/0 to 1/0 (Sh: P/L C.C. pavement at RD 0/600 to 0/669)	Rs.149551/-	Rs.3000/-	Two Month	Rs.350/-
2	R/R on Jol to Domehar road km 0/0 to 3/270 (SH: P/L C.C. interlocking paver block at RD 1/250 to 1/301)	Rs.195835/-	Rs.4000/-	One Month	Rs.350/-
3	C/o link road from Chhat to Dhinwa Ghatian road 0/0 to 3/0 (Sh: C/o P.C.C. U-shape road side drain and C.C. pavement at RD 0/682 to 0/840) SCSP	Rs.499331/-	Rs.10000/-	Two Month	Rs.350/-
4	R/R on link road Trountra Barota Sih road km 0/0 to 3/825 (SH: Extension of RCC H/pipe culvert at RD 2/640 along with wing wall)	Rs.145396/-	Rs.3000/-	Two Month	Rs.350/-
5	C/o link road from Dhingu to Sukkri Km 0/20 (AH: -C/o 900 mm 900 dia HPC with w/all at RD 1/030 (Both side)	Rs.248748/-	Rs.5000/-	Three Month	Rs.350/-
6	A/R & M/O to residence to Sr.Civil Judge cum ACJM Ghumarwin Baddu Tehsil Ghumarwin Distt. Bilaspur HP (SH:-P/L 100mm thick anti skit tile and minor repair)	Rs.120219/-	Rs.2400/-	Three Month	Rs.350/-
7	NRB HPPWD RH & AE office building at Bharari (SH:-C/o interlock paver block on court year of RH, edge wall etc. and court year of AE & JE office Bharari)	Rs.278651/-	Rs.5600/-	Two Month	Rs.350/-
8	AMP on Sannour Patta via Karyalag H/Basti Churan Gugga Temple road Km 0/0 to 6/0 (SH:-C/o CC pavement at RD 5/321 to 5/381 i/c edge wall and V-Shape drain at RD 5/321 to 5/450)	Rs.353575/-	Rs.8000/-	Two Month	Rs.350/-

Terms and conditions

- The XEN reserve the right to accept or reject the tenders without assigning any reason.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
- The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No. should be accompanied with application.
- Earnest money should be accompanied with application. Application without earnest money will not be entertained.
- CERTIFICATE**

Certified that the tenders have been invited in exigencies/emergency of work.

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW/GHD/CB/Tender/2021-

Copy along with Notice Inviting Tender list is forwarded to:-

- The Engineer-in-Chief HPPWD Shimla-2
- The Chief Engineer (HZ) HPPWD Hamirpur
- The Superintending Engineer, 10th Circle, HPPWD Bilaspur
- The Executive Engineer (IT) O/O Engineer-in-Chief HPPWD Shimla-2 eeict-pwd-shi[at]hp[dot]gov.in a/w schedule of quantity to download on the department portal.
- Drawing Branch
- Account Branch

Dated:- 15/11/2021

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs 149551/-ONLY.

EARNEST MONEY:- Rs 3000 Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-C/O Pachrani to Badhwin road km 0/0 to 1/0 (SH:- P/L C.C. pavement at RD. 0/600 to 0/669)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Preparation of sub-grade by dressing to chamber (Earth work) for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	210.45			Per Square metre	
2	Providing laying spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade and camber applying and brooming stone screening/binding materials to fill up the interstices of coarse aggregate watering and compacting to the required density Grade-I as per technical specification clause 405 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	21.04			Per cubic metre	
3	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	15.78			Per cubic metre	
4	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-25 (1:1.5:3) (One cement: one point five sand:three graded stone aggregate) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	21.04			Per cubic metre	
Total=						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs 195835/-NLY.

EARNEST MONEY:- Rs 4000/- Only.

TIME ALLOWED:-ONE MONTH.

NAME OF WORK:- R/R on Jol to Domehar road km 0/0 to 3/270 (SH:-P/L C.C. interlocking paver Block at RD. 1/250 to 1/301)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials(i) upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	17.21			Per cubic metre	
2	Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular subbase by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408.(i) Using naturally including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government. occurring gravel	6.22			Per cubic meter	
3	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	33.92			Per cubic metre	
4	Providing and laying interlocking concrete block pavement having thickness 80mm (sixty millimetre) as per drawing and technical specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	155.54			per square metre	
TOTAL=						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .499331/-ONLY.

EARNEST MONEY:- Rs 10000/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-C/O link road from Chhat to Dhinwa Ghatian road km 0/0 to 3/0 (SH:-C/O P.C.C. U-shape road side drain and C.C. pavement at RD. 0/682 to 0/840)SCSP.

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials(i) upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	177.75			Per cubic metre	
2	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	60.04			Per cubic metre	
3	Preparation of sub-grade by dressing to chamber (Earth work) for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	529.3			Per Square metre	
4	Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular subbase by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408.(i) Using naturally including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	75.84			Per cubic meter	
5	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size plain/reinforced concrete in open foundation complete as per drawing and HP.PWD., technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	50.56			Per cubic meter	
6	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-25 (1:1.5:3) (One cement: one point five sand: three graded stone aggregate) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	37.92			Per cubic metre	

Executive Engineer
 Building Division,
 H.R. PWD, Chumawin.

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .145396/-ONLY.

EARNEST MONEY:- Rs 3000 Only.

TIME ALLOWED:- TWO MONTH.

DE WORK:-R/R on link road Trountra Barota Silh road km 0/0 to 3/825 (SH:-Extension of RCC H/pipe culvert at RD.2/640 along with wing wall)

Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
		Figures	Words.		
Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials(i) upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	29.25			Per cubic metre	
2 Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size plain/reinforced concrete in open foundation complete as per drawing and H.P.W.D., technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1.48			Per cubic meter	
3 Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802, 803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	3.74			Per cubic metre	
4 Providing and cement concrete 1:5:10 (One cement: Five sand: Ten graded stone aggregate of form work for plain/reinforced concrete in retaining walls, breast walls, as per drawing and H.P.P.W.D., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	53.13			Per cubic metre	
5 Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement: Two sand) but excluding excavation protection work, back filling concrete and masonry work to head walls and parapets clause 1108 @ 900mm dia including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	2.50			Per Running Metre	
6 Providing weep holes in brick masonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614, 709, 1204.3.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	20.00			Each	
7 Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	15.25			Per cubic metre	
Total=					


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 2,48,748.00

Earnest Money:- Rs. 5,000.00

Time :- Two Month

Name of Work:- Construction of link road from Dhingu to Sukri km 0/0 to 2/0 (SH:- Construction of 900mm dia hume pipe culvert with w/all at RD 1/030 (Both side).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto all leads and lift. dressing of sides and bottom and back filling in trenches with excavated suitable material as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.35	Per cubic metre			
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) (40mm forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.55	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated cement concrete for plain/reinforced concrete in open foundations for all type of structure complete of plain cement concrete grade M-10(M-Ten) nominal mix 1:3:6(One cement: Three sand: Six graded crushed stone aggregate) 20mm(Twenty millimetre size) in or under water and curing complete including pumping of bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D. technical specification clause 802,803,1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.80	Per cubic metre			
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108.as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. (i)900 mm dia (nine hundred millimetre).	7.50	Per running metre			
5	Providing and Laying concrete 1:5:10 (one cement: five sand:ten crushed stone aggregate) 40 mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	82.01	Per cubic metre			
6	Back filling behind abutment, wing walls return wall complete as per drawings and technical specification clause 1204.3.8 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.64	Per cubic metre			

7	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Each			
	Total:-					


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 1,20,219.00

Earnest Money:- Rs. 2,500.00


Time :- One Month

Name of Work:- A/R & M/O to Residence of Senior Civil Judge Cum ACJM Ghumarwin (Baddu) Tehsil Ghumarwin District Bilaspur HP (SH:- Providing and laying 10mm thick anti skid tile and minor repair).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Dismantling tiled floors laid in mortar upto all floor level including stacking of serviceable materials and disposal of un-serviceable materials within any lead (wooden/concrete joists to be measured and paid for separately) For thickness of tiles above 25mm (twenty five millimetre) and upto 40mm (forty millimetre) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.03	Per square metre			
2	Providing and fixing 10mm (ten millimetre) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles NITCO or equivalent 600x600x10mm (six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring treads of steps and landing laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	51.76	Per square metre			
3	6mm (six millimetre) thick white glazed tiles of Kajaria, NITCO, Somani, orient, Rak, Johnson & Johnson in skirting risers of steps and dado upto any height on 12mm (Twelve millimetre) thick cement mortar 1:3 (One cement: Three sand) and jointed with cement slurry as per H.P.PWD. specification 1990 clause 13.7 and 13.8 including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.44	Per square metre			
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	176.29	Per square metre			
5	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on decorated wall surfaces (one coat) to give an even shade after thoroughly brushing the surface to remove all dirt, loose or softened paint. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	377.16	Per square metre			
6	Extra item for every sub sequent coat of water proofing cement paint of approved brand and manufacture. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	377.16	Per square metre			

	Providing and fixing 19mm (nineteen millimetre) thick Commercial Board water proof shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.66	Per square metre			
8	Providing and fixing water proof kit ply of standard quality ISI mark and approved shade and colour in panelling & wall lining including mitring at junctions, butt jointing and nails complete (Frame work for base to be measured & paid for separately) 9mm (nine millimetre) thick as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.66	Per square metre			
9	Providing and fixing M.S. hooks and eyes. 150 mm (one hundred fifty millimetre) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Each			
10	Providing and fixing bright finished brass ball catcher 10 mm (ten millimetre) dia as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.00	Each			
11	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm (zero point five six millimetre) for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws. 40 mm (forty millimetre) thick 2nd class deodar wood including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same and as per HP.PWD Specification 1990 vol-I clause 12.4.	1.80	Per square metre			
12	Providing and fixing plain square edged cover fillets (beading) 50mm x 12mm (fifty into twelve millimetre) section, with wood screws in ceiling and lining including mitring at junction. 1st class deodar wood as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Per running metre			
13	Repairs to plaster in patches of 2.50 Sq.M. (two point five zero per square metre) and under and 10 to 15mm (ten to fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within any lead with Cement Mortar 1:5 (one cement : five sand) including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.14	Per square metre			
14	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.386	Per quintel			

	Providing corrugated G.I sheet roofing fixed with galvanised iron J or L hooks bolts and nuts 8 mm (eight millimetre) diameter with bitumen and G.I. limpet washers filled with white lead complete excluding the cost of purlins rafters and trusses. 0.63 mm (zero point six three millimetre) thick sheet as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.48	Per square metre			
16	Providing and fixing brass curtain rail with rollers stop ends and brackets in pelmets instead of wooden curtain rod 25 mm dia and brackets of first class deodar wood (actual length) of rails to be measured as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.36	Per running metre			
17	Constructing course rubble hammer dressed 'U' shape open surface drain with side wall 15X22 cm (fifteen into twenty two centimeter). in cement mortar 1:6 (one cement: six sand) and inside plastering with cement plaster 1:3 (one cement: three sand) including earth work and laying 10 cm (ten centimeter). cement concrete in 1:5:10 (one cement: five sand: ten graded/crushed stone aggregate) of 40 mm (forty millimeter). nominal size and 7.5 cm (seven point five millimeter). cement concrete 1:2:4 (one cement: two sand: four graded /crushed stone aggregate 20 mm (twenty millimeter). nominal size) and finished with a floating coat of neat cement complete as per standard design including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Per running metre			
	Total:-					


Executive Engineer
 Ghumarwin Division
 H.P.R.W.D. Guwahati

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .278651/-ONLY.

EARNEST MONEY:- Rs 5600/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-N/R Building HP,PWD Rest House at Bharari & A.E Office Building at Bharari (SH:- C/O interlocking paver block on Court yard of Rest House , Edge wall etc. and Court yard of A.E.&J.E. office Bharari)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials(i) upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	70.88			Per cubic metre	
2	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	28.68			Per cubic metre	
3	Providing and laying interlocking concrete block pavement having thickness 80mm (sixty milimetre) as per drawing and technical specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	246.84			per square metre	
4	Providing laying concrete for plain / Reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 PCC grade M20 (1:2:4) nominal mix Cement concrete 1:2:4. (1 cement: sand : 4 graded stone aggregate 20mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	11.73			Per cubic metre	
	Total=					


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .353575/-ONLY.

EARNEST MONEY:- Rs 8000/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-Annual Maintenance Plan on Sannour Patta via Karyalag H/Basti Churan Gugga Temple road km 0/0 to 6/0 (SH:-C/O C.C. pavement at RD.5/321 to 5/381 i/c edge wall and V-shape drain at RD. 5/321 to 5/450)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	54.98			Per cubic metre	
2	Loosening of the ground upto a level of 300mm (Three hundred millimetre) below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical specification clause 303.5.2 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	68.04			Per Cubic Metre	
3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size plain/reinforced concrete in open foundation complete as per drawing and HP.PWD., technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	55.08			Per cubic meter	
4	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802, 803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	46.75			Per cubic metre	
5	Providing laying concrete for plain / Reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 PCC grade M20 (1:2:4) nominal mix Cement concrete 1:2:4. (1 cement: sand : 4 graded stone aggregate 20mm nominal size) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	22.68			Per cubic metre	
	Total=					

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.