

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

NO.PW.THG/CB/TENDER/Tender Notice/2020-21- 4323-25
To

Email: eenh-theog-hp@gov.in

Phone/ Fax No.: 01783-238900

Dated:- 11-11-2021


The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:-

Publication of tender Notice.


Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department

Notice Inviting Tender

Sealed item rate s tender form No 6 & 8 are hereby invited by the Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-

- | | | |
|---|---|--------------------------|
| 1 | Date of receipt of Applications for tender forms: | 18.11.2021 upto 12:00 PM |
| 2 | Date of issue/sale of Tender forms:- | 20.11.2021 upto 4:00 PM |
| 3 | Date of receipt of Tender:- | 22.11.2021 upto 10:30 AM |
| 4 | Date of opening of Tender | 22.11.2021 upto 11:00 AM |

Sr. No	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	A/R & M/o on Kalka Shimla Wangtoo Road NH 22(New NH05) from Km 155/0 to 236/0(SH: C/o R/wall at RD 170/695 to 170/705)	492954/-	9900/-	350	Two Months
2	R/R damages on Kalka Shimla Wangtoo Road NH 22(New NH 05) from Km 155/0 to 236/0(SH: C/o R/wall at RD 231/329 to 231/336)	474790/-	9500/-	350	Two Months
3	R/R damages on Kalka Shimla Wangtoo Road NH 22(New NH 05) from Km 155/0 to 236/0(SH: C/o R/wall at RD 231/320 to 231/327)	474852/-	9500/-	350	Two Months

Certificate: It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from any Nationalized Bank duly pledged in favour of the executive Engineer .
- 5 The earnest Money & Cost of Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 6 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 7 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

- 8 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 9 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 10 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 11 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 12 One Contractor should not have more than two works in hand at a time.
- 13 Works should be completed by the contractor within the stipulated period.


Executive Engineer,

NH Division,
H.P.P.W.D., Theog


Dated 11-11-2021

No/PW/NH/CB/Tender/2021

U3B-22

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar Shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Superintending Engineer NH Circle HP PWD Shimla . It is therefore requested to kindly issue the certificate the tender of above emergent nature in public interest.
- 4 All the Assistant Engineer working under this Division
- 5 The Drawing Branch/Account Branch in this office.
- 6 Notice Board.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O on Kalka Shimla Wangtoo Road NH-22 (NH-05) from Km 155/00 to 236/00(SH:- C/O R/wall at RD 170/695 to 170/705)

Estimated Cost:-492954.00

Earnest Money :- 9900.00

:- Two Months.

Time

Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount
				In figures	In words	
1	Excavation in soil by Manual Mean. Excavation ordinary soil using mechanically/ manual means including loading in truck and carrying out earth to embankment site with all lifts and leads , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge	21.40	Cum			
2	Excavation for Structures . Earth work in excavation of foundation of structures as per drawings and technical specifications, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge	22.50	Cum			
3	Providing and laying Plain /Reinforced Cement Concrete grade M15 (Sixty percentage of twenty millimetre and Forty percentage of ten millimetre nominal size) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 PCC Grade M15 , as per direction of the Engineer-in-Charge in all leads, lifts and carriage of materials by all means of transport etc.	79.35	Cum			
4	Providing weep holes in Brickmasonry/plain/reinforced concrete abutment,wing wall/return wall with 100mm dia PVC pipe extending through the full width of the structure with slope 1V:20H towards drawing face complete as per drawing and Technical Specification Clause 2706 & 2200 in all leads, lifts and carriage of materials by all means of transport etc as per the direction by the Engineer-in-charge .	25.00	Rmt.			
5	Providing and laying of Filter media with granular materials/stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2. of MoRTH specifications to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specification.	9.20	Cum			
Total						

Condition

- 1 Rates Should be quoted for all heights includings all leads and lifts.
- 2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.
- 3 Cement should be procured from HP State Civil Supply Corporation only.


Executive Engineer,
National Highway Division ,
H.P. P.W.D. Theog .

SCHEDULE OF QUANTITY

Name of Work:-R/R damages on Kalka Shimla Wangtoo Road NH-22 (NH-05) from Km 155/00 to 236/00(SH:- C/O R/wall at RD 231/329 to 231/336).

Estimated Cost:-474790.00

Earnest Money :- 9500.00

:- Two Months.

Time

Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount
				In figures	In words	
1	Excavation in soil by Manual Mean Excavation ordinary soil using mechanically/ manual means including loading in truck and carrying out earth to embankment site with all lifts and leads , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge	12.84	Cum			
2	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge	18.34	Cum			
3	Providing and laying Plain /Reinforced Cement Concrete grade M15 (Sixty percentage of twenty millimetre and Forty percentage of ten millimetre nominal size) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 PCC Grade M15 , as per direction of the Engineer-in-Charge in all leads, lifts and carriage of materials by all means of transport etc.	69.35	Cum			
4	Providing weep holes in Brickmasonry/plain/reinforced concrete abutment,wing wall/return wall with 100mm dia PVC pipe extending through the full width of the structure with slope 1V:20H towards drawing face complete as per drawing and Technical Specification Clause 2706 & 2200 in all leads, lifts and carriage of materials by all means of transport etc as per the direction by the Engineer-in-charge .	20.30	Rmt.			
5	Providing and laying of Filter media with granular materials/stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2. of MoRTH specifications to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specification.	14.56	Cum			
Total						

Condition

- 1 Rates Should be quoted for all heights including all leads and lifts.
- 2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.
- 3 Cement should be procured from HP State Civil Supply Corporation only.
- 4 Rates Should be quoted inclusive of GST.


Executive Engineer,
National Highway Division ,
H.P. P.W.D. Theog .

SCHEDULE OF QUANTITY

Name of Work:-R/R damages on Kalka Shimla Wangtoo Road NH-22 (NH-05) from Km 155/00 to 236/00(SH:- C/O R/wall at RD 231/320 to 231/327)				SCHEDULE OF QUANTITY		Estimated Cost:-474852.00 Earnest Money :- 9500.00 :- Two Months.		Time
Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount		
				In figures	In words			
1	Excavation in soil by Manual Mean Excavation ordinary soil using mechanically/ manual means including loading in truck and carrying out earth to embankment site with all lifts and leads , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge	12.84	Cum					
2	Excavation for Structures Earth work in excavation of foundation of structures as per drawings and technical specifications, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge	18.34	Cum					
3	Providing and laying Plain /Reinforced Cement Concrete grade M15 (Sixty percentage of twenty millimetre and Forty percentage of ten millimetre nominal size) in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 PCC Grade M15 , as per direction of the Engineer-in-Charge in all leads, lifts and carriage of materials by all means of transport etc.	69.36	Cum					
4	Providing weep holes in Brickmasonry/plain/reinforced concrete abutment,wing wall/return wall with 100mm dia PVC pipe extending through the full width of the structure with slope 1V:20H towards drawing face complete as per drawing and Technical Specification Clause 2706 & 2200 in all leads, lifts and carriage of materials by all means of transport etc as per the direction by the Engineer-in-charge .	20.30	Rmt.					
5	Providing and laying of Filter media with granular materials/stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specification.	14.56	Cum					
Total								


Condition

- Rates Should be quoted for all heights includings all leads and lifts.
- The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.
- Cement should be procured from HP State Civil Supply Corporation only.
- Rates Should be quoted inclusive of GST.


Executive Engineer,
National Highway Division ,
H.P. P.W.D. Theog .

Certificate

Certified that the tenders of works as called vide this office NIT No/PW/NH/CB/Tender/2021-4313-22 Dated 11.11.2021 are of urgent nature works.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog