



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

Dated 17-11-2021

No.-PW/OSDN/ Tender-NIT/2021-22

To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate

Ramp
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

Rm
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740

NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **26.11.2021** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **24.11.2021** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money (in Rupees)	Time	Cost of tender form Rs.
1	A/R & M/O Dalash Gungi road 0/00 to 3/120. (SH:- C/O retaining wall at RD 0/205 to 0/215).	168057.00	4000	One month	350/-
2	A/R & M/O residential quarter for PWD deparment at Nirmand Distt Kullu, H.P. (S.H.:-Providing painting, distempering and tile work etc in EE residence)	289682.00	6000	One month	350/-
3	A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (SH:- Providing and Supplying of premixed materials for premixed carpet and seal coat at site for patch work between km. 17/00 to 25/00)	349813.00	8000	Fifteen days	350/-
4	Extension of Raja Raghuvir Singh Stadium at Anni District Kullu H.P. (SH:- Balance work	497190.00	10000	One month	350/-

	of roofing.) under Deposit work				
5	A/R & M/O link road from Arsu Chunagai to Bari km. 0/00 to 3/500. (S.H:-C/O wire crate breast wall at RD 3/485 to 3/500)	144328.00	4000	One month	350/-
6	Construction of Degree College Anni at Haripur. (SH:- Construction of P.C.C. retaining wall in approach road at RD. 0/00 to 0/009).	430859.00	9000	One month	350/-
7	Restoration of rain damages on Farbog to Thach road road km. 0/00 to 2/870. (SH:- C/O PCC. retaining wall at RD 0/705 to 0/714.70)	390098.00	8000	One month	350/-
8	A/R & M/O Guhatan to Lote road road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/280 to 0/290)	416094.00	8000	One month	350/-
9	A/R & M/O Guhatan to Lote road road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/160 to 0/175)	430760.00	9000	One month	350/-
10	A/R & M/O Nagan Chheora Chhatttri road km. 0/00 to 12/240. (SH:- C/O retaining wall at RD 6/620 to 6/636)	421209.00	8500	One month	350/-
11	C/O road from Khobri Khad to Thaleen Km. 0/0 to 2/465 under BASP (SH:- C/O 900 mm dia RCC Hume pipe culverts at RD 0/132 and 0/283)	376612.00	8000	Three months	350/-
12	A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/210 to 22/235)	334157.00	7000	Two months	350/-
13	Construction of road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/250 to 22/270) under BASP Sr. No. 102	443306.00	10000	Two months	350/-
14	Construction of link road from Shani to Ghulat km. 0/00 to 5/210. (SH:- C/O breast walls at RD 3/030 to 3/045) under BASP	253442.00	6000	One month	350/-
15	Construction of Tandi to Chanthwa road km. 0/00 to 1/800. under BASP (Sub Head:- Construction of R/Wall at RD.0/010 to 0/016.50)	193016.00	4000	Two months	350/-
16	C/O road from Jn. of LDCK road to Jn. of NAS road Km. 24/0 to 32/0 (Jhjar Side) under MNP (SH:- C/O 900 mm dia RCC Hume pipe culverts at RD 23/540, 24/285, 26/270, 26/550 and 27/560)	497054.00	10000	Three months	350/-
17	C/O road from Jn. of LDCK road to Jn. of NAS road Km. 24/0 to 32/0 (Jhjar Side) under MNP (SH:- C/O 900 mm dia RCC Hume pipe culverts at RD 29/270, 29/885, 30/735, 31/435 and 31/200)	499854.00	10000	Three months	350/-
18	A/R & M/O rest house building at Neether. (SUB HEAD :- Providing painting, Plastering and Distempering etc.)	408140.00	10000	One month	350/-
19	Repair/construction of boundary wall to HSC	205228.00	5000	One	350/-

	building at Shani undr deposit work (SH:- Construction of boundary wal arounf Sub-Centre)		.	month	
20	M/T works on Behna Dalash road km. 0/00 to 17/345. under self deposit (SH:- C/O PCC retaining wall at RD. 9/210 to 9/230 and 11/375 to 11/385).	351037.00	8000	One month	350/-
21	A/R & M/O Wazir Bowali Mohali road km 0/00 to 26/00 (SH:- C/O R/Wall at RD. 25/270 to 25/282)	406423.00	9000	One month	350/-
22	A/R & M/O Brow Poshana road km. 0/00 to 13/180 . (SH:- C/O P.C.C. R/Walls at RD. 10/180 to 10/193)	315280.00	7000	One month	350/-
23	A/R & M/O Link road from Chaklot to Chunagai Km 0/000to 5/450. (SH :- Improvement / correction by Cutting at various Rds.)	486002.00	10000	One month	350/-
24	A/R & M/O Dalash Rewari road km. 0/00 to 1/300 (SH:- P/L patch work between km. 0/00 to 1/300) .	61622.00	2000	One month	350/-

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer
Outer Seraj Division
H.P. PWD, Nirmand
on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740

Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 10325-35 dated
17.11.2021 is very urgent nature. So may be uploaded on Departmental
website in public interest please.


**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand**
on behalf of Governor of Himachal Pradesh

Schedule of quantity									
Name of Work:- A/R & M/O Dalash Gungi road 0/00 to 3/120. (SH:- C/O retaining wall at RD 0/205 to 0/215).				Estimated cost:-		168057.00			
				Earnest Money		4000			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	15.3	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.9	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	31.4	Cubic Metre						
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	16	Each						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.25	Cubic Metre						
Total in Figures									

Executive Engineer
 Civil & Water Division
 H.P.W.D. Mandla

Schedule of Quantity									
Name of work - A/R & M/O residential quarter for PWD department at Nirmand Distt Kullu, H.P. (S.H.:-Providing and fixing wooden panelling, painting, distempering and tile work etc in AE office)									
Estimated cost:- Rs. 289682.00									
Earnest Money:- Rs.6000.00									
Time:- One month									
Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT			
				Figures	Words				
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	512.45	Per Square Metre						
2	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour two coats including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	512.45	Per Square Metre						
3	Painting with synthetic enamel paint of approved brand and manufacturer to give an even shade Two or more coats on new work including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	154.74	Per Square Metre						
4	Providing and fixing cup board shutters with 25 mm thick veneered particle board IS : 3097 marked, exterior grade (Grade I), of approved make, including 11nd class teak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of Engineer-in-Charge With decorative veneering on one side and commercial veneering on other side including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	9.360	Per Square Metre						
5	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	5.52	Per Square Metre						
6	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm thick including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	21.150	Per Square Metre						
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	1.580	Per Cubic Metre						
8	Providing and fixing precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	38.88	Per Square Metre						
9	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	12.20	Per Running Metre						
10	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete Fixed to openings /wooden frames with rawl plugs screws etc. including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	309.00	Per Kilogram me						

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
11	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	216.84	Per Kilogram me			
12	Providing and fixing 2nd class seasoned wood lipping/ moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/nails on the edges of the Pre-laminated particle board as per direction of Engineer-in-charge	87	Per Running Metre			
13	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	1.00	Each			
14	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	1000	Per Litre			
15	Providing and fixing nickel plated M.S. pipe curtain rods with nickel plated brackets 20 mm dia (heavy type) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	15.00	Per Running Metre			
16	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete Double strip (horizontal type) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	16.00	Each			
17	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete 125 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	8.00	Each			
	G.Total:-					


 Executive Engineer,
 Outer Seraj Division,
 HP J&K Narmad.

3

SCHEDULE OF QUANTITY						
Name of work:-A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (SH:-			Estimated cost:- Rs. 349813.00 only			
Providing and Supplying of premixed materials for premixed carpet and seal coat at site for			Earnest Money Rs. 8000.00 only			
patch work between km. 17/00 to 25/00)			Time:- Fifteen Days			
Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing and supplying of premixed material at site of work for open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm to 5.6 mm aggregates using penetration grade bitumen VG-10 including mixing in a suitable plant, as per Technical Specification Clause 508 including cost of grit and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge.(The bitumen will be supplied by the department free of cost at Plant site).	70.00			Per Cubic Metre	
2	Providing and supplying of premixed material at site of work for seal coat, Type B as per Technical Specification Clause 510 including cost of crushed sand defined as passing 2.36 mm sieve and retained on 180 micron sieve and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at plant site).	16.00			Per Cubic Metre	
Total						

Executive Engineer
Outer Seroj Division
H.P.W.D. Dhamand

Schedule of Quantity

Name of work: - Extension of Raja Raghuvir Singh Stadium at Anni District Kulllu H.P. (SH:- Balance work of roofing.)					Estimated cost:- Rs. 497190.00	
					Earnest Money:- Rs. 10000.00	
					Time:- One Month	
Sr. No.	Description of work	Qty.	Unit	Figures	Rate In Figures	
					Words	AMOUNT
1	Providing pre-painted steel sheet roofing over steel trusses (steel work in trusses to be measured and paid for separately) with pre-painted galvanised steel Hot dipped metallic zinc coated sheets conforming to IS-14246-1995 (Latest revision) 0.60 mm thick inclusive of the cost of fasteners including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	210.00	Square metre			
2	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	160.00	Square metre			
G.Total:-						


 Executive Engineer,
 Outer Seraj Division,
 HPPWD: Mandi.

5


Schedule of quantity						
Name of Work:-A/R & M/O link road from Arsu Chunagai to Bari km. 0/00 to 3/500. (S.H.:-C/O wire crate breast wall at RD 3/485 to 3/500)				Estimated cost:-		
				Earnest Money		
				Time		
				One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	34.87	Cubic Metre			
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	65.64	Cubic Metre			
Total in Figures						

Executive Engineer
Outer Serai Division
HPPWD, Alimnand

Signature of Tenderer with seal

Schedule of quantity

Name of Work:- Construction of Degree College Anni at Haripur. (SH:- Construction of P.C.C. retaining wall in approach road at RD. 0/00 to 0/009)					Estimated cost:- Earnest Money 9000		430859.00
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		One month AMOUNT
					Words	Time	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	24.12	Cubic Metre				
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	38.61	Cubic Metre				
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.77	Cubic Metre				
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	85.50	Cubic Metre				
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	25	Each				
Total in Figures							


 Executive Engineer
 Outer Seral Division
 HPWD Jalandhar

Signature of Tenderer with seal

7

Schedule of quantity

Name of work:- Restoration of rain damages on Farbog to Thach road road km. 0/00 to 2/870. (SH:- C/O PCC. retaining wall at RD 0/705 to 0/714.70)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-		One month	
				Figures	Words	Earnest Money	Time	AMOUNT	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	20.66	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	29.88	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.66	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	77.21	Cubic Metre						
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	28.00	Each						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.28	Cubic Metre						
Total in Figures									


 Executive Engineer
 District Survey Division
 HPPWB, Nimand

Signature of Tenderer with seal

8

Schedule of quantity									
Name of work:- A/R & M/O Guhatan to Lote road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/280 to 0/290)					Estimated cost:-		416094.00		
					Earnest Money		8000.00		
					Time		One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	21.40	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	16.70	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.00	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	79.60	Cubic Metre						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.57	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Seraj Division
 HPWD, Himmatnagar

9

Schedule of quantity									
Name of work:- A/R & M/O Guhatan to Lote road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/160 to 0/175)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		
					Words	Time	Earnest Money		
							One month		
							AMOUNT		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	10.50	Cubic Metre						430760.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	49.35	Cubic Metre						9000.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.45	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	79.35	Cubic Metre						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.47	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Saraj Division
 HPWD, Jalandhar

Signature of Tenderer with seal

10

Schedule of quantity

Name of work:- A/R & M/O Nagan Chheora Chhatttri road km. 0/00 to 12/240. (SH:- C/O retaining wall at RD 6/620 to 6/636)

SL. No.		Description of work	Qty.	Unit	RATE		Estimated cost:-	421209.00		
					Figures	Words				
									Time	Earnest Money
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	21.60	Cubic Metre							
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	31.36	Cubic Metre							
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.60	Cubic Metre							
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40.48	Cubic Metre							
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	67.04	Cubic Metre							
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.39	Cubic Metre							
		Total in Figures								

RW
Executive Engineer
Outer Sarda Division
HISAWD, Kirmant

Signature of Tenderer with seal

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O road from Khobri Khad to Thaleen Km. 0/0 to 2/465 under BASP (SH:- C/O 900 mm dia RCC Hume pipe culverts at RD 0/132 and 0/283)					Estimated Cost: 376612.00	
					Earnest money:- 8000.00	
					Time:- Three months	
Sr. No	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Earth work in excavation for structures as per drawing and technical specifications Clauses 305.1 & 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and back filling in trenches with excavated suitable material in all kind of soil upto any depth in earth work such as pick work, jumper work, pick jumper work, pick jumper blasting work, blasting work in soft and hard rock conglomerate rock or saturated soil and their intermediate classification of soil including chiseling/ wedging out of rocks (where blasting is prohibited) and pumping or bailing watering /dewatering and disposal of all surplus excavated earth, up to all leads, lifts and through all modes of transportation, disposed earth to be levelled and neatly dressed including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	83.11	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:6:12 (one cement: six sand: twelve graded crushed stone aggregate 40mm (forty millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	9.03	Per Cubic Metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 25mm twenty five millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	20.270	Per Cubic Metre			
4	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate 25mm (twenty five millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	22.990	Per Cubic Metre			

	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical Specification in cement mortar 1:3 (one cement : three sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.980	Per Cubic Metre			
6	Providing and laying reinforced cement concrete pipe 900mm (Nine hundred millimetre) dia NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.00	Per Running Metre			
7	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.00	Each			
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	8.86	Per Cubic Metre			


 Executive Engineer,
 Outer Survey Division,
 HPWD, Mirmand.

12

Schedule of quantity									
Name of Work: A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/210 to 22/235)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:- Earnest Money Time	Two months AMOUNT	
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.30	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	27.90	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.60	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	33.31	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	42.74	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.65	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Social Division
 HIGWAY

13

Schedule of quantity									
Name of Work: Construction of road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/250 to 22/270) under BASP									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		
					Words	Amount	Earnest Money		
							Time		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	12.40	Cubic Metre						443306.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	37.20	Cubic Metre						10000.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	12.80	Cubic Metre						Two months
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	42.74	Cubic Metre						AMOUNT
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	58.66	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.20	Cubic Metre						
Total in Figures									

22
Executive Engineer
Outer Sargaj Division
HDDWD, Mirmand

Schedule of quantity

Schedule of quantity									
Name of Work: Construction of link road from Shani to Ghulat km. 0/00 to 5/210. (SH:- C/O breast walls at RD 3/030 to 3/045) under BASP									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		AMOUNT
						Words	Earnest Money	Time	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	22.20	Cubic Metre						253442.00 6000.00 One month
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	18.45	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.59	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	29.87	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	22.03	Cubic Metre						
Total in Figures									

Executive Engineer,
Outer Seraj Division
H.P.W.D. Mirmand

Schedule of quantity

Name of Work: Construction of Tandi to Chanthwa road km. 0/00 to 1/800. under BASP (Sub Head:- Construction of R/Wall at RD.0/010 to 0/016.50))									
Sl. No.		Description of work	Qty.	Unit	Estimated cost:-		193016.00		Two months
					Figures	Words	Earnest Money		
							Time		
							AMOUNT		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	7.35	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	17.94	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.68	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	22.81	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.87	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.58	Cubic Metre						
		Total in Figures							


 Executive Engineer
 Outer Seraj Division
 H.P.W.D. Himachal Pradesh

Signature of Tenderer with seal

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O road from Jn. of LDCK road to Jn. of NAS road Km. 24/0 to 32/0 (Jhijar Side) under MNP (SH:- C/O 900 mm dia RCC Hume pipe culverts at RD 23/540, 24/285, 26/270, 26/550 and 27/560)					Estimated Cost: 497054.00 Earnest money:- 10000.00 Time:-Three months	
Sr. No	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Earth work in excavation for structures as per drawing and technical specifications Clauses 305.1 & 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and back filling in trenches with excavated suitable material in all kind of soil upto any depth in earth work such as pick work, jumper work, pick jumper work, pick jumper blasting work, blasting work in soft and hard rock conglomerate rock or saturated soil and their intermediate classification of soil including chiseling/ wedging out of rocks (where blasting is prohibited) and pumping or bailing watering /dewatering and disposal of all surplus excavated earth, up to all leads, lifts and through all modes of transportation, disposed earth to be levelled and neatly dressed including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	194.40	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:6:12 (one cement: six sand: twelve graded crushed stone aggregate 40mm (forty millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	8.75	Per Cubic Metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate 40mm (forty millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	35.220	Per Cubic Metre			
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical Specification in cement mortar 1:3 (one cement : three sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.450	Per Cubic Metre			

5	Providing and laying reinforced cement concrete pipe 900mm (Nine hundred millimetre) dia NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	37.50	Per Running Metre		
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	5.16	Per Cubic Metre		


 Executive Engineer,
 Outer Serai Division,
 HPCWD Mirmand.

SCHEDULE OF QUANTITY						
NAME OF WORK:- C/O road from Jn. of LDCK road to Jn. of NAS road Km. 24/0 to 32/0 (Jhijar Side) under MNP (SH:- C/O 900 mm dia RCC Hume pipe culverts at RD 29/270, 29/885, 30/735, 31/435 and 31/200)				Estimated Cost: 499854.00		
				Earnest money:- 10000.00		
				Time:- Three months		
Sr. No	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Earth work in excavation for structures as per drawing and technical specifications Clauses 305.1 & 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and back filling in trenches with excavated suitable material in all kind of soil upto any depth in earth work such as pick work, jumper work, pick jumper work, pick jumper blasting work, blasting work in soft and hard rock conglomerate rock or saturated soil and their intermediate classification of soil including chiseling/ wedging out of rocks (where blasting is prohibited) and pumping or bailing watering /dewatering and disposal of all surplus excavated earth, up to all leads, lifts and through all modes of transportation, disposed earth to be levelled and neatly dressed including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	194.40	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:6:12 (one cement: six sand: twelve graded crushed stone aggregate 40mm (forty millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	8.75	Per Cubic Metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete of mix design to have characteristic strength of nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate 40mm (forty millimetre) nominal size) in open foundation including dewatering, curing, formwork complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials within all leads, lifts and other incidental as per direction of Engineer-in-charge.	35.220	Per Cubic Metre			
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical Specification in cement mortar 1:3 (one cement : three sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.450	Per Cubic Metre			

5	Providing and laying reinforced cement concrete pipe 900mm (Nine hundred millimetre) dia NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	37.50	Per Running Metre		
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	7.16	Per Cubic Metre		


 Executive Engineer,
 Outer Serai Division,
 HP-PWD, Jalandhar.

Schedule of Quantity

Name of work:-A/R & M/O rest house building at Neether. (SUB HEAD :- Providing painting, Plastering and Distemping etc.)

Estimated cost:- Rs. 408140.00

Earnest Money:- Rs.10000.00

Time:- One month

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	1356.49	Per Square Metre			
2	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: 13.98.1 One or more coats on old work including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	1356.49	Per Square Metre			
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : 13.99.1 One or more coats on old work including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	560.24	Per Square Metre			
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer inCharge. With cement mortar 1:4 (1 cement : 4 fine sand) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	120.00	Per Square Metre			
5	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/sqm) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	44.80	Per Square Metre			
6	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	17.00	Each			
7	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). sal wood including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	0.2040	Per Cubic Metre			
8	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood 35 mm thick shutterswith ISI marked M.S. pressed butt hinges bright finished of required size Sal wood 35 mm thick including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	22.040	Per Square Metre			
9	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : Sal wood 35 mm thick including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	21.00	Per Square Metre			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
10	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality Rectangular shape 600x450 mm internal dimensions including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	3.00	Each			
11	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	2000.00	Per Litre			
12	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm dia nominal bore including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	40.00	Per running Metre			
13	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :15 mm nominal bore including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	8.00	Each			
14	Fixing water meter and stop cock in G.I. pipe line including cutting and threading the pipe and making long screws etc. complete (cost of water meter and stop cock to be paid separately). including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	4.00	Each			
15	Providing and fixing bright finished brass handles with screws etc. complete: 125 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	4.00	Each			
16	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x 16 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	4.00	Each			
17	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.					
a	200x10 mm	8.00	Each			
b	150x10 mm	74.00	Each			
18	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.					
a	125mm	6.00	Each			
b	100 mm	74	Each			
	G.Total:-					


 Executive Engineer
 Outer Sewer Division
 H.P.O. & B, Nirmal

Schedule of Quantity

Schedule of Quantity						
name of work Repair/construction of boundary wall to HSC building at Shani undr deposit work (SH:- Construction of boundary wal arounf Sub-Centre)				Estimated cost:- Rs. 205228.00 Earnest Mony:- Rs.5000.00 Time:- One month		
Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Earth work in excavation in all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains up to all depth including dressing of sides and ramming of bottoms, up to all leads and lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	10.80	Per Cubic Metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for Columns, piers, abutments, pillars, posts and struts including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	7.20	Per Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five fine sand : ten graded stone aggregate 40 mm nominal size) including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	5.28	Per Cubic Metre			
4	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size).ncluding curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	0.54	Per Cubic Metre			
5	teel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/workshop to construction site including placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	108.00	Per Kilogra mme			
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand) including curing and carriage of materials in all leads and lifts as per direction of Engineer – in –	4.400	Per Cubic Metre			
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in cement mortar 1:4 (1 cement :4 coarse sand) including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	49.01	Per Square Metre			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
8	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand) including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	6.48	Per Cubic Metre			
9	15 mm cement plaster on rough side of single or half brick wall of mix 1:6 (1 cement: 6 coarse sand) including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	166.32	Per Square Metre			
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	166.32	Per Square Metre			
11	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	162	Per Kilogramme			
	G.Total:-					


 Executive Engineer,
 Outer Seral Division,
 HP J&K D. Demand.

20

Schedule of quantity

Schedule of quantity						
Name of Work:- M/T works on Behna Dalash road km. 0/00 to 17/345, under self deposit (SH):- C/O PCC retaining wall at RD. 9/210 to 9/230 and 11/375 to 11/385).				Estimated cost:- Earnest Money		351037.00
				Time		8000
				One month		AMOUNT
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	12.00	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	30.60	Cubic Metre			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.80	Cubic Metre			
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	62.80	Cubic Metre			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.00	Cubic Metre			
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	32	Each			
Total in Figures						

20

Executive Engineer
Outer Seraj Division
HID/W/D

21

Schedule of quantity

Schedule of quantity									
Name of Work: A/R & M/O Wazir Bowali Mohali road km 0/00 to 26/00 (SH:- C/O R/Wall at RD. 25/270 to 25/282)				Estimated cost:-		406423.00			
				Earnest Money		9000.00			
				Time		One month			
Sl. No.	Description of work	Qty.	Unit	RATE		Figures	AMOUNT		
							Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	28.80	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	27.96	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	8.64	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	77.64	Cubic Metre						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.82	Cubic Metre						
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each						
Total in Figures									

22

Executive Engineer
Outer Sani Division
HPPD
W.B. Nirmand

Signature of Tenderer with seal

22

Schedule of quantity

Schedule of quantity										
Name of Work:- A/R & M/O Brow Poshana road km. 0/00 to 13/180 . (SH:- C/O P.C.C. R/Walls at RD. 10/180 to 10/193)				Qty.			Unit	Estimated cost:-		315280.00
								Earnest Money		7000
								Time		One month
								RATE		AMOUNT
Sl. No.	Description of work				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	20.02	Cubic Metre							
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	5.98	Cubic Metre							
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	62.01	Cubic Metre							
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	21.00	Cubic Metre							
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	16.00	Each							
							Total in Figures			

Executive Engineer
Outer Seral Division
HPI/WD, Nimala

Signature of Tenderer with seal

Schedule of quantity

Schedule of quantity						
Name of Work: A/R & M/O Link road from Chaklot to Chunagai Km 0/000to 5/450. (SH :-Improvement / correction by Cutting at various Rds.)				Estimated cost:-		486002.00
				Earnest Money		10000
				Time		One month
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 307.72 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1840.50	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Sesa Division
 HPWD, Nirmal

Signature of Tenderer with seal

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Dalash Rewari road km. 0/00 to 1/300 (SH:- P/L patch work between km. 0/00 to 1/300) .

Estimated Cost:-61622.00

Earnest money:- 2000.00

Time:- One month

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words		Amount
					Rate in words	Amount	
1	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 404, including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	6.75	Per Cubic Metre				
2	Providing and applying priming coat with bitumen emulsion (SS-1) using bitumen distributor at the rate of 0.85 kg. (Zero point eight five Kilogramme) per sqm. on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of Ministry of rural Development 2004 clause of 503 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	283.60	Per Square Metre				
3	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion pressure distributor @ 0.275 kg (Zero point two seven five Kilogramme) per square metre of the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of clause 503 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	283.60	Per Square Metre				
4	Providing and rolling of open-graded premix carpet of 20mm (twenty millimetres) thickness composed of 13.2mm to 5.6 mm (thirteen point two millimetre to five point six millimetre) coursed stone aggregates using paving bitumen @ 0.27 (Zero point two seven) cubic metre per square metre (VG-10) grade 14.6 (fourteen point six) kilogramme per ten square metre to required lines. Grades and levels to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel static roller 80-100 KN capacity, finished to required level and grades to be followed by seal coat of Type B as per Technical Specifications of Ministry of rural Development 2004 Clause 508, including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	283.60	Per Square Metre				
5	Providing and laying seal coat with bitumen (VG-10), grade @ 6.80 (six point eight zero) kilogramme per ten squaremetre and coursed sand @ 0.06 (zero point zero six) cubic metre per ten square metre sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall /camber using IRC Type B, as per Technical Specifications of Ministry of rural Development 2004 Clause 510, including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	283.60	Per Square Metre				