

Sealed item rate tenders on form No. 6 & 8 are hereby invited works shown below :- Date of receipt of Applications for tender forms:- 10.11.2021. upto 1.00 PM. Date of issue/sale of Tender forms 10.11.2021- 2:00 P.M. to 5.00 PM 3. Date of receipt of Tender:- ~~11.11.2021~~ at 11:00AM 4. Date of opening of Tender:- ~~11.11.2021~~ at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time
1.	(i) Preparation of road surface for Micro surfacing including on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 7/300 to 15/0 (SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 8/0 to 10/0).(ii) (i) Preparation of road surface for Micro surfacing including on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0 (SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 1/0 to 2/0) (Micro Surfacing for 2021-22).	235596.00	4700.00	Two Months.
2.	Preparation of road surface for Micro surfacing including on Sujampur Sandhol Marhi road km. 0/0 to 23/0.(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 4/0 to 12/0). (Micro Surfacing for 2021-22).	458024.00	9500.00	Two Months.
3.	Balance work of restoration of rain damages on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- P/L interlocking concrete block pavement at RD.2/216 to 2/239.50). (Deposit work).	98907.00	2000.00	Two Months.
4.	Improvement of Black spot on Barara to Bakkar Khad via Patnaun road km. 2/0 to 8/0. (SH:- Improvement of curves at RD. 2/225 to 2/245, 2/285 to 2/330, 4/120 to 4/150 and 4/405 to 4/435).	494983.00	10000.00	Two Months.
5.	C/o L/R Ayurvedic Dispensary Ree to Village Kuwali Gram Panchayat Ree Km.0/0 to 1/500(SH:- F/C 5/7 mtr wide Km. 0/0 to 0/337) (OTMNP)	472233.00	9500.00	Two Months.
6.	C/O link road Nallahi to Kangri via Sathotha Asthatha Sauran Da Gran km. 2/0 to 6/0.(SH:- ROFD in km. 4/420 to 4/525) (Under OTMNP).	478278.00	9500.00	Two Months.
7.	Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/635 to 6/721).	493854.00	10000.00	Two Months.
8.	Restoration of rain damages on link road to village Marahana km. 0/0 to 2/525.(SH:- C/O B/Wall at RD. 2/445 to 2/475 and 2/490 to 2/500).	263448.00	5300.00	Two Months.
9.	Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/510 to 3/540).	98905.00	2000.00	Two Months
10.	Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/540 to 3/570).	99211.00	2000.00	Two Months
11.	Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- C/O R/Wall at RD. 4/800 to 4/815).	321495.00	6500.00	Two Months
12.	A/R & M/O on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Improvement of curves F/C at RD. 1/022 to 1/097 & 1/107 to 1/150).	263891.00	5500.00	Two Months

13.	Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Cement concrete interlocking paver block at RD. 4/900 to 4/990).	465977.00	9500.00	Two Months
14.	C/O Missing C.D. on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- P/L interlocking concrete paver block at RD. 7/215 to 7/231 & 7/234 to 7/253).	199588.00	4000.00	Two Months
15.	A/R & M/O on EE residence HPPWD Tauni Devi (SH:- P/L heavy duty precast CC interlocking paver block in court yard)	182506.00	3500.00	Two Months
16.	C/o Link road Kothi to Jully km. 0/0 to 2/500 (SH:- C/o 900 mm dia RCC hume pipe culvert (double row) at RD 0/258 along with wing wall both side 10 mtr (OTMNP).	484573.00	10000.00	Two Months

TERMS AND CONDITIONS:-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit the following documents with the application:-

1. The valid enlistment/ registration of contractor in appropriate class.
2. Permanent Account Number (PAN).
3. GST Number.
4. Earnest money in the shape of National saving certificate/ Time deposit Account in any of the Post office in H.P. F.D.R. from any Nationalized Bank (i/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer.
5. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
6. Tax Clearance Certificate (T.C.C.) issued from the concerned Excise and Taxation department.
7. Ambiguous/ telegraphic/ Conditional tenders or tender by fax/E-mail shall not be entertained/considered and will summarily be rejected.
8. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
9. The offer of the tender shall remain valid upto 120 days after the opening of tender.
10. If the date given above happens to be a holiday, the same shall be processed on next working day.
11. The contractors/ firms must quote their rates in words as well as in figures failing which XEN reserves the right to accept / reject any or all tenders.
12. The tender forms will not be issued to those contractors/ firms whose previous performance is not found satisfactory and who have not executed/ completed the previous awarded works within the stipulated period of completion.
13. One contractor should not have more than two major works in hand at a time.
14. Work should be completed by the contractor within the stipulated period.
15. Works completion and work in hand certificate issued by the concerned Executive Engineer must be attached with the application for issue of tender form.

Executive Engineer,
Tauni Devi Division
HP:PWD., Tauni Devi

For and on behalf of the Governor of H. P.

Copy forwarded for information & necessary action to :-

1. The Engineer-in-Chief, HP:PWD, Shimla.
2. The Chief Engineer (HZ), HP:PWD, Hamirpur.
3. The Superintending Engineer, 8th Circle, HP:PWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Executive Engineer (IT cell), Nigam Bihar, Shimla-2 for uploading of Notice Inviting tenders on the departmental website please.
7. The Computer Cell o/o Executive Engineer (IT cell), Nigam Bihar, Shimla-2.
8. The Tehsildar, Tauni Devi.
9. The B. D. O. Tauni Devi.
10. The Municipal Committee, Hamirpur.
11. All the Assistant Engineers working under this Division.
12. Accounts Branch/ Drawing Branch/ Notice Board.
13. Lok Mitra, Tauni Devi.
14. Various Contractors/ Firms.

Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi

A certificate of exigencies /emergencies

It is certified that following works are in exigency/
emergency situation and as per in public interest / demands require immediate action
uploaded in HPPWD website:-

(i) Preparation of road surface for Micro surfacing including on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 7/300 to 15/0 .(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 8/0 to 10/0).(ii) (i) Preparation of road surface for Micro surfacing including on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0 .(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 1/0 to 2/0) (Micro Surfacing for 2021-22).
Preparation of road surface for Micro surfacing including on Sujampur Sandhol Marhi road km. 0/0 to 23/0.(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 4/0 to 12/0). (Micro Surfacing for 2021-22).
Balance work of restoration of rain damages on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- P/L interlocking concrete block pavement at RD.2/216 to 2/239.50). (Deposit work).
Improvement of Black spot on Barara to Bakkar Khad via Patnaun road km. 2/0 to 8/0. (SH:- Improvement of curves at RD. 2/225 to 2/245, 2/285 to 2/330, 4/120 to 4/150 and 4/405 to 4/435).
C/o L/R Ayurvedic Dispensary Ree to Village Kuwali Gram Panchayat Ree Km.0/0 to 1/500(SH:- F/C 5/7 mtr wide Km. 0/0 to 0/337) (OTMNP)
C/O link road Nallahi to Kangri via Sathotha Asthotha Sauran Da Gran km. 2/0 to 6/0.(SH:- ROFD in km. 4/420 to 4/525) (Under OTMNP).
Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/635 to 6/721).
Restoration of rain damages on link road to village Marahana km. 0/0 to 2/525.(SH:- C/O B/Wall at RD. 2/445 to 2/475 and 2/490 to 2/500).
Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/510 to 3/540).
Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/540 to 3/570).
Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- C/O R/Wall at RD. 4/800 to 4/815).
A/R & M/O on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Improvement of curves F/C at RD. 1/022 to 1/097 & 1/107 to 1/150).
Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Cement concrete interlocking paver block at RD. 4/900 to 4/990).
C/O Missing C.D. on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- P/L interlocking concrete paver block at RD. 7/215 to 7/231 & 7/234 to 7/253).
A/R & M/O on EE residence HPPWD Tauni Devi (SH:- P/L heavy duty precast CC interlocking paver block in court yard)
C/o Link road Kothi to Jully km. 0/0 to 2/500 (SH:- C/o 900 mm dia RCC hume pipe culvert (double row) at RD 0/258 along with wing wall both side 10 mtr (OTMNP).

Anil Kumar
Executive Engineer
Tauni Devi
H.P.P.W.D. Tauni Devi

Schedule of Quantity

Estimated Cost:- 235596.00
Earnest Money:- 4700.00
Time:- One Month.

Name of Work:- (i) Preparation of road surface for Micro surfacing including on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 7/300 to 15/0 (SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 8/0 to 10/0). (ii) (i) Preparation of road surface for Micro surfacing including on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0 (SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 1/0 to 2/0) (Micro Surfacing for 2021-22).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Providing and laying spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade with camber applying and brooming, crushable screening to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III as per technical specification clause 405 by manual means and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	48.25			Per cubic metre.	
2.	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2.503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1108.10			Per Square metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tauni Devi Division,
 HP-PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 458024.00
Earnest Money:- 9500.00
Time:- One Month.

Name of Work:- Preparation of road surface for Micro surfacing including on Sujjanpur Sandhol Marhi road km. 0/0 to 23/0.(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 4/0 to 12/0). (**Micro Surfacing for 2021-22**).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In fig.	In Words.		
1.	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred)weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	62.00			Per cubic metre.	
2.	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.70-1.0 kilogram (zero point seven zero to one point zero kilogram per square meter) using mechanical means as per technical specification clause -502 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	558.00			Per Square metre	
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2258.29			Per Square metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


Executive Engineer,
Tauni Devi Division,
HP-PWD., Tauni Devi.

Schedule of Quantity

Estimated Cost:- 98907.00
Earnest Money:- 2000.00
Time:- Two Months.

NAME OF WORK:- Balance work of restoration of rain damages on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- P/L interlocking concrete block pavement at RD 2/216 to 2/239.50). (Deposit work).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including storing an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	16.50			Per cubic metre	
2	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP-PWD., specification 100mm(one hundred millimeters) spread thickness (finished work including materials and labour) in all leads and lifts and dressing of sides and bottom and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts.	12.30			Per cubic metre	
3	Providing and laying mechanically mixed cement concrete 1:3:6 (one cement:three sand :six graded crushed stone aggregate on ground for under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.50			Per cubic metre	
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks of N.T.C make or its equivalent BIS certified blocks and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts.	82.25			Per square metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Ashish Chh
Executive Engineer,
Tauri Devi Division,
HP PWD., Tauri Devi

Schedule of Quantity

Estimated Cost:- 494983.00
Earnest Money:- 10000.00
Time:- Two Months.

Name of Work:- Improvement of Black spot on Barara to Bakkar Khad via Patnaun road km. 2/0 to 8/0. (SH:- Improvement of curves at RD. 2/225 to 2/245, 2/285 to 2/330, 4/120 to 4/150 and 4/405 to 4/435).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation for road way in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal with a lift upto 1.50mtr. (one point fifty metre) and lead upto 1000mtr. (one thousand metre) trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections as per technical specification clause 302.3.5 (Mechanical means) as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	1533.88			Per cubic Metre.	
					Total:-	

Note:- No creditable material i.e. stone received from cutting work because this road is conglomerate.


Executive Engineer,
Tauni Devi Division,
HP.PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 472233.00
Earnest Money:- 9500.00
Time:- Two Months.

Name of Work:- C/O link road Ayurvedic Dispensary Ree to village Kuwali Gram Panchayat Ree km. 0/0 to 1/500.(SH:- formation cutting 577mtr. wide road km. 0/00 to 0/337) (Under OTMNP)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 358.93/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 1,07,679/- only.	2991.09			Per cubic Metre.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

A. G. G. M.
Executive Engineer,
Tauni Devi Division,
MP-PWD, Tauni Devi.

Schedule of Quantity

Estimated Cost:- 478278.00
 Earnest Money:- 9500.00
 Time:- Two Months.

Name of Work:- C/O link road Nallahi to Kangri via ~~Sattar~~ Asthotha Sauran Da Gran km. 2/0 to 6/0. (SH:- ROFD in km. 4/420 to 4/525) (Under OTMNP)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 334.77/- cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs. 1,00,431/-only.	2792.70			Per cubic Metre.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Anil Kumar
 Executive Engineer,
 Jauni Devi Division,
 HP-PWD., Jauni Devi


Schedule of Quantity

Estimated Cost:- 493854.00
Earnest Money:- 10000.00
Time:- Two Months.

Name of Work:- Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/635 to 6/721).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation for road way in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal with a lift upto 1.50mtr. (one point fifty metre) and lead upto 1000mtr. (one thousand metre) trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections as per technical specification clause 302.3.5 (Mechanical means) as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals .	1530.38			Per cubic Metre.	
					Total:-	

Note:- No creditable material i.e. stone received from cutting work because this road is conglomerate.


Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 263448.00
 Earnest Money:- 5300.00
 Time:- Two Months.

NAME OF WORK:- Restoration of rain damages on link road to village Marahana km. 0/0 to 2/525.(SH:- C/O B/Wall at RD. 2/445 to 2/475 and 2/490 to 2/500).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	58.60			Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	129.50			Per Sqm.	
	Providing and laying mechanically mixed and vibrated cement concrete 1:5:10 (one cement five sand : ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls/breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-In-Charge including entire carriage of material within all leads and lifts and other incidentals.	94.08			Per cubic metre	
	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square, (four kilogramme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-In -Charge, including entire carriage of material within all leads and lifts and other incidentals.	32.00			Each	
					Total:-	

Terms and Condition:-

Work shall be executed as per PWD specification.


 Executive Engineer,
 Tajni Devi Division,
 HP-PWD, Jauri Devi

Schedule of Quantity

Estimated Cost:- 98905.00
Earnest Money:- 2000.00
Time:- Two Months.

Name of Work:- Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/510 to 3/540).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts.	489.00			Per cubic Metre.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Anil Ghu
Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 99211.00
Earnest Money:- 2000.00
Time:- Two Months.

Name of Work:- Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/540 to 3/570).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts.	490.51			Per cubic Metre.	
					Total:-	

Terms and Condition:-

Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 321495.00
Earnest Money:- 6500.00
Time:- Two Months.

NAME OF WORK:- Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- C/O R/Wall at RD. 4/800 to 4/815).

Sr. No.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m.(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	23.32			Per Cum.	
2.	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	76.35			Per Sqm.	
3.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	47.55			Per Cum.	
4.	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimeter) gap for thermal expansion, (i) Single socketed pipes. 110 mm (one hundred ten millimeters) diameter, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	22.40			Per Rmt.	
					Total:-	

Amr Chh
Executive Engineer,
Tauni Devi Division,
MP-PWD., Tauni Devi.

Schedule of Quantity

Estimated Cost:- 263891.00
Earnest Money:- 5500.00
Time:- Two Months.

Name of Work:- A/R & W/O on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Improvement of curves F/C at RD. 1/022 to 1/097 & 1/107 to 1/150).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation for road way in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal with a lift upto 1.50mtr. (one point fifty metre) and lead upto 1000mtr. (one thousand metre) trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections as per technical specification clause 302.3.5 (Mechanical means) as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals .	817.76			Per cubic Metre.	
Total:-						

Note:- No creditable material i.e. stone received from cutting work because this road is conglomerate.

Anil G. H.
Executive Engineer,
Tauni Devi Division,
HP.PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 465977.00
Earnest Money:- 9500.00
Time:- Two Months.

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/9/15.(SH:- Cement concrete interlocking paver block at RD. 4/900 to 4/990).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structuring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	90.00			Per cubic metre	
2	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site upto lead of 1000m (one thousand metre) spreading in uniform layers with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per technical specification clause 401 for grading-III material, as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.	60.75			Per cubic metre.	
3	Providing and laying mechanically mixed cement concrete 1:3:6 (one cement:three sand :six graded crushed stone aggregate on ground for under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.50			Per cubic metre	
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.25			Per cubic metre	
5	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks of N.T.C make or its equivalent BIS certified blocks and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts.	405.00			Per square metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

And
Executive Engineer,
Tauni Devi Division,
AP-PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 199588.00

Earnest Money:- 4000.00

Time:- Two Months.

NAME OF WORK C/O Missing C.D. on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- P/L interlocking concrete paver block at RD. 7/215 to 7/231 & 7/234 to 7/253).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	25.08			Per cubic metre	
2	Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP-PWD., specification in all leads and lifts and dressing of sides and bottom and as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	13.38			Per cubic metre	
3	Providing and laying mechanically mixed cement concrete 1:3:6 (one cement:three sand :six graded crushed stone aggregate on ground for under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals.	19.00			Per cubic metre	
4.	Providing and laying mechanically mixed cement concrete 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals.	6.52			Per cubic metre	
5	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks of N.T.C make or its equivalent BIS certified blocks and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts.	190.00			Per square metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

A. K. Singh
Executive Engineer,
Tauni Devi Division,
HP-PWD., Tauni Devi.

Schedule of Quantity

Estimated Cost:- 182506.00
Earnest Money:- 3500.00
Time:- Two Months.

NAME OF WORK:- A/R & M/O on E.E. residence HP:PWD., Division Tauni Devi Distt. Hamirpur (HP). (SH:- P/L heavy duty precast C.C. interlocking paver block in court yard).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 60mm(sixty millimeters) thick inter locking blocks of N.T.C make or its equivalent BIS certified blocks and as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	172.85			Per Sqmt.	
2	Providing and laying mechanically mixed cement concrete 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals.	4.98			Per cubic metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Arvind Chaur
Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Distt.

Schedule of Quantity

Estimated Cost:- 484573.00
Earnest Money:- 10000.00
Time:- Two Months.

NAME OF WORK:- C/O link road Kothi to Jolly km. 0/0 to 2/500.(SH:- C/O 900mm dia RCC hume pipe type culvert (double row) at RD. 0/258 along with wing wall both side 10mtr.) (Under OTMNP)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In fig.	In Words.		
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	80.53			Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203 P.C.C. grade 1:4:8 (one cement four sand: eight graded crushed stone aggregate) nominal mix as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.52			Per cubic metre	
3	Providing and laying mechanically mixed cement concrete 1:3:6 (one cement three sand :six graded crushed stone aggregate on ground for under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in open foundation for all types of structures complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	33.00			Per cubic metre	
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900mm(nine hundred millimeters) dia. as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	7.50			Per running meter	
5	Providing and laying mechanically mixed and vibrated cement concrete 1:5:10 (one cement :five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size)) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	134.80			Per cubic metre	
6	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finalex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of 1V: 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals.	100.00			Each	
7	Backfilling behind abutment, wing wall and return wall with granular material complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals.	68.85			Per cubic metre	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Anil Gaba
Executive Engineer,
Tauni Devi Division,
MP-PWD., Tauni Devi.

Sealed item rate tenders on form No. 6 & 8 are hereby invited works shown below :- Date of receipt of Applications for tender forms:- 10.11.2021. upto 1.00 PM. Date of issue/sale of Tender forms 10.11.2021- 2:00 P.M. to 5.00 PM 3. Date of receipt of Tender:- 11.10.2021 at 11.00 AM 4. Date of opening of Tender:- 11.10.2021 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time
1.	(i) Preparation of road surface for Micro surfacing including on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 7/300 to 15/0 .(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 8/0 to 10/0).(ii) (i) Preparation of road surface for Micro surfacing including on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0 .(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 1/0 to 2/0) (Micro Surfacing for 2021-22).	235596.00	4700.00	Two Months.
2.	Preparation of road surface for Micro surfacing including on Sujampur Sandhol Marhi road km. 0/0 to 23/0.(SH:- Repair of pot holes/crack sealing/patch work i/c G-III in km. 4/0 to 12/0). (Micro Surfacing for 2021-22).	458024.00	9500.00	Two Months.
3.	Balance work of restoration of rain damages on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- P/L interlocking concrete block pavement at RD.2/216 to 2/239.50). (Deposit work).	98907.00	2000.00	Two Months.
4.	Improvement of Black spot on Barara to Bakkar Khad via Patnaun road km. 2/0 to 8/0. (SH:- Improvement of curves at RD. 2/225 to 2/245, 2/285 to 2/330, 4/120 to 4/150 and 4/405 to 4/435).	494983.00	10000.00	Two Months.
5.	C/o L/R Ayurvedic Dispensary Ree to Village Kuwali Gram Panchayat Ree Km.0/0 to 1/500(SH:- F/C 5/7 mtr wide Km. 0/0 to 0/337) (OTMNP)	472233.00	9500.00	Two Months.
6.	C/O link road Nallahi to Kangri via Sathotha Asthotha Sauran Da Gran km. 2/0 to 6/0.(SH:- ROFD in km. 4/420 to 4/525) (Under OTMNP).	478278.00	9500.00	Two Months.
7.	Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/635 to 6/721).	493854.00	10000.00	Two Months.
8.	Restoration of rain damages on link road to village Marahana km. 0/0 to 2/525.(SH:- C/O B/Wall at RD. 2/445 to 2/475 and 2/490 to 2/500).	263448.00	5300.00	Two Months.
9.	Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/510 to 3/540).	98905.00	2000.00	Two Months
10.	Improvement of Black on Kakkar Sachuhi road km. 0/0 to 8/500.(SH:- Improvement of curves at RD. 3/540 to 3/570).	99211.00	2000.00	Two Months
11.	Improvement of black spot on Uhal to Indu-Di-Dhar via Jandroo road km. 0/0 to 9/0.(SH:- C/O R/Wall at RD. 4/800 to 4/815).	321495.00	6500.00	Two Months
12.	A/R & M/O on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Improvement of curves F/C at RD. 1/022 to 1/097 & 1/107 to 1/150).	263891.00	5500.00	Two Months

13.	Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- Cement concrete interlocking paver block at RD. 4/900 to 4/990).	465977.00	9500.00	Two Months
14.	C/O Missing C.D. on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915.(SH:- P/L interlocking concrete paver block at RD. 7/215 to 7/231 & 7/234 to 7/253).	199588.00	4000.00	Two Months
15.	A/R & M/O on EE residence HPPWD Tauni Devi (SH:- P/L heavy duty precast CC interlocking paver block in court yard)	182506.00	3500.00	Two Months
16.	C/o Link road Kothi to Jully km. 0/0 to 2/500 (SH:- C/o 900 mm dia RCC hume pipe culvert (double row) at RD 0/258 along with wing wall both side 10 mtr (OTMNP).	484573.00	10000.00	Two Months

TERMS AND CONDITIONS:-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit the following documents with the application:-

1. The valid enlistment/ registration of contractor in appropriate class.
2. Permanent Account Number (PAN).
3. GST Number.
4. Earnest money in the shape of National saving certificate/ Time deposit Account in any of the Post office in H.P. F.D.R. from any Nationalized Bank (I/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer.
5. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
6. Tax Clearance Certificate (T.C.C.) issued from the concerned Excise and Taxation department.
7. Ambiguous/ telegraphic/ Conditional tenders or tender by fax/E-mail shall not be entertained/considered and will summarily be rejected.
8. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
9. The offer of the tender shall remain valid upto 120 days after the opening of tender.
10. If the date given above happens to be a holiday, the same shall be processed on next working day.
11. The contractors/ firms must quote their rates in words as well as in figures failing which XEN reserves the right to accept / reject any or all tenders.
12. The tender forms will not be issued to those contractors/ firms whose previous performance is not found satisfactory and who have not executed/ completed the previous awarded works within the stipulated period of completion.
13. One contractor should not have more than two major works in hand at a time.
14. Work should be completed by the contractor within the stipulated period.
15. Works completion and work in hand certificate issued by the concerned Executive Engineer must be attached with the application for issue of tender form.

Executive Engineer,
Tauni Devi Division
HP-PWD., Tauni Devi.

For and on behalf of the Governor of H. P.

Copy forwarded for information & necessary action to :-

1. The Engineer-in-Chief, HP:PWD, Shimla.
2. The Chief Engineer (HZ), HP:PWD, Hamirpur.
3. The Superintending Engineer, 8th Circle, HP:PWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Executive Engineer (IT cell), Nigam Bihar, Shimla-2 for uploading of Notice Inviting tenders on the departmental website please.
7. The Computer Cell o/o Executive Engineer (IT cell), Nigam Bihar, Shimla-2.
8. The Tehsildar, Tauni Devi.
9. The B. D. O. Tauni Devi.
10. The Municipal Committee, Hamirpur.
11. All the Assistant Engineers working under this Division.
12. Accounts Branch/ Drawing Branch/ Notice Board.
13. Lok Mitra, Tauni Devi.
14. Various Contractors/ Firms.

Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi