

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rate tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on 17.12.2021 up to 11.30 AM and shall be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 10.30 AM on 17.12.2021.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Nahan Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	A/R & M/O Jhameria ramadhon road Km.0/0 to 26/300.(SH:-C/O R/wall at RD.17/910 to 17/935).	4,41,685/-	8,900/-	02 Month	350/-
2	A/R & M/O Jhameria ramadhon road Km.0/0 to 26/300.(SH:-C/O R/wall in wire crate a RD.20/350 to 20/356 & 21/330 to 21/348).	4,97,990/-	10,000/-	02 Month	350/-
3	R/O Govt. (Boys) Shamsher Senior Secondary School Nahan.(SH:-Dismantling, demolition, brick work, plastering & aluminium work etc.)	4,99,578/-	10,000/-	02 Month	350/-
4	R/R damages on L/R under Gram panchayat Mattar, bankala & Nahan.(SH:_Hiring of Excavator-cum-Loader for removal of slips & maintenance of road) under D.C. deposit.	4,99,500/-	10,000/-	01 Month	350/-
5	R/R damages on L/R under Gram panchayat Burma papri.(SH:_Hiring of Excavator-cum-Loader for removal of slips & maintenance of road) under D.C. deposit.	4,97,700/-	10,000/-	01 Month	350/-
6	Repair work of J.N.V. Nahan.(SH:-P/F vetrified tiles flooring in Corrdor Academic block).	3,93,300/-	7,900/-	01 Month	350/-
7	Improvement of Sainwala Burma papri road Km.0/0 11/0.(SH: Improvement of curves)	4,99,779/-	10,000/-	02 Month	350/-
8	R/R damages on L/R Nihog Borlightat Km.0/0 to 6/0(SH: R/O slips)	4,98,956/-	10,000/-	02 Month	350/-
9	R/R damages on dadahu Bechar ka Bag road Km.0/0 to 22/0.(SH:-C/O PCC R/wall at RD.12/220 to 12/232)	4,52,521/-	9,200/-	02 Month	350/-
10	R/R damages on dadahu Bechar ka Bag road Km.0/0 to 22/0.(SH:-C/O PCC R/wall at RD.5/555 to 5/569)	4,98,199/-	10,000/-	02 Month	350/-

CERTIFICATE:- It is certified that the tenders of above works are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must submit their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any HP PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No.PBW(B)A(3)1/2020 dated.Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

For & on behalf of Governor of Himachal Pradesh.

No. PWN/CB/Tender/2020-21-

7683-73

Dated:-

10/12/20

Copy forwarded to the following for information & further necessary action:-

1. The Engineer-in-Chief, HP.PWD., Shimla please.
2. The Chief Engineer(SZ), HP.PWD., Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. at Nahan please.
4. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
5. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD., Shimla-2 for uploading of Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please..
9. All the Assistant Engineers under this division to display on their respective Notice Boards.
10. The Notice Board.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

6

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Jhameria Ramadhon road Km 0/0 to 26/300(SH:-C/O R/Wall at RD 17/910 to17/935)

Estimated cost :- Rs.4,41,685-only

Earnest Money:- Rs.8,900/-only

Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	81.00	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	108.00	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.50	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	30.00	Each			
Total :-						

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

Schedule of Quantity

Name of work:-A/R & M/O Jhameria Ramadhon road Km 0/0 to 26/300(SH:-C/O R/Wall in wire crate at RD 20/350 to 20/356 & 21/330 to 21/348)

Estimated Cost:- Rs.4,97,990/-only

Earnest Money:- Rs.10,000/-only

Time allowed:- Two months

Sr. No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out,construction of shoring and bracing, removal of stumps and other deleterious material and disposal all lead dressing of sides and bottom and back filling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	76.44	Per Cubic metre			
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilograme) each as per drawing and technical Specifications Clause 1301. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	210.00	Per Cubic metre			

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

5

SCHEDULE OF QUANTITY

Name of work:- Repair of Govt. (Boys) Shamsher Senior secondary School Nahan. (SH:- Dismantling, demolition, brick work , plastering & aluminium work etc)

Estimated cost :- Rs :- 4,99,578/-

Earnest Money:- Rs:- 10,000/-

Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Demolition above G.L. upto floor two level unserviceable materials within all lead including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	22.63	Per Cubic metre			
2	Dismantling tiled floors laid in mortar upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 to be measured and paid for separately). including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	25.91	Per square metre			
3	Dismantling doors, windows and cleres ory windows, ventilators etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachements etc. complete and stacking them within all lead. Not exceeding 3 sq.m in area including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	3.00	Each			
4	Brick work using common burnt clay building bricks in foundation and plinth in :-Cement Mortar 1:6 (1 Cement : 6 Sand) Second Class Bricks including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	2.50	Per Cubic metre			
5	Half brick masonry in 2nd class common brunt clay building bricks in super strucutre in cement mortar 1:4 (1 cement : 4 sand) up to floor all level including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	22.80	Per square metre			
6	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone wall for interior plastering upto floor all level including arises, internal rounded angles, chamfers and or rounded angle in all girth & finished even & smooth on rough side with cement mortar 1:6 (one cement : six sand) upto all floor level including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	200.00	Per Square metre			
7	Providing and fixing 10mm thick anti skid water proof stain and impect resistent heavy duey vetrified tiles Nitco or equivalant 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	90.00	Per square metre			
8	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement :3 sand) and jointed with cement slurry. upto floor all level including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	55.00	Per Square metre			

9	Providing and fixing brick bed including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	9.29	Per Cubic metre			
10	Providing and laying cement concrete 1:4:8 (1 cement:4 sand:8 graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in: foundation and plinth: including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	1.86	Per Cubic metre			
11	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	526.60	Per Square metre			
12	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 (One thousand two hundred eighty five) anodised transparent or dyed to required shade according to IS 1868. (One thousand eight hundred sixty eight) (Minimum anodic coating of grade AC 15(Fifteen) fixed with rawlplugs and screws or with fixing clips, or with expansion hold fastners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/ panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-In-Charge. including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.					
a	For doors windows and ventilations and glazed partitions frames.	125.00	Per Kilogram			
b	For shutters of windows and ventilators including providing and fixing hinges/pivots and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required (fittings and glazing/panelling shall be paid for separately)	129.00	Per Kilogram			
	Total:					

Opened By Me
 Cutting
 Over Writing
 Erasing
 Condition

Executive Engineer,
 Nahan (B&R) Division,
 HP, PWD, Nahan.

Schedule of Quantity

Name of work:- Restoration of rain damages on link road under Gram Panchayat Mattar, Bankala & Nahan (SH:- Hiring of excavator cum loader for removal of slips & maintenance of road) under DC deposit

Estimated Cost:- Rs.4,99,500/- Only
Earnest money:- Rs.10,000/- Only
Time:- One Month.

Sr. No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Hiring of Excavator Cum loader for Formation Cutting/ excavation of earth work in all kinds of soil/ removal of slips in all depths and heights including saturated soil and disposal of surplus soil with in all leads and lifts as per direction of the Engineer-in- Charge and making surface smooth including P.O.L. Charges and other expences etc also including carriage of machinery and Labour upto all leads, lifts etc.	555.00	Per hour			

Note :- The cost of P.O.L. charges wear and tear of machinery salary and livery charges of operator and cleaner and repair of machinery etc, shall be born by the contractor himself and nothing will be paid for the same.

Executive Engineer,
Nahan (B&R) Division,
HP,PWD, Nahan.

Opened By Me
Cutting
Over Writing
Erasing
Condition

Schedule of Quantity

Name of work:- Restoration of rain damages on link road under Gram Panchayat Burma Papri(SH:- Hiring of excavator cum loader for removal of slips & maintenance of road) under DC deposit

Estimated Cost:- Rs.4,97,700/- Only
Earnest money:- Rs.10,000/- Only
Time:- One Month.

Sr. No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Hiring of Excavator Cum loader for Formation Cutting/ excavation of earth work in all kinds of soil/ removal of slips in all depths and heights including saturated soil and disposal of surplus soil with in all leads and lifts as per direction of the Engineer-in- Charge and making surface smooth including P.O.L. Charges and other expences etc also including carriage of machinery and Labour upto all leads, lifts etc.	553.00	Per hour			

Note :- The cost of P.O.L. charges wear and tear of machinery salary and livery charges of operator and cleaner and repair of machinery etc, shall be born by the contractor himself and nothing will be paid for the same.

Executive Engineer,
Nahan (B&R) Division,
HP,PWD, Nahan.

Opened By Me
Cutting
Over Writing
Erasing
Condition

6

SCHEDULE OF QUANTITY

Name of work:-Repair work of Jawahar Navodaya Vidyalaya Nahan(SH:- P/F Vetrified tiles flooring in corridor Academic block)

Estimated Cost:- Rs. 3,93,300/-only

Earnest money:- Rs 7,900/-only

Time:- One month.

Sr. No	Sub Head/Item of works	Quantity	Unit	Rate in figure	Rate in world	Amount
1	Providing and fixing 10(ten)mm thick anti skid water proof stain and impect resistant heavy duty vetrified tiles Nitco or equivalant 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings fixed with approved adhesive jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	230.00	Per square metre			

Opened By Me

Cutting

Over Writing

Erasing

Condition

Executive Engineer,
HP.PWD., Division
Nahan.

7

SCHEDULE OF QUANTITY

Name of Work:-Improvement of Sainwala Burma Papri road Km 0/0 to 11/0 (SH :-Improvement of curves)

Estimated Cost:- Rs.4,99,779/- only

Earnest money:- Rs. 10,000/- only

Time:- Two months

Sr No	Sub Head/Item of work	Quantity	Unit	Rate in figure	Rate in world	Amount
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soils including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification of Ministry of Rural Development for Rural Roads August, 2004 (Two Thousand Four),C-1603.1, 1603.2 (Clause - One Thousand Six Hundred Three point One, One Thousand Six Hundred Three point Two) to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places. in specified manner, systematically with due consideration to avoiding adverse effects on environment, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions to the entire satisfaction as directed by the Engineer-in charge for smooth plying of traffic. All useful material such as stones, shingle, aggregate and slates shall be sorted out and stacked along the road side not less than 144.71 cubic metre in all cases, failing which recovery at the rate of Rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.including haulage of mateial with in all leads, lifts and carriage of materials and as directed by the Engineer in-charge.	3512.15	Per Cubic metre			

Opened By Me
Cutting
Over Writing
Filing
Position

Executive Engineer
Nahan Division,
HP,PWD, Nahan.

8

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on link road Nihog Borlighat Km 0/0 to 6/0 (SH:-Removal of slips)

Estimated Cost:- Rs.4,98,956/- only

Earnest money:- Rs 10,000/- only

Time:- Two Months

Sr No	Sub Head/Item of work	Quantity	Unit	Rate in figure	Rate in word	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with all lead and lift as per technical specification 302.3.5 and 1611 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6929.95	Per Cubic metre			

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

SCHEDULE OF QUANTITY

Name of work:- R/R damages on Dadahu Bechar Ka Bag road Km 0/0 to 22/0(SH:-C/O PCC R/Wall at RD 12/220 to 12/232)

Estimated cost :- Rs.452521/-only

Earnest Money:- Rs.9200/-only

Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	58.73	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	105.00	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads, lifts and other incidentals, complete as per entire satisfaction of the Engineer-in-charge.	18.00	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614, 709, 1204, 3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	60.00	Each			
Total :-						

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

SCHEDULE OF QUANTITY

Name of work:- R/R damages on Dadahu Bechar Ka Bag road Km 0/0 to 22/0(SH:-C/O PCC R/Wall at RD 5/555 to 5/569)

Estimated cost :- Rs.498199/-only
Earnest Money:- Rs.10000/-only
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	66.06	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	118.00	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.94	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614, 709, 1204, 3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	65.00	Each			
Total :-						

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.