



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22 *10938-48*
To

Dated *29-11-2021*

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **10.12.2021** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **09.12.2021** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money (in Rupees)	Time	Cost of tender form Rs.
1	A/R & M/O residential quarter for PWD department at Nirmand Distt Kullu, H.P. (S.H.-Providing and fixing wooden panelling, painting, distempering and tile work etc in AE residence)	177041.00	4000	One month	350/-
2	Construction of AE office cum residence at Anni, Distt.- Kullu,H.P. (S.H.-Providing and fixing wooden plank ceiling in AE office, kitchen fixtures in A.E residence and W.S & S.I work) under self deposit	287921.00	6000	One month	350/-
3	Construction of Degree College Anni at Haripur. (SH:- Construction of P.C.C. retaining wall in approach road at RD. 0/010 to 0/019).	429299.00	9000	One month	350/-

4	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/135 to 1/435)	499640.00	10000	One month	350/-
5	Restoration of rain damages on Farbog to Thach road road km. 0/00 to 2/870. (SH:- C/O PCC. retaining wall at RD 0/714.70 to 0/724.40)	390814.00	8000	One month	350/-
6	A/R & M/O Guhatan to Lote road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/290 to 0/300)	415915.00	8000	One month	350/-
7	A/R & M/O Guhatan to Lote road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/175 to 0/190)	427176.00	9000	One month	350/-
8	Construction of road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/015 to 22/027) under BASP	265979.00	6000	Two months	350/-
9	A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.8/250 to 8/270)	443342.0	10000	Two months	350/-
10	Restoration of rain damages on road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/345 to 22/353) under BASP Sr. No. 98	239289.00	6000	Two months	350/-
11	A/R & M/O link road from Shani to Ghulat km. 0/00 to 5/210. (SH:- C/O breast walls at RD km. 0/675 to 0/690)	253442.00	6000	One month	350/-
12	M/T works on Behna Dalash road km. 0/00 to 17/345. under self deposit (SH:- C/O PCC retaining wall at RD. 9/667 to 9/675 and 12/600 to 12/615).	401068.00	9000	One month	350/-
13	A/R & M/O Brow Poshana road km 0/00 to 13/180 (SH:- C/O R/Wall at RD. 5/100 to 5/115).	403304.00	8500	One month	350/-
14	A/R & M/O Kandugad Patarna road km. 0/00 to 11/795 (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchra drain in km. 0/00 to 11/795)	225000.00	5000	One month	350/-
15	A/R & M/O Propeway foot bridge over River Satluj at Jagatkhana. (SH:-Replacement of damaged chequered plate decking of bridge.)	401584.00	10000	Two months	350/-
16	A/R & M/O Propeway foot bridge over River Satluj at Jagatkhana. (SH:-Replacement of damaged foot guard and plastering of Anchorage Blocks and painting of bridge.)	383554.00	8000	Two months	350/-
17	A/R & M/O LDCK km. 0/00 to 53/315. (Sub Head:- Construction of R/Wall at RD.4/355 to 4/365)	235836.00	5000	Two months	350/-
18	BSP/2019/230 P/L M/T works on Wazir Bowali Jhakhari Bye Pass road km. 0/00 to 15/00 under BASP). (Sub Head:- Providing	496127.00	10000	Two months	350/-

	and laying soling WBM G-I in essential reaches between km. 0/00 to 3/300)				
19	Construction of Rest House building (Additional Accommodation) at Anni in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	98000.00	2000	Three months	350/-
20	Construction of Sub Treasury building at Anni in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	98000.00	2000	Three months	350/-
21	Construction of Primary Health Centre building at Kungash in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	98000.00	2000	Three months	350/-
22	Construction of Primary Health Centre building at Jaon in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	148000.00	3000	Three months	350/-
23	Stock Storage. (SH:- Construction of diaframe wall for parking for PWD Division at Nirmand)	338653.00	8000	Three months	350/-
24	Stock Storage. (SH:- Site development work including construction of retaining walls for parking for PWD Division at Nirmand)	338653.00	8000	Three months	350/-

HIM SUCHANA AVAM JAN SAMPARK


**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand**



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 10938-48 dated
29.11.2021 is very urgent nature. So may be uploaded on Departmental
website in public interest please.


**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand**
on behalf of Governor of Himachal Pradesh

Schedule of Quantity

Name of work: - A/R & M/O residential quarter for PWD department at Nirmand Distt Kullu. H.P. (S.H.: Providing and fixing wooden panelling, painting, distempering and tile work etc in AE residence)

Estimated cost:- Rs. 177041.00

Earnest Money:- Rs.4000.00

Time:- One month

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge Kiln seasoned and chemically treated hollock wood 35 mm thick shutters including priming coat on unexposed surface with Decorative veneer facings of approved manufacture including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	5.29	Per Square Metre			
2	Providing and fixing cup board shutters 25 mm thick, with Pre-laminated flat pressed three layer particle board or graded wood particle board IS: 12823 marked, exterior grade (Grade I Type II), having one side decorative lamination and other side balancing lamination, including IInd class teak wood lipping of 25 mm wide x12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of the Engineer-in-Charge including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	12.29	Per Square Metre			
3	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws 35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Kiln seasoned and chemically treated hollock wood including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	2.00	Per Square Metre			
4	Providing and fixing wall panelling of 12mm thick Prelaminated particle board(One side) of approved brand on soft wood 4X4cm frames @ 60cm centre to centre on both side fixing with rawl plugs on wooden pegs and screwed and showing 8mm wide and 12mm deep grooves of required pattern in elevation and finished teak wood beading out of 25x12mm/cornish out of 75x60mm of different pattern in top middle and corner joints including polishing and painting groove complete. including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	48.23	Per Square Metre			
5	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	4.02	Per Square Metre			
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	224.00	Per Square Metre			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
7	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	224.00	Per Square Metre			
8	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	224.00	Per Square Metre			
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	78.27	Per Square Metre			
10	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 300x16 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	2.00	Each			
11	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 200x10 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	7.00	Each			
12	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 100 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	10.00	Each			
13	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete Single rubber stopper including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	2.00	Each			
14	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete 75 mm including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	6.00	Each			
15	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	1	Each			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
16	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	1	Each			
17	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	1	Each			
18	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing Rectangular shape 453x357 mm including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	1	Each			
19	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	2	Each			
20	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms 15 mm nominal bore including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	2	Each			
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	5.70	Each			
22	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately) Size of Tile 600x600 mm including curing and carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.					
	G.Total:-					


 Executive Engineer,
 Outer Sraji Division,
 HFDWD, Nanded.

Schedule of Quantity						
Name of work:- Construction of AE office cum residence at Anni, Distt.-Kullu,H.P. (S.H):-Providing and fixing wooden plank ceiling in AE office, kitchen fixtures in A.E residence and W.S & S.I work) under self deposit				Estimated cost:- Rs. 287921.00		
				Earnest Mony:- Rs. 6000.00		
				Time:- One month		
Sr No.	Description of work	Qty.	Unit	Figures	Rate In Figures	AMOUNT
				Words		
1	Providing and fixing plywood 4 mm thick, one side decorative veneer conforming to IS: 1328 (type-I), for plain lining / cladding with necessary screws, including priming coat on unexposed surface with Decorative veneer facings of approved manufacture including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	16.91	Per Square Metre			
2	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc Kiln seasoned and chemically treated hollock wood including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	0.366	Per Cubic Metre			
3	Providing and fixing 18 mm thick, 150 mm wide pelmet of coir veneer board ISI marked IS : 14842, including top cover of 6 mm coir veneer board, nickle plated M.S. Pipe 20 mm dia. (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. Flat 10 cm long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	55.00	Per Square Metre			
4	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick 5.0 mm thick glass panes (weight not less than 12.5 kg per sqm) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	3.20	Per Square Metre			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
5	Shutter/Partition 20 mm nominal thickness of approved shade, quality and make, made from rigid foam sheets (Single extruded) having density 600 Kg/cum and laminated on both side by laminate Sheet/PVC foil lamination. The exposed edges shall be sealed with Providing & fixing factory made kitchen cabinet Shutter shall be fixed to frame using approved hinges with necessary stainless steel screws, all complete as per direction of Engineer-in-charge including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	3.00	Per Square Metre			
6	Providing and fixing concealed hinge of approved quality for 19-20mm thick door with stainless steel screws complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	12.00	Each			
7	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	6.00	Each			
8	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete including carriage of materials in all leads and lifts as per direction of Engineer – in –	12.00	Each			
9	Providing and fixing magnetic catcher of approved quality in cupboard / wardrobe shutters, including fixing with necessary screws etc. complete Double strip (horizontal type) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	39.00	Each			
10	Providing and fixing one piece construction white vitreous china squatting plate with an integral longitudinal flushing pipe, white P.V.C. automatic flushing cistern, with fittings, standard size G.I. / PVC flush pipe for back and front flush with standard spreader pipes with fittings, G.I clamps and C.P. brass coupling complete, including painting of fittings and cutting and making good the walls and floors etc. wherever required Range of three squatting plates with 10 litre P.V.C. automatic flushing cistern including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	2	Each			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
11	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete 15 mm nominal bore including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	5	Each			
12	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	22	Each			
13	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet 100 mm diameter including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	3	Each			
14.1	Providing and fixing soil, waste and vent pipes 100 mm dia Centrifugally cast (spun) iron socket & spigot (S&S) pipe as per IS: 3989 including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	40	Per Runnin g			
14.2	75 mm diameter Centrifugally cast (spun) iron socketed pipe as per IS: 3989 including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	20	Per Runnin g			
15	Providing and fixing holder bat clamps of approved design to Sand Cast iron/cast iron (spun) pipe embedded in and including cement concrete blocks 10x10x10 cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including cost of cutting holes and making good the walls etc including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.					
15.1	For 100 mm dia pipe	20	Each			
15.2	For 75 mm dia pipe	5	Each			
16.1	Providing and fixing plain bend of required degree. 100 mm dia Hubless centrifugally cast (spun) iron pipes epoxy coated inside & outside IS:15905 including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	15	Each			
16.2	75 mm dia Hubless centrifugally cast (spun) iron pipes epoxy coated inside & outside IS:15905	5	Each			

Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
17	Providing and fixing 15 cm wide, 45 cm overall semicircular plain G.S. sheet gutter with iron brackets 40x3mm size, bolts, nuts and washers etc., including making necessary connections with rain water pipes complete. 0.80 mm thick with zinc coating not less than 275 gm/m ² including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	54.71	Per Running Metre			
18	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg), R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 Fine sand : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand), finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete as per standard design Inside dimensions 455x610 mm and 45 cm deep for single pipe line With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	9	Each			
	G.Total:-					


 Executive Engineer,
 Outer Searaj Division,
 HP PWD, Jalandhar.

Schedule of quantity						
Name of Work:- Construction of Degree College Anni at Haripur. (SH:- Construction of P.C.C. retaining wall in approach road at RD. 0/010 to 0/018)				Estimated cost:- Earnest Money		429299.00
				Time		9000
				One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	AMOUNT
				Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	24.12	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	38.61	Cubic Metre			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.77	Cubic Metre			
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	85.50	Cubic Metre			
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each			
Total in Figures						


 Executive Engineer
 Outer Serai Division
 Haripur, District

Schedule of quantity						
Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/135 to 1/435)						
Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-	
					Earnest Money	One month
					RATE	AMOUNT
					Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 283.31 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2124.86	Cubic Metre			499640.00
Total in Figures						10000


 Executive Engineer
 Outer Saraj Division
 HRPWD, Mirmand

Signature of Tenderer with seal

Schedule of quantity									
Name of work:- Restoration of rain damages on Farbog to Thach road road km. 0/00 to 2/870. (SH:- C/O PCC. retaining wall at RD 0/714.70 to 0/724.40)									
Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-		320814.00		
					RATE	Words	308862.90		
							8000.00		
							One month		
					Time		AMOUNT		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	19.50	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	32.20	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.66	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	77.21	Cubic Metre						
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	28.00	Each						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.28	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Sany Division
 HPPWD, Nilmand

6

Schedule of quantity									
Name of work:- A/R & M/O Guhatan to Lote road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/290 to 0/300)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		One month
					Words	Time	Earnest Money	415915.00	
					AMOUNT				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	20.40	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	16.70	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.00	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	79.60	Cubic Metre						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.57	Cubic Metre						
Total in Figures									

22

Executive Engineer
Outer Serai Division
HPPWD Armand

7

Schedule of quantity									
Name of work:- A/R & M/O Guhatan to Lote road road km. 0/00 to 0/500. (SH:- C/O PCC. retaining wall at RD 0/175 to 0/190)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		
							Earnest Money		
							Time		
									AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	10.50	Cubic Metre						427176.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	40.35	Cubic Metre						9000.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.45	Cubic Metre						One month
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	79.35	Cubic Metre						AMOUNT
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.47	Cubic Metre						
				Total in Figures					

Schedule of quantity									
Name of Work: Construction of road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.22/015 to 22/027) under BASP					Estimated cost:-		265979.00		
					Earnest Money		6000.00		
					Time		Two months		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	7.44	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	22.32	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.68	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	25.64	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	35.20	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	3.72	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Serai Division
 HPPWD, Almand

Schedule of quantity									
Name of Work: A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.8/250 to 8/270)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:- Earnest Money Time	443342.00 10000.00 Two months	AMOUNT
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	12.40	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	37.29	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	12.80	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	42.74	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	58.66	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.20	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Sanj Division
 HPPWD, Mirmand

Schedule of quantity

Schedule of quantity									
Name of Work: Restoration of rain damages on road from Jn. of LDCK to Jn. of NAS road km. 0/00 to Construction of R/Wall at RD.22/345 to 22/353) under BASP Sr. No. 98				32/00. (Sub Head:-			Estimated cost:-		
							Earnest Money		239289.00
							Time		6000.00
									Two months
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.04	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	22.08	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.76	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	28.90	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	24.86	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.44	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Seral Division
 HPPWD, Nirmand

Signature of Tenderer with seal

Schedule of quantity									
Name of Work: A/R & M/O link road from Shani to Ghulat km. 0/00 to 5/210. (SH:- C/O breast walls at RD km. 0/675 to 0/690)					Estimated cost:-		253442.00		
					Earnest Money		6000.00		
					Time		One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	22.20	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	18.45	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.59	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	29.87	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	22.03	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Seraj Division
 HPPWD, Jirmand

Schedule of quantity									
Name of Work:- M/T works on Behna Dalash road km. 0/00 to 17/345. under self deposit (SH:- C/O PCC retaining wall at RD. 9/667 to 9/675 and 12/600 to 12/615).				Estimated cost:- Earnest Money Time			401068.00		
							9000		
							One month		
							AMOUNT		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	Words			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	13.80	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	35.19	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.67	Cubic Metre						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	72.22	Cubic Metre						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.35	Cubic Metre						
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	30	Each						
Total in Figures									

13 22

Schedule of quantity									
Name of Work: A/R & M/O Brow Poshana road km 0/00 to 13/180 (SH:- C/O R/Wall at RD. 5/100 to 5/115)									
				Estimated cost:-		403304.00			
				Earnest Money		8500.00			
				Time		One month			
				RATE		AMOUNT			
				Figures		Words			
				Unit					
				Qty.					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					
				Cubic Metre					

20
Executive Engineer
Outer Seraj Division
HPPWD, Mand

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Kandugad Patarna road km. 0/00 to 11/795 (SH):- Hiring of Excavator cum loader for removal of slips and construction of road side kutchha drain in km. 0/00 to 11/795) Post rains.

Estimated Cost Rs. 225000/-
Earnest Money Rs. 5000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	180.00			Per Hour	
					Total	


Executive Engineer,
Outer Seal Division
HPPWD, Mirmand

Schedule of Quantity						
Name of work :- A/R & M/O Propeway ffit bridge over River Satluj at Jagatkhana. (SH:-Replacement of damaged chequered plate decking of bridge.)				Estimated cost:- Rs.401584.00		
				Earnest Mony:- Rs. 10000.00		
				Time:- Two months.		
Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT Rs. P
				Figures	Words	
1	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead inincluding carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	4019.28	Per Kilo-gramme			
2	Extra for dismantling trusses, rafters, purlins etc. of steel work for every additional span of one metre or part thereof beyond 10 metres including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	2411.56	Per Kilo-gramme			
3	Steel work welded in built up sections framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	3348.96	Per Kilo-gramme			
Total:-						


 Executive Engineer
 Outer Seraj Division
 HPPWD, Jalandhar

Schedule of Quantity						
Name of work :- A/R & M/O Propeway ffoot bridge over River Satluj at Jagatkhana. (SH:-Replacement of damaged foot guard and plastering of Anchorage Blocks and painting of bridge.)				Estimated cost:- Rs. 383554.00		
				Earnest Mony:- Rs. 8000.00		
				Time:- Two months.		
Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT Rs. P
				Figures	Words	
1	Steel work welded in built up sections framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	670.32	Per Kilo-gramme			
2	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	547.26	Square Metre			
3	20 mm cement plaster of mix 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	38.07	Square Metre			
4	Providing and fixing steel wire ropes of 20 mm (twenty milimetre) dia including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	300.00	Runnin gMetre			
5	Providing and fixing bulldog grief/clamps including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	40.00	Each			
6	Replacement and tightening of steel wire ropes of 20 mm (twenty milimetre) dia including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	1.00	Job			
7	Clearing rubbish etc from surrounding of abutments and anchorage blocks including disposal of the same to disposal points including all leads and lifts as per directions of The Engineer – in – Charge complete.	1.00	Job			
	Total:-					


 Executive Engineer
 Outer Serai Division
 HPPWD, Noida

Schedule of quantity

Name of Work: -A/R & M/O LDCK km. 0/00 to 53/315. (Sub Head:- Construction of R/Wall at RD.4/355 to 4/365)									
Sl. No.		Description of work	Qty.	Unit	RATE		Estimated cost:-	235836.00	
					Figures	Words		Earnest Money	5000.00
		Time		Two months		AMOUNT			
1		Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	13.70	Cubic Metre					
2		Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	15.00	Cubic Metre					
3		Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	3.66	Cubic Metre					
4		Providing and Laying cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	41.70	Cubic Metre					
5		Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	15.00	Each					
6		Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.40	Cubic Metre					
Total in Figures									


Executive Engineer
 Outer Seraj Division
 HPPWD, Noida

Signature of Tenderer with seal

SCHEDULE OF QUANTITY

Name of work:- BSP/2019/230 P/L M/T works on Wazir Bowali Jhakhari Bye Pass road km. 0/00 to 15/00 under BASP). (Sub Head:- Providing and laying soling WBM G-I in essential reaches between km. 0/00 to 3/300)					Estimated Cost:-496127.00	
					Earnest money:- 10000.00	
					Time:- Two months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404 By Mechanical Means including carriage of materials through all modes of transportaion with in all leads and lifts as per directions of the Engineer-In-Charge.	219.37	Per Cubic Metre			


 Executive Engineer,
 Outer Seraj Division,
 HP.PWD, Noida.

Schedule of quantity						
Name of Work: Construction of Rest House building (Additional Accommodation) at Anni in District Kullu (H.P.)				Estimated cost:-		98000.00
(Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).				Earnest Money		2000
				Time		Three months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Consultancy services for preparation of working estimate as per HSPR 2020 duly supported with analysis of rates for all scheduled items and non scheduled item on market rates in all respect in manuscript form and submission the same to higher office for proper scrutiny/approval. If any correction/ amendments has desired by the higher office, the same may be corrected complete in all respect as desired competent authority or directed by the Engineer-in-Charge. After that the DPR should be submitted in five copies duly computerized along with soft copy complete in all respect including obtaining approval of the same from competent authority and preparation/approval of bidding documents complete.	1.000	One Job			
				Total in Figures		

Condition for payment will be as under:-

- 1 On submission of manuscript copy to the Division office = 20%
- 2 On approval of the manuscript copy from the competent authority and submission of fair DPR in five copies alongwith soft copy of the same to Division office =30%
- 3 After approval of working estimate and bidding documents of the project from the competent authority. =50%
- 4 The rates are inclusive of all taxes including GST

Executive Engineer
Outer Seraj Division
HPPWD
Mirmand

Schedule of quantity						
Name of Work: Construction of Sub Treasury building at Anni in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).				Estimated cost:- Earnest Money Time		98000.00 2000 Three months
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Consultancy services for preparation of working estimate as per HSPR 2020 dully supported with analysis of rates for all scheduled items and non scheduled item on market rates in all respect in manuscript form and submission the same to higher office for proper scrutiny/approval. If any correction/ amendments has desired by the higher office, the same may be corrected complete in all respect as desired competent authority or directed by the Engineer-in-Charge. After that the DPR should be submitted in five copies dully computerized along with soft copy complete in all respect including obtaining approval of the same from competent authority and preparation/approval of bidding documents complete.	1.000	One Job			
Total in Figures						

Condition for payment will be as under:-

- 1 On submission of manuscript copy to the Division office = 20%
- 2 On approval of the manuscript copy from the competent authority and submission of fair DPR in five copies alongwith soft copy of the same to Division office =30%
- 3 After approval of working estimate and bidding documents of the project from the competent authority. =50%
- 4 The rates are inclusive of all taxes including GST


Executive Engineer
Outer Seraj Division
UPPWD, Jammu

Schedule of quantity						
Name of Work: Construction of Primary Health Centre building at Kungash in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).				Estimated cost:- Earnest Money Time Three months		98000.00 2000
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Consultancy services for preparation of working estimate as per HSPR 2020 dully supported with analysis of rates for all scheduled items and non scheduled item on market rates in all respect in manuscript form and submission the same to higher office for proper scrutiny/approval. If any correction/ amendments has desired by the higher office, the same may be corrected complete in all respect as desired competent authority or directed by the Engineer-in-Charge. After that the DPR should be submitted in five copies dully computerized along with soft copy complete in all respect including obtaining approval of the same from competent authority and preparation/approval of bidding documents complete.	1.000	One Job			
Total in Figures						

Condition for payment will be as under:-

- 1 On submission of manuscript copy to the Division office = 20%
- 2 On approval of the manuscript copy from the competent authority and
submission of fair DPR in five copies alongwith soft copy of the same to
Division office =30%
- 3 After approval of working estimate and bidding documents of the project
from the competent authority. =50%
- 4 The rates are inclusive of all taxes including GST

Executive Engineer
Outer Sani Division
Jammu & Kashmir

Schedule of quantity

Name of Work: Construction of Primary Health Centre building at Jaon in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).					Estimated cost:-		148000.00	
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT	
					Words			
					Time			
1	Consultancy services for preparation of working estimate as per HSPR 2020 dully supported with analysis of rates for all scheduled items and non scheduled item on market rates in all respect in manuscript form and submission the same to higher office for proper scrutiny/approval. If any correction/ amendments has desired by the higher office, the same may be corrected complete in all respect as desired competent authority or directed by the Engineer-in-Charge. After that the DPR should be submitted in five copies dully computerized along with soft copy complete in all respect including obtaining approval of the same from competent authority and preparation/approval of bidding documents complete.	1.000	One Job				3000	
Total in Figures								Three months

Condition for payment will be as under:-

- 1 On submission of manuscript copy to the Division office = 20%
- 2 On approval of the manuscript copy from the competent authority and
submission of fair DPR in five copies alongwith soft copy of the same to
Division office =30%
- 3 After approval of working estimate and bidding documents of the project
from the competent authority. =50%
- 4 The rates are inclusive of all taxes including GST


Executive Engineer
Outer Sanj Division
UPPWD, Nirmal

Schedule of quantity									
Name of Work:-Stock Storage. (SH:- Construction of diaframe wall for parking for PWD Division at Nirmand)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		338653.00
					Words	Amount	Earnest Money	Time	
1	Earth work in excavation in all kinds of soil by Hydraulic excavator/ manual means over areas in all height and depths including getting out and disposal of excavated earth upto all leads and lifts as directed by Engineer-incharge Ordinary rock including stacking of serviceable materials and disposal of un-serviceable materials within all leads and lifts and inclusive of carriage of materials in all leads and lifts and as per directions of The Engineer-in-Charge complete.	10.13	Per Cubic Metre						8000
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm (forty milimetre) nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	1.35	Per Cubic Metre						Three
3	Centering and shuttering including strutting, propping etc. and removal of form for : for mass concrete including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete in:-								
3.1	Foundations, footings, bases of columns, etc.	137.58	Per Square Metre						
3.2	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	121.20	Per Square Metre						
3.3	Columns, Pillars, Piers, Abutments, Posts and Struts	14.40	Per Square Metre						
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level1:1½:3 (1 Cement: 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete	2.34	Per Cubic Metre						

7	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete	21.06	Per Cubic Metre			
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete	2.97	Cubic Metre			
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. (steel will be issued by Department free of cost) including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete	3604.50	Per Kilogramme			
	Total:-					


 Executive Engineer,
 Outer Sector Division,
 HP.PWD, Jalandhar.

Schedule of quantity

Name of Work:- Stock Storage. (SH:- Site development work including construction of retaining walls for parking for PWD Division at Nirmand)						Estimated cost:-		497695.00
						Earnest Money		10000
						Time		Three months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT		
				Figures	Words			
1	Earth work in excavation in all kinds of soil by Hydraulic excavator/ manual means over areas in all height and depths including getting out and disposal of excavated earth lead upto all leads and lifts as directed by Engineer-in-charge Ordinary rock including stacking of serviceable materials and disposal of un-serviceable materials within all leads and lifts and inclusive of carriage of materials in all leads and lifts and as per directions of The Engineer-in-Charge complete.	246.51	Cubic Metre					
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm (forty millimetre) nominal size) including curing and carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	82.98	Cubic Metre					
3	Centering and shuttering including strutting, propping etc. and removal of form for :Foundations, footings, bases of columns, etc. for mass concrete including carriage of materials in all leads and lifts/ all levels and heights and as per directions of The Engineer-in-Charge complete.	132.00	Square Metre					
	Total:-							


 Executive Engineer,
 Outer Serey Division,
 HP.PWD, Nirmand.