

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDERS

Sealed item rates tenders on form 6&8 are hereby invited by the undersigned on behalf of Governor of Himachal Pradesh from the approved/eligible contractor registered in HP.PWD., for the following works so as to reach in this office on or before 14-12-2021 upto 11.00 A.M. and shall be opened on the same day at 3.30 P.M. in presence of the contractor or their authorized representatives who may like to be present. The tender form can be had from this office against cash payment (Non refundable) upto 5.00 P.M. on 13-12-2021 for which the application should reach in this office upto 1:00 P.M. 13-12-2021.

The earnest money in shape of National Saving Certificate/time deposit account / saving account in any of post office / nationalized bank in HP duly pledged in favour of the undersigned will be received along with application for obtaining tender forms. The conditional tenders will summarily be rejected. The offer of the tender shall be kept open for 90 days from the date of opening of tender. The undersigned reserves the right of reject any or all tenders without assigning any reasons. The contractor should append their enlistment/renewed certificates/sale tax registration numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr No.	Name of Work	Estimated Cost	Earnest Money	Time allowed	Cost of Form
1	R/R damage on Gadagusian Cheincha Pokhari road km 0/00 to 6/300 (SH:-Hiring of JCB /Excavator for removal of slips /Snow at various Rds between km 0/00 to 6/300)	99162.00	2000.00	One month	350/-
2	R/R damage on Gadagusain Tapnali h Ghat road km 0/00 to 21/00 (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds between km 10/500 to 21/00)	99162.00	2000.00	One month	350/-
3	R/R damage on Gadagusain Tapnali Ghat road km 0/00 to 21/00 (SH:-Hiring of JCB /Excavator for removal of slips /Snow at various Rds between km 0/00 to 10/500)	99162.00	2000.00	One month	350/-
4	R/R damage on Tapnali to Khouli road km 0/00 to 15/00 (SH:- Hiring of JCB/ Excavator for removal of slips/Snow on (Portion Khouli to Bhatkabad) at Rd 0/00 to 4/500)	99162.00	2000.00	One month	350/-
5	R/ R damage on Khouli to Reshan road km 0/00 to 6/500 (SH:- Hiring of JCB/ Excavator for removal of slips/Snow at various Rds between km 0/0 to 6/500)	99162.00	2000.00	One month	350/-
6	R/R damae on Various road in Chhatri Section 2 nd under sub Division Chhatri (SH:-Hiring of JCB /Excavator for removal of slips /Snow at various Rds in various roads) job No.II	99162.00	2000.00	One month	350/-
7	R/R damage on Jogni dhar to Bahlidhar road km 0/0 to 4/00 (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds in km 0/00 to 4/00)	99162.00	2000.00	One month	350/-
8	R/R damage on Nagan Chhatri road km 13/00 to 22/00 (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds in km 13/00 to 22/00)	99162.00	2000.00	One month	350/-
9	R/R damage on various road in Chhatri Section 2 nd under sub Division Chhatri 00 (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds in various roads) Job No. I	99162.00	2000.00	One month	350/-
10	R/R damage on Billagad Magrugalla road km 0/00 to 8/500 (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds between km 0/00 to 8/500)	99162.00	2000.00	One month	350/-
11	R/R damage on Kelodhar Chhatri roda km 19/0 to 232/00 (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds between km 19/00 to 32/00)	99162.00	2000.00	One month	350/-
12	R/R damage on Various road in Chhatri Section Ist under Sub Division Chahtri (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds in various roads) Job No.I	99162.00	2000.00	One month	350/-

13	R/R damage on Various road in Chhatri Section Ist under Sub Division Chahtri (SH:- Hiring of JCB /Excavator for removal of slips /Snow at various Rds in various roads) Job No.II	99162.00	2000.00	One month	350/-
14	A/R & M/o various roads under sub Diision Chhatri (SH:- Painting of concrete/steel surfaces on various roads)	99847.00	2000.00	Two month	350/-
15	A/R & M/O HPPWD Rest House at Chhatri (SH:- Providing and supplying of furnishing items)	80400.00	1650.00	Two Month	350/-
16	A/R & M/O HPPWD Rest House at Chhatri (SH:- Providing and supplying of furnishing items)	53250.00	1065.00	Two Month	350/-
17	R/R damage on Ruhmani Baryogi via Mahruti road km 0/00 ot 4/500 (SH:- C/o Retaining wall at Rd 3/400 to 3/410)	83454.00	1670.00	One month	350/-
18	R/ R damage on Ruhmani to Mahruti Naglai road km 0/00 ot 4/500 (SH:- C/o Retaining wall at Rd 1/100 to 1/115)	91799.00	1836.00	One month	350/-
19	R/R damage on Ruhmani Baryogi to Mahruti road km 0/00 to 4/500 (SH:- C/o Retaining wall at Rd 1/600 to 1/612)	99392.00	1988.00	One month	350/-

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

Tern and Conditions:

- 1 The Contractor/firm shall have his GST No. and attested copy of the same be attached with the application for issue of tender form.
- 2 The Contractor/Firm should attach attested copy of registration/renewal.
- 3 Copy of the PAN card be attached with the application.

Executive Engineer
HPPWD Division
Seraj at Janjehli

No: PW/SRJ/WS/NIT/2021-22- 15565-73

Dated: - 3/12/2021

Copy forwarded to the following for information and necessary action: -

1. The Deputy Commissioner, Mandi, Distt. Mandi with the request to display the NIT in your office notice board.
2. The Superintending Engineer, 1st Circle, HPPWD, Mandi with the request to issue necessary certificate regarding display of above tender notice in the notice board of Circle Office in view of the Principal Secretary (PW) to the Govt. of HP notification No. PBW(B)A(3)1/2020 dated 7.01.2021 and even file No. PBW(B)A(3)1/2020 dated 16.07.2021 please.
3. The Sub-Divisional Officer (Civil), Thunag, Distt. Mandi HP with the request to display the NIT in your office notice board.
4. The Block Development Officer, Janjehli with the request to display the NIT in your office notice board.
- ✓ 5. The Executive Engineer (IT Cell) O/o Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the departmental website.
6. All the Assistant Engineers working under this Division.
7. Notice Board.

Executive Engineer
HPPWD Division
Seraj at Janjehli

48

BILL OF QUANTITY

Name of Work:- RR Damages on Gadagusain Cheincha Pokhari road k 0/00 to 6/300
(SH:- Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 0/00 to 6/300)

Estimated cost Rs.- 99162.00
Earnest Money cost Rs. - 2000.00
Time - One Month

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
Total:-						99162.00	

Bill & qty approved for Rs - 99162 only

[Signature]
Executive Engineer
Seraj Division B&R
HPPWD Jajichii

15

2

BILL OF QUANTITY

Name of Work:-RRR Damages on Gadagusain Tapnath Ghat road km 0/00 to 21/00
(SH:-Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 10/500 to 21/00)

Estimated cost Rs.- 99162.00
Earnest Money cost Rs. - 2000.00

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Time - One Month		
					Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-servicable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
		Total:-				99162.00	

Bill & Qty approved for Rs. 99162.00

Executive Engineer
Seraj Division B&R
HPPWD Panjiali

BILL OF QUANTITY

Name of Work:- RR Damages on Gadagusain Tapnali Chat road km 0/00 to 21/00
(SH:- Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 0/00 to 10/500)

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (In. Rs.)	Estimated cost Rs.-		
					Earnest Money cost Rs. - 2000.00	Time - One Month	
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring which shall have to be the absolute responsibility of JCB/Excavator owner operational staff for excavator will be provided by him in all cases. The fuel and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
						99162.00	Rupees Ninety nine thousand one hundred sixty two only
					Total:-	99162.00	

Bill & Qty approved for Rs. 99162/-

Executive Engineer
Seraj Division B&R
HPPW Janjehli

43

BILL OF QUANTITY

Name of Work:- RR Damages on Tapnali to Khauli road km 0/00 to 15/00

(SH:-Hiring of JCB/Excavator for removal of Slips/Snow on (Portion Khauli to Bhatkabad) at various Rds between km 0/00 to 4/500)

Name of Work:-RR Damages on Tapnali to Khauli road km 0/00 to 15/00 (SH:-Hiring of JCB/Excavator for removal of Slips/Snow on (Portion Khauli to Bhaktabad) at various Rds between km 0/00 to 4/500)					Estimated cost Rs.- 99162.00		
					Earnest Money cost Rs. - 2000.00		
					Time - One Month		
Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-servicable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
					Total:-	99162.00	

Bill & copy approved for Rs- 99162/-

Executive Engineer
Seraj Division B&R
HPPW Jajchli

Bill & qty approved for Rs- 99162 only

Executive Engineer
Seraj Division B&R
HPWQ Janyehli

5

BILL OF QUANTITY

Name of Work:- RR Damages on Khauli to Reshan road km 0/00 to 6/500

(SH:- Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 0/00 to 6/500)

Estimated cost Rs.- 99162.00

Earnest Money cost Rs. - 2000.00

Time - One Month

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Ruppes Ninety nine thousand one hundred sixty two only
Total:-						99162.00	

Bill quantity approved for Rs- 99162/-

Executive Engineer
Seraj Division B&R
HPPWD
Janjehi

59

BILL OF QUANTITY

Name of Work:- RR Damages on Various road in Chhattri Section-2nd under Sub-Division Chhattri
(SH:- Hiring of JCB/Excavator for removal of Slips at various Rds in various roads) Job No-II

Estimated cost Rs.- 99162.00
Earnest Money cost Rs. - 2000.00

Time - One Month

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-servicable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/Excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	126.00	Per hour	787.00		99162.00	Ruppes Ninety nine thousand one hundred sixty two only
Total:-						99162.00	

Bill is Qty approved for Rs - 99162/only


Executive Engineer
Sraji Division B&R
HPPW Jamjehli

BILL OF QUANTITY

Name of Work:- RR Damages on Jogni dhar to Bahlidar road km 0/00 to 4/00
 SH:- Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 0/00 to 4/00)

Estimated cost Rs.- 99162.00
 Earnest Money cost Rs. - 2000.00

Time - One Month

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
Total:-						99162.00	

Bill & Qty approved for Rs. 99162/- only

Executive Engineer
 Seraj Division B&R
 HPPW, Janjehli

37

BILL OF QUANTITY

Name of Work:-RR Damages on Nagan Chhattri road km 13/00 to 22/00

(SH:-Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 13/00 to 22/00)

BILL OF QUANTITY							
Name of Work:-RR Damages on Nagan Chhattri road km 13/00 to 22/00 (SH:-Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 13/00 to 22/00)					Estimated cost Rs.- 99162.00		
					Earnest Money cost Rs. - 2000.00		
					Time - One Month		
Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupess Ninety nine thousand one hundred sixty two only
Total:-						99162.00	
Bill P Qty approved for Rs-99162							
Executive Engineer Seraj Division B&R HPPWD Jangchli							

Billed P Qty approved for Rs. 99162/-


Executive Engineer
Seraj Division B&R
HPPWD Jangeli

BILL OF QUANTITY

Name of Work:- RR Damages on Various road in Chhattri Section-2nd under Sub-Division Chhattri
(SII:-Hiring of JCB/Excavator for removal of Slips at various Rds in various roads) Job No-1

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in Rs.)	Estimated cost Rs.		
					Rate with all taxes including C.S.T in figures to be entered by the bidders Rs. P	Total amount with all taxes including C.S.T in Rs. P	Total amount with all taxes including C.S.T in words
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any grade and beds and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring which shall have to be the absolute responsibility of Jt. District Engineer. Operational staff for excavation will be provided by the owner. The repair and spare, watch and ward of excavation also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	126.00	Per hour	787.00		99162.00	
Total:-						99162.00	

21088 quantity approved
for Rs. 99162/- only

Executive Engineer
 Survey Division R&M
 H.P.W. Pimpri


52

BILL OF QUANTITY

Name of Work:- RR Damages on Billagad to Magrugalla road km 0/00 to 8/500
(SH:-Hiring of JCB/Excavator for removal of Slips at various Rds between km 0/00 to 8/500)

Name of Work:-RR Damages on Billagad to Magrugalla road km 0/00 to 8/500 (SH:-Hiring of JCB/Excavator for removal of Slips at various Rds between km 0/00 to 8/500)					Estimated cost Rs.- 99162.00		
					Earnest Money cost Rs. - 2000.00		
					Time - One Month		
Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-servicable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
Total:-						99162.00	

Bills ready approved for Rs-99162 only

Executive Engineer
Seraj Division B&R
HPPW Dhanjehli

Bill Rate approved for Rs- 99162 only

Executive Engineer
Seraj Division B&R
HPPW/Janjehli

58

BILL OF QUANTITY

Name of Work:- RR Damages on Kelodhar to Chhatari road km 19/00 to 32/00

(SH:-Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 19/00 to 32/00)

BILL OF QUANTITY							
Name of Work:- RR Damages on Kelodhar to Chhattri road km 19/00 to 32/00					Estimated cost Rs.-		99162.00
(SH:-Hiring of JCB/Excavator for removal of Slips/Snow at various Rds between km 19/00 to 32/00)					Earnest Money cost Rs. -		2000.00
					Time - One Month		
Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips/Snow and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
					Total:-	99162.00	
Bill & Qty approved for Rs-99162/-							
<div>Executive Engineer Seraj Division B&R HPPW Jaunehi</div>							

Bill is Qty approved 50115-99162/009

Executive Engineer
Scrij Division B&R
HPW/Janjehli

50

12

BILL OF QUANTITY

Name of Work:- RR Damages on Various road in Chhattri Section-I under Sub-Division Chhattri
 SH:- Hiring of JCB/Excavator for removal of Slips at various Rds in various roads) Job No-1

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Estimated cost Rs.-	99162.00
					Earnest Money cost Rs. - 2000.00	
					Time - One Month	
					Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P
						Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-servicable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/excution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	126.00	Per hour	787.00		Ruppes Ninety nine thousand one hundred sixty two only
Total:-					99162.00	

21.08.2019 approved for Rs. 99162/- only

Executive Engineer
 Seraj Division B&R
 HPPWD Panjehli

49

B.I.L. OF QUANTITY

Name of Work:- RR Damages on Various road in Chhattri Section-I under Sub-Division Chhattri
(SH-Hiring of JCB/Excavator for removal of Slips at various Rds in various roads) Job No-II

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Estimated cost Rs.- 99162.00		
					Earnest Money cost Rs. - 2000.00		
					Time - One Month		
					Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-servicable materials from the road surfaces up to any leads and lifts and dressing of road surface including stripping and filling with fresh selected soil as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	126.00	Per hour	787.00		99162.00	Rupees Ninety nine thousand one hundred sixty two only
Total:-						99162.00	

Bill & qty approved for Rs - 99162 only

Executive Engineer
Sraaj Division B&R
HPWTP, Jaunehi

22

Name of Work:- A/R & M/O HPPWD Rest House at Chhattri.
(SII:- Providing and supplying of furnishing items)

BILL OF QUANTITY

Name of Work:- A/R & M/O HPPWD Rest House at Chhattri. (SII:-Providing and supplying of furnishing items)					BILL OF QUANTITY		
Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Estimated cost Rs.	80400.00	
					Earnest Money cost Rs. - 1650.00		
					Time - Two Month		
					Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	
						Total amount with all taxes including GST in words	
1	Providing and Supplying Sofa set five seater of superior quality and as per direction of Engineer- in-Charge including carriage of material within all leads and lifts other incidentals.	1.00	Each	37800.00		Rupees ThirtySeven Thousand Eight Hundred Only	
2	Providing and Supplying Center Table with glass top of size 1.20 m x0.60 mx 0.45 m (one point twenty meter into zero point sixty meter into zero point forty five meter) of superior and as per direction of Engineer- in-Charge including carriage of material within all leads and lifts other incidentals.	1.00	Each	14400.00		Rupees Fourteen Thousand Four Hundred Only	
3	Providing and Supplying Double Bed box of superior quality and as per direction of Engineer- in-Charge including carriage of material within all leads and lifts other incidentals.	1.00	Each	28200.00		Rupees TwentyEight Thousand Two Hundred Only	
				Total	80400.00		
Bill of Qty. approved for Rs:- 80400/-							
Executive Engineer Seral Division B&R HPPWD Jamie							

Bill of Qty. approved for Rs. 80400 only

Executive Engineer
Serai Division B&R
HPPWD Janice

Name of Work: A/R & M/O HPPWD Rest House at Chhattri.
(SH:- Providing and supplying of furnishing items)

BILL OF QUANTITY

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in Rs.)	Estimated cost Rs.	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
					Time - Two Month Earnest Money cost Rs. - 1065.00		
1	Providing and Supplying Side table of size 1.20 m x 0.40 m x 0.45 m (one point twenty meter into zero point forty meter into two point zero meter) of superior quality and as per direction of Engineer- in-Charge including carriage of superior material within all leads and lifts other incidentals.	1.00	Each	3600.00		3600.00	Rupees Three Thousand Six Hundred Only
2	Providing and Supplying Dressing table of superior quality and as per direction of Engineer- in-Charge including carriage of material within all leads and lifts other incidentals.	1.00	Each	14750.00		14750.00	Rupees Fourteen Thousand Seven Hundred Fifty Only
3	Providing and Supplying Dinning Table with six chair of superior quality and as per direction of Engineer- in-Charge including carriage of material within all leads and lifts other incidentals.	1.00	Each	34900.00		34900.00	Rupees ThirtyFour Thousand Nine Hundred Only
				Total		53250.00	

Bill of Qty approved for Rs- 53250 Only

Executive Engineer
Seraf Division B&R
HPPWD Janigol

BILL OF QUANTITY									
Name of Work:- A/R & M/O various roads under sub division Chhatri. (SH:-Painting of concrete/steel surfaces on various roads)									
Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (In. Rs.)	Estimated cost Rs.		Total amount		Total amount with all taxes including GST in words
					Time - Two Month	Earnest Money cost Rs. - 2000.00	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	with all taxes including GST in Rs. P	
1	Painting two coats including prime coat with epoxy paint of approved brand on concrete/steel surfaces after through cleaning of surface to give an even shade as per drawing and Technical Specification Clause 1701 i/c all leads and lifts and other incidentals complete as per direction of Engineer-In-Charge.	701.30	Sqm.	142.37				99847.00	Rupees Ninety/Nine Thousand Eight Hundred FourtySeven
					Total		99847.00		

Bill of City approved for Rs. 99847 only

Executive Engineer
Seraj Division B&R
HPPWD Janjehi

BILL OF QUANTITY

Name of Work:- RRD on Ruhmani Baryogi via Mahruvi road km. 0/000 to 4/500. (SH:- C/o R/wall at RD. 3/400 to 3/406). J

Estimated cost Rs. - 89,255.00
Earnest Money cost Rs. - 1700.00

Time - Two Month

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift and a lead upto 1000 m. including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	3.12	Per Cubic metre	177.40		553.00	Rupees Five Hundred Fifty Three Only
2	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	10.92	Per Cubic metre	380.05		4150.00	Rupees Four Thousand One Hundred Fifty Only
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	22.02	Per Cubic metre	3768.55		82983.00	Rupees Eighty Two Thousand Nine Hundred Eighty Three Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1.08	Per cubic metre	1452.50		1569.00	Rupees One Thousand Five Hundred Sixty Nine Only
					Total:-	89255.00	

Bill of Qty. approved
for Rs = 89,255 only

Executive Engineer
Serai Division B&R
HPWD Jammu

61
Name of Work:- RRD on Ruhmani Baryogi via Mahruiti road km. 0/000 to 4/500. (SH:- C/o R/wall at RD. 1/600 to 1/606).

BILL OF QUANTITY

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Estimated cost Rs. - 89,255.00		
					Time - Two Month	Earnest Money cost Rs. - 1700.00	
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift and a lead upto 1000 m. including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	3.12	Per Cubic metre	177.40	Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
						553.00	Rupees Five Hundred Fifty Three Only
2	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	10.92	Per Cubic metre	380.05		4150.00	Rupees Four Thousand One Hundred Fifty Only
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	22.02	Per Cubic metre	3768.55		82983.00	Rupees Eighty Two Thousand Nine Hundred Eighty Three Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1.08	Per cubic metre	1452.50		1569.00	Rupees One Thousand Five Hundred Sixty Nine Only
					Total:-	89255.00	

Bill of Qty. approved
for Rs. 89,255/- only

Executive Engineer
Serai Division B&R
HPPW Dhanje

62

BILL OF QUANTITY

Name of Work:- RRD on Ruhmani Mahruvi Naglai road km. 0/000 to 4/500. (SH:- C/o R/wall at RD. 1/100 to 1/106).

Estimated cost Rs. - 89,255.00
 Earnest Money cost Rs. - 1700.00

Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Time - Two Month		Total amount with all taxes including GST in words
					Rate with all taxes including GST in figures to be entered by the bidders Rs. P	Total amount with all taxes including GST in Rs. P	
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift and a lead upto 1000 m. including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	3.12	Per Cubic metre	177.40		553.00	Rupees Five Hundred Fifty Three Only
2	Earthwork in excavation of foundation of structure as per drawing and technical specification including setting out construction of shoring and bracing removal of slumps and other deleterious matter dressing of sides and bottom back filling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	10.92	Per Cubic metre	380.05		4150.00	Rupees Four Thousand One Hundred Fifty Only
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification, with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge	22.02	Per Cubic metre	3768.55		82983.00	Rupees Eighty Two Thousand Nine Hundred Eighty Three Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1.08	Per cubic metre	1452.50		1569.00	Rupees One Thousand Five Hundred Sixty Nine Only
				Total:-		89255.00	

Bill of Qty. approved in
 Rs. 89,255 / only.

Executive Engineer
 Serai Division B&R
 HPPWD Jalandhar