

Himachal Pradesh
Public Works Department

Registered

No. PWN/CB/GA/E-27/Tender/2021-22- 4908
To


Dated:- 10/1/2022

The Executive Engineer (IT Cell),
Nigam Vihar Shimla.

Subject: - Publication of Tender Notice.

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting tender for uploading on department website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th, July 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA/As above.


Executive Engineer,
Nurpur Division, HP PWD,
Nurpur.

HPPWD
Tender Notice

Sealed Item rates Tenders on PWD form 6&8 are invited by the Executive Engineer HP.PWD Nurgpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R), so as to reach in his office on or before **24/01/2022** up to 11.00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative, if any. The tender forms can be obtained from this office against cash payment non-refundable during the working hours on **22/01/2022** up to 4.00 PM and no tender form shall be issued by post. Application for issue of tenders should reach in the office along with all the required documents on or before **21/01/2022**. The earnest money in the shape of FDR of any nationalized Bank in H.P, duly pledged in the name of Executive Engineer, Nurgpur Divn. HP.PWD Nurgpur must accompany with the application. The conditional tender and tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserves the right to reject any tender without assigning any reason.

Sl. No.	Name of work	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit	Cost of tender form (Rs)
1	2	3	4	5	6
1	Imp. of black spot on Tikka Nagrota HathiDhar road (SH:- P/F "W" metal crash barrier at RD 4/030 to 4/130 and 7/800 to 7/840).	426874/-	10000/-	One month	350/-
2	Imp. of black spot on Denkwani Rit Janera road (SH:- P/F "W" metal crash barrier at RD 4/735 to 4/775 and 4/515 to 4/605).	487861/-	10000/-	One month	350/-
3	Imp. of black spot on Bodh Ganoh road (SH:- P/F "W" metal crash barrier at RD 3/510 to 3/590) (Both side).	487861/-	10000/-	One month	350/-
4.	Imp. of black spot on Ganoh Sukhar road (SH:- P/F "W" metal crash barrier at RD 3/0 to 3/085 (Right side).	259186/-	6000/-	One month	350/-

1. Certified that tender of above works are being called of emergent nature in Exigency of public interest.

Executive Engineer
Nurgpur Division, HPPWD,
Nurgpur.
For on behalf of Governor of H.P.

SCHEDULE OF QUANTITY

Name of work :- Improvement of black spot on Tikka Nagrota Hathi Dhar road
(SH:-Providing and fixing 'W' Metal Crash Barrier at RD. 4/030 to 4/130
and 7/800 to 7/840 ,)

Estimated cost Rs. 426874.00
Earnest money Rs. 10000.00
Time limit : One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Words	Figures		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 as per direction and entire satisfaction of Engineer-in-charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	10.29 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in open foundation complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	10.14 cubic meter			Per cubic meter	
3	Providing and erecting "W" metal beam crash Barrier comprising of 3mm (three millimeters) thick corrugated sheet metal beam rail 70cm (seventy centimeter) above road ground level fixed on ISMC series channels vertical post 150x75x 5mm (one hundred fifty into seventy five into five millimeters) spaced 2 (two) meter centre to centre 1.80 M (one point eight zero meter) high 1.10 (one point one zero meter) meter below ground (road level) all steel parts and fitment to be galvanised by hot dip process all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government	140.00 running meter			Per running meter	
	Total					

Executive Engineer,
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :- Improvement of black spot on Dainkwan, Rit Janera road
(SHI-Providing and fixing "W" Metal Crash Barrier at RD. 4/735 to 4/775 = 40 mtr
and 4/515 to 4/605 = 90mtr and 4/825 to 4/855)

Estimated cost Rs. 487861.00
Earnest money Rs. 10000.00
Time limit : One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Words	Figures		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 as per direction and entire satisfaction of Engineer-in-charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	11.76 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in open foundation complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	11.59 cubic meter			Per cubic meter	
3	Providing and erecting "W" metal beam crash Barrier comprising of 3mm (three millimeters) thick corrugated sheat metal beam rail 70cm (seventy centimeter)above road ground level fixed on ISMC series channels vertical post 150x75x 5mm (one hundred fifty into seventy five into five millimeters) spaced 2 (two) meter centre to centre 1.80 M (one point eight zero meter) high 1.10 (one point one zero meter) meter below ground (road level) all steel parts and fitment to be galvanised by hot dip process all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm , 330 mm long complete as per clause 810 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government	160.00 running meter			Per running meter	
	Total					

Executive Engineer,
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :- Improvement of black spot on Both Ganoth road
(SH:-Providing and fixing 'W' Metal Crash Barrier at RD. D. 3/510 to 3/590) (Both side)

Estimated cost Rs. 487861.00
Earnest money Rs. 10000.00
Time limit : One month

Sr. No.	Description of items	Qty.	Words	Rate in Figures	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 as per direction and entire satisfaction of Engineer-in-charge including setting out ,shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	11.76 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in open foundation complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	11.59 cubic meter			Per cubic meter	
3	Providing and erecting "W" metal beam crash Barrier comprising of 3mm (three millimeters) thick corrugated sheat metal beam rail 70cm (seventy centimeter)above road ground level fixed on ISMC series channels vertical post 150x75x 5mm (one hundred fifty into seventy five into five millimeters) spaced 2 (two) meter centre to centre 1.80 M (one point eight zero meter) high 1.10 (one point one zero meter) meter below ground (road level) all steel parts and fitment to be galvanised by hot dip process all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm , 330 mm long complete as per clause 810 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government	160.00 running meter			Per running meter	
	Total					

Executive Engineer,
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :- Improvement of black spot on Ganoh Sukhar road
(SH:-Providing and fixing 'W' Metal Crash Barrier at RD. D. 3/00 to 3/085) (Right side)

Estimated cost Rs. 259186.00
Earnest money Rs. 6000.00
Time limit : One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Words	Figures		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 as per direction and entire satisfaction of Engineer-in-charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	6.25 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in open foundation complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	6.16 cubic meter			Per cubic meter	
3	Providing and erecting "W" metal beam crash Barrier comprising of 3mm (three millimeters) thick corrugated sheet metal beam rail 70cm (seventy centimeter) above road ground level fixed on ISMC series channels vertical post 150x75x 5mm (one hundred fifty into seventy five into five millimeters) spaced 2 (two) meter centre to centre 1.80 M (one point eight zero meter) high 1.10 (one point one zero meter) meter below ground (road level) all steel parts and fiment to be galvanised by hot dip process all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm , 330 mm long complete as per clause 810 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government	85.00 running meter			Per running meter	
	Total					

Executive Engineer,
Murpur Division HPPWD
Nurpur