

Himachal Pradesh
Public Works Department

Registered

No. PWN/CB/GA/E-27/Tender/2021-22- 4715
To


Dated:- 31/12/21,

The Executive Engineer (IT Cell),
Nigam Vihar Shimla.

Subject: - Publication of Tender Notice.

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting tender for uploading on department website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th, July 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA/As above.



Executive Engineer,
Nurpur Division, HP/PWD,
Nurpur.

HPPWD
Tender Notice

Sealed Item rates Tenders on PWD form 6&8 are invited by the Executive Engineer HP.PWD Nurpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R), so as to reach in his office on or before **07/01/2022** up to 11.00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative, if any. The tender forms can be obtained from this office against cash payment non-refundable during the working hours on **06/01/2022** up to 4.00 PM and no tender form shall be issued by post. Application for issue of tenders should reach in the office along with all the required documents on or before **05/01/2022**. The earnest money in the shape of FDR of any nationalized Bank in H.P, duly pledged in the name of Executive Engineer, Nurpur Divn. HP.PWD Nurpur must accompany with the application. The conditional tender and tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserves the right to reject any tender without assigning any reason.

Sl. No.	Name of work	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit	Cost of tender form (Rs)
1	2	3	4	5	6
1	Const.of link road from Tikka Nagrota Hathi Dhar Kms 0/0 to 0/050 (SH:- Formation cutting in kms 8/765 to 0/050	384813/-	7300/-	One month.	350/-
2	Construction of balance work of Govt. Senior Secondary School Ganoh in Tehsil Nurpur Distt. Kangra HP (SH:- Earth filling and vitrified tiles in flooring).	404470/-	9700/-	Two months	350/-
3	Construction of balance work of Govt. Senior Secondary School Ganoh in Tehsil Nurpur Distt. Kangra HP (SH:- Providing and fixing tiles in skirting and roofing).	253362/-	5100/-	Two months	350/-
4.	Construction of link road from Balakh Bridge to village Tarihar road kms 0/0 to 1/600 (SH:- Construction of R/wall for the approaches of 900mm dia hume pipe culvert at RD 0/413.45 to 0/418.35)(Length= 4.90 mtr.) Ht. 5.48 mtr. Both side and 0/421.65 to 0/426.55 Length = 4.90 mtr. Ht. 5.48 mtr. Both side).	326198/-	7000/-	Two months	350/-
5.	Const.of Bodh Ganoh road kms 0/0 to 6/0 (SH:- Construction of Cement concrete pavement at RD 1/185 to 1/215)	295720/-	6000/-	Two months	350/-
6.	Const.of Bodh Ganoh road kms 0/0 to 6/0 (SH:- Construction of Cement concrete pavement at RD 1/215 to 1/242)	289991/-	6000/-	Two months	350/-

1. Certified that tender of above works are being called of emergent nature in Exigency of public interest.


Executive Engineer
Nurpur Division, HPPWD,
Nurpur.
For on behalf of Governor of H.P.

Name of work :- Construction of link road from Tikka Nagrota Hathi Dhar km 0/0 to 9/050
(SH: Formation cutting in km. 8/765 to 9/050)

Estimated cost Rs. 384813.00
Earnest money Rs.7300.00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in soil in hilly area by in ordinary / hard rock (blasting prohibited) with rock breakers by mechanical means including cutting and trimming of sides slopes / breaking rock loading in tippers and disposing of excavated earth upto any lift and leads as per technical specification clause 302.3.5 including shoring and strutting and pumping and bailing out water (surface and sub soil water) complete as per entire satisfaction and as per the direction of Engineer-in-Charge Including carriage of materials within all leads and lifts and other incidental	605.90 cubic meter			Per cubic meter	
2	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted to meet requirement of Tables 300.1 and 300.2 as per technical specifications clause 301.5 as per directions of Engineer-in-charge. The rates is including royalty , malkana, toll tax , G.S.T or any other taxes and carriage of materials within all leads and lifts and other incidental.	4669.77 cubic meter			Per cubic meter	
				Total		


Executive Engineer,
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :-Construction of balance work of Govt. Senior Secondary school Ganoh in Tehsil Nurpur Distt. Kangra HP (SH: Earth filling and vitrified tiles in flooring)
At RD)

Estimated cost Rs. 404470.00
Earnest money Rs.9700 .00
Time limit :-Two month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Excavating supplying and filling of local earth by mechanical transport to site of work including ramming and watering of the earth in layers not exceeding 20 (twenty centimeters) filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	51.80 cubic meter			Per cubic meter	
2	Supplying filling , spreading and level stone hand packed tightly under floor including watering, ramming ,consolidating and dressing complete as directed by the Engineer-in Charge including carriage of materials within all leads and lifts and other incidental charges..	19.43 cubic meters			Per cubic meter	
3	Providing and fixing vitrified tile 10mm(ten millimeter) thick anti skid water proof stain and impact resistant heavy duty vitrified tiles of Kajaria / Rak / Nitco make in size 600x600x10mm (six hundred into six hundred into ten milimeters) thick of approved manufacture and shade and colour in floors treads steps and landings on a bed of 12mm(twelve millimeter) average thickness of chemical adhesive of superior quality jointed with neat cement slurry mixed with pigment to shade of tiles complete including carriage of material within all leads and lifts	266.30 Square meter			Per Square meter	
				Total		

Executive Engineer,
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :-Construction of balance work of Govt. Senior Secondary school Ganoh in Tehsil Nurpur Distt. Kangra HP (SH: Providing and fixing tiles in skirting and roofing)

Estimated cost Rs. 253362.00
Earnest money Rs.5100.00
Time limit :-Two month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing vitrified tile 8mm(eight millimeter) thick anti skid water proof stain and impact resistant heavy duty vitrified tiles of Kajaria/Rak/ Nitco make in size 600x600x8mm (six hundred into six hundred into eight milimeters) thick of approved manufacture and shade and colour in skirting, risers of steps and dado floors treads steps and landings on a bed of 12mm(twelve millimeter) average thickness of chemical adhesive of superior quality jointed with neat cement slurry mixed with pigment to shade of tiles complete including carriage of material within all leads and lifts	31.66 square meter			Per Square meter	
2	Providing and laying automatic hydraulically compressed and polished pre-cast chequered tiles of ISI marked No. IS-1237 of approved shade, 22mm (twenty two millimeters) thick with marble chips of specified size in floors, treads of steps and landing on a bed of 20mm (twenty millimeters) average thickness of cement mortar 1 : 4 (one cement : four sand) jointed with white/ grey cement slurry mixed with pigment to match the shade of tiles (wherever required) including rubbing and polishing complete white cement upto all floor level including carriage of materials with in all leads and lifts and other incidental...	46.44 cubic meters			Per cubic meter	
3	Distempering (two or more coats) with oil bound washer distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surfaces even and sand papered smooth and carriage of materials with in all lead and lifts.	306.34 Square meter			Per Square meter.	
4	Providing and fixing 0.60mm (zero point six zero millimeters) thick preprinted steel sheet in roofing with hot dipped zinc coated sheet with top coat of regulated modified polyester (R N P) organic coating of 20(twenty) micron over 5 (five) micron primer coating to back coat of polyester of 5 (five) micron over 5 (five) micron primer coating including fixing with preprinted iron J or L hooks, bolts and nuts 6mm dia meter with preprinted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge including carriage of materials within all leads and lifts	33.25 square meters			Per square meter	
5	Steel work welded in built up sections composed of beams, joist, channels, angles, Tee- flats, with connecting plates or angle cleats etcetera as in trusses, and trussed purlins main and cross-beams, hips and jack rafters -purlins connecting to common rafter and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a coat of red lead paint including carriage of materials within all leads and lifts.	352.46 kilogram			Per kilo gram	

6	Providing and fixing M.S. channel door, window frame manufactured from M.S. angle iron of section 75.18 x38.18 (Seventy five point one eight into thirty eight millimeter) and M.S. flat 75 x x40x 4 mm (seventy five into forty into four millimeter) as per design and drawings including hinges, jamb, lock Jamb, bead and if required angle threshold pressed steel welded or or rigidly fixed by mechanical means lugs with split end tails to each jambs including steel butt hinges 2.5 mm (two point five millimeter) thick with provision for locking arrangement and shock absorbers as specified and applying a coat of approved steel primer after pretreatment of the surface as per HPPWD specifications or as directed by the Engineer-in-Charge, including applying a priming coat of red lead paint after pretreatment of the surface and carriage of materials within all leads, lifts and other incidentals. The rate inclusive Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	128.00 Running meter			Per Running meter
				Total	


 Executive Engineer,
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work :-Construction of link road from Balkh Bridge to village Tarihar road Km 0/0 to 1/600
(SH: Construction of R/wall for the approaches of 900mm dia Hume pipe culvert
At RD 0/413.45 to 0/418.35)Length= 4.90 mtr. Ht 5.48 mtr. Both side and
0/421.65 to /426.55) Length 4.90 mtr. Ht 5.48 mtr. Both side)

Estimated cost Rs. 326198.00
Earnest money Rs.7000 .00
Time limit :-Two month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts , drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	76.76 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802.803, 1202, 1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	131.56 cubic meter			Per cubic meter	

3	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614, 709, 1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	70.00 Number	Each	
4	Back filling with granular materials behind abutment, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	35.28 cubic meter	Per cubic meter	
			Total	


 Executive Engineer,
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work :- Construction of Bodh Ganoh road km. 0/0 to 6/0
(SH:- Construction of Cement concrete pavement at RD 1/185 to 1/215)

Estimated cost Rs. 295720.00
Earnest money Rs. 6000.00
Time limit :- Two month

Sr. No.	Description of items	Quantity	Rate in Figure	Words		Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	92.60 cubic meter				Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	30.90 cubic meter				Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work and curing complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	61.80 cubic meter				Per cubic meter	
					Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur

Name of work :-	Construction of	Both Ganoh road	km. 0/0 to 6/0
(SH):-	Construction of	Cement concrete pavement	at RD 1/215 to 1/242)

Estimated cost Rs. 289991.00
Earnest money Rs. 6000.00
Time limit :- Two month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	90.90 cubic meter			Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement, four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	30.30 cubic meter			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work and curing complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G.S.T or any other taxes imposed by the Government.	60.60 cubic meter			Per cubic meter	
				Total		

~~Executive Engineer
Nurpur Division HPPWD
Nurpur~~