



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22 **12247-57**
To

Dated **29-12-2021**

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.**

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.**



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **07.01.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **05.01.2022** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money (in Rupees)	Time	Cost of tender form Rs.
1	Construction of link road to village kot km 0/00 to 1/450 under MMGSY(SH: F/C 5/7 mtr Wide road in km 0/720 to 0/810)	472208.00	10000	Three months	350/-
2	Construction of link road to village kot km 0/00 to 1/450 under MMGSY(SH: F/C 5/7 mtr Wide road in km 0/810 to 0/900)	494218.00	10000	Three months	350/-
3	Construction of link road to village kot km 0/00 to 1/450 under MMGSY(SH: F/C 5/7 mtr Wide road in km 0/900 to 1/045)	487537.00	10000	Three months	350/-
4	BSP/2020-89 Construction of link road from Patarna to Tipper km. 0/00 to 1/720 under BASP (SH:- P/L Kharanja stone soling in km. 0/0 to 0/550)	481726.00	10000	Three months	350/-
5	BSP/2020-89 Construction of link road from	481726.00	10000	Three	350/-

	Patarna to Tipper km. 0/00 to 1/720 under BASP (SH:- P/L Kharanja stone soling in km. 0/550 to 1/100)			months	
6	C/O of road from Shroo to Badari km 0/000 to 0/720 under MMGSY(SH:-Formation cutting 5/7 mtr wide road in km. 0/510 to 0/555)	451010.00	10000.00	One month	350/-
7	C/O of road from Shroo to Badari km 0/000 to 0/720 under MMGSY(SH:-Formation cutting 5/7 mtr wide road in km. 0/555 to 0/630)	420538.00	10000.00	One month	350/-
8	Repair of water supply and sanitary installation to CHC Anni, Distt.-Kullu, H.P. (S.H.:-Repair of plaster, P/L wall tiles)	481340.00	10000.00	One month	350/-
9	Repair of water supply and sanitary installation to CHC Anni, Distt.-Kullu, H.P. (S.H.:-Repair of plaster, P/L tile flooring.)	363491.00	10000.00	One month	350/-
10	Repair of water supply and sanitary installation to CHC Anni, Distt.-Kullu, H.P. (S.H.:- P/F water supply installation)	268020.00	10000.00	One month	350/-
11	Construction of link road from Main road Kalaras to Khrai km. 0/00 to 1/170 under MNP. (SH:-C/O PCC Retaining Wall at RD. 0/135 to 0/160)	369703.00	8000.00	One month	350/-
12	A/R & M/O Averi to Bayal road km. 0/00 to 4/290 . (SH:- C/O P.C.C. R/Walls at RD. 2/320 to 2/345) under BASP	498973.00	10000	Three months	350/-
13	A/R & M/O various roads under Nirmand Sub-Division. (Sub Head:- P/F kilometre stones on various roads under Nirmand Sub-Division)	154100.00	4000.00	One month	350/-
14	A/R & M/O Avera (Devdhank) to Ghatoo road km. 0/00 to 10/600. (SH:-C/O Retaining Wall at RD. 6/753 to 6/781)	459407.00	10000	Two months	350/-

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in


Phone No.-01904-255140

Fax No. 01904-255740



Certificate

**Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 12247-57 dated
29.12.2021 is very urgent nature. So may be uploaded on Departmental
website in public interest please.**


**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh**

Name of work	Estimated cost in Rupees	Latest Money in Rupees	Time	Cost of tender
Construction of link road to village Kharwa from 14/39 under MNCV (Sd. 14/37) and is defined in km 14/20 and 14/21	47278.00	10000	Three months	150
Construction of link road to village Kharwa from 14/39 under MNCV (Sd. 14/37) and is defined in km 14/20 and 14/21	49216.00	10000	Three months	210
Construction of link road to village Kharwa from 14/39 under MNCV (Sd. 14/37) and is defined in km 14/20 and 14/21	487332.00	10000	Three months	250
Construction of link road from village to village km. 042 to 14/20 under DASP (Sd. 14/37) and is defined in km 14/20 and 14/21	481726.00	10000	Three months	250
Construction of link road from village to village km. 042 to 14/20 under DASP (Sd. 14/37) and is defined in km 14/20 and 14/21	481726.00	10000	Three months	250

Schedule of quantity

Schedule of quantity						
Name of Work: Construction of link road to village kot km 0/00 to 1/450 under MMGSY(SH: F/C 5/7 mtr Wide road in km 0/720 to 0/810)				Estimated cost:- Earnest Money Time		472208.00 10000 Three months
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 308.62 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1763.55	Cubic Metre			
Total in Figures						

20
Executive Engineer,
Rural Sanitation,
M.D., M.M.

Schedule of quantity

Name of Work: Construction of link road to village kot km 0/00 to 1/450 under MMGSY(SH: F/C 5/7 mtr Wide road in km 0/810 to 0/900)					Estimated cost:- Earnest Money Time Three months	494218.00 10000
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	AMOUNT
					Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 323.01 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1845.75	Cubic Metre			
Total in Figures						


 Executive Engineer
 Survey and Design Division
 H.P. & D. Department


Schedule of quantity

Schedule of quantity							
Name of Work: Construction of link road to village kot km 0/00 to 1/450 under MMGSY(SH: F/C 5/7 mtr Wide road in km 0/900 to 1/045)				Estimated cost:-		487537.00	
				Earnest Money		10000	
				Time		Three months	
				RATE		AMOUNT	
Sl. No.	Description of work	Qty.	Unit	Figures	Words		
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract ot achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 418.63 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on	1820.80	Cubic Metre				
Total in Figures							

Executive Engineer
 Outer Seral Division
 HPPWD, Noida

4

Schedule of quantity						
Name of Work: BSP/2020-89 Construction of link road from Patarna to Tipper km. 0/00 to 1/720 under BASP (SH:- P/L Kharanja stone soling in km. 0/00 to 0/550)				Estimated cost:- Rs. 481726.00 Earnest Money:- Rs. 10000.00 Time :- Three months.		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1934.63	Square metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub grade including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1934.63	Square metre			
3	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 150mm spread thickness(finished work including materials and labour) and as per directions of the Engineer-In-Charge including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	264.21	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Seraj Division
 HPWD, Dind

Schedule of quantity

Schedule of quantity						
Name of Work: BSP/2020-89 Construction of link road from Patarna to Tipper km. 0/00 to 1/720 under BASP (SH:- P/L Kharanja stone soling in km. 0/550 to 1/100)				Estimated cost:- Rs. 481726.00 Earnest Money:- Rs. 10000.00 Time :- Three months.		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately dispending upon the classification of soil including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1934.63	Square metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub grade including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	1934.63	Square metre			
3	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 150mm spread thickness(finished work including materials and labour) and as per directions of the Engineer-In-Charge including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	264.21	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Survey Division
 H.P.P.W.D., Mandla

Signature of Tenderer with seal

6.

Schedule of quantity

Name of Work:- C/O of road from Shroo to Badari km 0/000 to 0/720 under MMGSY (SH:-Formation cutting 5/7 mtr wide road in km. 0/510 to 0/555)					Estimated cost:- Earnest Money	451010.00
					Time	10000
					One month	
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 299.79 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1394.33	Cubic Metre			
Total in Figures						

Executive Engineer
 Outer Serai Division
 U.P. WD. Noida

Schedule of quantity						
Name of Work:- C/O of road from Shroo to Badari km 0/000 to 0/720 under MMGSY(SH):-Formation cutting 5/7 mtr wide road in km. 0/555 to 0/630)						
Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-	
					Earnest Money	420538.00
					Time	10000
					RATE	
					Words	One month
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 279.53cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1300.12	Cubic Metre			
Total in Figures						

Schedule of Quantity						
Name of work:- Repair of water supply and sanitary installation to CHC Anni, Distt.-Kullu, H.P. (S.H):-Repair of plaster, P/L wall tiles)				Estimated cost:- Rs.481340.00 Money:- Rs. 10000.00 month.		
				Earnest Time:- One		
Sr. No.	Description of work	No. or Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge. With cement mortar 1:4 (1cement: 4 coarse sand) including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	80.01	Square Metre			
2	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	266.71	Square Metre			
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarsesand : 4 graded stone aggregate) finished with a floatingcoat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete including curing and carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	6.82	Cubic Metre			
Total in Figures						

Executive Engineer
Outer Sarai Division
HPWD, Noida

Schedule of Quantity						
Name of work: - Repair of water supply and sanitary installation to CHC Anni, Distt.-Kullu, H.P. (S.H.-Repair of plaster, P/L tile flooring.)				Estimated cost:- Rs.363491.00 Money:- Rs. 10000.00 month.		Earnest Time:- One
Sr. No.	Description of work	No.or Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge. With cement mortar 1:4 (1 cement: 4 coarse sand)	33.762	Square Metre			
2	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	112.54	Square Metre			
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarsesand : 4 graded stone aggregate) finished with a floatingcoat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.	6.82	Cubic Metre			
4	Providing and laying vitrified floor tiles in different sizes(thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete ng with bricks of class	90.90	Square Metre			
Total in Figures						


 Executive Engineer,
 Water Supply Division,
 H.P.W.D., Shimla.

Schedule of Quantity						
Name of work: - Repair of water supply and sanitary installation to CHC Anni, Distt.-Kullu, H.P. (S.H.- P/F water supply installation)				Estimated cost:- Rs.268020.00 Money:- Rs. 6000.00 month.		Earnest Time:- One
Sr. No.	Description of work	No.or Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete. 15 mm nominal bore.	44	Each			
2	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required Size 450x300x150 mm including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	3	Each			
3	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	10	Each			
4	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings. including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	10	Each			
5	Providing and fixing PVC floor floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floor etc including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	25	Each			
6	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials in all leads and lifts as per direction of Engineer - in - Charge complete.	25	Each			

7	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.: 15mm dia	30	Each			
8	Providing and fixing Polyethelene-AluminiumPolyethelene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge Concealed work, including cutting chases and making good the wall etc. 1216 (16 mm OD) pipe including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	280	Each			
9	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete. : 20 mm nominal	15	Rmt			
10	Providing and fixing 600mm x 450mm bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P brass screws and washers including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	10	Each			
11	Providing and fixing PTMT towel rail with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	10	Each			
12	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawplugs etc.including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	10	Each			

13	Providing and fixing PTMT Soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.	10	Each		
14	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per direction of Engineer – in – Charge complete.: 15 mm nominal bore	40	Each		
Total in Figures					


 Executive Engineer,
 Outer Seari Division,
 HP. PWD, Jalandhar.

Schedule of quantity

Name of Work:- Construction of link road from Main road Kalaras to Khrai km. 0/00 to 1/170). (SH:-C/O PCC Retaining Wall at RD. 0/135 to 0/160)									
Sl. No.	Description of work	Qty.	Unit	RATE		Estimated cost:-		369703.00	
				Figures	Words	Time	Earnest Money	Two months	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	11.37	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	25.75	Cubic Metre						
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	73.25	Cubic Metre						
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	11.50	Cubic Metre						
Total in Figures									

Executive Engineer
Outer Serai Division
HEAWD, NAWD

12

Schedule of quantity									
Name of Work:- A/R & M/O Averri to Bayal road km. 0/00 to 4/290 . (SH:- C/O P.C.C. R/Walls at RD. 2/320 to 2/345)									
					Estimated cost:-		498973.00		
					Earnest Money		10000		
					Time		Two months		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	38.25	Cubic Metre						
2	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	104.75	Cubic Metre						
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	15	Each						
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.25	Cubic Metre						
Total in Figures									



 Executive Engineer

 Outer Saraj Division

 HAWA, Daman

13

Schedule of quantity						
Name of Work: A/R & M/O various roads under Nirmand Sub-Division. (Sub Head:- P/F kilometre stones on various roads under Nirmand Sub-Division)				Estimated cost:-		
				Earnest Money		
				Time		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Providing and fixing at site Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	44.00	Each			
Total in Figures						
						154100.00
						4000.00
						One month

22
Executive Engineer
Outer Seral Division
H.P.W.D., Nirmand

Schedule of quantity									
Name of Work: A/R & M/O Avera (Devdhank) to Ghatoo road km. 0/00 to 10/600. (SH:-C/O Retaining Wall at RD. 6/753 to 6/781)				Estimated cost:-		459407.00			
				Earnest Money		10000			
				Time		Two months			
				RATE		AMOUNT			
Sl. No.	Description of work	Qty.	Unit	Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	22.68	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	18.20	Cubic Metre						
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	91.10	Cubic Metre						
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.00	Each						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.84	Cubic Metre						
Total in Figures									

20

Executive Engineer,
Outer Sewer Division
H&WDP, Mirmand