

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2020-21- 9844-45

Dated:- 18-01-2022

To

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental website.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP PWD, Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed items rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 02.02.2022 up to 10.30 AM and shall be opened on 02.02.2022 the same day at 11.00 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 01.02.2022 for which the applications should reach in this office up to 4.00 PM on 31.01.2022. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
✓1	Restoration of rain damages to link road to village Santoshgarh km 0/0 to 0/630. (SH:-Construction of V-shape drain at RD.0/0 to 0/630). (RHS).	Rs. 3,21,424/-	Rs. 6500/-	Two Months	350/-	C & D
✓2	Repair of Paonta Puruwalla Singhpura Bhagani Gojjar Dakpathar road km 0/0 to 26/500. (SH:-C/O parapets in essential portions in km 10/950 to 11/450) (Both sides) (under Additional Annual Maintenance Plan (AMP) for the year 2021-22).	Rs. 2,80,108/-	Rs. 5600/-	Two Months.	350/-	C & D
✓3	Restoration of rain damages to Jamniwala Khara road km 0/0 to 6/0 (SH:-Construction of cement concrete R/wall for protection of abutment of Khara Bridge No.3 (Khara side) (Repair of Bridge).	Rs. 2,64,368/-	Rs. 5300/-	Two Months.	350/-	C & D
4	Restoration of rain damages to link road Lohgarh km 0/0 to 5/150. (SH:-C/O R/wall in wire crate at RD 2/420 to 2/435).	Rs. 2,54,323/-	Rs. 5000/-	Three Months.	350/-	C & D


5	Construction of Jamnighat Jheel bankabara to Dhaunwala road km 0/0 to 5/020. (SH:-C/O R/wall at RD 3/880 to 3/910).Under SCSP.	Rs. 3,34,633/-	Rs. 6700/-	Two Months.	350/-	C & D
6	Construction of link road to Surajpur pation road km 0/0 to 3/185. (SH:-P/L wet mix Macadam at RD 1/960 to 2/180).Under MNP.	Rs. 2,90,431/-	Rs. 5800/-	Two Months.	350/-	C & D

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis.
10. Only two tender forms will be given to one contractor.



Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

No.PWP/CB-Tender Notice/2021-22- 9794-9843

Dated:- 18-01-2022

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
11. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

Job No - 1

SCHEDULE OF QUANTITIES.						
Name of work:-Restoration of rain damages to link road to village Santoshgarh km. 0/0 to 0/630 (SH:-C/O V-shape drain in km. 0/0 to 0/630)(RHS).		Estimated Cost :- Rs.3,21,424/-ONLY.				
		Earnest Money :- Rs.6,500/-ONLY.				
		Time Allowed :-Two Months.				
S.No.	Sub head and items of work.	Quantity.	Figures.	Rate in Words.	Unit.	Amount.
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30cm. (thirty centimetres)in depth, 1.5 m(one point five metre)in width as well as 10 sq.m.(ten square metres)on plan) including getting out and disposal of excavated earth any leads and lifts, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	88.20			Per cubic metre.	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- all work to plinth level 1:3:6 (one cement : three course sand : six graded stone aggregate 40mm(forty millimetres)nominal size ,including all leads, lifts and carriage of materials, as per entire satisfaction of Engineer-in-charge.	53.55			Per cubic metre.	
3	Providing and laying 300mm.(three hundred millimetres) dia RCC hume pipe on-pressure NP2 class (light duty)RCC pipe with collars jointed with stiff mixture of cement mortar in the proportion of 1:2(one cement : two fine sand) including testing of joints etc., complete, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	25.00			per running metre.	
					Total:-Rs.	

NOTE:- The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of HP. Letter No.PBW(B)(C)(17/2/2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.

Executive Engineer,
Paonta B&R Division,
HP PWD, Paonta Sahib.

Job No - 02.

SCHEDULE OF QUANTITIES.					
Name of work:- Repair of Paonta Puruwala Singhpura Bhagani Gojjar Dakpathar road km. 0/0 to 26/500 (SH:- Construction of parapets in essential portions in km. 10/950 to 11/450) (Both side).(under Additional Annual Maintenance Plan(AMP)for the year 2021-22).			Estimated Cost :- Rs.2,80,108/-ONLY. Earnest Money :- Rs.5,600/-ONLY. Time Allowed :-Two Months.		
S.No.	Sub head and items of work.	Quantity.	Figures.	Rate in Words.	Unit. Amount.
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 in P.C.C. M-10 grade (nominal mix 1:3:6(one cement : three sand : six graded stone aggregate) including cost of form work and carriage of materials upto all leads, lifts and carriage of materials, as the direction and entire satisfaction of the Engineer-in-charge at site of work.	51.65			Per cubic metere.
				Total:-Rs.	

NOTE:-The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of HP.Letter No.PBW(B)(C)(17)2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.


Executive Engineer,
Paonta B&R Division,
HP.PWD.Paonta Sahib.

Job No - 3.

Schedule of Quantities						
Name of work:- Restoration of Rain Damages to Jamniwala Khara Road Km 0/0 to 6/00 (SH:- Construction of Cement Concrete R/Wall for Protection of abutment of Khara Bridge NO. 3 (Khara side).						
S.No	Sub head and items of work	Qty	Rate in	Estimated Cost:- Rs. 2,64,368/- only		
				Earnest money :- Rs. 5300/- only		
				Time allowed:- Two months	Unit	Amount
1	Earth work in excavation for structure as per and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-In charge.	21.00			Per cubic metre	
2	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203, RCC Grade M:20 (1:2:4) including carriage of material with in all lead, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	45.36			Per cubic metre	
					Total	

Note:- The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of HP. Letter No. PBW(B)(C)(17/2/2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.

Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib,

Job No - 4

SCHEDULE OF QUANTITIES.				
Name of work:- Restoration of rain damages to link road Lohgarh km. 0/0 to 5/150 (SH:-Construction of retaining wall in wire crate at RD. 2/420 to 2/435).			Estimated Cost :- Rs.2,54,323/-ONLY.	
			Earnest Money :- Rs.5,000/-ONLY.	
			Time Allowed :-Two Months.	
S.No.	Sub head and items of work.	Quantity	Rate in Words.	Unit.
		Figures.		Amount.
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30cm.(thirty centimetres)in depth, 1.5 m(one point five metre)in width as well as 10 sq.m.(ten square metres)on plan) including getting out and disposal of excavated earth any leads and lifts, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	24.75		Per cubic metre.
2	Providing and laying apron laid in wire crates with 4mm(four milimetres)dia G.I. wire conforming to IS :280 and IS : 48236 in 100x100 (hundred into hundred)mesh (woven diagonally) including 10%(ten percent) extra over lad and joints with stone boulders drawing and technical specification wieghting not less then 25kg.(twenty five kilograms) as per clause 1301.including all leads, lifts and carriage of materials, as per entire satisfaction of Engineer-in-charge.	85.32		Per cubic metre.
			Total:-Rs.	

NOTE:-The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of. HP.Letter No.PBW(B)(C)(17)2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.

Executive Engineer,
Paonta B&R Division,
HP.PWD.Paonta Sahib.

Job No - S.

SCHEDULE OF QUANTITIES.						
Name of work:-Construction of Jamnighat Jheel Bankabara to Dhaunwala road km. 0/0 to 5/020 (SH:-Construction of breast wall at RD. 3/880 to 3/910).						
			Estimated Cost :- Rs.3,34,633/- ONLY.			
			Earnest Money :- Rs.6,700/- ONLY.			
			Time Allowed :-Two Months.			
S.No.	Sub head and items of work.	Quantity	Figures.	Rate in Words.	Unit.	Amount.
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30cm.(thirty centimetres)in depth, 1.5 m(one point five metre)in width as well as 10 sq.m.(ten square metres)on plan) including getting out and disposal of excavated earth any leads and lifts, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	34.80			Per cubic metre.	
2	Centering and shuttering including strutting, propping etc., and removal of form work for retaining walls, returnwalls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc., including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	63.60			per square metre.	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work upto plinth level 1: 4: 8 (one cement : four coarse sand : eight graded stone aggregate)40mm.(forty millimetres)nominal size, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	60.48			Per cubic metre.	
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment, wing wall, return wall with 100mm.(hundred millimetres) dia PVC pipe extending through the full width of the structure with slope of (v):20 (H) towards drawing face complete as per drawing technical specification, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	15.00			Each.	
					Total:-Rs.	

NOTE:- The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of. HP.Letter No.PBW(B)(C)(17)2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.


Executive Engineer,
Paonta B&R Division,
HP.PWD.Paonta Sahib.

Job No - 6

SCHEDULE OF QUANTITIES.					
Name of work:- Construction of link road Surajpur Patlion road km. 0/0 to 3/185 (SH:-Providing and laying wet mix macadam (size 53mm. To 0.075mm) at RD. 1/960 to 2/180) Under M.N.P.			Estimated Cost :- Rs.2,90,431/-ONLY. Earnest Money :- Rs.5,800/-ONLY. Time Allowed :-Two Months.		
S.No.	Sub head and items of work.	Quantity	Figures.	Rate in Words.	Unit. Amount.
1	Providing, laying spreading and compacting graded stone aggregate (size range 53mm. to 0.075mm(Fifty three milimetres to zero point zero seven five millimetre)) to wet mix macadam (WMM) specification included premixing the erial with water at OMC in for all leads, lifts, laying in uniform layers with mechanical paver finisher in sub base/base course on well prepared surface and compecting with vibratory roller of 8 to 10 (eight to ten)tonne capacity to hieve the desired density, complete, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	110.55			Per cubic metere.
					Total:-Rs.

NOTE:- The construction materials will be procured by the contractor/ firm from the agencies given in the list of preferred makes of material for Civil /Sanitary works strictly in accordance with the ACS(PW) to the Govt. of. HP.Letter No.PBW(B)(C)(17)2/2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.

Executive Engineer
Paonta B&R Division,
HP.PWD,Paonta Sahib.