

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 07.01.2022 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Sechedule	
1	Last date for tender receipt of application for tender form	05.01.2022 upto 4:00 PM
2.	Last date of sale of tender forms.	06.01.2022 upto 4:00 PM
3.	Date of receipt of tender forms	07.01.2022 upto 10:30AM
4.	Date of opening of tenders	07.01.2022 at 11:00AM

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1.	A/R/&M/O & R/R Damages on various road for Habban Section under Habban Sub-Division (SH:- Removal of snow and slips).	1,08,410/-	2200/-	Two months	350/-
2.	A/R/&M/O & R/R Damages on various road for Rajgarh-I Section under Rajgarh Sub-Division (SH:- Removal of snow and slips).	1,10,784/-	3100/-	Two months	350/-
3.	A/R/&M/O & R/R Damages on various road for Dhamander Section under Habban Sub-Division (SH:- Removal of snow and slips).	1,10,784/-	2300/-	Two months	350/-
4.	A/R/&M/O & R/R Damages on various road for Fagu Section under Habban Sub-Division (SH:- Removal of snow and slips).	1,10,264/-	2300/-	Two months	350/-
5.	A/R/&M/O & R/R Damages on various road for Chandol Section under Habban Sub-Division (SH:- Removal of snow and slips).	1,10,784/-	2300/-	Two months	350/-
6.	A/R/&M/O & R/R Damages on various road for Deedag Section under Rajgarh Sub-Division (SH:- Removal of snow and slips).	1,10,784/-	2300/-	Two months	350/-
7.	C/O Canteen in ITI, building at Rajgarh, Distt. Sirmour HP (SH:- C/O Canteen).	265214/-	5500/-	Two months	350/-
8.	Pulling and lifting of accidental loader cum back hoe having registration No. HP-16-1549 L&T Machine from accidental site at Pallu near Habban on B.B.R.C road at RD 107/010)	1,20,000/-	2500/-	10 days	350/-

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who dose not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 crore each.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.

10. The above job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW(B)A(3)1/2020 dt. 22.07.2020 & 07.10.2021. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.

11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.


Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh

Tel. No. 01799-221023

Mail. ee-raj-hp@nic.in

Dated:- 30-12-21

No.PW/RGH/Estt-Tender/2021-22-

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O & R/R damages for Habban Section under Habban Sub-Division (SH:- Removal of snow and slips).

Estimated cost:-Rs.1,08,410/-
Earnest money:- Rs.2,200/-
Time Limit:- Two Month

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Snow clearance from road surface by a JCB/ Bulldozer 165 HP and disposing it on the velly side as per MORTH and IRC specification 48-1998. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18500.00	Per Cubic meter.			
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and ifts as per direction of the Engineer-in-Charge , as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	150.00	Per cubic meter.			


 Executive Engineer,
 Rajgarh Division,
 HP, PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work : A/R & M/O & R/R damages for Rajgarh-I Section under Rajgarh Sub-Division (SH:- Removal of snow and slips).

Estimated cost:-Rs.1,10,784/-
Earnest money: - Rs. 2,300/-
Time Limit: - Two Month

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Snow clearance from road surface by a JCB/ Bulldozer 165 HP and disposing it on the velly side as per MORTH and IRC specification 48-1998. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18800.00	Per Cubic meter.			
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per direction of the Engineer-in-Charge , as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	160.00	Per cubic meter.			


Executive Engineer,
Rajgarh Division,
HP, PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work : A/R & M/O & R/R damages for Dhamander Section under Habban Sub-Division (SH:- Removal of snow and slips).

Estimated cost:-Rs.1,10,784/-
Earnest money:- Rs.2,300/-
Time Limit:- Two Month

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Snow clearance from road surface by a JCB/ Bulldozer 165 HP and disposing it on the velly side as per MORTH and IRC specification 48-1998. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18800.00	Per Cubic meter.			
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per direction of the Engineer-in-Charge , as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	160.00	Per cubic meter.			


Executive Engineer,
Rajgarh Division,
HP, PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work : A/R & M/O & R/R damages for Fagu Section under Habban Sub-Division (SH:- Removal of snow and slips).
Estimated cost:-Rs.1,10,264/-
Earnest money: - Rs.2,300/-
Time Limit: - Two Month

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Snow clearance from road surface by a JCB/ Bulldozer 165 HP and disposing it on the velly side as per MORTH and IRC specification 48-1998. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18700.00	Per Cubic meter.			
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per direction of the Engineer-in-Charge , as per H.P.PWD. specification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	160.00	Per cubic meter.			


Executive Engineer,
Rajgarh Division,
HP, PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O & R/R damages for Chandol Section under Habban Sub-Division (SH:- Removal of snow and slips).

Estimated cost:-Rs.1,08,784/-
Earnest money: - Rs.2,200/-
Time Limit: - Two Month

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Snow clearance from road surface by a JCB/ Bulldozer 165 HP and disposing it on the velly side as per MORTH and IRC specification 48-1998. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18500.00	Per Cubic meter.			
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lall leads and ifts as per direction of the Engineer-in-Charge , as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	154.59	Per cubic meter.			


Executive Engineer,
Rajgarh Division,
HP, PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O & R/R damages for Deedag Section under Rajgarh Sub-Division (SH:- Removal of snow and slips).

Estimated cost:-Rs.1,08,784/-
Earnest money: - Rs.2,200/-
Time Limit: - Two Month

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Snow clearance from road surface by a JCB/ Bulldozer 165 HP and disposing it on the velly side as per MORTH and IRC specification 48-1998. in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	18500.00	Per Cubic meter.			
2	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and ifts as per direction of the Engineer-in-Charge , as per H.P.PWD. spesification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	154.59	Per cubic meter.			


Executive Engineer,
Rajgarh Division,
HP, PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of Work:- Construction of ITI , building at Rajgarh, District Sirmaur H.P.(Sh:- Construction of Canteen).

Name of Work:- Construction of IT1 , building at Rajgarh, District Sirmaur H.P.(Sh:- Construction of Canteen).		Estimated Cost: -		2,62,514		
		Earnest Money: -		5500.00		
		Time: -		Two Month		
Sl. No.	Description	Qty.	Unit	Figures	RATE In Words	AMOUNT Rs.
1	2	3	4		5	6
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.	3.96	Per Cubic Mtrs.	290.15		
2	Providing form work with steel plates 3.15 (Three point One Five) millimeters thick welded with angle iron in frame 30 x 30 x 5 (Thirty into Five) millimeters, so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies /steel pipes in all heights of propping and centering below supporting floor to ceiling and removal of the same in-situ-reinforced concrete and plain concrete work in Flat surfaces such as soffits of suspended floors, roofs, landings and the like, as per H.P.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	5.95	Per Square mtrs.	468.30		
3	Providing and laying cement concrete 1:4:8 (1 cement:4 sand: 8 graded stone aggregate 40mm(Forty millimetre nominal size) in Foundation and plinth, mechanically mixed vibrated and curing complete excluding cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	0.40	Per Cubic Mtrs.	4955.20		
4	Providing and Laying cement concrete 1:3:6 (One cement :three sand : six graded crushed hard stone aggregate 40mm(forty millimeters nominal size) mechanically mixed vibrated and curing complete , excluding cost of form work in foundation and plinth , as per H.P.P.W.D. specification 1990 Volume-I including carriage of all labour , equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	2.03	Per Cubic Mtrs.	5291.95		
5	Providing and laying mix M-25 grade cement concrete 1:1.5:3 (One cement isto One point Five sand isto Three graded stone aggregate 20 mm nominal size)in Suspended floor, roofs landing shelves and their support balconies, beam, girders bressumers and cantilevers in all floor up to all hights and levels in position machine batched and machine mixed design for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, as per direction of Engineer-in-charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	0.60	Per Cubic Mtrs.	7835.75		
6	Providing tor steel reinforcement for reinforced cement concrete work including bending binding and placing in position complete up to floor level all heights as per direction of Engineer-in-charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	48.00	Per Kg	76.85		
7	Half brick masonry with common burnt clay F.P.S. (modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level with Cement mortar 1:4 (1 cement :4 coarse sand) as per direction of Engineer-in-charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.80	Per Square mtrs.	747.65		

8	Marble stone flooring with Pink plain marble 18 mm thick marble stone, as per sample of marble approved by Engineer-in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete as per direction of Engineer-in-charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	5.95	Per Square mtrs.	1720.45	
9	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet of TATA/ /DUROSHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts , 6mm diameter with pre-painted limpet and rubber washers complete with all accessories as required as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	6.50	Rmtrs.	391.30	
10	Providing and fixing ridges or hips 90cm. (Ninety centimetres) overall with 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheets TATA/ /DUROSHINE in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20(Twenty) microns over 5 (Five) micron primer coating + back coat of polyester of 5 (Five) microns over 5 micro primer coating including fixing with pre-painted iron, J or L hooks bolts and nuts ,6mm (Six millimetre) diameter and pre-painted G.I limpet and bitumen washer complete with all accessories as required and as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	76.32	Per Square mtrs.	842.00	
11	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete e as per direction of Engineer-in-charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1395.49	Per Kg	86.65	
12	Painting steel work with deluxe multi surface paint to give an even shade two or more coat applied @0.90 lt/10 sqm over an under coat of primer applied@ 0.80lt/10sqm of approved brand and manufacture other than white as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	30.27	Per Square mtrs.	89.90	
13	Providing and fixing Polyethelene-Aluminium Polyethelene PE-Al-PE composite pressure pipes conforming to IS-15450, U.V. stabilized with carbon back having thermal stability for hot & cold water supply, capable to withstand temperature up to 80 degree c , including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc. with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including testing of joints complete. Concealed work, including cutting chases and making good the wall etc. as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. (i) 1216 (16 mm OD) pipe	20.00	Rmtrs.	191.00	
14	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors 100 mm(Hundred millimetre)w inlet and 100 mm (hundred millimetre) outlet as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	1178.60	

15	P/F vitreous chain pedestal for wash basin (half pedestal in white shade of perryware/Jaqr/ Hindware/ Cera or equivalent including cutting holes & making good the same as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	1420.15		
16	Providing and fixing CP Brass 32mm (thirty Two) size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	883.05		
17	Providing and fixing 600x450mm (Six hundred into four hundred fifty millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	1009.90		
18	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm (four hundred fifty millimetre) long towel rail with total length of 495 mm (four hundred Ninte five millimetre), 78 mm (Seventy Eight illimetre) wide and effective height of 88 mm (Eighty Eight millimetre) weighing not less than 170 gms (One hundred Seventy grams) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	415.15		
19	Providing and fixing PTMT liquid soap container 109 mm (One hundred Nine millimetre), wide, 125 mm (One hundred Twenty five millimetre), high and 112 mm (One hundred Twelve millimetre), distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms. (One hundred Five grams) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	158.55		
20	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	130.50		
21	Providing and fixing brass bib cock of approved quality : 15 mm nominal bore as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	4.00	Each	302.55		
22	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required: White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	2643.75		
23	Providing and fixing kitchen sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C. P. brass waste complete, including painting the fittings and brackets, cutting and making good the walls wherever required: White glazed fire clay kitchen sink of size 600x450x 250 mm as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	2792.75		

24	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	532.00		
25	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete flexible pipe 32 mm dia as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	101.10		
26	Providing and fixing M.S. handles 100 mm(hundred millimetre) ISI marked oxidised conforming to IS:4992 with necessary screws etc complete as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	7.00	Each	25.50		
27	Providing and fixing M.S. tower bolt black finish, (Barrel type) 200x10 mm (Two hundred into Ten millimetre) ISI marked oxidised with necessary screws etc. complete as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	56.50		
28	Providing and fixing M.S. sliding door bolts 250x16 mm (Two hundred into Sixteen millimetre) ISI marked oxidised with nuts and screws etc. complete as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	56.50		
29	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1000.00	Per litres	8.80		
30	Providing and fixing uplasticated PVC connection pipe with brass unions 45 cm (Forty Five Centimetre) length, 20 mm (Twenty millimetre) nominal bore as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	100.40		
31	Fixing water meter and stop cock in G.I. pipe line including cutting and threading the pipe and making long screws etc. complete (cost of water meter and stop cock to be paid separately) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	386.15		
32	Providing and fixing 110mm high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete, as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	20.00	Rmtrs.	274.00		
33	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete 110 mm (one hundred Ten millimetre) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	77.00		

34	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm (three millimetre) thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete 110mm (one hundred Ten millimetre) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	123.00		
35	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	94.30		


 Executive Engineer,
 HPPWD Division Rajgarh,

SCHEDULE OF QUANTITY

Name of work : Pulling and lifting of accidental loader cum back hoe having registration No. HP-16-1549 L&T Machine form accidental site at Pallu near Habban on B.B.R.C road at RD 107/010 .

Estimated cost:-Rs.1,20,000/-
Earnest money: - Rs. 2,500/-
Time Limit: - Ten Days

Sr No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Pulling and lifting of accidental loader cum back hoe having registration No. HP-16-1549 L&T Machine form accidental site at Pallu near Habban on B.B.R.C road at RD 107/010. The machine laying on outside the road on valley side and have to be brought at Rajgarh including toeing hooking with steel rpoes, clamps etc. with heavy duty crane machine two Nos, then toeing of machine with crane to bring the accidental manchine at Rajgarh including all leads lifts and carrige of machine complete job in all respect. including all taxes etc.	1.00	Each			


Executive Engineer,
Rajgarh Division,
HP, PWD, Rajgarh.