

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 28.01.2022 upto 4.00 PM
2. Date and time of issue of tender form: 01.02.2022 upto 5.00 PM
3. Date and time of receipt of tenders: 02.02.2022 upto 11.00 AM
4. Date and time of opening of tenders: 02.02.2022 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 8/0 to 8/240)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
2	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 8/250 to 8/490)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
3	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 8/500 to 8/740)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
4	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 8/750 to 8/990)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
5	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 9/0 to 9/240)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
6	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 9/250 to 9/490)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
7	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 9/500 to 9/740)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-
8	Preventie Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km. 0/0 to 39/180(SH: Providing and laying Microsurfacing layer at RD 9/750 to 9/990)	Rs.4,95,801/-	Rs.10,000/-	One month	Rs.350/-

1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application):
(i)	Copy of Registration/Latest renewal of enlistment.
(ii)	PAN (Permanent Account No.)
(iii)	Registration under GST No.
(iv)	EPF(Employee Provident Fund Account No.)
(v)	The proof owenership/hire/lease, buying of required machinery for microsurfacing wokrs.
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).
4	The offer of the tender shall remain valid upto 30 days after the opening.

1.Ceritifed that the above work is of an emergent nature in exigency of public interest .

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P
on behalf of Governor of Himachal Pradesh

Endst.No.PWD/DEH/CB/Tender/2021-22:- 10695-701

Dated :- 19/1/22

Copy forwarded to the following:-

1. The F.C. Cum Principal Secretary(PW) to the Govt. of Himachal Pradesh Shimla-2
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, 9th Circle HP.PWD. Nurpur.
5. Notice Board.
6. The Computer Cell office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Departmental website.
7. All eligible Contractors

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- One Month.

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 8/00 to 8/240).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified, Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimac, which should be having width of minimum 1.50mtr. (one point five zero metre) to maximum 2.0 mtr. (Two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge The rate is including Royalty Malkhana Occroi, GST, Toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Occroi, GST, Toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- One Month.

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH):- Providing and Laying Microsurfacing Layer at RD 8/250 to 8/490).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight milimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified., Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimac, which should be having width of minimum 1.50mtr. (one point five zero metre) to maximum 2.0 mtr. (Two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge.The rate is including Royalty Malkhana Ocrroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Ocrroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 8/500 to 8/740).
Estimate Cost :- Rs. 4,95,801.00
Earnest Money :- Rs. 10,000.00
Time Limit :- One Month.

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified., Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimac, which should be having width of minimum 1.50mtr. (one point five zero metre) to maximum 2.0 mtr. (two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge. The rate is including Royalty Malkhana Ocroi, GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Ocroi, GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- One Month.

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 8/750 to 8/990).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified., Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimax, which should be having width of minimum 1.50mtr. (one point five zero metre) to maximum 2.0 mtr. (two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge.The rate is including Royalty Malkhana Ocroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Ocroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00

Earnest Money :- Rs. 10,000.00

Time Limit :- One Month.

Name of work: - Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 9/0 to 9/240).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified., Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre), Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimac, which should be having width of minimum 1.50mtr. (one point five zero metre) to maximum 2.0 mtr. (two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge.The rate is including Royalty Malkhana Ocroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Ocroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


Executive Engineer,
Dehra Division,
HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- One Month.

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 9/250 to 9/490).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified., Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimac, which should be having width of minimum 1.50mtr (one point five zero metre) to maximum 2.0 mtr. (two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge.The rate is including Royalty Malkhana Oorroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Oorroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00

Earnest Money :- Rs. 10,000.00

Time Limit :- One Month.

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 9/500 to 9/740).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six-to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified, Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimax, which should be having width of minimum 1.50mtr. (one point five zero metre) to maximum 2.0 mtr. (two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge. The rate is including Royalty Malkhana Oorroi , GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Oorroi, GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,801.00

Earnest Money :- Rs. 10,000.00

Time Limit :- One Month.

Name of work:- Preventive Maintenance for the year 2021-22 on Dehra Jawali Raja Ka Talab road in Km 0/0 to 39/180 (SH:- Providing and Laying Microsurfacing Layer at RD 9/750 to 9/990).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying micro-surfacing type-III 6-8 mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14kg/Sqm (at the rate of fourteen kilogram per square metre) of road surface coverage, modified., Modified Cationic Bitumin Emulsion @ 1.82 kg/Sqm (at the rate of one point eight two kilogram per square metre). Portland cement as a mineral filler @ 2% (at the rate of two percent) of by weight of crushed aggregate. Break control Additives @ 2% (at the rate of two percent) of by weight of crushed aggregate and purified water with PH 6-7 10% (ten percent) by weight of crushed aggregate using specialized microsurfacing paver and other material, machinery etcetra. Microsurfacing paver should be equivalent to Tasi Minimac, which should be having width of minimum 1.50mtr (one point five zero metre) to maximum 2.0 mtr. (two point zero metre) spreader box and on six wheel tyre chassis to have smooth traffic movement as per table 3 of IRC: SP 81 -2008 and provision 512-514 of Morth specifications 5th revision including entire carriage of materials, labour and equipments to various location of site of work through all modes of transportation in all leads and other incidental charges as per direction and entire satisfaction of the Engineer-in Charge. The rate is including Royalty Malkhana Ocroi, GST, toll tax, Sale tax or any other taxes imposed by the Government.	1701.00 Square metre			Per Square meter	
2	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications. The rate is including Royalty Malkhana Ocroi, GST, toll tax, Sale tax or any other taxes imposed by the Government.	60.00 Square metre			Per Square meter	
	Total					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra